



## Projects Under Construction and About to Start Construction As of Summer 2016 (\*all costs approximate)

### 14 Total Projects Currently Funded for Construction for \$86.5 million

7 projects under construction totaling \$53.4 million

7 about to start construction totaling \$33.1 million

#### ▲ *Currently under construction*

#### Clark County

##### Las Vegas Wash – Sloan to Bonanza and Flamingo Wash – Confluence to Nellis ▲

This phase of the project consists of lining the channel with concrete from just south of Stewart Avenue to Nellis Boulevard. Included in this project is the construction of a new trail along the east side of the channel and a pedestrian bridge over Charleston Boulevard.

**Estimated Total Construction Cost:** \$78.4 million (RFCD share)

**Estimated Construction Cost This Phase:** \$20.4 million

**Estimated Completion Date:** December 2016

##### Flamingo Diversion- Rainbow Branch ▲

This project consists of installing 5,300 feet of concrete box culvert varying in size up to 12 feet wide by 6-feet high.

**Estimated Construction Cost:** \$8.7 million (RFCD share)

**Estimated Completion Date:** April 2017

##### Duck Creek Las Vegas Boulevard

This project includes installation of approximately 6,700 feet of concrete box culvert varying in size up to 20 feet wide by 8 feet high.

**Estimated Construction Cost:** \$6 million (RFCD share)

**Estimated Completion Date:** September 2017

##### Las Vegas Wash-Water Reclamation Channel ▲

This project consists of approximately 5,000 feet of 150 feet wide and 11 feet deep concrete channel.

**Estimated Construction Cost:** \$3.4 million (RFCD share)

**Estimated Completion Date:** April 2018

#### City of Las Vegas

##### Centennial Parkway Channel West – CC 215, Pioneer Way to US95 ▲

This project consists of approximately 3,260 feet of 32-foot wide by 10-foot high reinforced concrete box culvert and 235 feet of 32-foot wide by 8-foot deep rectangular channel.

**Estimated Construction Cost:** \$13.4 million (RFCD share)

**Estimated Completion Date:** November 2016

##### Freeway Channel – Washington, MLK to Rancho Drive

This project consists of approximately 5,200 feet of concrete box culvert varying in size up to 8 feet wide by 6 feet high.

**Estimated Construction Cost:** \$9 million (RFCD share)

**Estimated Completion Date:** September 2017



# P R O J E C T H I G H L I G H T S

## **Lexington Street Storm Drain Improvements**

This project consists of constructing a 36-inch diameter storm drain and drop inlets along Lexington Street.

**Estimated Construction Cost:** \$1 million (RFCD share)

**Estimated Completion Date:** April 2017

## **City of Henderson**

### **Pittman North Detention Basin and Outfall Phase 1 ▲**

This project consists of four barrel 24-foot wide by 8-foot high reinforced concrete box culvert crossing at Volunteer Road with a 1,500 foot long channel/levee collector.

**Estimated Construction Cost:** \$3.5 million (RFCD share)

**Estimated Completion Date:** January 2017

### **Center Street Storm Drain**

This project consists of approximately 3,800 feet of storm drain ranging in size from 72 inch diameter pipe to 10 foot by 4 foot concrete box culvert.

**Estimated Construction Cost:** \$9 million (RFCD share)

**Estimated Completion Date:** May 2017

### **Pittman North Detention Basin and Outfall Phase II – Starr Avenue**

This project consists of approximately 1,100 feet of double concrete box culvert 8 feet wide by 8 feet high.

**Estimated Construction Cost:** \$1.4 million (RFCD Share)

**Estimated Completion Date:** June 2017

### **Pittman, West Horizon – Palm Hills**

This project consists of 1,600 feet of reinforced concrete box culvert ranging in size from 8 feet by 6 feet to 10 feet by 6 feet.

**Estimated Construction Cost:** \$1.8 million

**Estimated Completion Date:** January 2017

### **Racetrack Channel, Drake to Burkholder ▲**

This project consists of lining an existing 20 foot wide earthen bottom rectangular channel, approximately 2,500 feet in length.

**Estimated Construction Cost:** \$821,000 (RFCD share)

**Estimated Completion Date:** December 2016

## **City of North Las Vegas**

### **Las Vegas Wash- N Channel, Cheyenne to Gowan Road ▲**

This project consists of approximately 2,600 feet of concrete channel between Gowan Road and Cheyenne Avenue.

**Estimated Construction Cost:** \$2.8 million

**Estimated Completion Date:** January 2017

### **Ann Road Channel East-ULVW to Fifth Street**

This project consists of approximately 4,300 feet of 8 feet wide by 7 feet high of reinforced concrete box culvert.

**Estimated Construction Cost:** \$5.3 million (RFCD share)

**Estimated Completion Date:** May 2017