05-09-0577R

Request for a Conditional Letter of Map Revision
Sloan Channel Improvements
Charleston Boulevard to Las Vegas Wash
Clark County, Nevada



Prepared for

CLARK COUNTY
REGIONAL FLOOD CONTROL DISTRICT

Clark County Regional Flood Control District
600 S. Grand Central Parkway
Las Vegas, NV 89155

Prepared by

PBS&J

2270 Corporate Circle, Suite 100
Henderson, NV 89074
(702) 263-7275

January 2005

TABLE OF CONTENTS

Description	Page
Introduction	1
Hydrology	2
Hydraulics	3
Results	4
Photo Log	5
Conclusion	7
References	8

APPENDICES

Appendix A — FEMA Forms

-FEMA 'Overview and Concurrence Form'-MT-2 Form 1
-FEMA 'Riverine Hydrology & Hydraulics Form'- MT-2 Form 2
-FEMA 'Hydraulic Structures Form'-MT-2 Form 3
-Statement of Explanations

Appendix B — Figures

-Figure 1 Vicinity Map
-Figure 2 CCRFCD Flood Control Facilities Map
-Figure 2A CCRFCD Flood Control Facilities Inventory
-Figure 3 FEMA Flood Zone Map
-Figure 4 FEMA Annotated Flood Zone Map
-Figure 5 HEC-RAS Work map
-Figure 6 Proposed Flood Zone Delineation Map

Appendix C — Hydrology

-1996 Range Wash Flood Insurance Restudy by PBS&J

Appendix D — Hydraulic Models

-Revised/Post-Project Conditions HEC-RAS (post.prj)

Appendix E — Plans

-Sloan Channel Improvement Plans by G.C. Wallace

Appendix F — Reference Material

-1996 Range Wash Flood Insurance Restudy Technical Support Data by PBS&J

Appendix G — Data CD

-Electronic Hydraulic Models
-Figures

INTRODUCTION

This request for a Conditional Letter of Map Revision (CLOMR) is to address a proposed construction project consisting of channel improvements to a portion of the Sloan Channel immediately downstream of Charleston Boulevard to its confluence with the Las Vegas Wash. The existing channel is currently located within a FEMA Flood Zone A from Charleston Boulevard to the Las Vegas Wash; please refer to **Figure 3** for the FEMA Flood Zone Map. The existing channel in the project reach is earthen with irregular erosion protection on both banks. Immediately upstream of the proposed channel improvements is the Charleston Boulevard Bridge (3 span). The Sloan Channel upstream of Charleston Boulevard is fully improved consisting of a 60' wide concrete channel, 5' deep, and 2:1 side slopes. The proposed improvements consist of approximately 7,000 feet of concrete lining of the channel bottom and sides for the entire length of the project reach. Please refer to **Figure 1 Area/Vicinity Map** for an overall view of the project area. Also, refer to **Figure 2** and **Figure 2A CCRFCD Flood Control Facilities Map** that shows existing and proposed facilities within and adjacent to the project area. Appendix E includes the improvement plans for the proposed Sloan Channel.

This study analyzes the proposed Sloan Channel improvements from Charleston Boulevard to the Las Vegas Wash and demonstrates that the proposed conditions no longer warrant the flood zone delineation as shown on the current effective FIRM Panel 2195 dated September 27, 2002.

HYDROLOGY

The regulatory discharge in the channel for the 100-year storm is 3,072 cfs at the upstream limits of the study (NODE.V4) and 3,990 cfs at the downstream limits of this study (NODE.CC). The hydrology is reported in the 1996 Flood Insurance Restudy for the Range Wash prepared by PBS&J for the Clark County Regional Flood Control District (CCRFCD) and processed by FEMA under Case No. 98-09-1054P. The corresponding hydrologic reference material and the stream node diagram has been provided in Appendix C.

It should be noted that the HGL shown on the improvement plans is based on the channel 100-year design flow of 4,200 cfs. This represents ultimate build-out condition in which the tributary watershed to the Sloan Channel is fully developed. However, the analysis of the proposed channel improvements uses the regulatory flows from 3,072 cfs to 3,990 cfs, please refer to Appendix D for flow change locations.

HYDRAULICS

Hydraulic modeling of the proposed Sloan Channel improvements was performed using the U.S. Army Corp of Engineers' River Analysis System (HEC-RAS), version 3.1.1 and conforming to local standards that are specified in the CCRFCD Hydrologic Criteria and Drainage Design Manual. The post-project conditions model for this study is based on the proposed improvement plans prepared by G.C. Wallace, see Appendix E.

Note that the hydraulic model does not include the Charleston Boulevard bridge or any portion of the improved channel upstream of Charleston Boulevard. The hydraulic model will account for the proposed improvements only which start immediately downstream of Charleston Boulevard.

SLOAN CHANNEL RESULTS

The post-project conditions model for the study reach was modeled with HEC-RAS using the mixed flow option. The upstream boundary condition for the model was set at critical depth. The downstream boundary condition for the model is the approved water surface elevation of 1694.20 feet (approximately 200' upstream of FIS Section ZO) from the effective FIRM Panel 2195. This is the effective WSEL in the Las Vegas Wash at the confluence with the Sloan Channel. The results show that the supercritical flow is contained within the channel throughout the project reach. However, the model does show that a hydraulic jump occurs between cross-sections 140 and 90. This is caused by the confluence of the Orchards Channel with the Sloan Channel where an additional 1,021 cfs is introduced to the system. The hydraulic jump results in a peak WSEL of 1709.27' at cross-section 110 with a corresponding depth of 6.37'. The rectangular portion of the concrete channel in the vicinity of the Orchards confluence is approximately 8' deep. Also note that the energy grade elevation of 1710.10 would also be contained within the channel at station 110.


The upstream limit of the post-project conditions model results in a water surface elevation of 1724.40 feet at cross-section 210. The downstream end of the post-project conditions model results in a water surface elevation of 1694.20 feet at cross-section 10.

Figure 5 is the workmap for this study and shows the locations of the cross sections modeled in the post-project conditions. The revised Zone A boundaries and the upstream and downstream limits of this study are shown on the workmap. Please refer to **Figure 6** that shows the proposed post-project flood zone delineation.

PHOTO LOG



View of Sloan Channel Looking South (Downstream) from Charleston Boulevard



View of Sloan Channel Looking North (Upstream) from Charleston Boulevard



View of Sloan Channel Looking South (Downstream) from Sahara Avenue



View of Sloan Channel Looking North (Upstream) from Sahara Avenue

CONCLUSION

The proposed flood zone revision for the proposed Sloan Channel improvements is based on the best available data, approved improvement plans, and supporting calculations. We believe that based on this information the revisions to the Sloan Channel are acceptable. Please refer to **Figure 3 FEMA Flood Zone Map** and **Figure 4 Annotated FEMA Flood Zone Map**. **Figure 6** shows the proposed revisions to the current effective flood zone delineation.

Once approved and upon completion of the proposed channel improvements to the Sloan Channel, a request for a LOMR will be submitted with the appropriate supporting information to request revision of the current Zone A flood zone.

REFERENCES

HCDDM — Clark County Regional Flood Control District, *Hydrologic Criteria and Drainage Design Manual*, 1999.

2002 MPU — Clark County Regional Flood Control District, *2002 Master Plan Update*. Prepared by PBS&J, Louis Berger and G.C. Wallace.

HEC-RAS — U.S. Army Corps of Engineers' River Analysis System (HEC-RAS) V3.1.1, Hydrologic Engineering Center, 2002.

G.C. Wallace — GCW. *Improvement Plans for Sloan Channel.* Prepared by G.C. Wallace, dated March 2004.

PBSJ — PBS&J *1996 FIS Restudy for The Range Wash.* Prepared by PBS&J, dated February 1996.

Appendix A: FEMA Forms

C. REVIEW FEE

Has the review fee for the appropriate request category been included? ☐ Yes Fee amount: $_____

☒ No, Attach Explanation

Please see the FEMA Web site at http://www.fema.gov/fhm/frm_fees.shtm **for Fee Amounts and Exemptions.**

D. SIGNATURE

All documents submitted in support of this request are correct to the best of my knowledge. I understand that any false statement may be punishable by fine or imprisonment under Title 18 of the United States Code, Section 1001.

Name: Brian K. Loffman	Company: PBS&J	
Mailing Address: 2270 Corporate Circle Drive Suite 100 Henderson, NV 89074-7755	Daytime Telephone No.: 702-263-7275	Fax No.: 702-263-7200
	E-Mail Address: bloffman@pbsj.com	
Signature of Requester (required):		Date: 12/21/04

As the community official responsible for floodplain management, I hereby acknowledge that we have received and reviewed this Letter of Map Revision (LOMR) or conditional LOMR request. Based upon the community's review, we find the completed or proposed project meets or is designed to meet all of the community floodplain management requirements, including the requirement that no fill be placed in the regulatory floodway, and that all necessary Federal, State, and local permits have been, or in the case of a conditional LOMR, will be obtained. In addition, we have determined that the land and any existing or proposed structures to be removed from the SFHA are or will be reasonably safe from flooding as defined in 44CFR 65.2(c), and that we have available upon request by FEMA, all analyses and documentation used to make this determination.

Community Official's Name and Title: David Betley, P.E., Principal Engineer, Civil Engineering Division		Telephone No.: (702) 455-6108
Community Name: Clark County Unincorporated Areas	Community Official's Signature (required):	Date: 2/4/05


CERTIFICATION BY REGISTERED PROFESSIONAL ENGINEER AND/OR LAND SURVEYOR

This certification is to be signed and sealed by a licensed land surveyor, registered professional engineer, or architect authorized by law to certify elevation information. All documents submitted in support of this request are correct to the best of my knowledge. I understand that any false statement may be punishable by fine or imprisonment under Title 18 of the United States Code, Section 1001.

Certifier's Name: Mathew S. Baird	License No.: NV 13684	Expiration Date: 12/31/04
Company Name: PBS&J	Telephone No.: 702-263-7275	Fax No.: 702-263-7200
Signature: Matthew S. Baird		Date: 12/21/04

Ensure the forms that are appropriate to your revision request are included in your submittal.

Form Name and (Number)	Required if ...
☒ Riverine Hydrology and Hydraulics Form (Form 2)	New or revised discharges or water-surface elevations
☒ Riverine Structures Form (Form 3)	Channel is modified, addition/revision of bridge/culverts, addition/revision of levee/floodwall, addition/revision of dam
☐ Coastal Analysis Form (Form 4)	New or revised coastal elevations
☐ Coastal Structures Form (Form 5)	Addition/revision of coastal structure
☐ Alluvial Fan Flooding Form (Form 6)	Flood control measures on alluvial fans



C. REVIEW FEE

Has the review fee for the appropriate request category been included? ☐ Yes Fee amount: $_____

☒ No, Attach Explanation

Please see the FEMA Web site at http://www.fema.gov/fhm/frm_fees.shtm **for Fee Amounts and Exemptions.**

D. SIGNATURE

All documents submitted in support of this request are correct to the best of my knowledge. I understand that any false statement may be punishable by fine or imprisonment under Title 18 of the United States Code, Section 1001.

Name: Brian K. Loffman	Company: PBS&J	
Mailing Address: 2270 Corporate Circle Drive Suite 100 Henderson, NV 89074-7755	Daytime Telephone No.: 702-263-7275	Fax No.: 702-263-7200
	E-Mail Address: bloffman@pbsj.com	
Signature of Requester (required):		Date: 12/21/04

As the community official responsible for floodplain management, I hereby acknowledge that we have received and reviewed this Letter of Map Revision (LOMR) or conditional LOMR request. Based upon the community's review, we find the completed or proposed project meets or is designed to meet all of the community floodplain management requirements, including the requirement that no fill be placed in the regulatory floodway, and that all necessary Federal, State, and local permits have been, or in the case of a conditional LOMR, will be obtained. In addition, we have determined that the land and any existing or proposed structures to be removed from the SFHA are or will be reasonably safe from flooding as defined in 44CFR 65.2(c), and that we have available upon request by FEMA, all analyses and documentation used to make this determination.

Community Official's Name and Title: David Betley, P.E., Principal Engineer, Civil Engineering Division		Telephone No.:
Community Name: Clark County Unincorporated Areas	Community Official's Signature (required):	Date:


CERTIFICATION BY REGISTERED PROFESSIONAL ENGINEER AND/OR LAND SURVEYOR

This certification is to be signed and sealed by a licensed land surveyor, registered professional engineer, or architect authorized by law to certify elevation information. All documents submitted in support of this request are correct to the best of my knowledge. I understand that any false statement may be punishable by fine or imprisonment under Title 18 of the United States Code, Section 1001.

Certifier's Name: Mathew S. Baird	License No.: NV 13684	Expiration Date: 12/31/04
Company Name: PBS&J	Telephone No.: 702-263-7275	Fax No.: 702-263-7200
Signature: Matthew S. Baird		Date: 12/21/04

Ensure the forms that are appropriate to your revision request are included in your submittal.

Form Name and (Number)	Required if ...
☒ Riverine Hydrology and Hydraulics Form (Form 2)	New or revised discharges or water-surface elevations
☒ Riverine Structures Form (Form 3)	Channel is modified, addition/revision of bridge/culverts, addition/revision of levee/floodwall, addition/revision of dam
☐ Coastal Analysis Form (Form 4)	New or revised coastal elevations
☐ Coastal Structures Form (Form 5)	Addition/revision of coastal structure
☐ Alluvial Fan Flooding Form (Form 6)	Flood control measures on alluvial fans



FEDERAL EMERGENCY MANAGEMENT AGENCY

RIVERINE HYDROLOGY & HYDRAULICS FORM

O.M.B No. 3067-0148
Expires September 30, 2005

PAPERWORK REDUCTION ACT

Public reporting burden for this form is estimated to average 3 hours per response. The burden estimate includes the time for reviewing instructions, searching existing data sources, gathering and maintaining the needed data, and completing, reviewing, and submitting the form. You are not required to respond to this collection of information unless a valid OMB control number appears in the upper right corner of this form. Send comments regarding the accuracy of the burden estimate and any suggestions for reducing this burden to: Information Collections Management, Federal Emergency Management Agency, 500 C Street, SW, Washington DC 20472, Paperwork Reduction Project (3067-0148). Submission of the form is required to obtain or retain benefits under the National Flood Insurance Program. **Please do not send your completed survey to the above address.**

Flooding Source: Range Wash
Note: Fill out one form for each flooding source studied

A. HYDROLOGY

1. Reason for New Hydrologic Analysis (check all that apply)

☒ Not revised (skip to section 2) ☐ No existing analysis ☐ Improved data
☐ Alternative methodology ☐ Proposed Conditions (CLOMR) ☐ Changed physical condition of watershed

2. Comparison of Representative 1%-Annual-Chance Discharges

Location	Drainage Area (Sq. Mi.)	FIS (cfs)	Revised (cfs)

3. Methodology for New Hydrologic Analysis (check all that apply)

☐ Statistical Analysis of Gage Records ☐ Precipitation/Runoff Model [TR-20, HEC-1, HEC-HMS etc.]
☐ Regional Regression Equations ☐ Other (please attach description)

Please enclose all relevant models in digital format, maps, computations (including computation of parameters) and documentation to support the new analysis. The document, "Numerical Models Accepted by FEMA for NFIP Usage" lists the models accepted by FEMA. This document can be found at: http://www.fema.gov/fhm/en_modl.shtm.

4. Review/Approval of Analysis

If your community requires a regional, state, or federal agency to review the hydrologic analysis, please attach evidence of approval/review.

5. Impacts of Sediment Transport on Hydrology

Was sediment transport considered? ☐ Yes ☒ No If yes, then fill out Section F (Sediment Transport) of Form 3. If No, then attach your explanation for why sediment transport was not considered.

B. HYDRAULICS

1. Reach to be Revised

	Description	Cross Section	Water-Surface Elevations (ft.)	
			Effective	Proposed/Revised
Downstream Limit	FEMA Tie-In w/Las Vegas Wash	10	1694.20	1694.20
Upstream Limit	Charleston Bridge	210	N/A	1724.58

2. Hydraulic Method Used

Hydraulic Analysis HEC-RAS V3.11 [HEC-2 , HEC-RAS, Other (Attach description)]

B. HYDRAULICS (CONTINUED)

3. Pre-Submittal Review of Hydraulic Models

FEMA has developed two review programs, CHECK-2 and CHECK-RAS, to aid in the review of HEC-2 and HEC-RAS hydraulic models, respectively. These review programs verify that the hydraulic estimates and assumptions in the model data are in accordance with NFIP requirements, and that the data are comparable with the assumptions and limitations of HEC-2/HEC-RAS. CHECK-2 and CHECK-RAS identify areas of potential error or concern. These tools do not replace engineering judgment. CHECK-2 and CHECK-RAS can be downloaded from http://www.fema.gov/fhm/frm_soft.shtm. We recommend that you review your HEC-2 and HEC-RAS models with CHECK-2 and CHECK-RAS. If you disagree with a message, please attach an explanation of why the message is not valid in this case. Review of your submittal and resolution of valid modeling discrepancies will result in reduced review time.

HEC-2/HEC-RAS models reviewed with CHECK-2/CHECK-RAS? ☐ Yes ☒ No

4. Models Submitted

Duplicate Effective Model*	Natural File Name: N/A	Floodway File Name: N/A
Corrected Effective Model*	Natural File Name: N/A	Floodway File Name: N/A
Existing or Pre-Project Conditions Model	Natural File Name: N/A	Floodway File Name: N/A
Revised or Post-Project Conditions Model	Natural File Name: post.prj	Floodway File Name: N/A
Other - (attach description)	Natural File Name:	Floodway File Name:

*Not required for revisions to approximate 1%-annual-chance floodplains (Zone A) – for details, refer to the corresponding section of the instructions.

The document "Numerical Models Accepted by FEMA for NFIP Usage" lists the models accepted by FEMA. This document can be found at: http://www.fema.gov/fhm/en_modl.shtm.

C. MAPPING REQUIREMENTS

A **certified topographic map** must be submitted showing the following information (where applicable): the boundaries of the effective, existing, and proposed conditions 1%-annual-chance floodplain (for approximate Zone A revisions) or the boundaries of the 1%- and 0.2%-annual-chance floodplains and regulatory floodway (for detailed Zone AE, AO, and AH revisions); location and alignment of all cross sections with stationing control indicated; stream, road, and other alignments (e.g., dams, levees, etc.); current community easements and boundaries; boundaries of the requester's property; certification of a registered professional engineer registered in the subject State; location and description of reference marks; and the referenced vertical datum (NGVD, NAVD, etc.).

Note that the boundaries of the existing or proposed conditions floodplains and regulatory floodway to be shown on the revised FIRM and/or FBFM must tie-in with the effective floodplain and regulatory floodway boundaries. Please attach **a copy of the effective FIRM and/or FBFM,** annotated to show the boundaries of the revised 1%- and 0.2%-annual-chance floodplains and regulatory floodway that tie-in with the boundaries of the effective 1%- and 0.2%-annual-chance floodplain and regulatory floodway at the upstream and downstream limits of the area of revision.

D. COMMON REGULATORY REQUIREMENTS

1. For CLOMR requests, do Base Flood Elevations (BFEs) increase? ☐ Yes ☒ No

For CLOMR requests, if either of the following is true, please submit evidence of compliance with Section 65.12 of the NFIP regulations:
- The proposed project encroaches upon a regulatory floodway and would result in increases above 0.00 foot.
- The proposed project encroaches upon a SFHA with BFEs established and would result in increases above 1.00 foot.

2. Does the request involve the placement or proposed placement of fill? ☐ Yes ☒ No

If Yes, the community must be able to certify that the area to be removed from the special flood hazard area, to include any structures or proposed structures, meets all of the standards of the local floodplain ordinances, and is reasonably safe from flooding in accordance with the NFIP regulations set forth at 44 CFR 60.3(a)(3), 65.5(a)(4), and 65.6(a)(14). Please see the MT-2 instructions for more information.

3. For LOMR requests, is the regulatory floodway being revised? ☐ Yes ☐ No

If Yes, attach evidence of regulatory floodway revision notification. As per Paragraph 65.7(b)(1) of the NFIP Regulations, notification is required for requests involving revisions to the regulatory floodway. (Not required for revisions to approximate 1%-annual-chance floodplains [studied Zone A designation] unless a regulatory floodway is being added. Elements and examples of regulatory floodway revision notification can be found in the MT-2 Form 2 Instructions.)

4. For LOMR requests, does this request require property owner notification and acceptance of BFE increases? ☐ Yes ☐ No

If Yes, please attach proof of property owner notification and acceptance (if available). Elements of and examples of property owner notification can be found in the MT-2 Form 2 Instructions.

FEDERAL EMERGENCY MANAGEMENT AGENCY

RIVERINE STRUCTURES FORM

O.M.B. No. 3067-0148
Expires September 30, 2005

PAPERWORK REDUCTION ACT

Public reporting burden for this form is estimated to average 7 hours per response. The burden estimate includes the time for reviewing instructions, searching existing data sources, gathering and maintaining the needed data, and completing, reviewing, and submitting the form. You are not required to respond to this collection of information unless a valid OMB control number appears in the upper right corner of this form. Send comments regarding the accuracy of the burden estimate and any suggestions for reducing this burden to: Information Collections Management, Federal Emergency Management Agency, 500 C Street, SW, Washington DC 20472, Paperwork Reduction Project (3067-0148). Submission of the form is required to obtain or retain benefits under the National Flood Insurance Program. **Please do not send your completed survey to the above address.**

Flooding Source: Range Wash
Note: Fill out one form for each flooding source studied

A. GENERAL

Complete the appropriate section(s) for each Structure listed below:

Channelization ..... complete Section B
Bridge/Culvert ..... complete Section C
Dam ..... complete Section D
Levee/Floodwall ..... complete Section E
Sediment Transport ..... complete Section F (if required)

Description Of Structure

1. Name of Structure: Sloan Channel Improvements-Charleston Bl to Las Vegas Wash

Type (check one): ☒ Channelization ☐ Bridge/Culvert ☐ Levee/Floodwall ☐ Dam

Location of Structure: Range Wash

Downstream Limit/Cross Section: 20

Upstream Limit/Cross Section: 210

2. Name of Structure: Sahara Avenue Bridge

Type (check one): ☐ Channelization ☒ Bridge/Culvert ☐ Levee/Floodwall ☐ Dam

Location of Structure: Sahara Avenue at Sloan Channel

Downstream Limit/Cross Section: 40

Upstream Limit/Cross Section: 60

3. Name of Structure:

Type (check one) ☐ Channelization ☐ Bridge/Culvert ☐ Levee/Floodwall ☐ Dam

Location of Structure:

Downstream Limit/Cross Section:

Upstream Limit/Cross Section:

NOTE: For more structures, attach additional pages as needed.

B. CHANNELIZATION

Flooding Source: Range Wash

Name of Structure: Sloan Channel

1. Accessory Structures

The channelization includes (check one):

- ☐ Levees [Attach Section E (Levee/Floodwall)]
- ☐ Superelevated sections
- ☐ Debris basin/detention basin
- ☐ Other (Describe):
- ☐ Drop structures
- ☒ Transitions in cross sectional geometry
- ☐ Energy dissipator

2. Drawing Checklist

Attach the plans of the channelization certified by a registered professional engineer, as described in the instructions.

3. Hydraulic Considerations

The channel was designed to carry 4200 (cfs) and/or the 100-year flood.

The design elevation in the channel is based on (check one):

☐ Subcritical flow ☐ Critical flow ☒ Supercritical flow ☐ Energy grade line

If there is the potential for a hydraulic jump at the following locations, check all that apply and attach an explanation of how the hydraulic jump is controlled without affecting the stability of the channel.

☐ Inlet to channel ☐ Outlet of channel ☐ At Drop Structures ☐ At Transitions
☒ Other locations (specify): At the confluence with the Orchards Channel (XS 100)

4. Sediment Transport Considerations

Was sediment transport considered? ☐ Yes ☒ No If Yes, then fill out Section F (Sediment Transport).
If No, then attach your explanation for why sediment transport was not considered.

C. BRIDGE/CULVERT

Flooding Source: Range Wash

Name of Structure: Sahara Ave. Bridge

1. This revision reflects (check one):

- ☐ New bridge/culvert not modeled in the FIS
- ☐ Modified bridge/culvert previously modeled in the FIS
- ☒ New analysis of bridge/culvert previously modeled in the FIS

2. Hydraulic model used to analyze the structure (e.g., HEC-2 with special bridge routine, WSPRO, HY8): HEC-RAS V3.11
If different than hydraulic analysis for the flooding source, justify why the hydraulic analysis used for the flooding source could not analyze the structures. Attach justification.

3. Attach plans of the structures certified by a registered professional engineer. The plan detail and information should include the following (check the information that has been provided):

- ☒ Dimensions (height, width, span, radius, length)
- ☐ Shape (culverts only)
- ☐ Material
- ☐ Beveling or Rounding
- ☐ Wing Wall Angle
- ☐ Skew Angle
- ☒ Distances Between Cross Sections
- ☐ Erosion Protection
- ☒ Low Chord Elevations – Upstream and Downstream
- ☒ Top of Road Elevations – Upstream and Downstream
- ☐ Structure Invert Elevations – Upstream and Downstream
- ☐ Stream Invert Elevations – Upstream and Downstream
- ☒ Cross-Section Locations

4. Sediment Transport Considerations

Was sediment transport considered? ☐ Yes ☒ No If yes, then fill out Section F (Sediment Transport).
If No, then attach your explanation for why sediment transport was not considered.

D. DAM

Flooding Source:

Name of Structure:

1. This request is for (check one): ☐ Existing dam ☐ New dam ☐ Modification of existing dam

2. The dam was designed by (check one): ☐ Federal agency ☐ State agency ☐ Local government agency

   ☐ Private organization Name of the agency or organization:

3. Does the project involve revised hydrology? ☐ Yes ☐ No

   If Yes, complete the Riverine Hydrology & Hydraulics Form (Form 2).

4. Does the submittal include debris/sediment yield analysis? ☐ Yes ☐ No

   If yes, then fill out Section F (Sediment Transport).
   If No, then attach your explanation for why debris/sediment analysis was not considered.

5. Does the Base Flood Elevation behind the dam or downstream of the dam change?

   ☐ Yes ☐ No If Yes, complete the Riverine Hydrology & Hydraulics Form (Form 2) and complete the table below.

Stillwater Elevation Behind the Dam

FREQUENCY (% annual chance)	FIS	REVISED
10-year (10%)		
50-year (2%)		
100-year (1%)		
500-year (0.2%)		
Normal Pool Elevation		

6. Please attach a copy of the formal Operation and Maintenance Plan

E. LEVEE/FLOODWALL

1. System Elements

a. This Levee/Floodwall analysis is based on (check one):

☐ upgrading of an existing levee/floodwall system
☐ a newly constructed levee/floodwall system
☐ reanalysis of an existing levee/floodwall system

b. Levee elements and locations are (check one):

☐ earthen embankment, dike, berm, etc.	Station	to
☐ structural floodwall	Station	to
☐ Other (describe):	Station	to

c. Structural Type (check one):

☐ monolithic cast-in place reinforced concrete
☐ reinforced concrete masonry block
☐ sheet piling
☐ Other (describe):

d. Has this levee/floodwall system been certified by a Federal agency to provide protection from the base flood?

☐ Yes ☐ No

If Yes, by which agency?

e. Attach certified drawings containing the following information (indicate drawing sheet numbers):

1. Plan of the levee embankment and floodwall structures. Sheet Numbers:
2. A profile of the levee/floodwall system showing the Base Flood Elevation (BFE), levee and/or wall crest and foundation, and closure locations for the total levee system. Sheet Numbers:
3. A profile of the BFE, closure opening outlet and inlet invert elevations, type and size of opening, and kind of closure. Sheet Numbers:
4. A layout detail for the embankment protection measures. Sheet Numbers:
5. Location, layout, and size and shape of the levee embankment features, foundation treatment, floodwall structure, closure structures, and pump stations. Sheet Numbers:

2. Freeboard

a. The minimum freeboard provided above the BFE is:

Riverine

3.0 feet or more at the downstream end and throughout	☐ Yes	☐ No
3.5 feet or more at the upstream end	☐ Yes	☐ No
4.0 feet within 100 feet upstream of all structures and/or constrictions	☐ Yes	☐ No

Coastal

1.0 foot above the height of the one percent wave associated with the 1%-annual-chance stillwater surge elevation or maximum wave runup (whichever is greater).	☐ Yes	☐ No
2.0 feet above the 1%-annual-chance stillwater surge elevation	☐ Yes	☐ No

E. LEVEE/FLOODWALL (CONTINUED)

2. Freeboard (continued)

Please note, occasionally exceptions are made to the minimum freeboard requirement. If an exception is requested, attach documentation addressing Paragraph 65.10(b)(1)(ii) of the NFIP Regulations.

If No is answered to any of the above, please attach an explanation.

b. Is there an indication from historical records that ice-jamming can affect the BFE? ☐ Yes ☐ No

If Yes, provide ice-jam analysis profile and evidence that the minimum freeboard discussed above still exists.

3. Closures

a. Openings through the levee system (check one): ☐ exists ☐ does not exist

If opening exists, list all closures:

Channel Station	Left or Right Bank	Opening Type	Highest Elevation for Opening Invert	Type of Closure Device

(Extend table on an added sheet as needed and reference)

Note: Geotechnical and geologic data

In addition to the required detailed analysis reports, data obtained during field and laboratory investigations and used in the design analysis for the following system features should be submitted in a tabulated summary form. (Reference U.S. Army Corps of Engineers [USACE] EM-1110-2-1906 Form 2086.)

4. Embankment Protection

a. The maximum levee slope landside is:

b. The maximum levee slope floodside is:

c. The range of velocities along the levee during the base flood is: (min.) to (max.)

d. Embankment material is protected by (describe what kind):

e. Riprap Design Parameters (check one): ☐ Velocity ☐ Tractive stress
Attach references

Reach	Sideslope	Flow Depth	Velocity	Curve or Straight	Stone Riprap			Depth of Toedown
					D_{100}	D_{50}	Thickness	
Sta to								
Sta to								
Sta to								
Sta to								
Sta to								
Sta to								

(Extend table on an added sheet as needed and reference each entry)

4. Embankment Protection (continued)

f. Is a bedding/filter analysis and design attached? ☐ Yes ☐ No

g. Describe the analysis used for other kinds of protection used (include copies of the design analysis):

Attach engineering analysis to support construction plans.

5. Embankment And Foundation Stability

a. Identify locations and describe the basis for selection of critical location for analysis:

☐ Overall height: Sta. ; height ft.

☐ Limiting foundation soil strength:

Sta. , depth to

strength ϕ = degrees, c = psf

slope: SS = (h) to (v)

(Repeat as needed on an added sheet for additional locations)

b. Specify the embankment stability analysis methodology used (e.g., circular arc, sliding block, infinite slope, etc.):

c. Summary of stability analysis results:

Case	Loading Conditions	Critical Safety Factor	Criteria (Min.)
I	End of construction		1.3
II	Sudden drawdown		1.0
III	Critical flood stage		1.4
IV	Steady seepage at flood stage		1.4
VI	Earthquake (Case I)		1.0
(Reference: USACE EM-1110-2-1913 Table 6-1)			

d. Was a seepage analysis for the embankment performed? ☐ Yes ☐ No

If Yes, describe methodology used:

e. Was a seepage analysis for the foundation performed? ☐ Yes ☐ No

f. Were uplift pressures at the embankment landside toe checked? ☐ Yes ☐ No

g. Were seepage exit gradients checked for piping potential? ☐ Yes ☐ No

h. The duration of the base flood hydrograph against the embankment is hours.

Attach engineering analysis to support construction plans.

E. LEVEE/FLOODWALL (CONTINUED)

6. Floodwall And Foundation Stability

a. Describe analysis submittal based on Code (check one):

☐ UBC (1988) or ☐ Other (specify):

b. Stability analysis submitted provides for:

☐ Overturning ☐ Sliding If not, explain:

c. Loading included in the analyses were:

☐ Lateral earth @ P_A = psf; P_p = psf

☐ Surcharge-Slope @ , ☐ surface psf

☐ Wind @ P_w = psf

☐ Seepage (Uplift); ☐ Earthquake @ P_{eq} = %g

☐ 1%-annual-chance significant wave height: ft.

☐ 1%-annual-chance significant wave period: sec.

d. Summary of Stability Analysis Results: Factors of Safety.

Itemize for each range in site layout dimension and loading condition limitation for each respective reach.

Loading Condition	Criteria (Min)		Sta	To	Sta	To
	Overturn	Sliding	Overturn	Sliding	Overturn	Sliding
Dead & Wind	1.5	1.5				
Dead & Soil	1.5	1.5				
Dead, Soil, Flood, & Impact	1.5	1.5				
Dead, Soil, & Seismic	1.3	1.3				

(Ref: FEMA 114 Sept 1986; USACE EM 1110-2-2502)

(Note: Extend table on an added sheet as needed and reference)

e. Foundation bearing strength for each soil type:

Bearing Pressure	Sustained Load (psf)	Short Term Load (psf)
Computed design maximum		
Maximum allowable		

f. Foundation scour protection ☐ is, ☐ is not provided. If provided, attach explanation and supporting documentation:

Attach engineering analysis to support construction plans.

E. LEVEE/FLOODWALL (CONTINUED)

7. Settlement

a. Has anticipated potential settlement been determined and incorporated into the specified construction elevations to maintain the established freeboard margin? ☐ Yes ☐ No

b. The computed range of settlement is ft. to ft.

c. Settlement of the levee crest is determined to be primarily from :

☐ Foundation consolidation
☐ Embankment compression
☐ Other (Describe):

d. Differential settlement of floodwalls ☐ has ☐ has not been accommodated in the structural design and construction.

Attach engineering analysis to support construction plans.

8. Interior Drainage

a. Specify size of each interior watershed:

Draining to pressure conduit: acres
Draining to ponding area: acres

b. Relationships Established

Ponding elevation vs. storage	☐ Yes	☐ No
Ponding elevation vs. gravity flow	☐ Yes	☐ No
Differential head vs. gravity flow	☐ Yes	☐ No

c. The river flow duration curve is enclosed: ☐ Yes ☐ No

d. Specify the discharge capacity of the head pressure conduit: cfs

e. Which flooding conditions were analyzed?

• Gravity flow (Interior Watershed)	☐ Yes	☐ No
• Common storm (River Watershed)	☐ Yes	☐ No
• Historical ponding probability	☐ Yes	☐ No
• Coastal wave overtopping	☐ Yes	☐ No

If No for any of the above, attach explanation.

f. Interior drainage has been analyzed based on joint probability of interior and exterior flooding and the capacities of pumping and outlet facilities to provide the established level of flood protection. ☐ Yes ☐ No

If No, attach explanation.

g. The rate of seepage through the levee system for the base flood is cfs

h. The length of levee system used to drive this seepage rate in item g: ft.

E. LEVEE/FLOODWALL (CONTINUED)

8. Interior Drainage (continued)

i. Will pumping plants be used for interior drainage? ☐ Yes ☐ No

If Yes, include the number of pumping plants:
For each pumping plant, list:

	Plant #1	Plant #2
The number of pumps		
The ponding storage capacity		
The maximum pumping rate		
The maximum pumping head		
The pumping starting elevation		
The pumping stopping elevation		
Is the discharge facility protected?		
Is there a flood warning plan?		
How much time is available between warning and flooding?		

Will the operation be automatic? ☐ Yes ☐ No

If the pumps are electric, are there backup power sources? ☐ Yes ☐ No

(Reference: USACE EM-1110-2-3101, 3102, 3103, 3104, and 3105)

Include a copy of supporting documentation of data and analysis. Provide a map showing the flooded area and maximum ponding elevations for all interior watersheds that result in flooding.

9. Other Design Criteria

a. The following items have been addressed as stated:

Liquefaction ☐ is ☐ is not a problem
Hydrocompaction ☐ is ☐ is not a problem
Heave differential movement due to soils of high shrink/swell ☐ is ☐ is not a problem

b. For each of these problems, state the basic facts and corrective action taken:

Attach supporting documentation

c. If the levee/floodwall is new or enlarged, will the structure adversely impact flood levels and/or flow velocities floodside of the structure?
☐ Yes ☐ No

Attach supporting documentation

d. Sediment Transport Considerations:

Was sediment transport considered? ☐ Yes ☐ No If Yes, then fill out Section F (Sediment Transport).
If No, then attach your explanation for why sediment transport was not considered.

E. LEVEE/FLOODWALL (CONTINUED)

10. Operational Plan And Criteria

    a. Are the planned/installed works in full compliance with Part 65.10 of the NFIP Regulations? ☐ Yes ☐ No

    b. Does the operation plan incorporate all the provisions for closure devices as required in Paragraph 65.10(c)(1) of the NFIP regulations? ☐ Yes ☐ No

    c. Does the operation plan incorporate all the provisions for interior drainage as required in Paragraph 65.10(c)(2) of the NFIP regulations? ☐ Yes ☐ No

    If the answer is No to any of the above, please attach supporting documentation.

11. Maintenance Plan

    a. Are the planned/installed works in full compliance with Part 65.10 of the NFIP Regulations? ☐ Yes ☐ No
    If No, please attach supporting documentation.

12. Operations and Maintenance Plan

    Please attach a copy of the formal Operations and Maintenance Plan for the levee/floodwall.

F. SEDIMENT TRANSPORT

Flooding Source:

Name of Structure:

If there is any indication from historical records that sediment transport (including scour and deposition) can affect the Base Flood Elevation (BFE); and/or based on the stream morphology, vegetative cover, development of the watershed and bank conditions, there is a potential for debris and sediment transport (including scour and deposition) to affect the BFEs, then provide the following information along with the supporting documentation:

Sediment load associated with the base flood discharge: Volume acre-feet

Debris load associated with the base flood discharge: Volume acre-feet

Sediment transport rate (percent concentration by volume)

Method used to estimate sediment transport:

Most sediment transport formulas are intended for a range of hydraulic conditions and sediment sizes; attach a detailed explanation for using the selected method.

Method used to estimate scour and/or deposition:

Method used to revise hydraulic or hydrologic analysis (model) to account for sediment transport:
Please note that bulked flows are used to evaluate the performance of a structure during the base flood; however, FEMA does not map BFEs based on bulked flows.

If a sediment analysis has not been performed, an explanation as to why sediment transport (including scour and deposition) will not affect the BFEs or structures must be provided.

STATEMENT OF EXPLANATIONS


- MT-2 FORM –1

  C: Clark County Regional Flood Control District will submit fee upon receiving an invoice from FEMA.

- MT-2 FORM-3

  B-4 & C-4: Sediment transport was not considered since the channel is lined and any sediment entering the system from upstream would be transported to the channel outlet at the Las Vegas Wash.

Appendix B: Figures



GRAPHIC SCALE

,000 500 0 1,000 2,000 3,000

(In Feet)

1 inch = 1,000 ft.


FIGURE 1: VICINITY MAP

Sloan Channel Improvements CLOMR

Proposed Channel Improvements Alignment

PBS&J
2270 Corporate Circle
Suite 100
Henderson, Nevada 89074
Tele: 702-263-7275
Fax: 702-263-7200
ENGINEERING - PLANNING - SURVEYING - CONSTRUCTION SERVICES

FIGURE 1



PROJECT LOCATION
LAKE MEAD BLVD
CHARLESTON BLVD
STEWART AVE
OAKEY BLVD
WYOMING AVE
KAREN AVE
SAHARA AVE
LAS VEGAS BLVD
LVMD 1476
LVMD 1119
LVMD 1069
LVMD 1045
LVMD 1061
LVMD 0948
LVMD 0825
LVMD 0827
LVMD 0823
LVMD 0829
LVMD 0833
LVMD 0835
LVMD 0837
LVMD 0839
LVMD 0841
LVMD 0843
LVMD 0845
LVMD 0847
LVMD 0849
LVMD 0851
LVMD 0853
LVMD 0855
LVMD 0857
LVMD 0859
LVMD 0861
LVMD 0863
LVMD 0865
LVMD 0867
LVMD 0869
LVMD 0871
LVMD 0873
LVMD 0875
LVMD 0877
LVMD 0879
LVMD 0881
LVMD 0883
LVMD 0885
LVMD 0887
LVMD 0889
LVMD 0891
LVMD 0893
LVMD 0895
LVMD 0897
LVMD 0899
LVMD 0901
LVMD 0903
LVMD 0905
LVMD 0907
LVMD 0909
LVMD 0911
LVMD 0913
LVMD 0915
LVMD 0917
LVMD 0919
LVMD 0921
LVMD 0923
LVMD 0925
LVMD 0927
LVMD 0929
LVMD 0931
LVMD 0933
LVMD 0935
LVMD 0937
LVMD 0939
LVMD 0941
LVMD 0943
LVMD 0945
LVMD 0947
LVMD 0949
LVMD 0951
LVMD 0953
LVMD 0955
LVMD 0957
LVMD 0959
LVMD 0961
LVMD 0963
LVMD 0965
LVMD 0967
LVMD 0969
LVMD 0971
LVMD 0973
LVMD 0975
LVMD 0977
LVMD 0979
LVMD 0981
LVMD 0983
LVMD 0985
LVMD 0987
LVMD 0989
LVMD 0991
LVMD 0993
LVMD 0995
LVMD 0997
LVMD 0999
LVMD 1001
LVMD 1003
LVMD 1005
LVMD 1007
LVMD 1009
LVMD 1011
LVMD 1013
LVMD 1015
LVMD 1017
LVMD 1019
LVMD 1021
LVMD 1023
LVMD 1025
LVMD 1027
LVMD 1029
LVMD 1031
LVMD 1033
LVMD 1035
LVMD 1037
LVMD 1039
LVMD 1041
LVMD 1043
LVMD 1047
LVMD 1049
LVMD 1051
LVMD 1053
LVMD 1055
LVMD 1057
LVMD 1059
LVMD 1063
LVMD 1065
LVMD 1067
LVMD 1071
LVMD 1073
LVMD 1075
LVMD 1077
LVMD 1079
LVMD 1081
LVMD 1083
LVMD 1085
LVMD 1087
LVMD 1089
LVMD 1091
LVMD 1093
LVMD 1095
LVMD 1097
LVMD 1099
LVMD 1101
LVMD 1103
LVMD 1105
LVMD 1107
LVMD 1109
LVMD 1111
LVMD 1113
LVMD 1115
LVMD 1117
LVMD 1121
LVMD 1123
LVMD 1125
LVMD 1127
LVMD 1129
LVMD 1131
LVMD 1133
LVMD 1135
LVMD 1137
LVMD 1139
LVMD 1141
LVMD 1143
LVMD 1145
LVMD 1147
LVMD 1149
LVMD 1151
LVMD 1153
LVMD 1155
LVMD 1157
LVMD 1159
LVMD 1161
LVMD 1163
LVMD 1165
LVMD 1167
LVMD 1169
LVMD 1171
LVMD 1173
LVMD 1175
LVMD 1177
LVMD 1179
LVMD 1181
LVMD 1183
LVMD 1185
LVMD 1187
LVMD 1189
LVMD 1191
LVMD 1193
LVMD 1195
LVMD 1197
LVMD 1199
LVMD 1201
LVMD 1203
LVMD 1205
LVMD 1207
LVMD 1209
LVMD 1211
LVMD 1213
LVMD 1215
LVMD 1217
LVMD 1219
LVMD 1221
LVMD 1223
LVMD 1225
LVMD 1227
LVMD 1229
LVMD 1231
LVMD 1233
LVMD 1235
LVMD 1237
LVMD 1239
LVMD 1241
LVMD 1243
LVMD 1245
LVMD 1247
LVMD 1249
LVMD 1251
LVMD 1253
LVMD 1255
LVMD 1257
LVMD 1259
LVMD 1261
LVMD 1263
LVMD 1265
LVMD 1267
LVMD 1269
LVMD 1271
LVMD 1273
LVMD 1275
LVMD 1277
LVMD 1279
LVMD 1281
LVMD 1283
LVMD 1285
LVMD 1287
LVMD 1289
LVMD 1291
LVMD 1293
LVMD 1295
LVMD 1297
LVMD 1299
LVMD 1301
LVMD 1303
LVMD 1305
LVMD 1307
LVMD 1309
LVMD 1311
LVMD 1313
LVMD 1315
LVMD 1317
LVMD 1319
LVMD 1321
LVMD 1323
LVMD 1325
LVMD 1327
LVMD 1329
LVMD 1331
LVMD 1333
LVMD 1335
LVMD 1337
LVMD 1339
LVMD 1341
LVMD 1343
LVMD 1345
LVMD 1347
LVMD 1349
LVMD 1351
LVMD 1353
LVMD 1355
LVMD 1357
LVMD 1359
LVMD 1361
LVMD 1363
LVMD 1365
LVMD 1367
LVMD 1369
LVMD 1371
LVMD 1373
LVMD 1375
LVMD 1377
LVMD 1379
LVMD 1381
LVMD 1383
LVMD 1385
LVMD 1387
LVMD 1389
LVMD 1391
LVMD 1393
LVMD 1395
LVMD 1397
LVMD 1399
LVMD 1401
LVMD 1403
LVMD 1405
LVMD 1407
LVMD 1409
LVMD 1411
LVMD 1413
LVMD 1415
LVMD 1417
LVMD 1419
LVMD 1421
LVMD 1423
LVMD 1425
LVMD 1427
LVMD 1429
LVMD 1431
LVMD 1433
LVMD 1435
LVMD 1437
LVMD 1439
LVMD 1441
LVMD 1443
LVMD 1445
LVMD 1447
LVMD 1449
LVMD 1451
LVMD 1453
LVMD 1455
LVMD 1457
LVMD 1459
LVMD 1461
LVMD 1463
LVMD 1465
LVMD 1467
LVMD 1469
LVMD 1471
LVMD 1473
LVMD 1475
LVMD 1477
LVMD 1479
LVMD 1481
LVMD 1483
LVMD 1485
LVMD 1487
LVMD 1489
LVMD 1491
LVMD 1493
LVMD 1495
LVMD 1497
LVMD 1499
LVMD 1501
LVMD 1503
LVMD 1505
LVMD 1507
LVMD 1509
LVMD 1511
LVMD 1513
LVMD 1515
LVMD 1517
LVMD 1519
LVMD 1521
LVMD 1523
LVMD 1525
LVMD 1527
LVMD 1529
LVMD 1531
LVMD 1533
LVMD 1535
LVMD 1537
LVMD 1539
LVMD 1541
LVMD 1543
LVMD 1545
LVMD 1547
LVMD 1549
LVMD 1551
LVMD 1553
LVMD 1555
LVMD 1557
LVMD 1559
LVMD 1561
LVMD 1563
LVMD 1565
LVMD 1567
LVMD 1569
LVMD 1571
LVMD 1573
LVMD 1575
LVMD 1577
LVMD 1579
LVMD 1581
LVMD 1583
LVMD 1585
LVMD 1587
LVMD 1589
LVMD 1591
LVMD 1593
LVMD 1595
LVMD 1597
LVMD 1599
LVMD 1601
LVMD 1603
LVMD 1605
LVMD 1607
LVMD 1609
LVMD 1611
LVMD 1613
LVMD 1615
LVMD 1617
LVMD 1619
LVMD 1621
LVMD 1623
LVMD 1625
LVMD 1627
LVMD 1629
LVMD 1631
LVMD 1633
LVMD 1635
LVMD 1637
LVMD 1639
LVMD 1641
LVMD 1643
LVMD 1645
LVMD 1647
LVMD 1649
LVMD 1651
LVMD 1653
LVMD 1655
LVMD 1657
LVMD 1659
LVMD 1661
LVMD 1663
LVMD 1665
LVMD 1667
LVMD 1669
LVMD 1671
LVMD 1673
LVMD 1675
LVMD 1677
LVMD 1679
LVMD 1681
LVMD 1683
LVMD 1685
LVMD 1687
LVMD 1689
LVMD 1691
LVMD 1693
LVMD 1695
LVMD 1697
LVMD 1699
LVMD 1701
LVMD 1703
LVMD 1705
LVMD 1707
LVMD 1709
LVMD 1711
LVMD 1713
LVMD 1715
LVMD 1717
LVMD 1719
LVMD 1721
LVMD 1723
LVMD 1725
LVMD 1727
LVMD 1729
LVMD 1731
LVMD 1733
LVMD 1735
LVMD 1737
LVMD 1739
LVMD 1741
LVMD 1743
LVMD 1745
LVMD 1747
LVMD 1749
LVMD 1751
LVMD 1753
LVMD 1755
LVMD 1757
LVMD 1759
LVMD 1761
LVMD 1763
LVMD 1765
LVMD 1767
LVMD 1769
LVMD 1771
LVMD 1773
LVMD 1775
LVMD 1777
LVMD 1779
LVMD 1781
LVMD 1783
LVMD 1785
LVMD 1787
LVMD 1789
LVMD 1791
LVMD 1793
LVMD 1795
LVMD 1797
LVMD 1799
LVMD 1801
LVMD 1803
LVMD 1805
LVMD 1807
LVMD 1809
LVMD 1811
LVMD 1813
LVMD 1815
LVMD 1817
LVMD 1819
LVMD 1821
LVMD 1823
LVMD 1825
LVMD 1827
LVMD 1829
LVMD 1831
LVMD 1833
LVMD 1835
LVMD 1837
LVMD 1839
LVMD 1841
LVMD 1843
LVMD 1845
LVMD 1847
LVMD 1849
LVMD 1851
LVMD 1853
LVMD 1855
LVMD 1857
LVMD 1859
LVMD 1861
LVMD 1863
LVMD 1865
LVMD 1867
LVMD 1869
LVMD 1871
LVMD 1873
LVMD 1875
LVMD 1877
LVMD 1879
LVMD 1881
LVMD 1883
LVMD 1885
LVMD 1887
LVMD 1889
LVMD 1891
LVMD 1893
LVMD 1895
LVMD 1897
LVMD 1899
LVMD 1901
LVMD 1903
LVMD 1905
LVMD 1907
LVMD 1909
LVMD 1911
LVMD 1913
LVMD 1915
LVMD 1917
LVMD 1919
LVMD 1921
LVMD 1923
LVMD 1925
LVMD 1927
LVMD 1929
LVMD 1931
LVMD 1933
LVMD 1935
LVMD 1937
LVMD 1939
LVMD 1941
LVMD 1943
LVMD 1945
LVMD 1947
LVMD 1949
LVMD 1951
LVMD 1953
LVMD 1955
LVMD 1957
LVMD 1959
LVMD 1961
LVMD 1963
LVMD 1965
LVMD 1967
LVMD 1969
LVMD 1971
LVMD 1973
LVMD 1975
LVMD 1977
LVMD 1979
LVMD 1981
LVMD 1983
LVMD 1985
LVMD 1987
LVMD 1989
LVMD 1991
LVMD 1993
LVMD 1995
LVMD 1997
LVMD 1999
LVMD 2001
LVMD 2003
LVMD 2005
LVMD 2007
LVMD 2009
LVMD 2011
LVMD 2013
LVMD 2015
LVMD 2017
LVMD 2019
LVMD 2021
LVMD 2023
LVMD 2025
LVMD 2027
LVMD 2029
LVMD 2031
LVMD 2033
LVMD 2035
LVMD 2037
LVMD 2039
LVMD 2041
LVMD 2043
LVMD 2045
LVMD 2047
LVMD 2049
LVMD 2051
LVMD 2053
LVMD 2055
LVMD 2057
LVMD 2059
LVMD 2061
LVMD 2063
LVMD 2065
LVMD 2067
LVMD 2069
LVMD 2071
LVMD 2073
LVMD 2075
LVMD 2077
LVMD 2079
LVMD 2081
LVMD 2083
LVMD 2085
LVMD 2087
LVMD 2089
LVMD 2091
LVMD 2093
LVMD 2095
LVMD 2097
LVMD 2099
LVMD 2101
LVMD 2103
LVMD 2105
LVMD 2107
LVMD 2109
LVMD 2111
LVMD 2113
LVMD 2115
LVMD 2117
LVMD 2119
LVMD 2121
LVMD 2123
LVMD 2125
LVMD 2127
LVMD 2129
LVMD 2131
LVMD 2133
LVMD 2135
LVMD 2137
LVMD 2139
LVMD 2141
LVMD 2143
LVMD 2145
LVMD 2147
LVMD 2149
LVMD 2151
LVMD 2153
LVMD 2155
LVMD 2157
LVMD 2159
LVMD 2161
LVMD 2163
LVMD 2165
LVMD 2167
LVMD 2169
LVMD 2171
LVMD 2173
LVMD 2175
LVMD 2177
LVMD 2179
LVMD 2181
LVMD 2183
LVMD 2185
LVMD 2187
LVMD 2189
LVMD 2191
LVMD 2193
LVMD 2195
LVMD 2197
LVMD 2199
LVMD 2201
LVMD 2203
LVMD 2205
LVMD 2207
LVMD 2209
LVMD 2211
LVMD 2213
LVMD 2215
LVMD 2217
LVMD 2219
LVMD 2221
LVMD 2223
LVMD 2225
LVMD 2227
LVMD 2229
LVMD 2231
LVMD 2233
LVMD 2235
LVMD 2237
LVMD 2239
LVMD 2241
LVMD 2243
LVMD 2245
LVMD 2247
LVMD 2249
LVMD 2251
LVMD 2253
LVMD 2255
LVMD 2257
LVMD 2259
LVMD 2261
LVMD 2263
LVMD 2265
LVMD 2267
LVMD 2269
LVMD 2271
LVMD 2273
LVMD 2275
LVMD 2277
LVMD 2279
LVMD 2281
LVMD 2283
LVMD 2285
LVMD 2287
LVMD 2289
LVMD 2291
LVMD 2293
LVMD 2295
LVMD 2297
LVMD 2299
LVMD 2301
LVMD 2303
LVMD 2305
LVMD 2307
LVMD 2309
LVMD 2311
LVMD 2313
LVMD 2315
LVMD 2317
LVMD 2319
LVMD 2321
LVMD 2323
LVMD 2325
LVMD 2327
LVMD 2329
LVMD 2331
LVMD 2333
LVMD 2335
LVMD 2337
LVMD 2339
LVMD 2341
LVMD 2343
LVMD 2345
LVMD 2347
LVMD 2349
LVMD 2351
LVMD 2353
LVMD 2355
LVMD 2357
LVMD 2359
LVMD 2361
LVMD 2363
LVMD 2365
LVMD 2367
LVMD 2369
LVMD 2371
LVMD 2373
LVMD 2375
LVMD 2377
LVMD 2379
LVMD 2381
LVMD 2383
LVMD 2385
LVMD 2387
LVMD 2389
LVMD 2391
LVMD 2393
LVMD 2395
LVMD 2397
LVMD 2399
LVMD 2401
LVMD 2403
LVMD 2405
LVMD 2407
LVMD 2409
LVMD 2411
LVMD 2413
LVMD 2415
LVMD 2417
LVMD 2419
LVMD 2421
LVMD 2423
LVMD 2425
LVMD 2427
LVMD 2429
LVMD 2431
LVMD 2433
LVMD 2435
LVMD 2437
LVMD 2439
LVMD 2441
LVMD 2443
LVMD 2445
LVMD 2447
LVMD 2449
LVMD 2451
LVMD 2453
LVMD 2455
LVMD 2457
LVMD 2459
LVMD 2461
LVMD 2463
LVMD 2465
LVMD 2467
LVMD 2469
LVMD 2471
LVMD 2473
LVMD 2475
LVMD 2477
LVMD 2479
LVMD 2481
LVMD 2483
LVMD 2485
LVMD 2487
LVMD 2489
LVMD 2491
LVMD 2493
LVMD 2495
LVMD 2497
LVMD 2499
LVMD 2501
LVMD 2503
LVMD 2505
LVMD 2507
LVMD 2509
LVMD 2511
LVMD 2513
LVMD 2515
LVMD 2517
LVMD 2519
LVMD 2521
LVMD 2523
LVMD 2525
LVMD 2527
LVMD 2529
LVMD 2531
LVMD 2533
LVMD 2535
LVMD 2537
LVMD 2539
LVMD 2541
LVMD 2543
LVMD 2545
LVMD 2547
LVMD 2549
LVMD 2551
LVMD 2553
LVMD 2555
LVMD 2557
LVMD 2559
LVMD 2561
LVMD 2563
LVMD 2565
LVMD 2567
LVMD 2569
LVMD 2571
LVMD 2573
LVMD 2575
LVMD 2577
LVMD 2579
LVMD 2581
LVMD 2583
LVMD 2585
LVMD 2587
LVMD 2589
LVMD 2591
LVMD 2593
LVMD 2595
LVMD 2597
LVMD 2599
LVMD 2601
LVMD 2603
LVMD 2605
LVMD 2607
LVMD 2609
LVMD 2611
LVMD 2613
LVMD 2615
LVMD 2617
LVMD 2619
LVMD 2621
LVMD 2623
LVMD 2625
LVMD 2627
LVMD 2629
LVMD 2631
LVMD 2633
LVMD 2635
LVMD 2637
LVMD 2639
LVMD 2641
LVMD 2643
LVMD 2645
LVMD 2647
LVMD 2649
LVMD 2651
LVMD 2653
LVMD 2655
LVMD 2657
LVMD 2659
LVMD 2661
LVMD 2663
LVMD 2665
LVMD 2667
LVMD 2669
LVMD 2671
LVMD 2673
LVMD 2675
LVMD 2677
LVMD 2679
LVMD 2681
LVMD 2683
LVMD 2685
LVMD 2687
LVMD 2689
LVMD 2691
LVMD 2693
LVMD 2695
LVMD 2697
LVMD 2699
LVMD 2701
LVMD 2703
LVMD 2705
LVMD 2707
LVMD 2709
LVMD 2711
LVMD 2713
LVMD 2715
LVMD 2717
LVMD 2719
LVMD 2721
LVMD 2723
LVMD 2725
LVMD 2727
LVMD 2729
LVMD 2731
LVMD 2733
LVMD 2735
LVMD 2737
LVMD 2739
LVMD 2741
LVMD 2743
LVMD 2745
LVMD 2747
LVMD 2749
LVMD 2751
LVMD 2753
LVMD 2755
LVMD 2757
LVMD 2759
LVMD 2761
LVMD 2763
LVMD 2765
LVMD 2767
LVMD 2769
LVMD 2771
LVMD 2773
LVMD 2775
LVMD 2777
LVMD 2779
LVMD 2781
LVMD 2783
LVMD 2785
LVMD 2787
LVMD 2789
LVMD 2791
LVMD 2793
LVMD 2795
LVMD 2797
LVMD 2799
LVMD 2801
LVMD 2803
LVMD 2805
LVMD 2807
LVMD 2809
LVMD 2811
LVMD 2813
LVMD 2815
LVMD 2817
LVMD 2819
LVMD 2821
LVMD 2823
LVMD 2825
LVMD 2827
LVMD 2829
LVMD 2831
LVMD 2833
LVMD 2835
LVMD 2837
LVMD 2839
LVMD 2841
LVMD 2843
LVMD 2845
LVMD 2847
LVMD 2849
LVMD 2851
LVMD 2853
LVMD 2855
LVMD 2857
LVMD 2859
LVMD 2861
LVMD 2863
LVMD 2865
LVMD 2867
LVMD 2869
LVMD 2871
LVMD 2873
LVMD 2875
LVMD 2877
LVMD 2879
LVMD 2881
LVMD 2883
LVMD 2885
LVMD 2887
LVMD 2889
LVMD 2891
LVMD 2893
LVMD 2895
LVMD 2897
LVMD 2899
LVMD 2901
LVMD 2903
LVMD 2905
LVMD 2907
LVMD 2909
LVMD 2911
LVMD 2913
LVMD 2915
LVMD 2917
LVMD 2919
LVMD 2921
LVMD 2923
LVMD 2925
LVMD 2927
LVMD 2929
LVMD 2931
LVMD 2933
LVMD 2935
LVMD 2937
LVMD 2939
LVMD 2941
LVMD 2943
LVMD 2945
LVMD 2947
LVMD 2949
LVMD 2951
LVMD 2953
LVMD 2955
LVMD 2957
LVMD 2959
LVMD 2961
LVMD 2963
LVMD 2965
LVMD 2967
LVMD 2969
LVMD 2971
LVMD 2973
LVMD 2975
LVMD 2977
LVMD 2979
LVMD 2981
LVMD 2983
LVMD 2985
LVMD 2987
LVMD 2989
LVMD 2991
LVMD 2993
LVMD 2995
LVMD 2997
LVMD 2999
LVMD 3001
LVMD 3003
LVMD 3005
LVMD 3007
LVMD 3009
LVMD 3011
LVMD 3013
LVMD 3015
LVMD 3017
LVMD 3019
LVMD 3021
LVMD 3023
LVMD 3025
LVMD 3027
LVMD 3029
LVMD 3031
LVMD 3033
LVMD 3035
LVMD 3037
LVMD 3039
LVMD 3041
LVMD 3043
LVMD 3045
LVMD 3047
LVMD 3049
LVMD 3051
LVMD 3053
LVMD 3055
LVMD 3057
LVMD 3059
LVMD 3061
LVMD 3063
LVMD 3065
LVMD 3067
LVMD 3069
LVMD 3071
LVMD 3073
LVMD 3075
LVMD 3077
LVMD 3079
LVMD 3081
LVMD 3083
LVMD 3085
LVMD 3087
LVMD 3089
LVMD 3091
LVMD 3093
LVMD 3095
LVMD 3097
LVMD 3099
LVMD 3101
LVMD 3103
LVMD 3105
LVMD 3107
LVMD 3109
LVMD 3111
LVMD 3113
LVMD 3115
LVMD 3117
LVMD 3119
LVMD 3121
LVMD 3123
LVMD 3125
LVMD 3127
LVMD 3129
LVMD 3131
LVMD 3133
LVMD 3135
LVMD 3137
LVMD 3139
LVMD 3141
LVMD 3143
LVMD 3145
LVMD 3147
LVMD 3149
LVMD 3151
LVMD 3153
LVMD 3155
LVMD 3157
LVMD 3159
LVMD 3161
LVMD 3163
LVMD 3165
LVMD 3167
LVMD 3169
LVMD 3171
LVMD 3173
LVMD 3175
LVMD 3177
LVMD 3179
LVMD 3181
LVMD 3183
LVMD 3185
LVMD 3187
LVMD 3189
LVMD 3191
LVMD 3193
LVMD 3195
LVMD 3197
LVMD 3199
LVMD 3201
LVMD 3203
LVMD 3205
LVMD 3207
LVMD 3209
LVMD 3211
LVMD 3213
LVMD 3215
LVMD 3217
LVMD 3219
LVMD 3221
LVMD 3223
LVMD 3225
LVMD 3227
LVMD 3229
LVMD 3231
LVMD 3233
LVMD 3235
LVMD 3237
LVMD 3239
LVMD 3241
LVMD 3243
LVMD 3245
LVMD 3247
LVMD 3249
LVMD 3251
LVMD 3253
LVMD 3255
LVMD 3257
LVMD 3259
LVMD 3261
LVMD 3263
LVMD 3265
LVMD 3267
LVMD 3269
LVMD 3271
LVMD 3273
LVMD 3275
LVMD 3277
LVMD 3279
LVMD 3281
LVMD 3283
LVMD 3285
LVMD 3287
LVMD 3289
LVMD 3291
LVMD 3293
LVMD 3295
LVMD 3297
LVMD 3299
LVMD 3301
LVMD 3303
LVMD 3305
LVMD 3307
LVMD 3309
LVMD 3311
LVMD 3313
LVMD 3315
LVMD 3317
LVMD 3319
LVMD 3321
LVMD 3323
LVMD 3325
LVMD 3327
LVMD 3329
LVMD 3331
LVMD 3333
LVMD 3335
LVMD 3337
LVMD 3339
LVMD 3341
LVMD 3343
LVMD 3345
LVMD 3347
LVMD 3349
LVMD 3351
LVMD 3353
LVMD 3355
LVMD 3357
LVMD 3359
LVMD 3361
LVMD 3363
LVMD 3365
LVMD 3367
LVMD 3369
LVMD 3371
LVMD 3373
LVMD 3375
LVMD 3377
LVMD 3379
LVMD 3381
LVMD 3383
LVMD 3385
LVMD 3387
LVMD 3389
LVMD 3391
LVMD 3393
LVMD 3395
LVMD 3397
LVMD 3399
LVMD 3401
LVMD 3403
LVMD 3405
LVMD 3407
LVMD 3409
LVMD 3411
LVMD 3413
LVMD 3415
LVMD 3417
LVMD 3419
LVMD 3421
LVMD 3423
LVMD 3425
LVMD 3427
LVMD 3429
LVMD 3431
LVMD 3433
LVMD 3435
LVMD 3437
LVMD 3439
LVMD 3441
LVMD 3443
LVMD 3445
LVMD 3447
LVMD 3449
LVMD 3451
LVMD 3453
LVMD 3455
LVMD 3457
LVMD 3459
LVMD 3461
LVMD 3463
LVMD 3465
LVMD 3467
LVMD 3469
LVMD 3471
LVMD 3473
LVMD 3475
LVMD 3477
LVMD 3479
LVMD 3481
LVMD 3483
LVMD 3485
LVMD 3487
LVMD 3489
LVMD 3491
LVMD 3493
LVMD 3495
LVMD 3497
LVMD 3499
LVMD 3501
LVMD 3503
LVMD 3505
LVMD 3507
LVMD 3509
LVMD 3511
LVMD 3513
LVMD 3515
LVMD 3517
LVMD 3519
LVMD 3521
LVMD 3523
LVMD 3525
LVMD 3527
LVMD 3529
LVMD 3531
LVMD 3533
LVMD 3535
LVMD 3537
LVMD 3539
LVMD 3541
LVMD 3543
LVMD 3545
LVMD 3547
LVMD 3549
LVMD 3551
LVMD 3553
LVMD 3555
LVMD 3557
LVMD 3559
LVMD 3561
LVMD 3563
LVMD 3565
LVMD 3567
LVMD 3569
LVMD 3571
LVMD 3573
LVMD 3575
LVMD 3577
LVMD 3579
LVMD 3581
LVMD 3583
LVMD 3585
LVMD 3587
LVMD 3589
LVMD 3591
LVMD 3593
LVMD 3595
LVMD 3597
LVMD 3599
LVMD 3601
LVMD 3603
LVMD 3605
LVMD 3607
LVMD 3609
LVMD 3611
LVMD 3613
LVMD 3615
LVMD 3617
LVMD 3619
LVMD 3621
LVMD 3623
LVMD 3625
LVMD 3627
LVMD 3629
LVMD 3631
LVMD 3633
LVMD 3635
LVMD 3637
LVMD 3639
LVMD 3641
LVMD 3643
LVMD 3645
LVMD 3647
LVMD 3649
LVMD 3651
LVMD 3653
LVMD 3655
LVMD 3657
LVMD 3659
LVMD 3661
LVMD 3663
LVMD 3665
LVMD 3667
LVMD 3669
LVMD 3671
LVMD 3673
LVMD 3675
LVMD 3677
LVMD 3679
LVMD 3681
LVMD 3683
LVMD 3685
LVMD 3687
LVMD 3689
LVMD 3691
LVMD 3693
LVMD 3695
LVMD 3697
LVMD 3699
LVMD 3701
LVMD 3703
LVMD 3705
LVMD 3707
LVMD 3709
LVMD 3711
LVMD 3713
LVMD 3715
LVMD 3717
LVMD 3719
LVMD 3721
LVMD 3723
LVMD 3725
LVMD 3727
LVMD 3729
LVMD 3731
LVMD 3733
LVMD 3735
LVMD 3737
LVMD 3739
LVMD 3741
LVMD 3743
LVMD 3745
LVMD 3747
LVMD 3749
LVMD 3751
LVMD 3753
LVMD 3755
LVMD 3757
LVMD 3759
LVMD 3761
LVMD 3763
LVMD 3765
LVMD 3767
LVMD 3769
LVMD 3771
LVMD 3773
LVMD 3775
LVMD 3777
LVMD 3779
LVMD 3781
LVMD 3783
LVMD 3785
LVMD 3787
LVMD 3789
LVMD 3791
LVMD 3793
LVMD 3795
LVMD 3797
LVMD 3799
LVMD 3801
LVMD 3803
LVMD 3805
LVMD 3807
LVMD 3809
LVMD 3811
LVMD 3813
LVMD 3815
LVMD 3817
LVMD 3819
LVMD 3821
LVMD 3823
LVMD 3825
LVMD 3827
LVMD 3829
LVMD 3831
LVMD 3833
LVMD 3835
LVMD 3837
LVMD 3839
LVMD 3841
LVMD 3843
LVMD 3845
LVMD 3847
LVMD 3849
LVMD 3851
LVMD 3853
LVMD 3855
LVMD 3857
LVMD 3859
LVMD 3861
LVMD 3863
LVMD 3865
LVMD 3867
LVMD 3869
LVMD 3871
LVMD 3873
LVMD 3875
LVMD 3877
LVMD 3879
LVMD 3881
LVMD 3883
LVMD 3885
LVMD 3887
LVMD 3889
LVMD 3891
LVMD 3893
LVMD 3895
LVMD 3897
LVMD 3899
LVMD 3901
LVMD 3903
LVMD 3905
LVMD 3907
LVMD 3909
LVMD 3911
LVMD 3913
LVMD 3915
LVMD 3917
LVMD 3919
LVMD 3921
LVMD 3923
LVMD 3925
LVMD 3927
LVMD 3929
LVMD 3931
LVMD 3933
LVMD 3935
LVMD 3937
LVMD 3939
LVMD 3941
LVMD 3943
LVMD 3945
LVMD 3947
LVMD 3949
LVMD 3951
LVMD 3953
LVMD 3955
LVMD 3957
LVMD 3959
LVMD 3961
LVMD 3963
LVMD 3965
LVMD 3967
LVMD 3969
LVMD 3971
LVMD 3973
LVMD 3975
LVMD 3977
LVMD 3979
LVMD 3981
LVMD 3983
LVMD 3985
LVMD 3987
LVMD 3989
LVMD 3991
LVMD 3993
LVMD 3995
LVMD 3997
LVMD 3999
LVMD 4001
LVMD 4003
LVMD 4005
LVMD 4007
LVMD 4009
LVMD 4011
LVMD 4013
LVMD 4015
LVMD 4017
LVMD 4019
LVMD 4021
LVMD 4023
LVMD 4025
LVMD 4027
LVMD 4029
LVMD 4031
LVMD 4033
LVMD 4035
LVMD 4037
LVMD 4039
LVMD 4041
LVMD 4043
LVMD 4045
LVMD 4047
LVMD 4049
LVMD 4051
LVMD 4053
LVMD 4055
LVMD 4057
LVMD 4059
LVMD 4061
LVMD 4063
LVMD 4065
LVMD 4067
LVMD 4069
LVMD 4071
LVMD 4073
LVMD 4075
LVMD 4077
LVMD 4079
LVMD 4081
LVMD 4083
LVMD 4085
LVMD 4087
LVMD 4089
LVMD 4091
LVMD 4093
LVMD 4095
LVMD 4097
LVMD 4099
LVMD 4101
LVMD 4103
LVMD 4105
LVMD 4107
LVMD 4109
LVMD 4111
LVMD 4113
LVMD 4115
LVMD 4117
LVMD 4119
LVMD 4121
LVMD 4123
LVMD 4125
LVMD 4127
LVMD 4129
LVMD 4131
LVMD 4133
LVMD 4135
LVMD 4137
LVMD 4139
LVMD 4141
LVMD 4143
LVMD 4145
LVMD 4147
LVMD 4149
LVMD 4151
LVMD 4153
LVMD 4155
LVMD 4157
LVMD 4159
LVMD 4161
LVMD 4163
LVMD 4165
LVMD 4167
LVMD 4169
LVMD 4171
LVMD 4173
LVMD 4175
LVMD 4177
LVMD 4179
LVMD 4181
LVMD 4183
LVMD 4185
LVMD 4187
LVMD 4189
LVMD 4191
LVMD 4193
LVMD 4195
LVMD 4197
LVMD 4199
LVMD 4201
LVMD 4203
LVMD 4205
LVMD 4207
LVMD 4209
LVMD 4211
LVMD 4213
LVMD 4215
LVMD 4217
LVMD 4219
LVMD 4221
LVMD 4223
LVMD 4225
LVMD 4227
LVMD 4229
LVMD 4231
LVMD 4233
LVMD 4235
LVMD 4237
LVMD 4239
LVMD 4241
LVMD 4243
LVMD 4245
LVMD 4247
LVMD 4249
LVMD 4251
LVMD 4253
LVMD 4255
LVMD 4257
LVMD 4259
LVMD 4261
LVMD 4263
LVMD 4265
LVMD 4267
LVMD 4269
LVMD 4271
LVMD 4273
LVMD 4275
LVMD 4277
LVMD 4279
LVMD 4281
LVMD 4283
LVMD 4285
LVMD 4287
LVMD 4289
LVMD 4291
LVMD 4293
LVMD 4295
LVMD 4297
LVMD 4299
LVMD 4301
LVMD 4303
LVMD 4305
LVMD 4307
LVMD 4309
LVMD 4311
LVMD 4313
LVMD 4315
LVMD 4317
LVMD 4319
LVMD 4321
LVMD 4323
LVMD 4325
LVMD 4327
LVMD 4329
LVMD 4331
LVMD 4333
LVMD 4335
LVMD 4337
LVMD 4339
LVMD 4341
LVMD 4343
LVMD 4345
LVMD 4347
LVMD 4349
LVMD 4351
LVMD 4353
LVMD 4355
LVMD 4357
LVMD 4359
LVMD 4361
LVMD 4363
LVMD 4365
LVMD 4367
LVMD 4369
LVMD 4371
LVMD 4373
LVMD 4375
LVMD 4377
LVMD 4379
LVMD 4381
LVMD 4383
LVMD 4385
LVMD 4387
LVMD 4389
LVMD 4391
LVMD 4393
LVMD 4395
LVMD 4397
LVMD 4399
LVMD 4401
LVMD 4403
LVMD 4405
LVMD 4407
LVMD 4409
LVMD 4411
LVMD 4413
LVMD 4415
LVMD 4417
LVMD 4419
LVMD 4421
LVMD 4423
LVMD 4425
LVMD 4427
LVMD 4429
LVMD 4431
LVMD 4433
LVMD 4435
LVMD 4437
LVMD 4439
LVMD 4441
LVMD 4443
LVMD 4445
LVMD 4447
LVMD 4449
LVMD 4451
LVMD 4453
LVMD 4455
LVMD 4457
LVMD 4459
LVMD 4461
LVMD 4463
LVMD 4465
LVMD 4467
LVMD 4469
LVMD 4471
LVMD 4473
LVMD 4475
LVMD 4477
LVMD 4479
LVMD 4481
LVMD 4483
LVMD 4485
LVMD 4487
LVMD 4489
LVMD 4491
LVMD 4493
LVMD 4495
LVMD 4497
LVMD 4499
LVMD 4501
LVMD 4503
LVMD 4505
LVMD 4507
LVMD 4509
LVMD 4511
LVMD 4513
LVMD 4515
LVMD 4517
LVMD 4519
LVMD 4521
LVMD 4523
LVMD 4525
LVMD 4527
LVMD 4529
LVMD 4531
LVMD 4533
LVMD 4535
LVMD 4537
LVMD 4539
LVMD 4541
LVMD 4543
LVMD 4545
LVMD 4547
LVMD 4549
LVMD 4551
LVMD 4553
LVMD 4555
LVMD 4557
LVMD 4559
LVMD 4561
LVMD 4563
LVMD 4565
LVMD 4567
LVMD 4569
LVMD 4571
LVMD 4573
LVMD 4575
LVMD 4577
LVMD 4579
LVMD 4581
LVMD 4583
LVMD 4585
LVMD 4587
LVMD 4589
LVMD 4591
LVMD 4593
LVMD 4595
LVMD 4597
LVMD 4599
LVMD 4601
LVMD 4603
LVMD 4605
LVMD 4607
LVMD 4609
LVMD 4611
LVMD 4613
LVMD 4615
LVMD 4617
LVMD 4619
LVMD 4621
LVMD 4623
LVMD 4625
LVMD 4627
LVMD 4629
LVMD 4631
LVMD 4633
LVMD 4635
LVMD 4637
LVMD 4639
LVMD 4641
LVMD 4643
LVMD 4645
LVMD 4647
LVMD 4649
LVMD 4651
LVMD 4653
LVMD 4655
LVMD 4657
LVMD 4659
LVMD 4661
LVMD 4663
LVMD 4665
LVMD 4667
LVMD 4669
LVMD 4671
LVMD 4673
LVMD 4675
LVMD 4677
LVMD 4679
LVMD 4681
LVMD 4683
LVMD 4685
LVMD 4687
LVMD 4689
LVMD 4691
LVMD 4693
LVMD 4695
LVMD 4697
LVMD 4699
LVMD 4701
LVMD 4703
LVMD 4705
LVMD 4707
LVMD 4709
LVMD 4711
LVMD 4713
LVMD 4715
LVMD 4717
LVMD 4719
LVMD 4721
LVMD 4723
LVMD 4725
LVMD 4727
LVMD 4729
LVMD 4731
LVMD 4733
LVMD 4735
LVMD 4737
LVMD 4739
LVMD 4741
LVMD 4743
LVMD 4745
LVMD 4747
LVMD 4749
LVMD 4751
LVMD 4753
LVMD 4755
LVMD 4757
LVMD 4759
LVMD 4761
LVMD 4763
LVMD 4765
LVMD 4767
LVMD 4769
LVMD 4771
LVMD 4773
LVMD 4775
LVMD 4777
LVMD 4779
LVMD

ID / River Mile	Status	Facility Description	Length (ft.)	Flow (cfs)	HEC-1 Node	HEC-1 Model	Tributary Area (sq.mi.)	Channel Slope (%) **
BHSA		**BOULDER HIGHWAY SAHARA AVENUE**						
0000	E	72" RCP	1350	3462	CSA11*	SW3SC	7.76	0.79
0000	P1	14' X 12' RCB	1350	3462	CSA11*	SW3SC	7.76	0.79
0026	P1	12' X 12' RCB	4000	3462	CSA11*	SW3SC	7.76	1.30
0075	P1	12' X 10' RCB	5280	3462	CSA11*	SW3SC	7.76	2.11
0175	P1	14' X 13' RCB	6000	3462	CSA11*	SW3SC	7.76	0.67
0289	P1	14' X 12' RCB	2300	3462	CSA11	SW3SC	7.76	0.87
CABZ		**CEDAR AVENUE - BONANZA**						
0000	E	72" RCP	310	1085	DCA06-C	SW3SC	1.54	0.30
0000	P0	11' X 10' RCB	310	1085	DCA06-C	SW3SC	1.54	0.30
0006	E	60" RCP	1294	1085	DCA06-C	SW3SC	1.54	0.30
0006	P0	11' X 10' RCB	1294	1085	DCA06-C	SW3SC	1.54	0.30
0021	E	68" x 43 CMAP	160	943	CBN08-C	SW3SC	1.30	0.45
0021	P0	9' X 9' RCB	160	943	CBN08-C	SW3SC	1.30	0.45
0028	E	54" SSP	935	943	CBN08-C	SW3SC	1.30	0.45
0028	P0	9' X 9' RCB	935	943	CBN08-C	SW3SC	1.30	0.45
0045	E	48" SSP	1234	943	CBN08-C	SW3SC	1.30	0.80
0045	P0	9' X 8' RCB	1234	943	CBN08-C	SW3SC	1.30	0.80
0066	E	42" SSP	704	763	CBN03-C	SW3SC	1.09	0.80
0066	P0	8' X 7' RCB	704	763	CBN03-C	SW3SC	1.09	0.80
0080	E	36" SSP	1919	763	CBN03-C	SW3SC	1.09	0.75
0080	P0	8' X 6' RCB	1919	763	CBN03-C	SW3SC	1.09	0.75
CACH		**CEDAR AVENUE CHANNEL**						
0000	E	Conc Chnl 10'W 8'D 1.5:1 SS	1524	2417	CCA10-C	SW3SC	2.15	0.35
0000	P1	Conc Chnl 27'W 8'D 0:1 SS	1524	2417	CCA10-C	SW3SC	2.15	0.35
0027	E	2: 5' X 15' RCBC @ Marion	100	2417	CCA10-C	SW3SC	2.15	0.35
0027	P1	3: 12' X 8' RCBC @ Marion	100	2417	CCA10-C	SW3SC	2.15	0.35
0028	E	Conc Chnl 10'W 8'D 1.5:1 SS	1400	2417	CCA10-C	SW3SC	2.15	0.34
0028	P1	Conc Chnl 27'W 8'D 0:1 SS	1224	2417	CCA10-C	SW3SC	2.15	0.34
0051	E	2: 5' X 15' RCBC @ Page	100	2417	CCA10-C	SW3SC	2.15	0.34
0051	P1	4: 11' X 8' RCBC @ Page	100	2417	CCA10-C	SW3SC	2.15	0.34
0052	E	Conc Chnl 10'W 6'D 1.5:1 SS	1198	2417	CCA10-C	SW3SC	2.15	0.34
0052	P1	Conc Chnl 45'W 6'D 0:1 SS	1198	2417	CCA10-C	SW3SC	2.15	0.34
0079	E	2: 6' X 12' RCBC @ Lamb	100	2403	CCA08-C	SW3SC	1.95	0.30
0079	P1	4: 12' X 7' RCBC @ Lamb	100	2403	CCA08-C	SW3SC	1.95	0.30
0080	E	Conc Chnl 12'W 6'D 1.5:1 SS	2640	2403	CCA08-C	SW3SC	1.95	0.30
0080	P1	Conc Chnl 45'W 6'D 0:1 SS	2640	2403	CCA08-C	SW3SC	1.95	0.30
0127	E	3: 4' X 12' RCBC @ Sandhill	100	2403	CCA08-C	SW3SC	1.95	0.30
0127	P1	3: 12' X 8' RCBC @ Sandhill	100	2403	CCA08-C	SW3SC	1.95	0.30
0128	E	Conc Chnl 10'W 8'D 1.5:1 SS	900	2403	CCA08-C	SW3SC	1.95	0.30
0128	P1	Conc Chnl 28'W 8'D 0:1 SS	900	2403	CCA08-C	SW3SC	1.95	0.30
0146	E	2: 5.5' X 12' RCBC @ Honolulu	100	2403	CCA08-C	SW3SC	1.95	0.30
0146	P1	3: 12' X 8' RCBC @ Honolulu	100	2403	CCA08-C	SW3SC	1.95	0.30
0147	E	Conc Chnl 10'W 8'D 1.5:1 SS	1640	2403	CCA08-C	SW3SC	1.95	0.30
0147	P1	Conc Chnl 28'W 8'D 0:1 SS	1640	2403	CCA08-C	SW3SC	1.95	0.30
CACN		**CEDAR AVENUE - CHARLESTON**						
0000	E	72" RCP	800	922	CCA05	SW3SC	0.96	0.50
0000	P0	10' X 8' RCB	800	922	CCA05	SW3SC	0.96	0.50
0015	E	2: 48" RCP	600	922	CCA05	SW3SC	0.96	0.50
0015	P0	10' X 8' RCB	600	922	CCA05	SW3SC	0.96	0.50
0026	E	66" RCP	2700	922	CCA05	SW3SC	0.96	0.50
0026	P0	10' X 8' RCB	2700	922	CCA05	SW3SC	0.96	0.50
COLM		**COLORADO / LAMB**						
0000	E	72" RCP	1500	471	CCH94	SW3SC	0.63	1.17
FLBN		**FLAMINGO- BOULDER HIGHWAY NORTH**						
0000	E	Conc Chnl 5'W 6'D 2:1 SS	2200	3827	CFR03	SW5SC	12.68	0.70
0000	P1	3: 10' X 9' RCB	2200	3827	CFR03	SW5SC	12.68	0.70
0038	E	Channel - Unknown Characteristics	6600	2706	CFR04	SW3SC	3.86	0.59
0038	P1	3: 9' X 8' RCB	6600	2706	CFR04	SW3SC	3.86	0.59
0167	P1	2: 10' X 6' RCB	700	2027	CCH68-C	SW3SC	2.86	1.14
0180	P1	2: 10' X 6' RCB	1300	1777	CCH67-C	SW3SC	2.55	1.31
0205	P1	10' X 6' RCB	4000	1431	CCH63-C	SW3SC	1.88	2.30
0281	P1	2: 7' X 6' RCB	3100	1233	CCH56	SW3SC	1.64	1.33
0342	P1	10' X 6' RCB	4300	532	CCH52-C	SW3SC	0.55	0.42
FLBS		**FLAMINGO- BOULDER HIGHWAY SOUTH**						
0167	E	Unlined Median Chnl 0'W 3.5'D 9:1 SS	8850	959	CB4	FLAM3SC	1.38	0.90
FLMP		**FLAMINGO WASH-MARYLAND PARKWAY SYSTEM**						
0000	P1	8' X 6' RCB	3800	484	CCH60A-C	SW3SC	0.75	0.49
FLWA		**FLAMINGO WASH**						
0000	E	Grass Chnl 107'W 5'D 2:1 SS	4570	10241	CFW38	FLAM5SC	34.59	0.40
0078	E	3 Span Bridge 108.25'W 5.5'D @ Nellis	120	10162	CFW36	FLAM5SC	34.04	0.70
0079	E	Earth Chnl 50'W 12'D 1:1 SS	5080	10162	CFW36	FLAM5SC	34.04	1.20
0079	P1	Conc Chnl 50'W 8.5'D 1:1 SS	5080	10162	CFW36	FLAM5SC	34.04	1.20
0174	E	9: 10' X 6' RCBC @ Lamb	110	10082	CFW34	FLAM5SC	33.56	1.40
0175	E	Earth Chnl 50'W 12'D 1:1 SS	2400	10082	CFW34	FLAM5SC	33.56	0.70
0175	P1	Conc Chnl 50'W 9'D 1:1 SS	2400	10082	CFW34	FLAM5SC	33.56	0.70
0226	E	Free Span Bridge 100'W 10'D @ I-515	170	10082	CFW34	FLAM5SC	33.56	0.80
0228	E	Earth Chnl 50'W 12'D 1:1 SS	1500	10082	CFW34	FLAM5SC	33.56	0.80
0228	P1	Conc Chnl 50'W 9'D 1:1 SS	1500	10082	CFW34	FLAM5SC	33.56	0.80
0255	E	2 Span Bridge 150'W 9'D @ Boulder Hwy	65	7469	CFW31*	FLAM5SC	18.97	1.00
0256	E	Conc Chnl 60'W 7.5'D 0:1 SS	40	7469	CFW31*	FLAM5SC	18.97	1.00

ID / River Mile	Status	Facility Description	Length (ft.)	Flow (cfs)	HEC-1 Node	HEC-1 Model	Tributary Area (sq.mi.)	Channel Slope (%) **
FLWA		**FLAMINGO WASH -- continued**						
0257	E	2 Span Bridge 150'W 9'D @ Boulder Hwy	60	7469	CFW31*	FLAM5SC	18.97	1.00
0258	E	Conc Chnl 60'W 7.5'D 0:1 SS	750	7469	CFW31*	FLAM5SC	18.97	0.44
0273	E	Free Span Bridge 60'W 9.0'D @ Trailer Park	10	7469	CFW31*	FLAM5SC	18.97	0.40
0274	E	Conc Chnl 60'W 8.1'D 0:1 SS	1370	7469	CFW31*	FLAM5SC	18.97	1.00
0295	E	Conc Chnl 60'W 8.1'D 0:1 SS	430	7469	CFW31*	FLAM5SC	18.97	0.80
0307	E	Conc Chnl 60'W 8.1'D 2:1 SS	410	7469	CFW31*	FLAM5SC	18.97	0.70
0314	E	Conc Chnl 60'W 8.1'D 2:1 SS	1500	7469	CFW31	FLAM5SC	18.97	0.90
FW15		**FREEWAY CHANNEL FROM DESERT INN TO EXPRESSWAY**						
0000	E	3: 12' X 10' RCB	2074	3366	CAL96	SW4SC	10.22	0.17
0010	E	3: 12' X 10' RCB	677	3366	CAL96	SW4SC	10.22	0.17
0038	E	3: 12' X 10' RCB	1893	3284	CCCH22	SW4SC	10.04	0.17
0050	E	3: 12' X 10' RCB	812	3284	CCCH22	SW4SC	10.04	0.17
0089	E	3: 12' X 10' RCB	922	2156	COK11-C	SW3SC	7.78	0.17
0100	E	3: 12' X 9' RCB	1669	2156	COK11-C	SW3SC	7.78	0.17
FWCH		**WEST CHARLESTON DRAINS**						
0000	E	84" RCP	1600	1051	CCH22	SW3SC	1.54	0.93
FWRR		**FREEWAY CHANNEL BYPASS FACILITY RR BRANCH**						
0000	E	48" RCP	35					1.22
0010	E	Conc Chnl 5'W 5'D 0:1 SS	215					1.22
FWUP		**FREEWAY CHANNEL BYPASS FACILITY**						
0000	E	12' X 9' RCB	426	221	CH50	SW3SC	0.26	0.37
0010	E	10' X 8' RCB	804	221	CH50	SW3SC	0.26	0.37
0059	E	6' X 5' RCB	2680	221	CH50	SW3SC	0.48	0.56
FWWL		**FREEWAY CHANNEL-WALDMAN AVENUE**						
0000	E	6' X 6' RCB	1110	497	CWAL2	SW3SC	0.54	0.20
LCCH		**LAS VEGAS CREEK CHANNEL**						
0000	E	2: 12' X 7' RCB	655	2689	CLC20-C	MEADOWS4	9.47	1.28
0013	E	2: 12' X 6' RCB	2152	2689	CLC20-C	MEADOWS4	9.47	0.82
LV15		**FREEWAY CHANNEL**						
0059	E	Conc Chnl 20'W 10'D 1:1 SS	1600	4669	2CLV1D-5	CWEST4	10.41	0.18
0080	E	Conc Chnl 20'W 10'D 1:1 SS	4100	4346	CLV1D-4	CWEST4	9.61	0.18
0190	E	Conc Chnl 20'W 10'D 1:1 SS with Drop Structures	100	4185	CW1C2	NW4SC	9.04	0.18
0191	E	Conc Chnl 20'W 10'D 1:1 SS with Drop Structures	100	4185	CW1C2	NW4SC	9.04	0.18
0193	E	Conc Chnl 20'W 10'D 1:1 SS with Drop Structures	1300	4185	CW1C2	NW4SC	9.04	0.18
0210	E	Conc Chnl 8'W 8'D 1:1 SS	1000	3697	CVG24	NW3SC	7.09	0.18
0210	P0	Conc Chnl 60'W 8'D 0:1 SS	1000	3697	CVG24	NW3SC	7.09	0.18
0229	E	2: 7.5' X 3' RCBC	80	3697	CVG24	NW3SC	7.09	0.18
0229	P1	5: 14' X 8' RCBC	80	3697	CVG24	NW3SC	7.09	0.18
0230	E	Conc Chnl 8'W 8'D 1:1 SS	2900	2725	CCVG10	NW3SC	5.25	0.18
0230	P0	Conc Chnl 45'W 8'D 0:1 SS	3000	2725	CCVG10	NW3SC	5.25	0.18
0284	E	11' X 6' RCB	3000	1295	CVG10-C	NW3SC	4.82	0.56
0337	E	9' X 6' RCB	4500	1067	CWA20C	NW3SC	4.48	0.66
0424	P1	8' X 7' RCB	5500	627	CWA15-C	NW3SC	3.69	0.73
LVBR		**LAS VEGAS - BROOK**						
0000	P1	Conc Chnl 12'W 4.5'D 2:1 SS	700	994	CLV1D-5	CWEST3	0.80	2.90
0011	P1	8' X 7' RCBC @ N. 5th St	100	994	CLV1D-5	CWEST3	0.80	2.90
0013	E	Conc Chnl 12'W 4.5'D 2:1 SS	850	994	CLV1D-5	CWEST3	0.80	2.60
0014	P1	8' X 7' RCBC @ Losee	100	994	CLV1D-5	CWEST3	0.80	2.60
0026	P1	Conc Chnl 12'W 4.5'D 2:1 SS	850	994	CLV1D-5	CWEST3	0.80	4.30
LVCH		**RANGE WASH - CHRISTY LATERAL**						
0000	P1	12' X 9' RCB	6100	1072	C326B3	RW3	1.97	0.33
0114	P1	10' X 7' RCB	2600	844	C324-5	RW3	1.60	0.58
LVCO		**COLORADO AVENUE SYSTEM**						
0000	E	14' X 8' RCB	3400	1036	CNEL06	SW3SC	1.30	0.25
0064	E	10' X 8' RCB	2200	1036	CNEL06	SW3SC	1.30	0.25
0106	E	14' X 6' RCBC @ Lamb	500	830	CCCH94	SW3SC	0.98	0.25
0109	E	10' X 5' RCB	2500	394	CCH92-C	SW3SC	0.35	0.25
LVLE		**LAKE MEAD DRAIN TO LAS VEGAS WASH**						
0000	P1	12' X 9' RCB	2500	1185	CLV1B-2	CWEST3	1.28	0.40
0047	P1	12' X 7' RCB	2600	1000	CLV1B-1	CWEST3	0.97	0.50
LVLM		**LAS VEGAS WASH - LAKE MEAD**						
0000	E	54" RCP	978	1005	CLM20-C	NW3SC	1.36	4.46
0000	P0	7' X 6' RCB	978	1005	CLM20-C	NW3SC	1.36	4.46
0016	E	42" X 68" HERCP	772	1005	CLM20-C	NW3SC	1.36	1.00
0016	P0	8' X 8' RCB	772	1005	CLM20-C	NW3SC	1.36	1.00
0033	E	66" RCP	1186	1005	CLM20-C	NW3SC	1.36	1.26
0033	P0	8' X 8' RCB	1186	1005	CLM20-C	NW3SC	1.36	1.26
0059	E	66" RCP	5952	1005	CLM20-C	NW3SC	1.36	1.07
0059	P0	8' X 8' RCB	5952	1005	CLM20-C	NW3SC	1.36	1.07
LVLV		**LAS VEGAS BLVD DRAIN**						
0000	P1	2: 10' X 9' RCB	2600	1031	CLW075-4	CWEST3	1.03	0.10
LVMD		**LAS VEGAS WASH - MIDDLE**						
0639	P0	Rip Rap Levee (West) 2'	9050	18714	CRWSL	LVWSC2	200.00	0.14
0640	P2	Earth/Rip Rap/Soil Cement Chnl 170'W 13'D 3:1 SS	9150	18714	CRWSL	LVWSC2	200.00	0.21
0716	P0	Rip Rap Levee (East) 2'	9050	18714	CRWSL	LVWSC2	200.00	0.14
0819	E	Conc Chnl 120'W 13.3'D 3:1 SS	390	18714	CRWSL	LVWSC2	200.00	0.14
0826	E	10: 12' X 10' RCBC @ Vegas Valley	90	18714	CRWSL	LVWSC2	200.00	0.10
0827	E	Conc Chnl 120'W 10'D 3:1 SS	1290	18714	CRWSL	LVWSC2	200.00	0.40
0873	E	Conc Chnl 120'W 10'D 3:1 SS	550	16443	CFLWA	LVWSC2	200.00	0.40
0883	P2	Conc Chnl 120'W 10'D 2:1 SS	1120	16443	CFLWA	LVWSC2	200.00	0.40

ID / River Mile	Status	Facility Description	Length (ft.)	Flow (cfs)	HEC-1 Node	HEC-1 Model	Tributary Area (sq.mi.)	Channel Slope (%) **
LVMD		**LAS VEGAS WASH - MIDDLE -- continued**						
0908	P2	Reinforced Grass Chnl 120'W 12.5'D 2:1 SS	970	16443	CFLWA	LVWSC2	200.00	0.40
0915	E	Earth Chnl 40'W 8-10'D 1:1 SS	1300	14774	CFW37	CLVWASH5	120.82	0.50
0915	P1	Conc Chnl 120'W 8'D 0:1 SS	1300	14774	CFW37	CLVWASH5	120.82	0.50
0923	E	5 Span Bridge 50'W 5'D @ Desert Rose CC	100	14774	CFW37	CLVWASH5	120.82	0.50
0923	P1	Bridge 250'W 6'D @ Desert Rose CC with Conc Bottom	100	14774	CFW37	CLVWASH5	120.82	0.50
0924	E	Grass Chnl 400'W 4'-6'D 1:1 SS	1150	14774	CFW37	CLVWASH5	120.82	0.50
0948	E	3 Span Bridge 130'W 5'D @ Sahara	100	14763	CLVCH	CLVWASH5	120.42	0.50
0948	P1	Bridge 250'W 6'D @ Sahara with Conc Bottom	250	14763	CLVCH	CLVWASH5	120.42	0.50
0949	E	Grass Chnl 400'W 4'-6'D 1:1 SS	1900	14763	CLVCH	CLVWASH5	120.42	0.50
0973	E	Grass Chnl 400'W 4'-6'D 1:1 SS	2300	14490	CNLWY	CLVWASH5	118.33	0.30
1031	E	Free Span Bridge 50'W 10'-12'D @ Desert Rose CC	100	14490	CNLWY	CLVWASH5	118.33	0.30
1032	E	Earth Chnl 75'W 10'-12'D 1:1 SS	739	14490	CNLWY	CLVWASH5	118.33	0.30
1032	P1	Conc Chnl 75'W 11'D 1:1 SS	739	14490	CNLWY	CLVWASH5	118.33	0.30
1046	E	5 Span Bridge 75'W 10'-12'D 1:1 SS @ Nellis	120	14424	CCNEL06	CLVWASH5	117.87	0.52
1047	E	Earth Chnl 80'W 8'D 2:1 SS	1162	14176	CNEL04-2	CLVWASH5	116.57	0.50
1047	P1	Conc Chnl 120'W 8'D 0:1 SS	1162	14176	CNEL04-2	CLVWASH5	116.57	0.50
1069	E	5 Span Bridge 90'W 8'D 2:1 SS @ Charleston	120	14176	CNEL04-2	CLVWASH5	116.57	0.50
1070	E	Earth Chnl 90'W 10'-12'D 1.5:1 SS	2587	13358	CCST03-C	CLVWASH5	111.52	0.43
1070	P1	Conc Chnl 90'W 8.5'D 1.5:1 SS	2587	13358	CCST03-C	CLVWASH5	111.52	0.43
1119	E	5 Span Bridge 90'W 12'D 2:1 SS @ Stewart	120	13358	CCST03-C	CLVWASH5	111.52	0.20
1120	E	Earth Chnl 90'W 12'D 1:1 SS	1400	13255	CCCA10-C	CLVWASH5	111.05	0.20
1120	P1	Conc Chnl 90'W 10.5'D 1:1 SS	1400	13255	CCCA10-C	CLVWASH5	111.05	0.20
1148	E	Earth Chnl 70'W 18'-20'D 1.5:1 SS	1675	12581	CCBN15-C	CLVWASH5	108.05	0.41
1148	P1	Conc Chnl 70'W 9.5'D 1.5:1 SS	1675	12581	CCBN15-C	CLVWASH5	108.05	0.41
1176	E	5 Span Bridge 110'W 20'D 2:1 SS @ Bonanza	80	12581	CCBN15-C	CLVWASH5	108.05	0.57
1178	E	Earth Chnl 30'W 18'-20'D 2:1 SS	2900	12415	CLVW04-C	CLVWASH5	107.30	0.57
1178	P1	Conc Chnl 60'W 9.5'D 2:1 SS	2900	12415	CLVW04-C	CLVWASH5	107.30	0.57
1232	E	Earth Chnl 48'W 8'D 1.5:1 SS	2059	12415	CLVW04-C	CLVWASH5	107.30	0.73
1232	P1	Conc Chnl 90'W 8'D 0:1 SS	2059	12415	CLVW04-C	CLVWASH5	107.30	0.73
1271	E	4 Span Bridge 94'W 10'-12'D 2:1 SS @ Lamb	120	12372	CCLVW03	CLVWASH5	107.01	0.38
1272	E	Earth Chnl 80'W 10'D 2:1 SS	2400	11776	CLVW01	CLVWASH5	103.64	0.38
1272	P1	Conc Chnl 80'W 8.5'D 2:1 SS	2400	11776	CLVW01	CLVWASH5	103.64	0.38
1321	P1	Conc Chnl 80'W 7.5'D 2:1 SS	2200	8911	2CLV1B-2*	CLVWASH5	78.65	0.38
1354	E	5 Span Bridge 110'W 7'-8'D 2:1 SS @ Owens	120	8911	2CLV1B-2*	CLVWASH5	78.65	0.58
1355	E	Gabion Chnl 100'W 10'D 2:1 SS	3432	8911	2CLV1B-2	CLVWASH5	78.65	0.58
1420	E	7: 8'-12' X 8' RCBC	200	8892	2CLV1B-2	CCWEST5	78.65	0.60
1421	E	Earth Chnl 60'W 8'D 1:1SS	3221	8782	CLW64-4	CCWEST5	77.37	0.60
1421	P2	Conc Chnl 84'W 10'D 0:1 SS	3221	8782	CLW64-4	CCWEST5	77.37	0.33
1482	E	5: 120" CMP @ Carey	120	8782	CLW64-4	CCWEST5	77.37	0.40
1482	P2	2 Span Bridge 84'W 6.5'D @ Carey	120	8782	CLW64-4	CCWEST5	77.37	0.39
1483	E	Earth Chnl 75'W 6'D 2:1SS	2693	8782	CLW64-4	CCWEST5	77.37	0.40
1483	P2	Conc Chnl 80'W 10'D 1.5:1 SS	1300	8782	CLW64-4	CCWEST5	77.37	0.36
1509	P2	Conc Chnl 80'W 10'D 1.5:1 SS	1400	8712	2CLW1A-4	CCWEST5	76.42	0.36
1534	E	5: 12' X 7' RCBC @ Las Vegas Blvd	120	8712	2CLW1A-4	CCWEST5	76.42	0.70
1534	P2	2 Span Bridge 95.5'W 6'D @ Las Vegas Blvd	120	8712	2CLW1A-4	CCWEST5	76.42	0.70
1535	E	Earth Chnl 80'W 6'D 3:1SS	730	8578	2CLW100	CCWEST5	74.73	0.90
1535	P2	Conc Chnl 80'W 10'D 1.5:1 SS	899	8578	2CLW100	CCWEST5	74.73	0.52
1549	E	Earth Chnl 70'W 8'-10'D 1:1 SS	2376	8226	CHYPEAK	CCWEST5	74.73	0.50
1549	P2	Conc Chnl 80'W 10'D 1.5:1 SS	2218	8226	CHYPEAK	CCWEST5	74.45	0.52
LVNC		**LAS VEGAS WASH - N CHANNEL**						
0000	E	Earth Chnl 40'W 8'-10'D 2:1 SS	400	987	CLW100	CWEST5	13.99	0.70
0000	P1	Conc Chnl 12'W 5.5'D 2:1 SS	400	987	CLW100	CWEST5	13.99	0.70
0007	E	Drop Structure 18'W 2.8'D 3:1 SS	50	987	CLW100	CWEST5	13.99	0.70
0008	E	Conc Chnl 18'W 10'D 2:1 SS	1531	987	CLW100	CWEST5	13.99	0.70
LVOE		**OWENS AVENUE - EAST**						
0000	P1	15' X 10' RCB	4700	2234	CK-C	SW5	24.71	0.47
0085	P1	12' X 11' RCB	2600	2191	CG	SW5	24.39	0.62
0134	P1	12' X 9' RCB	5300	2141	CE-C	SW5	24.16	1.00
0236	P1	10' X 10' RCB	2640	1964	CH-C	SW5	23.63	1.33
LVOW		**OWENS AVENUE SYSTEM**						
0000	E	96" RCP	7700	1506	CLM16B-C	NW3SC	2.36	0.70
LVSR		**LAS VEGAS WASH - SMOKE RANCH**						
0000	E	Conc Chnl 22'W 8'D 0:1 SS	50	1451	CS1-C	NW3SC	1.59	2.32
0001	E	Free Span Bridge 22'W 10'D	50	1451	CS1-C	NW3SC	1.59	2.32
0002	E	Conc Chnl 22'W 8'D 0:1 SS	370	1451	CS1-C	NW3SC	1.59	2.32
0009	E	72" RCP	581	1451	CS1-C	NW3SC	1.59	2.32
0009	P1	10' X 6' RCB	581	1451	CS1-C	NW3SC	1.59	2.32
0020	E	60" RCP	1320	1451	CS1-C	NW3SC	1.59	3.03
0020	P1	10' X 6' RCB	1320	1451	CS1-C	NW3SC	1.59	3.03
0045	E	54" RCP	1320	1451	CS1-C	NW3SC	1.59	3.41
0045	P1	10' X 6' RCB	1320	1451	CS1-C	NW3SC	1.59	3.41
0070	E	66" RCP	4118	1126	CS	NW3SC	1.12	0.73
0070	P1	10' X 8' RCB	4118	1126	CS	NW3SC	1.12	0.73
0148	E	54" RCP	2587	1126	CS	NW3SC	1.12	0.58
0148	P1	11' X 8' RCB	2587	1126	CS	NW3SC	1.12	0.58
LVWH		**WASHINGTON AVENUE CHANNEL**						
0086	E	3: 12' X 8' RCB	1111	3997	CLVW01-C	SW5	24.96	0.33
0087	E	3: 12' X 8' RCB	1466	3997	CLVW01-C	SW5	24.96	0.33
0136	E	3: 12' X 8' RCB	2250	3918	CQ-C	SW5	24.72	0.33

ID / River Mile	Status	Facility Description	Length (ft.)	Flow (cfs)	HEC-1 Node	HEC-1 Model	Tributary Area (sq.mi.)	Channel Slope (%) **
LVWH		**WASHINGTON AVENUE CHANNEL -- continued**						
0155	E	3: 10' X 8' RCB	3773	3918	CQ-C	SW5	24.72	0.68
0234	E	2: 12' X 8' RCB	620	3718	CN-C	SW5	24.15	0.71
0240	E	2: 12' X 8' RCB	3435	3718	CN-C	SW5	24.15	1.50
0303	E	12' X 8' RCB	4000	2631	DCV1-C	SW5	23.34	0.90
0305	E	12' X 8' RCB	468	2631	DCV1-C	SW5	23.34	2.40
0390	E	12' X 8' RCB	2057	2631	DCV1-C	SW5	23.34	0.50
0429	E	Splitter Structure (2: 12' X 8' RCB)	115	5030	CLC21	SW5	22.72	1.90
0431	E	3: 14.33' X 10' RCB	766	4765	CCAL93	SW5	22.12	0.15
0446	E	3: 14.33' X 10' RCB Junction at F Street	69	4765	CCAL93	SW5	22.12	0.15
0447	E	3: 14.33' X 10' RCB	1942	4765	CCAL93	SW5	22.12	0.15
0484	E	Confluence Structure (3: 14.33' X 10' RCB)	246	4765	CCAL93	SW5	22.12	0.15
NLFL		**NELLIS FLAMINGO STORM DRAIN**						
0131	E	42" RCP	650	351	M1	FLAM3SC	0.51	0.23
0144	E	36" RCP	620	351	M1	FLAM3SC	0.51	0.20
NLWY		**NELLIS-WYOMING CHANNEL**						
0000	E	Conc Chnl 8'W 4'D 1.3:1 SS	260	342	FW35	FLAM3SC	0.47	1.71
0004	E	15' X 6' Arch Culvert	80	342	FW35	FLAM3SC	0.47	1.30
0006	E



FIRM

FLOOD INSURANCE RATE MAP

CLARK COUNTY,
NEVADA AND
INCORPORATED AREAS

PANEL 2195 OF 4090

(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
LAS VEGAS, CITY OF	325276	2195	E
CLARK COUNTY, UNINCORPORATED AREAS	320003	2195	E

Notice to User: The **Map Number** shown below should be used when placing map orders; the **Community Number** shown above should be used on insurance applications for the subject community.

MAP NUMBER
32003C2195 E

MAP REVISED:
SEPTEMBER 27, 2002

Federal Emergency Management Agency

GRAPHIC SCALE

1,000 500 0 1,000 2,000 3,000 4,000


(In Feet)

1 inch = 1000 ft.

FIGURE 3

FEMA FLOODZONE MAP

PBS&J
2270 Corporate Circle
Suite 100
Henderson, Nevada 8907
Tele: 702-263-7275
Fax: 702-263-7200



ZONE A TO BE Removed

GRAPHIC SCALE

1,000 500 0 1,000 2,000 3,000 4,000

(In Feet)

1 inch = 1000 ft.

FIRM

FLOOD INSURANCE RATE MAP

CLARK COUNTY, NEVADA AND INCORPORATED AREAS

PANEL 2195 OF 4090

(SEE MAP INDEX FOR FIRM PANEL LAYOUT)

CONTAINS:

COMMUNITY	NUMBER	PANEL	SUFFIX
LAS VEGAS, CITY OF	320276	2195	E
CLARK COUNTY, UNINCORPORATED AREAS	320003	2195	E

Notice to User: The **Map Number** shown below should be used when placing map orders; the **Community Number** shown above should be used on insurance applications for the subject community.

MAP NUMBER 32003C2195 E

MAP REVISED: SEPTEMBER 27, 2002

Federal Emergency Management Agency


Proposed Flood Zone

FIGURE 4

ANNOTATED POST PROJECT FEMA FLOODZONE MAP

PBS&J
2270 Corporate Circle
Suite 100
Henderson, Nevada 89074
Tele: 702-263-7275
Fax: 702-263-7200

ENGINEERING - PLANNING - SURVEYING - CONSTRUCTION SERVICES



AIR PHOTO COLLECTED SPRING, 2004

500 250 0 500 1,000

(In Feet)

1 inch = 500 ft.

NOTES

1. THE HECRAS MODEL CROSS-SECTION ELEVATIONS ARE BASED ON NAVD 88.

I HEREBY CERTIFY THAT THE INFORMATION USED TO PREPARE THIS CLOMR IS IN SUBSTANTIAL CONFORMANCE WITH THE PROPOSED CHANNEL IMPROVEMENT PLANS LOCATED IN APPENDIX E.


MATTHEW S. BAIRD, NV 13684 — DATE 12/21/04

POST PROJECT CONDITIONS CROSS SECTION (TYP)

WORKMAP

CHARLESTON BLVD TO LAS VEGAS WASH FIGURE 5

PBS&J
2270 Corporate Circle
Suite 100
Henderson, Nevada 89074
Tele: 702-263-7275
Fax: 702-263-7200
ENGINEERING - PLANNING - SURVEYING - CONSTRUCTION SERVICES



Proposed Flood Zone

Flood Zone

- Zone A
- Zone AE
- Zone AO

NOTES

1. THE HECRAS MODEL CROSS-SECTION ELEVATIONS ARE BASED ON NAVD 88.

500 250 0 500 1,000

(In Feet)

1 inch = 500 ft.

PROPOSED FLOODZONE

CHARLESTON BLVD TO
LAS VEGAS WASH
FIGURE 6

PBS&J
2270 Corporate Circle
Suite 100
Henderson, Nevada 89074
Tele: 702-263-7275
Fax: 702-263-7200
ENGINEERING - PLANNING - SURVEYING - CONSTRUCTION SERVICES

Appendix C: Hydrology

RFIS-CC.OUT

```
1*****************************************
*                                       *
*   FLOOD HYDROGRAPH PACKAGE  (HEC-1)   *
*              JUN  1998                *
*            VERSION 4.1                *
*                                       *
*  RUN DATE   30SEP04  TIME  13:09:52   *
*                                       *
*****************************************
```

```
*****************************************
*                                       *
*    U.S. ARMY CORPS OF ENGINEERS       *
*    HYDROLOGIC ENGINEERING CENTER      *
*         609 SECOND STREET             *
*       DAVIS, CALIFORNIA 95616         *
*           (916) 756-1104              *
*                                       *
*****************************************
```

```
X     X  XXXXXXX   XXXXX           X
X     X  X        X     X         XX
X     X  X        X               X
XXXXXXX  XXXX     X        XXXXX  X
X     X  X        X               X
X     X  X        X     X         X
X     X  XXXXXXX   XXXXX          XXX
```

THIS PROGRAM REPLACES ALL PREVIOUS VERSIONS OF HEC-1 KNOWN AS HEC1 (JAN 73), HEC1GS, HEC1DB, AND HEC1KW.

THE DEFINITIONS OF VARIABLES -RTIMP- AND -RTIOR- HAVE CHANGED FROM THOSE USED WITH THE 1973-STYLE INPUT STRUCTURE.
THE DEFINITION OF -AMSKK- ON RM-CARD WAS CHANGED WITH REVISIONS DATED 28 SEP 81. THIS IS THE FORTRAN77 VERSION
NEW OPTIONS: DAMBREAK OUTFLOW SUBMERGENCE , SINGLE EVENT DAMAGE CALCULATION, DSS:WRITE STAGE FREQUENCY,
DSS:READ TIME SERIES AT DESIRED CALCULATION INTERVAL LOSS RATE:GREEN AND AMPT INFILTRATION
KINEMATIC WAVE: NEW FINITE DIFFERENCE ALGORITHM


```
          LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

                    *DIAGRAM
*** FREE ***
               1    ID                    RANGE WASH - FLOOD INSURANCE RESTUDY
               2    ID              FOR: CLARK COUNTY REGIONAL FLOOD CONTROL DISTRICT
               3    ID                 BY: POST, BUCKLEY, SCHUH & JERNIGAN, INC.
               4    ID                          JOB. NO. 51804
               5    ID                       HEC-1 FILE: RFIS-CC.DAT
               6    ID                          DECEMBER 1995
               7    ID
               8    ID                    EXISTING CONDITIONS DOWNSTREAM OF THE
               9    ID           CONFLUENCE DETENTION BASIN, CURRENTLY UNDER CONSTRUCTION.
              10    ID         STORM CENTERING FOR NODE V2, AT SLOAN CHANNEL DOWNSTREAM OF STEWART,
              11    ID         AND FOR NODE CC, AT THE SLOAN CHANNEL AND LAS VEGAS WASH CONFLUENCE.
              12    ID
              13    ID    ************************************************************************
              14    ID    *              FROM: CCRFCD LAS VEGAS VALLEY MASTER PLAN UPDATE        *
              15    ID    *                          RANGE WASH WATERSHED                        *
              16    ID    *                JAMES M. MONTGOMERY, CONSULTING ENGINEERS, INC.       *
              17    ID    *                              JANUARY 1991                            *
              18    ID    *                  PRESENT CONDITIONS, EXISTING FACILITIES             *
              19    ID    *                   BASED ON RANGE WASH FACILITIES STUDY               *
              20    ID    *                      BOYLE ENGINEERS CORP-JULY 1989                  *
              21    ID    *                                                                      *
              22    ID    *                   (CONVERTED RK TO RM IN UPLAND SUBAREAS)            *
              23    ID    *MODIFIED TO REMOVE SUBAREAS TRIBUTARY TO WEST RANGE DIVERSION DIKE (1/91)*
              24    ID    ************************************************************************
              25    ID    *                    100-YEAR, 6-HOUR STORM, AMC 2.0                   *
              26    ID    ************************************************************************
              27    ID    * STORM DISTRIBUTION 5 (SDN 5) FOR TOTAL BASIN AREA GREATER THAN 10 SQ.MI.*
              28    ID    *  ONLY FOR DRAINAGE BASINS DOWNSTREAM OF CONFLUENCE THE DETENTION BASIN, *
              29    ID    *  JR DARF RATIO 0.85 FOR NODE V2, AT SLOAN CHANNEL DOWNSTREAM OF STEWART *
              30    ID    *  AND 0.82 FOR NODE CC, AT THE SLOAN CHANNEL/LAS VEGAS WASH CONFLUENCE.  *
              31    ID    ************************************************************************
              32    ID
              33    IT       05       0       0     200
              34    IO        5       0       0
              35    JR     PREC    0.85    0.82

              36    KK     318C
              37    KM    BASIN 318C CONTRIBUTES FLOW TO NODE M1.
              38    KM    NODE M1 GIVES THE TOTAL FLOW IN THE SLOAN CHANNEL JUST UPSTREAM OF
              39    KM    THE CONFLUENCE WITH THE RANGE WASH CHANNEL.
              40    BA     1.28
              41    PB     2.93
              42    PC     .000    .020    .059    .080    .110    .144    .150    .160    .168    .171
              43    PC     .180    .182    .187    .190    .197    .202    .210    .220    .230    .241
              44    PC     .250    .259    .265    .280    .290    .300    .305    .309    .310    .317
              45    PC     .321    .327    .333    .346    .361    .381    .408    .430    .477    .514
              46    PC     .561    .630    .710    .720    .731    .752    .779    .790    .795    .804
              47    PC     .810    .820    .826    .840    .859    .889    .910    .938    .966    .970
              48    PC     .974    .979    .981    .983    .985    .989    .990    .992    .993    .996
              49    PC     .997    .999   1.00
              50    LS        0      79
              51    UD     0.75
                    *
```



```
          LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

              52    KK     321-M
              53    KM    BASIN 321-M CONTRIBUTES FLOW TO THE RANGE WASH CHANNEL UPSTREAM OF
              54    KM    ITS CONFLUENCE WITH THE SLOAN CHANNEL.
              55    BA    0.691
              56    PB     2.77
              57    LS        0      67
              58    UD     1.66
```

```
                *
     59         KK NODE.M3
     60         KM   COMBINE FLOWS FROM M1 AND M2 AT NODE M3.
     61         KM   NODE M3 IS THE TOTAL FLOW AT THE CONFLUENCE OF THE SLOAN CHANNEL
     62         KM   AND THE RANGE WASH CHANNEL AT SLOAN AND CAREY AVENUE.
     63         HC       2
                *
     64         KK   M3-S1
     65         KM   ROUTE FLOW FROM NODE M3 THROUGH THE SLOAN CHANNEL TO NODE S1.
     66         RK    2640   0.004   0.015       0    TRAP      40       3
                *
     67         KK   48A-M
     68         KM   BASIN 48A-M CONTRIBUTES FLOW TO NODE S1.
     69         BA   0.715
     70         PB    2.93
     71         LS       0      83
     72         UD    0.44
                *
     73         KK      S1
     74         KM   COMBINE FLOW FROM M3 WITH FLOW FROM BASIN 48A-M.
     75         KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL AT LAKE MEAD BLVD.
     76         HC       2
                *
     77         KK   S1-S2
     78         KM   ROUTE FLOW FROM S1 THROUGH THE SLOAN CHANNEL TO S2.
     79         RK    2640   0.002   0.015       0    TRAP      50       2
                *
     80         KK     48B
     81         KM   BASIN 48B CONTRIBUTES FLOW TO NODE R.
     82         BA   1.142
     83         PB    3.10
     84         LS       0      89
     85         UD    0.51
                *
     86         KK    R-S2
     87         KM   ROUTE FLOW FROM R THROUGH BASIN 49A-M TO NODE S2.
     88         RK   10500   0.022    0.02       0    TRAP      10      20
                *
1                                        HEC-1 INPUT                                                    PAGE  3

           LINE  ID.......1.......2.......3.......4.......5.......6.......7.......8.......9......10

     89         KK   49A-M
     90         KM   BASIN 49A-M CONTRIBUTES FLOW TO NODE S2.
     91         BA   0.693
     92         PB    2.85
     93         LS       0      79
     94         UD    0.49
                *
     95         KK NODE.S2
     96         KM   COMBINE FLOW FROM NODES S1 AND R WITH FLOW FROM BASIN 49A-M AT NODE S2.
     97         KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL AT OWENS AVENUE.
     98         HC       3
                *
     99         KK   S2-S3
    100         KM   ROUTE FLOW FROM S2 THROUGH THE SLOAN CHANNEL TO S3.
    101         RK    2640   0.004   0.014       0    TRAP      60       2
                *
    102         KK     49C
    103         KM   BASIN 49C CONTRIBUTES FLOW TO NODE S3.
    104         BA   0.426
    105         PB    2.85
    106         LS       0      76
    107         UD    0.53
                *
    108         KK NODE.S3
    109         KM   COMBINE FLOW FROM S2 WITH FLOW FROM BASIN 49C AT NODE S3.
    110         KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL AT WASHINGTON AVE.
    111         HC       2
                *
    112         KK   49B-M
    113         KM   BASIN 49B-M CONTRIBUTES FLOW TO NODE T1.
    114         KM   NODE T1 REPRESENTS THE TOTAL FLOW TO THE DIVERSION CHANNEL ALONG
    115         KM   WASHINGTON AVE. JUST UPSTREAM OF THE SLOAN CHANNEL.
    116         BA   1.977
    117         PB    3.00
    118         LS       0      85
    119         UD    0.61
                *
    120         KK NODE.S4
    121         KM   COMBINE FLOW FROM S3 WITH FLOW FROM T1 AT NODE S4.
    122         KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL AT HARRIS AVE.
    123         HC       2
                *
1                                        HEC-1 INPUT                                                    PAGE  4

           LINE  ID.......1.......2.......3.......4.......5.......6.......7.......8.......9......10

    124         KK   50B-M
    125         KM   BASIN 50B-M CONTRIBUTES FLOW TO NODE V1.
```

```
126          BA   0.628
127          PB    3.00
128          LS       0      80
129          UD    0.39
             *

130          KK NODE.V1
131          KM   COMBINE FLOW FROM S4 WITH FLOW FROM BASIN 50B-M AT NODE V1.
132          KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL AT BONANZA RD.
133          HC       2
             *

134          KK   V1-V2
135          KM   ROUTE FLOWS FROM V1 THROUGH THE SLOAN CHANNEL TO NODE V2.
136          RK    2640   0.008   0.014        0    TRAP      60       2
             *

137          KK   50A-M
138          KM   BASIN 50A-M CONTRIBUTES FLOW TO NODE V2.
139          BA   0.207
140          PB    2.85
141          LS       0      73
142          UD    0.46
             *

143          KK NODE.V2
144          KM   COMBINE FLOW FROM V1 WITH FLOW FROM BASIN 50A-M AT NODE V2.
145          KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL AT STEWART AVE.
146          HC       2
             *

147          KK   324-M
148          KM   BASIN 324-M CONTRIBUTES FLOW TO NODE V3.
149          BA   3.026
150          PB    2.85
151          LS       0      72
152          UD    0.77
             *

153          KK    STEW
154          KM   DIVERT FLOWS WHICH CONTINUE IN CHRISTY & LINN LANES, ETC
155          KM   FLOW IN STEWART GOES TO SLOAN CHANNEL
156          KM   FLOW IN CHRISTY GOES TOWARD LAS VEGAS WASH
157          DT      CL
158          DI       0      15     600
159          DQ       0       0     330
             *
```



```
LINE         ID.......1.......2.......3.......4.......5.......6.......7.......8.......9......10

160          KK NODE.V3
161          KM   COMBINE FLOW FROM V2 WITH FLOW FROM BASIN 324-M AT NODE V3.
162          KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL
163          KM   SOUTH OF STEWART AVE.
164          HC       2
             *

165          KK   V3-V4
166          KM   ROUTE V3 THROUGH THE SLOAN CHANNEL TO V4.
167          RK    2000   0.003    0.03        0    TRAP      80       2
             *

168          KK     CLR
169          KM   RETREIVE FLOW IN CHRISTY AND LINN LANES
170          DR      CL
             *

171          KK    LINN
172          KM   FLOW IN LINN LANE GOES TO BASIN 326-A THEN TO SLOAN CHANNEL
173          KM   FLOW IN CHRISTY GOES TO LAS VEGAS WASH
174          DT   CHRIS
175          DI       0     100     500
176          DQ       0      78     390
             *

177          KK   326-A
178          KM   BASIN 326-A CONTRIBUTES FLOW TO NODE V4.
179          KM   GIVES TOTAL FLOW IN THE SECTION OF CHARLESTON BLVD. WEST OF SLOAN CHANNEL.
180          BA   0.231
181          PB    2.85
182          LS       0      79
183          UD    0.39
             *

184          KK  326-AL
185          KM   BASIN 326-A AND FLOW IN LINN LANE
186          HC       2
             *

187          KK    OR-1
188          KM   ORCHARDS OFFSITE DRAINAGE BASIN 01; CONTRIBUTES FLOW TO NODE X1.
189          KM   * BASINS WITH THE "OR" PREFIX ARE TAKEN FROM THE "CONCEPTUAL MASTER        *
190          KM   * DRAINAGE STUDY FOR LEWIS HOMES - ORCHARDS," BY PENTACORE, JANUARY, 1992. *
191          KM   * THE MAJORITY OF THE ORCHARDS SITE IS CONSTRUCTED; HOWEVER, THE PLANNED   *
192          KM   * ORCHARDS DETENTION BASIN IS NOT CONSTRUCTED. HYDROLOGY FROM THE ORCHARDS *
193          KM   * DRAINAGE STUDY HAS BEEN MODIFIED TO REPRESENT APPROXIMATE EXISTING       *
194          KM   * CONDITIONS, RATHER THAN FULLY DEVELOPED CONDITIONS.                      *
195          PB    3.00
196          BA   0.279
197          LS       0      89
198          UD    0.18
             *
```

```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

 199      KK   X1-X2
 200      KM   ROUTE X1 THROUGH BASIN OR-2 TO NODE X2.
 201      RK   10000   0.033    0.02       0    TRAP      20       10
          *

 202      KK    OR-2
 203      KM   ORCHARDS OFFSITE DRAINAGE BASIN 02; CONTRIBUTES FLOW TO NODE X2.
 204      BA   1.206
 205      PB    2.93
 206      LS       0      75
 207      UD    0.60
          *

 208      KK NODE.X2
 209      KM   COMBINE FLOW FROM X1 AND BASIN OR-2 AT NODE X2.
 210      KM   GIVES TOTAL FLOW IN THE SECTION OF CHARLESTON BLVD. EAST OF SLOAN CHANNEL.
 211      HC       2
          *

 212      KK NODE.V4
 213      KM   COMBINE FLOW FROM V3, X2 AND BASIN 326-A.
 214      KM   GIVES TOTAL FLOW TO THE SLOAN CHANNEL AT CHARLESTON BLVD.
 215      HC       3
          *

 216      KK   OR-11
 217      KM   ORCHARDS ONSITE BASIN OR-11 CONTRIBUTES FLOW TO NODE V5.
 218      BA  0.0428
 219      PB    2.85
 220      LS       0      75
 221      UD    0.20
          *

 222      KK NODE.V5
 223      KM   COMBINE FLOW FROM V4 AND BASIN OR-11.
 224      KM   TOTAL FLOW TO THE SLOAN CHANNEL APPROX. 1500 FT. SOUTH OF CHARLESTON BLVD.
 225      HC       2
          *

 226      KK   V5-Z2
 227      KM   ROUTE V5 THROUGH SLOAN CHANNEL TO THE ORCHARDS CHANNEL CONFLUENCE AT Z2.
 228      RK    2800   0.005    0.03       0    TRAP      60       2
          *

 229      KK    OR-3
 230      KM   ORCHARDS OFFSITE DRAINAGE BASIN O3.
 231      KM   GIVES FLOW TO NODE Y1, LOCATED AT CHARLESTON WEST OF HOLLYWOOD.
 232      BA   0.205
 233      PB    3.00
 234      LS       0      82
 235      UD    0.42
          *
```



```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

 236      KK   Y1-Z1
 237      KM   ROUTE NODE Y1 THROUGH BASIN OR-12 TO NODE Z1.
 238      RK    5500   0.011   0.016       0    TRAP      50       1
          *

 239      KK    OR-4
 240      KM   ORCHARDS OFFSITE DRAINAGE BASIN O4.
 241      KM   CONTRIBUTES FLOW TO NODE Y2.
 242      BA   0.448
 243      PB    3.00
 244      LS       0      88
 245      UD    0.29
          *

 246      KK   Y2-Y3
 247      KM   ROUTE NODE Y2 THROUGH BASIN OR-5 TO NODE Y3.
 248      RM       4    0.33    0.15
          *

 249      KK    OR-5
 250      KM   ORCHARDS OFFSITE DRAINAGE BASIN O5.
 251      KM   CONTRIBUTES FLOW TO NODE Y3.
 252      BA   0.373
 253      PB    3.00
 254      LS       0      77
 255      UD    0.44
          *

 256      KK      Y3
 257      KM   COMBINE FLOWS FROM Y2 AND BASIN OR-5 AT HOLLYWOOD.
 258      HC       2
          *

 259      KK   Y3-Z1
 260      KM   ROUTE Y3 THROUGH BASIN OR-12 TO NODE Z1.
 261      RK    5000   0.012   0.016       0    TRAP      50       1
          *

 262      KK   OR-6A
 263      KM   ORCHARDS OFFSITE DRAINAGE BASIN O6A.
 264      BA   0.264
 265      PB    3.00
 266      LS       0      88
 267      UD     .13
```

```
                *
  268           KK   OR-6B
  269           KM   ORCHARDS OFFSITE DRAINAGE BASIN O6B,
  270           BA   0.160
  271           PB    3.00
  272           LS       0      89
  273           UD     .14
                *
1                                        HEC-1 INPUT                                                    PAGE  8

 LINE           ID.......1.......2.......3.......4.......5.......6.......7.......8.......9......10

  274           KK   OR-6C
  275           KM   ORCHARDS OFFSITE DRAINAGE BASIN O6C.
  276           BA   0.191
  277           PB    3.00
  278           LS       0      87
  279           UD     .18
                *
  280           KKNODE.AA1
  281           KM   COMBINE FLOWS FROM BASINS OR-6A, OR-6B & OR-6C.
  282           HC       3
                *
  283           KK AA1-AA2
  284           KM   ROUTE AA1 THROUGH BASIN OR-7 TO NODE AA2.
  285           RM       4    0.32    0.15
                *
  286           KK    OR-7
  287           KM   ORCHARDS OFFSITE DRAINAGE BASIN O7.
  288           BA   0.613
  289           PB    3.00
  290           LS       0      77
  291           UD    0.49
                *
  292           KKNODE.AA2
  293           KM   COMBINE AA1 WITH FLOW FROM BASIN OR-7 AT NODE AA2.
  294           HC       2
                *
  295           KK  AA2-Z1
  296           KM   ROUTE AA2 THROUGH BASIN OR-12 TO NODE Z1.
  297           RK    4500   0.013   0.016       0    TRAP      50       1
                *
  298           KK    OR-8
  299           KM   ORCHARDS OFFSITE BASIN O8; CONTRIBUTES FLOW TO NODE AA3.
  300           BA   0.017
  301           PB    3.00
  302           LS       0      77
  303           UD    0.18
                *
  304           KK  R8-AA3
  305           KM   ROUTE FLOW FROM BASIN OR-8 THROUGH BASIN OR-9 TO NODE AA3 AT HOLLYWOOD.
  306           RM      10    0.82    0.15
                *
1                                        HEC-1 INPUT                                                    PAGE  9

 LINE           ID.......1.......2.......3.......4.......5.......6.......7.......8.......9......10

  307           KK    OR-9
  308           KM   ORCHARDS OFFSITE DRAINAGE BASIN O9; CONTRIBUTES FLOW TO NODE AA3.
  309           BA   0.278
  310           PB    3.00
  311           LS       0      77
  312           UD    0.65
                *
  313           KKNODE.AA3
  314           KM   COMBINE FLOWS FROM BASINS OR-8 AND OR-9 AT NODE AA3.
  315           HC       2
                *
  316           KK  AA3-Z1
  317           KM   ROUTE AA3 THROUGH BASIN OR-12 TO NODE Z1.
  318           RK    4500   0.012   0.016       0    TRAP      50       1
                *
  319           KK   OR-12
  320           KM   ORCHARDS ONSITE DRAINAGE BASIN 12; CONTRIBUTES FLOW TO NODE Z1.
  321           BA   0.525
  322           PB    2.85
  323           LS       0      76
  324           UD    0.39
                *
  325           KK NODE.Z1
  326           KM   COMBINE FLOW FROM NODES Y1, Y3, AA2, AA3 AND BASIN OR-12 AT NODE Z1.
  327           KM   NODE Z1 REPRESENTS THE TOTAL FLOW IN THE CONCRETE-LINED ORCHARDS CHANNEL
  328           KM   TRIBUTARY TO THE SLOAN CHANNEL.
  329           HC       5
                *
  330           KK NODE.Z2
  331           KM   COMBINE FLOW FROM NODES V5 AND Z1.
  332           KM   TOTAL FLOW IN THE SLOAN CHANNEL AT ITS CONFLUENCE WITH THE ORCHARDS CHANNEL.
  333           HC       2
                *
```

```
 334          KK   OR-13
 335          KM   ORCHARDS ONSITE DRAINAGE BASIN OR-13; CONTRIBUTES FLOW TO NODE Z3.
 336          BA   0.120
 337          PB    2.85
 338          LS       0       84
 339          UD    0.29
              *

 340          KK NODE.Z3
 341          KM   COMBINE FLOW FROM NODES Z2 AND BASIN OR-13 AT NODE Z3.
 342          KM   NODE Z3 IS THE TOTAL FLOW IN THE SLOAN CHANNEL AT APPROXIMATELY
 343          KM   450 FEET SOUTH OF THE ORCHARDS CHANNEL CONFLUENCE.
 344          HC       2
              *
1                                          HEC-1 INPUT                                                    PAGE 10

LINE          ID.......1.......2.......3.......4.......5.......6.......7.......8.......9......10

 345          KK   OR-10
 346          KM   ORCHARDS OFFSITE DRAINAGE BASIN O10.
 347          KM   CONTRIBUTES FLOW TO NODE BB1, LOCATED AT THE HOLLYWOOD/SAHARA INTERSECTION.
 348          BA  0.0984
 349          PB    3.00
 350          LS       0       77
 351          UD    0.45
              *

 352          KK BB1-BB2
 353          KM   ROUTE BB1 THROUGH SAHARA AVENUE TO NODE BB2.
 354          RK    4000   0.014   0.016       0    TRAP     100       1
              *

 355          KK   OR-14
 356          KM   ORCHARDS ONSITE DRAINAGE BASIN 14; CONTRIBUTES FLOW TO NODE BB2.
 357          BA  0.0937
 358          PB    2.85
 359          LS       0       75
 360          UD    0.33
              *

 361          KKNODE.BB2
 362          KM   NODE BB2 REPRESENTS THE TOTAL FLOW IN SAHARA AVE. EAST OF THE SLOAN CHANNEL.
 363          HC       2
              *

 364          KKNODE.BB3
 365          KM   COMBINE FLOW FROM Z3 WITH FLOW FROM BB2.
 366          KM   NODE BB3 IS THE TOTAL FLOW IN SLOAN CHANNEL AT SAHARA AVE.
 367          HC       2
              *


 368          KK  BB3-CC
 369          KM   ROUTE BB3 THROUGH THE SLOAN CHANNEL TO NODE CC.
 370          RK    1700   0.006   0.025       0    TRAP      80       2
              *


 371          KK   52A-M
 372          KM   BASIN 52A-M CONTRIBUTES FLOW TO NODE CC.
 373          BA   0.286
 374          PB    2.85
 375          LS       0       73
 376          UD    0.84
              *

 377          KK NODE.CC
 378          KM   COMBINE FLOW FROM  NODE BB3 WITH FLOW FROM BASINS 326-B AND 52A-M.
 379          KM   NODE CC REPRESENTS THE TOTAL FLOW IN THE SLOAN CHANNEL JUST UPSTREAM OF
 380          KM   ITS CONFLUENCE WITH THE LAS VEGAS WASH.
 381          HC       2
              *
 382          ZZ
1
           SCHEMATIC DIAGRAM OF STREAM NETWORK
 INPUT
  LINE     (V) ROUTING          (--->) DIVERSION OR PUMP FLOW

   NO.     (.) CONNECTOR        (<---) RETURN OF DIVERTED OR PUMPED FLOW

    36       318C
               .
               .
    52         .       321-M
               .         .
               .         .
    59     NODE.M3.............
             V
             V
    64      M3-S1
               .
               .
    67         .       48A-M
               .         .
               .         .
    73        S1.............
              V
              V
    77      S1-S2
               .
               .
    80         .        48B
               .         V
               .         V
    86         .       R-S2
```


89
49A-M
95
NODE.S2
99
S2-S3
102
49C
108
NODE.S3
112
49B-M
120
NODE.S4
124
50B-M
130
NODE.V1
134
V1-V2
137
50A-M
143
NODE.V2
147
324-M
157
CL
153
STEW
160
NODE.V3
165
V3-V4
170
CL
168
CLR
174
CHRIS
171
LINN
177
326-A
184
326-AL
187
OR-1
199
X1-X2
202
OR-2
208
NODE.X2
212
NODE.V4
216
OR-11
222
NODE.V5
226
V5-Z2
229
OR-3
236
Y1-Z1
239
OR-4
246
Y2-Y3
249
OR-5
256
Y3



(***) RUNOFF ALSO COMPUTED AT THIS LOCATION

```
1*****************************************
*                                       *
*   FLOOD HYDROGRAPH PACKAGE  (HEC-1)   *
*              JUN  1998                *
*           VERSION 4.1                 *
*                                       *
*  RUN DATE   30SEP04  TIME  13:09:52   *
*                                       *
*****************************************
```

```
*****************************************
*                                       *
*   U.S. ARMY CORPS OF ENGINEERS        *
*   HYDROLOGIC ENGINEERING CENTER       *
*        609 SECOND STREET              *
*      DAVIS, CALIFORNIA 95616          *
*         (916) 756-1104                *
*                                       *
*****************************************
```

RANGE WASH - FLOOD INSURANCE RESTUDY
FOR: CLARK COUNTY REGIONAL FLOOD CONTROL DISTRICT
BY: POST, BUCKLEY, SCHUH & JERNIGAN, INC.
JOB. NO. 51804
HEC-1 FILE: RFIS-CC.DAT
DECEMBER 1995

EXISTING CONDITIONS DOWNSTREAM OF THE

CONFLUENCE DETENTION BASIN, CURRENTLY UNDER CONSTRUCTION.
STORM CENTERING FOR NODE V2, AT SLOAN CHANNEL DOWNSTREAM OF STEWART,
AND FOR NODE CC, AT THE SLOAN CHANNEL AND LAS VEGAS WASH CONFLUENCE.

```
**********************************************************************
*            FROM: CCRFCD LAS VEGAS VALLEY MASTER PLAN UPDATE        *
*                          RANGE WASH WATERSHED                      *
*              JAMES M. MONTGOMERY, CONSULTING ENGINEERS, INC.       *
*                               JANUARY 1991                         *
*                PRESENT CONDITIONS, EXISTING FACILITIES            *
*                 BASED ON RANGE WASH FACILITIES STUDY              *
*                    BOYLE ENGINEERS CORP-JULY 1989                 *
*                                                                   *
*                  (CONVERTED RK TO RM IN UPLAND SUBAREAS)          *
*MODIFIED TO REMOVE SUBAREAS TRIBUTARY TO WEST RANGE DIVERSION DIKE (1/91)*
**********************************************************************
*                        100-YEAR, 6-HOUR STORM, AMC 2.0             *
**********************************************************************
* STORM DISTRIBUTION 5 (SDN 5) FOR TOTAL BASIN AREA GREATER THAN 10 SQ.MI.*
*  ONLY FOR DRAINAGE BASINS DOWNSTREAM OF CONFLUENCE THE DETENTION BASIN, *
*  JR DARF RATIO 0.85 FOR NODE V2, AT SLOAN CHANNEL DOWNSTREAM OF STEWART *
*  AND 0.82 FOR NODE CC, AT THE SLOAN CHANNEL/LAS VEGAS WASH CONFLUENCE.  *
**********************************************************************
```

```
   34 IO          OUTPUT CONTROL VARIABLES
                        IPRNT           5  PRINT CONTROL
                        IPLOT           0  PLOT CONTROL
                        QSCAL          0.  HYDROGRAPH PLOT SCALE

      IT          HYDROGRAPH TIME DATA
                        NMIN            5  MINUTES IN COMPUTATION INTERVAL
                       IDATE       1    0  STARTING DATE
                       ITIME         0000  STARTING TIME
                          NQ          200  NUMBER OF HYDROGRAPH ORDINATES
                      NDDATE       1    0  ENDING DATE
                      NDTIME        1635  ENDING TIME
                       ICENT          19  CENTURY MARK

                    COMPUTATION INTERVAL      .08 HOURS
                         TOTAL TIME BASE    16.58 HOURS

            ENGLISH UNITS
                 DRAINAGE AREA          SQUARE MILES
                 PRECIPITATION DEPTH    INCHES
                 LENGTH, ELEVATION      FEET
                 FLOW                   CUBIC FEET PER SECOND
                 STORAGE VOLUME         ACRE-FEET
                 SURFACE AREA           ACRES
                 TEMPERATURE            DEGREES FAHRENHEIT

      JP          MULTI-PLAN OPTION
                      NPLAN           1  NUMBER OF PLANS

      JR          MULTI-RATIO OPTION
                      RATIOS OF PRECIPITATION
                       .85       .82
1
```

PEAK FLOW AND STAGE (END-OF-PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
FLOWS IN CUBIC FEET PER SECOND, AREA IN SQUARE MILES
TIME TO PEAK IN HOURS

OPERATION	STATION	AREA	PLAN		RATIOS APPLIED TO PRECIPITATION RATIO 1 .85	RATIO 2 .82
HYDROGRAPH AT						
+	318C	1.28	1	FLOW	312.	290.
				TIME	4.25	4.25
HYDROGRAPH AT						
+	321-M	.69	1	FLOW	45.	41.
				TIME	5.92	5.92
2 COMBINED AT						
+	NODE.M3	1.97	1	FLOW	323.	299.
				TIME	4.25	4.25
ROUTED TO						
+	M3-S1	1.97	1	FLOW	322.	298.
				TIME	4.25	4.25
HYDROGRAPH AT						
+	48A-M	.71	1	FLOW	290.	272.
				TIME	3.83	3.83
2 COMBINED AT						
+	S1	2.69	1	FLOW	545.	507.
				TIME	4.00	4.08
ROUTED TO						
+	S1-S2	2.69	1	FLOW	545.	507.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	48B	1.14	1	FLOW	627.	596.
				TIME	3.92	3.92
ROUTED TO						
+	R-S2	1.14	1	FLOW	621.	589.
				TIME	4.00	4.08
HYDROGRAPH AT						

				TIME	4.08	4.08
HYDROGRAPH AT						
+	OR-11	.04	1	FLOW	14.	13.
				TIME	3.58	3.58
2 COMBINED AT						
+	NODE.V5	12.54	1	FLOW	3078.	2876.
				TIME	4.08	4.08
ROUTED TO						
+	V5-Z2	12.54	1	FLOW	3060.	2855.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	OR-3	.20	1	FLOW	84.	79.
				TIME	3.83	3.83
ROUTED TO						
+	Y1-Z1	.20	1	FLOW	83.	77.
				TIME	3.92	3.92
HYDROGRAPH AT						
+	OR-4	.45	1	FLOW	293.	278.
				TIME	3.67	3.67
ROUTED TO						
+	Y2-Y3	.45	1	FLOW	258.	245.
				TIME	4.00	4.00
HYDROGRAPH AT						
+	OR-5	.37	1	FLOW	111.	102.
				TIME	3.83	3.83
2 COMBINED AT						
+	Y3	.82	1	FLOW	362.	342.
				TIME	4.00	4.00
ROUTED TO						
+	Y3-Z1	.82	1	FLOW	359.	339.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	OR-6A	.26	1	FLOW	223.	212.
				TIME	3.58	3.58
HYDROGRAPH AT						
+	OR-6B	.16	1	FLOW	140.	133.
				TIME	3.58	3.58
HYDROGRAPH AT						
+	OR-6C	.19	1	FLOW	146.	138.
				TIME	3.58	3.58
3 COMBINED AT						
+	NODE.AA1	.62	1	FLOW	508.	483.
				TIME	3.58	3.58
ROUTED TO						
+	AA1-AA2	.62	1	FLOW	408.	387.
				TIME	3.83	3.83
HYDROGRAPH AT						
+	OR-7	.61	1	FLOW	173.	160.
				TIME	3.92	3.92
2 COMBINED AT						
+	NODE.AA2	1.23	1	FLOW	578.	544.
				TIME	3.83	3.83
ROUTED TO						
+	AA2-Z1	1.23	1	FLOW	572.	539.
				TIME	3.92	3.92
HYDROGRAPH AT						
+	OR-8	.02	1	FLOW	8.	7.
				TIME	3.58	3.58
ROUTED TO						
+	R8-AA3	.02	1	FLOW	5.	5.
				TIME	4.42	4.42
HYDROGRAPH AT						
+	OR-9	.28	1	FLOW	68.	63.
				TIME	4.08	4.08
2 COMBINED AT						
+	NODE.AA3	.29	1	FLOW	72.	66.
				TIME	4.17	4.17
ROUTED TO						
+	AA3-Z1	.29	1	FLOW	71.	66.
				TIME	4.25	4.25
HYDROGRAPH AT						
+	OR-12	.52	1	FLOW	137.	126.
				TIME	3.83	3.83
5 COMBINED AT						
+	NODE.Z1	3.07	1	FLOW	1177.	1101.
				TIME	3.92	3.92
2 COMBINED AT						
+	NODE.Z2	15.62	1	FLOW	4163.	3891.
				TIME	4.08	4.08

FOR PLAN = 1 RATIO= .85

V1-V2	MANE	.67	2419.16	241.61	1.01	5.00	2409.21	245.00	1.01

CONTINUITY SUMMARY (AC-FT) - INFLOW= .4070E+03 EXCESS= .0000E+00 OUTFLOW= .4070E+03 BASIN STORAGE= .1041E-01 PERCENT ERROR= .0

FOR PLAN = 1 RATIO= .82

V1-V2	MANE	.61	2269.59	241.59	.95	5.00	2262.06	245.00	.95

CONTINUITY SUMMARY (AC-FT) - INFLOW= .3815E+03 EXCESS= .0000E+00 OUTFLOW= .3815E+03 BASIN STORAGE= .1066E-01 PERCENT ERROR= .0

FOR PLAN = 1 RATIO= .85

V3-V4	MANE	1.18	2614.11	247.01	.78	5.00	2610.32	245.00	.78

CONTINUITY SUMMARY (AC-FT) - INFLOW= .4507E+03 EXCESS= .0000E+00 OUTFLOW= .4508E+03 BASIN STORAGE= .2760E-01 PERCENT ERROR= .0

FOR PLAN = 1 RATIO= .82

V3-V4	MANE	1.20	2447.30	247.21	.73	5.00	2441.87	245.00	.73

CONTINUITY SUMMARY (AC-FT) - INFLOW= .4216E+03 EXCESS= .0000E+00 OUTFLOW= .4217E+03 BASIN STORAGE= .2788E-01 PERCENT ERROR= .0

FOR PLAN = 1 RATIO= .85

X1-X2	MANE	4.27	229.82	223.45	1.51	5.00	219.70	225.00	1.51

CONTINUITY SUMMARY (AC-FT) - INFLOW= .2230E+02 EXCESS= .0000E+00 OUTFLOW= .2254E+02 BASIN STORAGE= .2110E-03 PERCENT ERROR= -1.1

FOR PLAN = 1 RATIO= .82

X1-X2	MANE	4.24	209.83	221.69	1.43	5.00	205.56	225.00	1.43

CONTINUITY SUMMARY (AC-FT) - INFLOW= .2113E+02 EXCESS= .0000E+00 OUTFLOW= .2129E+02 BASIN STORAGE= .1659E-03 PERCENT ERROR= -.8

FOR PLAN = 1 RATIO= .85

V5-Z2	MANE	1.18	3075.27	247.18	.80	5.00	3060.30	245.00	.80

CONTINUITY SUMMARY (AC-FT) - INFLOW= .5348E+03 EXCESS= .0000E+00 OUTFLOW= .5350E+03 BASIN STORAGE= .3889E-01 PERCENT ERROR= -.1

FOR PLAN = 1 RATIO= .82

V5-Z2	MANE	1.12	2873.14	247.49	.75	5.00	2854.86	245.00	.75

CONTINUITY SUMMARY (AC-FT) - INFLOW= .4997E+03 EXCESS= .0000E+00 OUTFLOW= .4999E+03 BASIN STORAGE= .3920E-01 PERCENT ERROR= -.1

FOR PLAN = 1 RATIO= .85

Y1-Z1	MANE	3.99	83.27	238.87	1.04	5.00	83.14	235.00	1.04

CONTINUITY SUMMARY (AC-FT) - INFLOW= .1131E+02 EXCESS= .0000E+00 OUTFLOW= .1134E+02 BASIN STORAGE= .1712E-02 PERCENT ERROR= -.3

FOR PLAN = 1 RATIO= .82

Y1-Z1	MANE	4.04	77.97	235.57	.97	5.00	77.49	235.00	.97

CONTINUITY SUMMARY (AC-FT) - INFLOW= .1059E+02 EXCESS= .0000E+00 OUTFLOW= .1063E+02 BASIN STORAGE= .1776E-02 PERCENT ERROR= -.4

FOR PLAN = 1 RATIO= .85

Y3-Z1	MANE	2.13	360.97	242.90	1.13	5.00	359.37	245.00	1.13

CONTINUITY SUMMARY (AC-FT) - INFLOW= .4939E+02 EXCESS= .0000E+00 OUTFLOW= .4946E+02 BASIN STORAGE= .1313E-02 PERCENT ERROR= -.2

FOR PLAN = 1 RATIO= .82

Y3-Z1	MANE	2.17	340.80	244.17	1.06	5.00	338.70	245.00	1.06

CONTINUITY SUMMARY (AC-FT) - INFLOW= .4642E+02 EXCESS= .0000E+00 OUTFLOW= .4650E+02 BASIN STORAGE= .1471E-02 PERCENT ERROR= -.2

FOR PLAN = 1 RATIO= .85

AA2-Z1	MANE	1.52	576.80	232.93	1.10	5.00	572.49	235.00	1.10

CONTINUITY SUMMARY (AC-FT) - INFLOW= .7186E+02 EXCESS= .0000E+00 OUTFLOW= .7197E+02 BASIN STORAGE= .1299E-02 PERCENT ERROR= -.2

FOR PLAN = 1 RATIO= .82

AA2-Z1	MANE	1.63	540.39	234.43	1.03	5.00	539.02	235.00	1.03

CONTINUITY SUMMARY (AC-FT) - INFLOW= .6749E+02 EXCESS= .0000E+00 OUTFLOW= .6759E+02 BASIN STORAGE= .1101E-02 PERCENT ERROR= -.1

FOR PLAN = 1 RATIO= .85

AA3-Z1	MANE	3.45	71.41	256.18	.77	5.00	71.33	255.00	.77

CONTINUITY SUMMARY (AC-FT) - INFLOW= .1214E+02 EXCESS= .0000E+00 OUTFLOW= .1216E+02 BASIN STORAGE= .1216E-02 PERCENT ERROR= -.2

```
          FOR PLAN = 1  RATIO=  .82
            AA3-Z1  MANE          3.45     66.15    256.72        .72       5.00     65.98    255.00          .72

CONTINUITY SUMMARY (AC-FT) - INFLOW= .1126E+02 EXCESS= .0000E+00 OUTFLOW= .1127E+02 BASIN STORAGE= .1284E-02 PERCENT ERROR=   -.1

          FOR PLAN = 1  RATIO=  .85
            BB1-BB2  MANE         5.00     28.84    240.58        .78       5.00     28.66    240.00          .78

CONTINUITY SUMMARY (AC-FT) - INFLOW= .4051E+01 EXCESS= .0000E+00 OUTFLOW= .4070E+01 BASIN STORAGE= .1893E-02 PERCENT ERROR=   -.5

          FOR PLAN = 1  RATIO=  .82
            BB1-BB2  MANE         5.00     26.55    244.95        .72       5.00     26.54    245.00          .72

CONTINUITY SUMMARY (AC-FT) - INFLOW= .3754E+01 EXCESS= .0000E+00 OUTFLOW= .3767E+01 BASIN STORAGE= .2057E-02 PERCENT ERROR=   -.4

          FOR PLAN = 1  RATIO=  .85
            BB3-CC  MANE           .55   4239.29    245.74        .84       5.00   4237.45    245.00          .84

CONTINUITY SUMMARY (AC-FT) - INFLOW= .7117E+03 EXCESS= .0000E+00 OUTFLOW= .7118E+03 BASIN STORAGE= .3026E-01 PERCENT ERROR=    .0

          FOR PLAN = 1  RATIO=  .82
            BB3-CC  MANE           .64   3961.05    245.72        .78       5.00   3958.59    245.00          .78

CONTINUITY SUMMARY (AC-FT) - INFLOW= .6655E+03 EXCESS= .0000E+00 OUTFLOW= .6655E+03 BASIN STORAGE= .2962E-01 PERCENT ERROR=    .0


*** NORMAL END OF HEC-1 ***
```

Appendix D: Hydraulic Models

HEC-RAS Version 3.1.1 May 2003
U.S. Army Corp of Engineers
Hydrologic Engineering Center
609 Second Street, Suite D
Davis, California 95616-4687
(916) 756-1104

```
X     X  XXXXXX    XXXX        XXXX       XX      XXXX
X     X  X        X    X       X   X     X  X     X
X     X  X        X            X   X    X    X    X
XXXXXXX  XXXX     X       XXX  XXXX     XXXXXX    XXXX
X     X  X        X            X  X     X    X        X
X     X  X        X    X       X   X    X    X        X
X     X  XXXXXX    XXXX        X    X   X    X   XXXXX
```

```
*****************************************************************************

PROJECT DATA
Project Title: slo_post
Project File : post.prj
Run Date and Time: 12/13/2004 4:31:33 PM

Project in English units

Project Description:

      FLOODPLAIN DETERMINATION


 STARTING WSE = NORMAL DEPTH
      SUBCRITICAL RUN



*****************************************************************************

PLAN DATA

Plan Title: Post-Project
Plan File : C:\Documents and Settings\jy18038\Desktop\PROJECTS\Sloan Channel\Post-Project\post.p01

          Geometry Title: Post-Project
          Geometry File : C:\Documents and Settings\jy18038\Desktop\PROJECTS\Sloan Channel\Post-Project\post.g01

          Flow Title    : Post-Project
          Flow File     : C:\Documents and Settings\jy18038\Desktop\PROJECTS\Sloan Channel\Post-Project\post.f01

Plan Summary Information:
Number of:  Cross Sections =   61    Mulitple Openings  =    0
            Culverts       =    0    Inline Structures  =    0
            Bridges        =    1    Lateral Structures =    0

Computational Information
    Water surface calculation tolerance =  0.01
    Critical depth calculaton tolerance =  0.01
    Maximum number of interations       =  20
    Maximum difference tolerance        =  0.3
    Flow tolerance factor               =  0.001

Computation Options
    Critical depth computed only where necessary
    Conveyance Calculation Method: At breaks in n values only
    Friction Slope Method:         Average Conveyance
    Computational Flow Regime:     Mixed Flow


*****************************************************************************

FLOW DATA

Flow Title: Post-Project
Flow File : C:\Documents and Settings\jy18038\Desktop\PROJECTS\Sloan Channel\Post-Project\post.f01

Flow Data (cfs)
*************************************************************
* River          Reach          RS      *    Post-Project *
* Range Wash     Sloan Channel  210     *            3072 *
* Range Wash     Sloan Channel  145     *            3078 *
* Range Wash     Sloan Channel  100     *            3891 *
* Range Wash     Sloan Channel  75      *            3921 *
* Range Wash     Sloan Channel  60      *            3964 *
* Range Wash     Sloan Channel  40      *            3990 *
*************************************************************

Boundary Conditions
*****************************************************************************************************************
* River          Reach          Profile          *          Upstream                  Downstream    *
*****************************************************************************************************************
* Range Wash     Sloan Channel  Post-Project     *             Critical          Known WS = 1694.2 *
*****************************************************************************************************************
Changes in WS and EG
*****************************************************************************
* River          Reach          RS      Profile         Type       Value *
* Range Wash     Sloan Channel  10      Post-Project  Known WS    1694.2 *
*****************************************************************************

*****************************************************************************

GEOMETRY DATA

Geometry Title: Post-Project
Geometry File : C:\Documents and Settings\jy18038\Desktop\PROJECTS\Sloan Channel\Post-Project\post.g01

CROSS SECTION


RIVER: Range Wash
REACH: Sloan Channel      RS: 210

INPUT
```

Description: PLAN STA 118+89
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1727.2	1011.86	1721.27	1046.86	1720.22	1081.86	1721.27	1093.72	1727.2

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1093.72 35.96 35.96 35.96 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1726.32	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.74	Wt. n-Val.		0.015	
W.S. Elev (ft)	1724.58	Reach Len. (ft)	35.96	35.96	35.96
Crit W.S. (ft)	1724.58	Flow Area (sq ft)		290.22	
E.G. Slope (ft/ft)	*0.002215	Area (sq ft)		290.22	
Q Total (cfs)	3072.00	Flow (cfs)		3072.00	
Top Width (ft)	83.23	Top Width (ft)		83.23	
Vel Total (ft/s)	10.59	Avg. Vel. (ft/s)		10.59	
Max Chl Dpth (ft)	4.36	Hydr. Depth (ft)		3.49	
Conv. Total (cfs)	65276.0	Conv. (cfs)		65276.0	
Length Wtd. (ft)	35.96	Wetted Per. (ft)		84.83	
Min Ch El (ft)	1720.22	Shear (lb/sq ft)		0.47	
Alpha	1.00	Stream Power (lb/ft s)		5.01	
Frctn Loss (ft)		Cum Volume (acre-ft)		42.25	
C & E Loss (ft)		Cum SA (acres)		11.93	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 200

INPUT
Description: PLAN STA 119+25
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1726.22	1011.86	1720.29	1046.86	1719.24	1081.86	1720.29	1093.72	1726.22

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1093.72 77.79 87.33 93.71 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1726.02	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.46	Wt. n-Val.		0.015	
W.S. Elev (ft)	1722.56	Reach Len. (ft)	77.79	87.33	93.71
Crit W.S. (ft)	1723.60	Flow Area (sq ft)		205.76	
E.G. Slope (ft/ft)	*0.006465	Area (sq ft)		205.76	
Q Total (cfs)	3072.00	Flow (cfs)		3072.00	
Top Width (ft)	79.07	Top Width (ft)		79.07	
Vel Total (ft/s)	14.93	Avg. Vel. (ft/s)		14.93	
Max Chl Dpth (ft)	3.32	Hydr. Depth (ft)		2.60	
Conv. Total (cfs)	38207.2	Conv. (cfs)		38207.2	
Length Wtd. (ft)	87.33	Wetted Per. (ft)		80.17	
Min Ch El (ft)	1719.24	Shear (lb/sq ft)		1.04	
Alpha	1.00	Stream Power (lb/ft s)		15.46	
Frctn Loss (ft)	0.13	Cum Volume (acre-ft)		42.05	
C & E Loss (ft)	0.17	Cum SA (acres)		11.86	

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 197.5*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1725.87	1011.86	1719.94	1046.86	1718.89	1081.86	1719.94	1093.72	1725.87

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1093.72 77.79 87.33 93.71 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1725.37	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.95	Wt. n-Val.		0.015	
W.S. Elev (ft)	1722.42	Reach Len. (ft)	77.79	87.33	93.71
Crit W.S. (ft)	1723.25	Flow Area (sq ft)		222.93	
E.G. Slope (ft/ft)	*0.005029	Area (sq ft)		222.93	
Q Total (cfs)	3072.00	Flow (cfs)		3072.00	
Top Width (ft)	79.93	Top Width (ft)		79.93	
Vel Total (ft/s)	13.78	Avg. Vel. (ft/s)		13.78	
Max Chl Dpth (ft)	3.53	Hydr. Depth (ft)		2.79	
Conv. Total (cfs)	43321.2	Conv. (cfs)		43321.2	
Length Wtd. (ft)	87.33	Wetted Per. (ft)		81.14	
Min Ch El (ft)	1718.89	Shear (lb/sq ft)		0.86	

Alpha	1.00	Stream Power (lb/ft s)		11.89				
Frctn Loss (ft)	0.50	Cum Volume (acre-ft)		41.62				
C & E Loss (ft)	0.15	Cum SA (acres)		11.70				

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 195.*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1725.52	1011.86	1719.59	1046.86	1718.54	1081.86	1719.59	1093.72	1725.52

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	77.79	87.33	93.71	.1 .3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1724.89	Element		0.015	
Vel Head (ft)	2.67	Wt. n-Val.		0.015	
W.S. Elev (ft)	1722.21	Reach Len. (ft)	77.79	87.33	93.71
Crit W.S. (ft)	1722.90	Flow Area (sq ft)		234.20	
E.G. Slope (ft/ft)	0.004310	Area (sq ft)		234.20	
Q Total (cfs)	3072.00	Flow (cfs)		3072.00	
Top Width (ft)	80.50	Top Width (ft)		80.50	
Vel Total (ft/s)	13.12	Avg. Vel. (ft/s)		13.12	
Max Chl Dpth (ft)	3.67	Hydr. Depth (ft)		2.91	
Conv. Total (cfs)	46791.3	Conv. (cfs)		46791.3	
Length Wtd. (ft)	87.33	Wetted Per. (ft)		81.77	
Min Ch El (ft)	1718.54	Shear (lb/sq ft)		0.77	
Alpha	1.00	Stream Power (lb/ft s)		10.11	
Frctn Loss (ft)	0.41	Cum Volume (acre-ft)		41.16	
C & E Loss (ft)	0.08	Cum SA (acres)		11.54	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 192.5*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1725.17	1011.86	1719.24	1046.86	1718.19	1081.86	1719.24	1093.72	1725.17

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	77.79	87.33	93.71	.1 .3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1724.50	Element		0.015	
Vel Head (ft)	2.60	Wt. n-Val.		0.015	
W.S. Elev (ft)	1721.91	Reach Len. (ft)	77.79	87.33	93.71
Crit W.S. (ft)	1722.55	Flow Area (sq ft)		237.50	
E.G. Slope (ft/ft)	0.004126	Area (sq ft)		237.50	
Q Total (cfs)	3072.00	Flow (cfs)		3072.00	
Top Width (ft)	80.66	Top Width (ft)		80.66	
Vel Total (ft/s)	12.93	Avg. Vel. (ft/s)		12.93	
Max Chl Dpth (ft)	3.71	Hydr. Depth (ft)		2.94	
Conv. Total (cfs)	47823.8	Conv. (cfs)		47823.8	
Length Wtd. (ft)	87.33	Wetted Per. (ft)		81.95	
Min Ch El (ft)	1718.19	Shear (lb/sq ft)		0.75	
Alpha	1.00	Stream Power (lb/ft s)		9.66	
Frctn Loss (ft)	0.37	Cum Volume (acre-ft)		40.68	
C & E Loss (ft)	0.02	Cum SA (acres)		11.38	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 190

INPUT
Description: PLAN STA 122+74
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1724.82	1011.86	1718.89	1046.86	1717.84	1081.86	1718.89	1093.72	1724.82

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	225.65	225.65	225.65	.1 .3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1724.15	Element			
Vel Head (ft)	2.58	Wt. n-Val.		0.015	

W.S. Elev (ft)	1721.56	Reach Len. (ft)	225.65	225.65	225.65			
Crit W.S. (ft)	1722.20	Flow Area (sq ft)		238.21				
E.G. Slope (ft/ft)	0.004088	Area (sq ft)		238.21				
Q Total (cfs)	3072.00	Flow (cfs)		3072.00				
Top Width (ft)	80.69	Top Width (ft)		80.69				
Vel Total (ft/s)	12.90	Avg. Vel. (ft/s)		12.90				
Max Chl Dpth (ft)	3.72	Hydr. Depth (ft)		2.95				
Conv. Total (cfs)	48046.7	Conv. (cfs)		48046.7				
Length Wtd. (ft)	225.65	Wetted Per. (ft)		81.99				
Min Ch El (ft)	1717.84	Shear (lb/sq ft)		0.74				
Alpha	1.00	Stream Power (lb/ft s)		9.56				
Frctn Loss (ft)	0.36	Cum Volume (acre-ft)		40.21				
C & E Loss (ft)	0.00	Cum SA (acres)		11.22				

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 180

INPUT
Description: PLAN STA 125+00
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1723.92	1011.86	1717.99	1046.86	1716.94	1081.86	1717.99	1093.72	1723.92

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1093.72 100 100 100 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

		Element	Left OB	Channel	Right OB
E.G. Elev (ft)	1723.23				
Vel Head (ft)	2.54	Wt. n-Val.		0.015	
W.S. Elev (ft)	1720.69	Reach Len. (ft)	100.00	100.00	100.00
Crit W.S. (ft)	1721.29	Flow Area (sq ft)		240.34	
E.G. Slope (ft/ft)	0.003976	Area (sq ft)		240.34	
Q Total (cfs)	3072.00	Flow (cfs)		3072.00	
Top Width (ft)	80.80	Top Width (ft)		80.80	
Vel Total (ft/s)	12.78	Avg. Vel. (ft/s)		12.78	
Max Chl Dpth (ft)	3.75	Hydr. Depth (ft)		2.97	
Conv. Total (cfs)	48717.9	Conv. (cfs)		48717.9	
Length Wtd. (ft)	100.00	Wetted Per. (ft)		82.11	
Min Ch El (ft)	1716.94	Shear (lb/sq ft)		0.73	
Alpha	1.00	Stream Power (lb/ft s)		9.29	
Frctn Loss (ft)	0.91	Cum Volume (acre-ft)		38.97	
C & E Loss (ft)	0.01	Cum SA (acres)		10.80	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 170

INPUT
Description: PLAN STA 126+00
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1722.67	1011.46	1716.94	1041.46	1716.04	1071.46	1716.94	1082.92	1722.67

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1082.92 51.96 51.96 51.96 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

		Element	Left OB	Channel	Right OB
E.G. Elev (ft)	1722.80				
Vel Head (ft)	2.81	Wt. n-Val.		0.015	
W.S. Elev (ft)	1719.99	Reach Len. (ft)	51.96	51.96	51.96
Crit W.S. (ft)	1720.68	Flow Area (sq ft)		228.44	
E.G. Slope (ft/ft)	0.004075	Area (sq ft)		228.44	
Q Total (cfs)	3072.00	Flow (cfs)		3072.00	
Top Width (ft)	72.19	Top Width (ft)		72.19	
Vel Total (ft/s)	13.45	Avg. Vel. (ft/s)		13.45	
Max Chl Dpth (ft)	3.95	Hydr. Depth (ft)		3.16	
Conv. Total (cfs)	48125.5	Conv. (cfs)		48125.5	
Length Wtd. (ft)	51.96	Wetted Per. (ft)		73.66	
Min Ch El (ft)	1716.04	Shear (lb/sq ft)		0.79	
Alpha	1.00	Stream Power (lb/ft s)		10.61	
Frctn Loss (ft)	0.40	Cum Volume (acre-ft)		38.43	
C & E Loss (ft)	0.03	Cum SA (acres)		10.62	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 160

INPUT
Description: PLAN STA 126+52
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1722.47	1011.46	1716.74	1041.46	1715.84	1071.46	1716.74	1082.92	1722.47

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

```
 Bank Sta: Left   Right    Lengths: Left Channel   Right     Coeff Contr.   Expan.
          1000 1082.92             89.2    89.2    89.2            .1       .3

 CROSS SECTION OUTPUT  Profile #Post-Project
 ********************************************************************************************
 * E.G. Elev (ft)        * 1722.59  * Element               *  Left OB *  Channel * Right OB *
 * Vel Head (ft)         *    2.79  * Wt. n-Val.            *          *    0.015 *          *
 * W.S. Elev (ft)        * 1719.80  * Reach Len. (ft)       *   89.20  *    89.20 *   89.20  *
 * Crit W.S. (ft)        * 1720.47  * Flow Area (sq ft)     *          *   229.22 *          *
 * E.G. Slope (ft/ft)    *0.004032  * Area (sq ft)          *          *   229.22 *          *
 * Q Total (cfs)         * 3072.00  * Flow (cfs)            *          * 3072.00 *          *
 * Top Width (ft)        *   72.23  * Top Width (ft)        *          *   72.23 *          *
 * Vel Total (ft/s)      *   13.40  * Avg. Vel. (ft/s)      *          *   13.40 *          *
 * Max Chl Dpth (ft)     *    3.96  * Hydr. Depth (ft)      *          *    3.17 *          *
 * Conv. Total (cfs)     * 48378.5  * Conv. (cfs)           *          * 48378.5 *          *
 * Length Wtd. (ft)      *   89.20  * Wetted Per. (ft)      *          *   73.70 *          *
 * Min Ch El (ft)        * 1715.84  * Shear (lb/sq ft)      *          *    0.78 *          *
 * Alpha                 *    1.00  * Stream Power (lb/ft s) *          *   10.49 *          *
 * Frctn Loss (ft)       *    0.21  * Cum Volume (acre-ft)  *          *   38.16 *          *
 * C & E Loss (ft)       *    0.01  * Cum SA (acres)        *          *   10.54 *          *
 ********************************************************************************************

 CROSS SECTION


 RIVER: Range Wash
 REACH: Sloan Channel      RS: 158.*

 INPUT
 Description:
 Station Elevation Data    num=      7
      Sta     Elev     Sta     Elev     Sta     Elev     Sta     Elev     Sta     Elev
 ********************************************************************************
     1000 1722.13 1010.47  1716.9 1011.74  1716.4 1042.46  1715.5  1070.2 1716.37
  1071.74 1716.54 1082.92 1722.13

 Manning's n Values        num=      3
      Sta   n Val     Sta   n Val     Sta   n Val
 ***********************************************
     1000     .015    1000     .015 1082.92     .015

 Bank Sta: Left   Right    Lengths: Left Channel   Right     Coeff Contr.   Expan.
          1000 1082.92             89.2    89.2    89.2            .1       .3

 CROSS SECTION OUTPUT  Profile #Post-Project
 ********************************************************************************************
 * E.G. Elev (ft)        * 1722.22  * Element               *  Left OB *  Channel * Right OB *
 * Vel Head (ft)         *    2.71  * Wt. n-Val.            *          *    0.015 *          *
 * W.S. Elev (ft)        * 1719.51  * Reach Len. (ft)       *   89.20  *    89.20 *   89.20  *
 * Crit W.S. (ft)        * 1720.14  * Flow Area (sq ft)     *          *   232.33 *          *
 * E.G. Slope (ft/ft)    *0.003866  * Area (sq ft)          *          *   232.33 *          *
 * Q Total (cfs)         * 3072.00  * Flow (cfs)            *          * 3072.00 *          *
 * Top Width (ft)        *   72.43  * Top Width (ft)        *          *   72.43 *          *
 * Vel Total (ft/s)      *   13.22  * Avg. Vel. (ft/s)      *          *   13.22 *          *
 * Max Chl Dpth (ft)     *    4.01  * Hydr. Depth (ft)      *          *    3.21 *          *
 * Conv. Total (cfs)     * 49405.0  * Conv. (cfs)           *          * 49405.0 *          *
 * Length Wtd. (ft)      *   89.20  * Wetted Per. (ft)      *          *   73.87 *          *
 * Min Ch El (ft)        * 1715.50  * Shear (lb/sq ft)      *          *    0.76 *          *
 * Alpha                 *    1.00  * Stream Power (lb/ft s) *          *   10.04 *          *
 * Frctn Loss (ft)       *    0.35  * Cum Volume (acre-ft)  *          *   37.68 *          *
 * C & E Loss (ft)       *    0.02  * Cum SA (acres)        *          *   10.39 *          *
 ********************************************************************************************

 CROSS SECTION


 RIVER: Range Wash
 REACH: Sloan Channel      RS: 156.*

 INPUT
 Description:
 Station Elevation Data    num=      7
      Sta     Elev     Sta     Elev     Sta     Elev     Sta     Elev     Sta     Elev
 ********************************************************************************
     1000  1721.8 1010.72 1716.44 1012.01 1716.05 1043.46 1715.17 1070.52 1716.04
  1072.01 1716.34 1082.92  1721.8

 Manning's n Values        num=      3
      Sta   n Val     Sta   n Val     Sta   n Val
 ***********************************************
     1000     .015    1000     .015 1082.92     .015

 Bank Sta: Left   Right    Lengths: Left Channel   Right     Coeff Contr.   Expan.
          1000 1082.92             89.2    89.2    89.2            .1       .3

 CROSS SECTION OUTPUT  Profile #Post-Project
 ********************************************************************************************
 * E.G. Elev (ft)        * 1721.89  * Element               *  Left OB *  Channel * Right OB *
 * Vel Head (ft)         *    2.71  * Wt. n-Val.            *          *    0.015 *          *
 * W.S. Elev (ft)        * 1719.18  * Reach Len. (ft)       *   89.20  *    89.20 *   89.20  *
 * Crit W.S. (ft)        * 1719.80  * Flow Area (sq ft)     *          *   232.65 *          *
 * E.G. Slope (ft/ft)    *0.003849  * Area (sq ft)          *          *   232.65 *          *
 * Q Total (cfs)         * 3072.00  * Flow (cfs)            *          * 3072.00 *          *
 * Top Width (ft)        *   72.44  * Top Width (ft)        *          *   72.44 *          *
 * Vel Total (ft/s)      *   13.20  * Avg. Vel. (ft/s)      *          *   13.20 *          *
 * Max Chl Dpth (ft)     *    4.01  * Hydr. Depth (ft)      *          *    3.21 *          *
 * Conv. Total (cfs)     * 49519.2  * Conv. (cfs)           *          * 49519.2 *          *
 * Length Wtd. (ft)      *   89.20  * Wetted Per. (ft)      *          *   73.87 *          *
 * Min Ch El (ft)        * 1715.17  * Shear (lb/sq ft)      *          *    0.76 *          *
 * Alpha                 *    1.00  * Stream Power (lb/ft s) *          *    9.99 *          *
 * Frctn Loss (ft)       *    0.34  * Cum Volume (acre-ft)  *          *   37.21 *          *
 * C & E Loss (ft)       *    0.00  * Cum SA (acres)        *          *   10.24 *          *
 ********************************************************************************************

 CROSS SECTION


 RIVER: Range Wash
 REACH: Sloan Channel      RS: 154.*

 INPUT
 Description:
 Station Elevation Data    num=      7
```

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1721.46	1010.97	1715.98	1012.29	1715.71	1044.46	1714.83	1070.83	1715.71
1072.29	1716.15	1082.92	1721.46						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	89.2	89.2	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1721.55	Element		0.015	
Vel Head (ft)	2.71	Wt. n-Val.	89.20	89.20	89.20
W.S. Elev (ft)	1718.84	Reach Len. (ft)		232.44	
Crit W.S. (ft)	1719.47	Flow Area (sq ft)		232.44	
E.G. Slope (ft/ft)	*0.003859	Area (sq ft)		3072.00	
Q Total (cfs)	3072.00	Flow (cfs)		72.42	
Top Width (ft)	72.42	Top Width (ft)		13.22	
Vel Total (ft/s)	13.22	Avg. Vel. (ft/s)		3.21	
Max Chl Dpth (ft)	4.01	Hydr. Depth (ft)		49454.8	
Conv. Total (cfs)	49454.8	Conv. (cfs)		73.85	
Length Wtd. (ft)	89.20	Wetted Per. (ft)		0.76	
Min Ch El (ft)	1714.83	Shear (lb/sq ft)		10.02	
Alpha	1.00	Stream Power (lb/ft s)		36.73	
Frctn Loss (ft)	0.34	Cum Volume (acre-ft)		10.09	
C & E Loss (ft)	0.00	Cum SA (acres)			

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 152.*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1721.13	1011.21	1715.52	1012.57	1715.37	1045.46	1714.5	1071.15	1715.39
1072.57	1715.95	1082.92	1721.13						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	89.2	89.2	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1721.21	Element		0.015	
Vel Head (ft)	2.69	Wt. n-Val.	89.20	89.20	89.20
W.S. Elev (ft)	1718.52	Reach Len. (ft)		233.23	
Crit W.S. (ft)	1719.14	Flow Area (sq ft)		233.23	
E.G. Slope (ft/ft)	*0.003821	Area (sq ft)		3072.00	
Q Total (cfs)	3072.00	Flow (cfs)		72.47	
Top Width (ft)	72.47	Top Width (ft)		13.17	
Vel Total (ft/s)	13.17	Avg. Vel. (ft/s)		4.02	
Max Chl Dpth (ft)	4.02	Hydr. Depth (ft)		49698.2	
Conv. Total (cfs)	49698.2	Conv. (cfs)		89.20	
Length Wtd. (ft)	89.20	Wetted Per. (ft)		1714.50	
Min Ch El (ft)	1714.50	Shear (lb/sq ft)		1.00	
Alpha	1.00	Stream Power (lb/ft s)		0.34	
Frctn Loss (ft)	0.34	Cum Volume (acre-ft)		0.01	
C & E Loss (ft)	0.01	Cum SA (acres)			

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 150

INPUT
Description: PLAN STA 130+97
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1720.79	1011.46	1715.06	1046.46	1714.16	1071.46	1715.06	1082.92	1720.79

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	72.79	72.79	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1720.87	Element		0.015	
Vel Head (ft)	2.69	Wt. n-Val.	72.79	72.79	72.79
W.S. Elev (ft)	1718.18	Reach Len. (ft)		233.32	
Crit W.S. (ft)	1718.79	Flow Area (sq ft)		233.32	
E.G. Slope (ft/ft)	*0.003818	Area (sq ft)		3072.00	
Q Total (cfs)	3072.00	Flow (cfs)		72.46	
Top Width (ft)	72.46	Top Width (ft)		13.17	
Vel Total (ft/s)	13.17	Avg. Vel. (ft/s)		4.02	
Max Chl Dpth (ft)	4.02	Hydr. Depth (ft)		49717.3	
Conv. Total (cfs)	49717.3	Conv. (cfs)		72.79	
Length Wtd. (ft)	72.79	Wetted Per. (ft)		1714.16	
Min Ch El (ft)	1714.16	Shear (lb/sq ft)		1.00	
Alpha	1.00	Stream Power (lb/ft s)		0.34	
Frctn Loss (ft)	0.34	Cum Volume (acre-ft)		0.00	
C & E Loss (ft)	0.00	Cum SA (acres)			

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 148.75*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1720.57	1011.46	1714.84	1046.46	1713.94	1071.46	1714.84	1082.92	1720.57

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	72.79	72.79	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1720.50	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.20	Wt. n-Val.		0.015	
W.S. Elev (ft)	1718.29	Reach Len. (ft)	72.79	72.79	72.79
Crit W.S. (ft)	1718.57	Flow Area (sq ft)		257.85	
E.G. Slope (ft/ft)	0.002810	Area (sq ft)		257.85	
Q Total (cfs)	3072.00	Flow (cfs)		3072.00	
Top Width (ft)	73.80	Top Width (ft)		73.80	
Vel Total (ft/s)	11.91	Avg. Vel. (ft/s)		11.91	
Max Chl Dpth (ft)	4.35	Hydr. Depth (ft)		3.49	
Conv. Total (cfs)	57947.3	Conv. (cfs)		57947.3	
Length Wtd. (ft)	72.79	Wetted Per. (ft)		75.46	
Min Ch El (ft)	1713.94	Shear (lb/sq ft)		0.60	
Alpha	1.00	Stream Power (lb/ft s)		7.14	
Frctn Loss (ft)	0.21	Cum Volume (acre-ft)		35.37	
C & E Loss (ft)	0.24	Cum SA (acres)		9.68	

Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water surface that had the least amount of error between computed and assumed values.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 147.5*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1720.34	1011.46	1714.61	1046.46	1713.71	1071.46	1714.61	1082.92	1720.34

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	72.79	72.79	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1720.28	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.28	Wt. n-Val.		0.015	
W.S. Elev (ft)	1718.00	Reach Len. (ft)	72.79	72.79	72.79
Crit W.S. (ft)	1718.34	Flow Area (sq ft)		253.57	
E.G. Slope (ft/ft)	0.002958	Area (sq ft)		253.57	
Q Total (cfs)	3072.00	Flow (cfs)		3072.00	
Top Width (ft)	73.57	Top Width (ft)		73.57	
Vel Total (ft/s)	12.12	Avg. Vel. (ft/s)		12.12	
Max Chl Dpth (ft)	4.29	Hydr. Depth (ft)		3.45	
Conv. Total (cfs)	56482.2	Conv. (cfs)		56482.2	
Length Wtd. (ft)	72.79	Wetted Per. (ft)		75.20	
Min Ch El (ft)	1713.71	Shear (lb/sq ft)		0.62	
Alpha	1.00	Stream Power (lb/ft s)		7.54	
Frctn Loss (ft)	0.21	Cum Volume (acre-ft)		34.94	
C & E Loss (ft)	0.01	Cum SA (acres)		9.55	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 146.25*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1720.11	1011.46	1714.39	1046.46	1713.48	1071.46	1714.39	1082.92	1720.11

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	72.79	72.79	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1720.05	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.26	Wt. n-Val.		0.015	
W.S. Elev (ft)	1717.79	Reach Len. (ft)	72.79	72.79	72.79
Crit W.S. (ft)	1718.12	Flow Area (sq ft)		254.65	
E.G. Slope (ft/ft)	0.002920	Area (sq ft)		254.65	
Q Total (cfs)	3072.00	Flow (cfs)		3072.00	

Top Width (ft)	73.63	Top Width (ft)			73.63		
Vel Total (ft/s)	12.06	Avg. Vel. (ft/s)			12.06		
Max Chl Dpth (ft)	4.31	Hydr. Depth (ft)			3.46		
Conv. Total (cfs)	56852.2	Conv. (cfs)			56852.2		
Length Wtd. (ft)	72.79	Wetted Per. (ft)			75.27		
Min Ch El (ft)	1713.48	Shear (lb/sq ft)			0.62		
Alpha	1.00	Stream Power (lb/ft s)			7.44		
Frctn Loss (ft)	0.21	Cum Volume (acre-ft)			34.52		
C & E Loss (ft)	0.01	Cum SA (acres)			9.43		

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 145

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1719.89	1011.46	1714.16	1046.46	1713.26	1071.46	1714.16	1082.92	1719.89

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	189.27	189.27	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1719.83	Element		0.015	
Vel Head (ft)	2.25	Wt. n-Val.		0.015	
W.S. Elev (ft)	1717.58	Reach Len. (ft)	189.27	189.27	189.27
Crit W.S. (ft)	1717.91	Flow Area (sq ft)		255.50	
E.G. Slope (ft/ft)	0.002902	Area (sq ft)		255.50	
Q Total (cfs)	3078.00	Flow (cfs)		3078.00	
Top Width (ft)	73.67	Top Width (ft)		73.67	
Vel Total (ft/s)	12.05	Avg. Vel. (ft/s)		12.05	
Max Chl Dpth (ft)	4.32	Hydr. Depth (ft)		3.47	
Conv. Total (cfs)	57142.0	Conv. (cfs)		57142.0	
Length Wtd. (ft)	189.27	Wetted Per. (ft)		75.32	
Min Ch El (ft)	1713.26	Shear (lb/sq ft)		0.61	
Alpha	1.00	Stream Power (lb/ft s)		7.40	
Frctn Loss (ft)	0.21	Cum Volume (acre-ft)		34.09	
C & E Loss (ft)	0.00	Cum SA (acres)		9.31	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 144.615*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1719.16	1011.37	1713.48	1012.74	1713.4	1046.08	1712.53	1071.34	1713.43	1072.74	1714.07	1082.92	1719.16

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	189.27	189.27	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1719.20	Element		0.015	
Vel Head (ft)	2.56	Wt. n-Val.		0.015	
W.S. Elev (ft)	1716.64	Reach Len. (ft)	189.27	189.27	189.27
Crit W.S. (ft)	1717.17	Flow Area (sq ft)		239.79	
E.G. Slope (ft/ft)	0.003523	Area (sq ft)		239.79	
Q Total (cfs)	3078.00	Flow (cfs)		3078.00	
Top Width (ft)	72.82	Top Width (ft)		72.82	
Vel Total (ft/s)	12.84	Avg. Vel. (ft/s)		12.84	
Max Chl Dpth (ft)	4.11	Hydr. Depth (ft)		3.29	
Conv. Total (cfs)	51855.8	Conv. (cfs)		51855.8	
Length Wtd. (ft)	189.27	Wetted Per. (ft)		74.34	
Min Ch El (ft)	1712.53	Shear (lb/sq ft)		0.71	
Alpha	1.00	Stream Power (lb/ft s)		9.11	
Frctn Loss (ft)	0.60	Cum Volume (acre-ft)		33.01	
C & E Loss (ft)	0.03	Cum SA (acres)		8.99	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 144.230*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1718.43	1011.27	1712.79	1012.63	1712.67	1045.69	1711.8	1071.22	1712.69	1072.63	1713.28	1082.92	1718.43

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	189.27	189.27	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1718.50	Element	Left OB	Channel	Right OB	
Vel Head (ft)	2.65	Wt. n-Val.		0.015		
W.S. Elev (ft)	1715.85	Reach Len. (ft)	189.27	189.27	189.27	
Crit W.S. (ft)	1716.44	Flow Area (sq ft)		235.59		
E.G. Slope (ft/ft)	*0.003719	Area (sq ft)		235.59		
Q Total (cfs)	3078.00	Flow (cfs)		3078.00		
Top Width (ft)	72.60	Top Width (ft)		72.60		
Vel Total (ft/s)	13.06	Avg. Vel. (ft/s)		13.06		
Max Chl Dpth (ft)	4.05	Hydr. Depth (ft)		3.25		
Conv. Total (cfs)	50471.9	Conv. (cfs)		50471.9		
Length Wtd. (ft)	189.27	Wetted Per. (ft)		74.08		
Min Ch El (ft)	1711.80	Shear (lb/sq ft)		0.74		
Alpha	1.00	Stream Power (lb/ft s)		9.65		
Frctn Loss (ft)	0.69	Cum Volume (acre-ft)		31.98		
C & E Loss (ft)	0.01	Cum SA (acres)		8.67		

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 143.846*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1717.7	1011.18	1712.11	1012.52	1711.94	1045.31	1711.07	1071.1	1711.96
1072.52	1712.5	1082.92	1717.7						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	189.27	189.27	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1717.78	Element	Left OB	Channel	Right OB	
Vel Head (ft)	2.68	Wt. n-Val.		0.015		
W.S. Elev (ft)	1715.10	Reach Len. (ft)	189.27	189.27	189.27	
Crit W.S. (ft)	1715.71	Flow Area (sq ft)		234.11		
E.G. Slope (ft/ft)	*0.003791	Area (sq ft)		234.11		
Q Total (cfs)	3078.00	Flow (cfs)		3078.00		
Top Width (ft)	72.51	Top Width (ft)		72.51		
Vel Total (ft/s)	13.15	Avg. Vel. (ft/s)		13.15		
Max Chl Dpth (ft)	4.03	Hydr. Depth (ft)		3.23		
Conv. Total (cfs)	49992.8	Conv. (cfs)		49992.8		
Length Wtd. (ft)	189.27	Wetted Per. (ft)		73.97		
Min Ch El (ft)	1711.07	Shear (lb/sq ft)		0.75		
Alpha	1.00	Stream Power (lb/ft s)		9.85		
Frctn Loss (ft)	0.71	Cum Volume (acre-ft)		30.96		
C & E Loss (ft)	0.00	Cum SA (acres)		8.36		

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 143.461*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1716.97	1011.08	1711.43	1012.42	1711.21	1044.92	1710.34	1070.98	1711.22
1072.42	1711.72	1082.92	1716.97						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	189.27	189.27	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1717.06	Element	Left OB	Channel	Right OB	
Vel Head (ft)	2.70	Wt. n-Val.		0.015		
W.S. Elev (ft)	1714.36	Reach Len. (ft)	189.27	189.27	189.27	
Crit W.S. (ft)	1714.98	Flow Area (sq ft)		233.34		
E.G. Slope (ft/ft)	*0.003828	Area (sq ft)		233.34		
Q Total (cfs)	3078.00	Flow (cfs)		3078.00		
Top Width (ft)	72.47	Top Width (ft)		72.47		
Vel Total (ft/s)	13.19	Avg. Vel. (ft/s)		13.19		
Max Chl Dpth (ft)	4.02	Hydr. Depth (ft)		3.22		
Conv. Total (cfs)	49746.6	Conv. (cfs)		49746.6		
Length Wtd. (ft)	189.27	Wetted Per. (ft)		73.91		
Min Ch El (ft)	1710.34	Shear (lb/sq ft)		0.75		
Alpha	1.00	Stream Power (lb/ft s)		9.95		
Frctn Loss (ft)	0.72	Cum Volume (acre-ft)		29.94		
C & E Loss (ft)	0.00	Cum SA (acres)		8.04		

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 143.076*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev

1000 1716.24 1010.99 1710.74 1012.31 1710.48 1044.54 1709.61 1070.86 1710.49
1072.31 1710.93 1082.92 1716.24

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	189.27	189.27	189.27	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1716.33	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.71	Wt. n-Val.		0.015	
W.S. Elev (ft)	1713.62	Reach Len. (ft)	189.27	189.27	189.27
Crit W.S. (ft)	1714.25	Flow Area (sq ft)		232.87	
E.G. Slope (ft/ft)	*0.003853	Area (sq ft)		232.87	
Q Total (cfs)	3078.00	Flow (cfs)		3078.00	
Top Width (ft)	72.45	Top Width (ft)		72.45	
Vel Total (ft/s)	13.22	Avg. Vel. (ft/s)		13.22	
Max Chl Dpth (ft)	4.01	Hydr. Depth (ft)		3.21	
Conv. Total (cfs)	49590.2	Conv. (cfs)		49590.2	
Length Wtd. (ft)	189.27	Wetted Per. (ft)		73.88	
Min Ch El (ft)	1709.61	Shear (lb/sq ft)		0.76	
Alpha	1.00	Stream Power (lb/ft s)		10.02	
Frctn Loss (ft)	0.73	Cum Volume (acre-ft)		28.93	
C & E Loss (ft)	0.00	Cum SA (acres)		7.73	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 142.692*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1715.51	1010.89	1710.06	1012.2	1709.76	1044.15	1708.88	1070.73	1709.75
1072.2	1710.15	1082.92	1715.51						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	189.27	189.27	189.27	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1715.60	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.71	Wt. n-Val.		0.015	
W.S. Elev (ft)	1712.89	Reach Len. (ft)	189.27	189.27	189.27
Crit W.S. (ft)	1713.52	Flow Area (sq ft)		233.01	
E.G. Slope (ft/ft)	*0.003845	Area (sq ft)		233.01	
Q Total (cfs)	3078.00	Flow (cfs)		3078.00	
Top Width (ft)	72.46	Top Width (ft)		72.46	
Vel Total (ft/s)	13.21	Avg. Vel. (ft/s)		13.21	
Max Chl Dpth (ft)	4.01	Hydr. Depth (ft)		3.22	
Conv. Total (cfs)	49640.3	Conv. (cfs)		49640.3	
Length Wtd. (ft)	189.27	Wetted Per. (ft)		73.89	
Min Ch El (ft)	1708.88	Shear (lb/sq ft)		0.76	
Alpha	1.00	Stream Power (lb/ft s)		10.00	
Frctn Loss (ft)	0.73	Cum Volume (acre-ft)		27.92	
C & E Loss (ft)	0.00	Cum SA (acres)		7.41	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 142.307*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1714.77	1010.8	1709.38	1012.1	1709.03	1043.77	1708.14	1070.61	1709.02
1072.1	1709.36	1082.92	1714.77						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	189.27	189.27	189.27	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1714.87	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.72	Wt. n-Val.		0.015	
W.S. Elev (ft)	1712.15	Reach Len. (ft)	189.27	189.27	189.27
Crit W.S. (ft)	1712.79	Flow Area (sq ft)		232.46	
E.G. Slope (ft/ft)	*0.003873	Area (sq ft)		232.46	
Q Total (cfs)	3078.00	Flow (cfs)		3078.00	
Top Width (ft)	72.43	Top Width (ft)		72.43	
Vel Total (ft/s)	13.24	Avg. Vel. (ft/s)		13.24	
Max Chl Dpth (ft)	4.01	Hydr. Depth (ft)		3.21	
Conv. Total (cfs)	49457.2	Conv. (cfs)		49457.2	
Length Wtd. (ft)	189.27	Wetted Per. (ft)		73.85	
Min Ch El (ft)	1708.14	Shear (lb/sq ft)		0.76	
Alpha	1.00	Stream Power (lb/ft s)		10.08	
Frctn Loss (ft)	0.73	Cum Volume (acre-ft)		26.91	
C & E Loss (ft)	0.00	Cum SA (acres)		7.10	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 141.923*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1714.04	1010.7	1708.69	1011.99	1708.3	1043.38	1707.41	1070.49	1708.28
1071.99	1708.58	1082.92	1714.04						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	189.27	189.27	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1714.14	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.72	Wt. n-Val.		0.015	
W.S. Elev (ft)	1711.42	Reach Len. (ft)	189.27	189.27	189.27
Crit W.S. (ft)	1712.06	Flow Area (sq ft)		232.64	
E.G. Slope (ft/ft)	0.003864	Area (sq ft)		232.64	
Q Total (cfs)	3078.00	Flow (cfs)		3078.00	
Top Width (ft)	72.44	Top Width (ft)		72.44	
Vel Total (ft/s)	13.23	Avg. Vel. (ft/s)		13.23	
Max Chl Dpth (ft)	4.01	Hydr. Depth (ft)		3.21	
Conv. Total (cfs)	49515.0	Conv. (cfs)		49515.0	
Length Wtd. (ft)	189.27	Wetted Per. (ft)		73.87	
Min Ch El (ft)	1707.41	Shear (lb/sq ft)		0.76	
Alpha	1.00	Stream Power (lb/ft s)		10.05	
Frctn Loss (ft)	0.73	Cum Volume (acre-ft)		25.90	
C & E Loss (ft)	0.00	Cum SA (acres)		6.78	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 141.538*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1713.31	1010.61	1708.01	1011.89	1707.57	1043	1706.68	1070.37	1707.55
1071.89	1707.8	1082.92	1713.31						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	189.27	189.27	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1713.41	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.72	Wt. n-Val.		0.015	
W.S. Elev (ft)	1710.69	Reach Len. (ft)	189.27	189.27	189.27
Crit W.S. (ft)	1711.32	Flow Area (sq ft)		232.63	
E.G. Slope (ft/ft)	0.003865	Area (sq ft)		232.63	
Q Total (cfs)	3078.00	Flow (cfs)		3078.00	
Top Width (ft)	72.43	Top Width (ft)		72.43	
Vel Total (ft/s)	13.23	Avg. Vel. (ft/s)		13.23	
Max Chl Dpth (ft)	4.01	Hydr. Depth (ft)		3.21	
Conv. Total (cfs)	49511.8	Conv. (cfs)		49511.8	
Length Wtd. (ft)	189.27	Wetted Per. (ft)		73.87	
Min Ch El (ft)	1706.68	Shear (lb/sq ft)		0.76	
Alpha	1.00	Stream Power (lb/ft s)		10.05	
Frctn Loss (ft)	0.73	Cum Volume (acre-ft)		24.89	
C & E Loss (ft)	0.00	Cum SA (acres)		6.47	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 141.153*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1712.58	1010.51	1707.33	1011.78	1706.84	1042.61	1705.95	1070.25	1706.82
1071.78	1707.01	1082.92	1712.58						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	189.27	189.27	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1712.68	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.72	Wt. n-Val.		0.015	
W.S. Elev (ft)	1709.96	Reach Len. (ft)	189.27	189.27	189.27
Crit W.S. (ft)	1710.59	Flow Area (sq ft)		232.68	
E.G. Slope (ft/ft)	0.003863	Area (sq ft)		232.68	
Q Total (cfs)	3078.00	Flow (cfs)		3078.00	
Top Width (ft)	72.44	Top Width (ft)		72.44	
Vel Total (ft/s)	13.23	Avg. Vel. (ft/s)		13.23	

E.G. Elev (ft)	1710.45	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.30	Wt. n-Val.		0.015	
W.S. Elev (ft)	1709.15	Reach Len. (ft)	50.00	50.00	50.00
Crit W.S. (ft)	1708.42	Flow Area (sq ft)		336.70	
E.G. Slope (ft/ft)	0.001255	Area (sq ft)		336.70	
Q Total (cfs)	3078.00	Flow (cfs)		3078.00	
Top Width (ft)	77.96	Top Width (ft)		77.96	
Vel Total (ft/s)	9.14	Avg. Vel. (ft/s)		9.14	
Max Chl Dpth (ft)	5.39	Hydr. Depth (ft)		4.32	
Conv. Total (cfs)	86869.8	Conv. (cfs)		86869.8	
Length Wtd. (ft)	50.00	Wetted Per. (ft)		80.11	
Min Ch El (ft)	1703.76	Shear (lb/sq ft)		0.33	
Alpha	1.00	Stream Power (lb/ft s)		3.01	
Frctn Loss (ft)	0.06	Cum Volume (acre-ft)		20.62	
C & E Loss (ft)	0.04	Cum SA (acres)		5.20	

Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 130

INPUT
Description: PLAN STA 159+00
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1710.2	1011.46	1704.47	1041.46	1703.57	1071.46	1704.47	1082.92	1710.2

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	129.35	129.35	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1710.35	Element	Left OB	Channel	Right OB
Vel Head (ft)	1.18	Wt. n-Val.		0.015	
W.S. Elev (ft)	1709.18	Reach Len. (ft)	129.35	129.35	129.35
Crit W.S. (ft)		Flow Area (sq ft)		353.57	
E.G. Slope (ft/ft)	0.001084	Area (sq ft)		353.57	
Q Total (cfs)	3078.00	Flow (cfs)		3078.00	
Top Width (ft)	78.82	Top Width (ft)		78.82	
Vel Total (ft/s)	8.71	Avg. Vel. (ft/s)		8.71	
Max Chl Dpth (ft)	5.60	Hydr. Depth (ft)		4.49	
Conv. Total (cfs)	93497.2	Conv. (cfs)		93497.2	
Length Wtd. (ft)	129.35	Wetted Per. (ft)		81.07	
Min Ch El (ft)	1703.57	Shear (lb/sq ft)		0.30	
Alpha	1.00	Stream Power (lb/ft s)		2.57	
Frctn Loss (ft)	0.12	Cum Volume (acre-ft)		20.22	
C & E Loss (ft)	0.07	Cum SA (acres)		5.11	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 120

INPUT
Description: PLAN STA 160+29
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1711.59	1015.2	1703.99	1045.2	1703.09	1075.2	1703.99	1090.4	1711.59

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1090.4	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1090.4	50	50	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1710.16	Element	Left OB	Channel	Right OB
Vel Head (ft)	0.94	Wt. n-Val.		0.015	
W.S. Elev (ft)	1709.22	Reach Len. (ft)	50.00	50.00	50.00
Crit W.S. (ft)		Flow Area (sq ft)		395.80	
E.G. Slope (ft/ft)	0.000773	Area (sq ft)		395.80	
Q Total (cfs)	3078.00	Flow (cfs)		3078.00	
Top Width (ft)	80.93	Top Width (ft)		80.93	
Vel Total (ft/s)	7.78	Avg. Vel. (ft/s)		7.78	
Max Chl Dpth (ft)	6.13	Hydr. Depth (ft)		4.89	
Conv. Total (cfs)	110698.6	Conv. (cfs)		110698.6	
Length Wtd. (ft)	50.00	Wetted Per. (ft)		83.43	
Min Ch El (ft)	1703.09	Shear (lb/sq ft)		0.23	
Alpha	1.00	Stream Power (lb/ft s)		1.78	
Frctn Loss (ft)	0.03	Cum Volume (acre-ft)		19.11	
C & E Loss (ft)	0.03	Cum SA (acres)		4.87	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 110

INPUT
Description: PLAN STA 160+79
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1712.33	1000	1703.83	1031	1702.9	1072.5	1704.15	1072.5	1712.65

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1072.5	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1072.5	100	100	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1710.10	Element		0.015	
Vel Head (ft)	0.83	Wt. n-Val.		0.015	
W.S. Elev (ft)	1709.27	Reach Len. (ft)	100.00	100.00	100.00
Crit W.S. (ft)		Flow Area (sq ft)		421.13	
E.G. Slope (ft/ft)	0.000625	Area (sq ft)		421.13	
Q Total (cfs)	3078.00	Flow (cfs)		3078.00	
Top Width (ft)	72.50	Top Width (ft)		72.50	
Vel Total (ft/s)	7.31	Avg. Vel. (ft/s)		7.31	
Max Chl Dpth (ft)	6.37	Hydr. Depth (ft)		5.81	
Conv. Total (cfs)	123098.2	Conv. (cfs)		123098.2	
Length Wtd. (ft)	100.00	Wetted Per. (ft)		83.08	
Min Ch El (ft)	1702.90	Shear (lb/sq ft)		0.20	
Alpha	1.00	Stream Power (lb/ft s)		1.45	
Frctn Loss (ft)	0.09	Cum Volume (acre-ft)		18.64	
C & E Loss (ft)	0.07	Cum SA (acres)		4.78	

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 100

INPUT
Description: PLAN STA 161+79
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1711.95	1000	1703.45	1031	1702.52	1072.5	1703.57	1072.5	1712.27

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1072.5	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1072.5	100	100	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1709.93	Element		0.015	
Vel Head (ft)	1.56	Wt. n-Val.		0.015	
W.S. Elev (ft)	1708.37	Reach Len. (ft)	100.00	100.00	100.00
Crit W.S. (ft)		Flow Area (sq ft)		387.60	
E.G. Slope (ft/ft)	0.001300	Area (sq ft)		387.60	
Q Total (cfs)	3891.00	Flow (cfs)		3891.00	
Top Width (ft)	72.50	Top Width (ft)		72.50	
Vel Total (ft/s)	10.04	Avg. Vel. (ft/s)		10.04	
Max Chl Dpth (ft)	5.85	Hydr. Depth (ft)		5.35	
Conv. Total (cfs)	107936.6	Conv. (cfs)		107936.6	
Length Wtd. (ft)	100.00	Wetted Per. (ft)		82.24	
Min Ch El (ft)	1702.52	Shear (lb/sq ft)		0.38	
Alpha	1.00	Stream Power (lb/ft s)		3.84	
Frctn Loss (ft)	0.08	Cum Volume (acre-ft)		17.71	
C & E Loss (ft)	0.23	Cum SA (acres)		4.61	

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 90

INPUT
Description: PLAN STA 162+79
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1712.14	1000	1703.61	1049	1702.14	1090.5	1703.39	1090.5	1710.16

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1090.5	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1090.5	50	50	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1709.62	Element		0.015	
Vel Head (ft)	0.80	Wt. n-Val.		0.015	
W.S. Elev (ft)	1708.82	Reach Len. (ft)	50.00	50.00	50.00
Crit W.S. (ft)		Flow Area (sq ft)		542.57	
E.G. Slope (ft/ft)	0.000558	Area (sq ft)		542.57	
Q Total (cfs)	3891.00	Flow (cfs)		3891.00	
Top Width (ft)	90.50	Top Width (ft)		90.50	
Vel Total (ft/s)	7.17	Avg. Vel. (ft/s)		7.17	
Max Chl Dpth (ft)	6.68	Hydr. Depth (ft)		6.00	
Conv. Total (cfs)	164664.6	Conv. (cfs)		164664.6	
Length Wtd. (ft)	50.00	Wetted Per. (ft)		101.18	
Min Ch El (ft)	1702.14	Shear (lb/sq ft)		0.19	
Alpha	1.00	Stream Power (lb/ft s)		1.34	
Frctn Loss (ft)	0.05	Cum Volume (acre-ft)		16.64	
C & E Loss (ft)	0.14	Cum SA (acres)		4.43	

```
**********************************************************************************************

Warning: The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for
         additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than
         0.7 or greater than 1.4.  This may indicate the need for additional cross sections.

CROSS SECTION


RIVER: Range Wash
REACH: Sloan Channel       RS: 80

INPUT
Description: PLAN STA 163+29
Station Elevation Data    num=       5
     Sta    Elev     Sta    Elev     Sta    Elev     Sta    Elev     Sta    Elev
**********************************************************************************
    1000 1708.85  1011.5 1702.85  1041.5 1701.95  1071.5 1702.85    1083 1708.85

Manning's n Values        num=       3
     Sta   n Val     Sta   n Val     Sta   n Val
***********************************************
    1000    .015    1000    .015    1083    .015

Bank Sta: Left   Right    Lengths: Left Channel   Right     Coeff Contr.   Expan.
          1000    1083              300     300     300             .1       .3

CROSS SECTION OUTPUT  Profile #Post-Project
**********************************************************************************************
* E.G. Elev (ft)         * 1709.43  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)          *    2.16  * Wt. n-Val.           *          *    0.015  *          *
* W.S. Elev (ft)         * 1707.27  * Reach Len. (ft)      *  300.00  *  300.00  *  300.00  *
* Crit W.S. (ft)         * 1707.27  * Flow Area (sq ft)    *          *  329.71  *          *
* E.G. Slope (ft/ft)     *0.002117  * Area (sq ft)         *          *  329.71  *          *
* Q Total (cfs)          * 3891.00  * Flow (cfs)           *          * 3891.00  *          *
* Top Width (ft)         *   76.95  * Top Width (ft)       *          *   76.95  *          *
* Vel Total (ft/s)       *   11.80  * Avg. Vel. (ft/s)     *          *   11.80  *          *
* Max Chl Dpth (ft)      *    5.32  * Hydr. Depth (ft)     *          *    4.28  *          *
* Conv. Total (cfs)      * 84562.7  * Conv. (cfs)          *          * 84562.7  *          *
* Length Wtd. (ft)       *  300.00  * Wetted Per. (ft)     *          *   79.14  *          *
* Min Ch El (ft)         * 1701.95  * Shear (lb/sq ft)     *          *    0.55  *          *
* Alpha                  *    1.00  * Stream Power (lb/ft s) *          *    6.50  *          *
* Frctn Loss (ft)        *    0.64  * Cum Volume (acre-ft)  *          *   16.14  *          *
* C & E Loss (ft)        *    0.00  * Cum SA (acres)        *          *    4.33  *          *
**********************************************************************************************

Warning: The energy equation could not be balanced within the specified number of iterations.  The
         program used critical depth for the water surface and continued on with the calculations.
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section.
         This may indicate the need for additional cross sections.
Warning: During the standard step iterations, when the assumed water surface was set equal to critical
         depth, the calculated water surface came back below critical depth.  This indicates that there is
         not a valid subcritical answer.  The program defaulted to critical depth.

CROSS SECTION


RIVER: Range Wash
REACH: Sloan Channel       RS: 75

INPUT
Description:
Station Elevation Data    num=       5
     Sta    Elev     Sta    Elev     Sta    Elev     Sta    Elev     Sta    Elev
**********************************************************************************
    1000 1707.45  1011.5 1701.45  1041.5 1700.55  1071.5 1701.45    1083 1707.45

Manning's n Values        num=       3
     Sta   n Val     Sta   n Val     Sta   n Val
***********************************************
    1000    .015    1000    .015    1083    .015

Bank Sta: Left   Right    Lengths: Left Channel   Right     Coeff Contr.   Expan.
          1000    1083             86.82   86.82   86.82             .1       .3

CROSS SECTION OUTPUT  Profile #Post-Project
**********************************************************************************************
* E.G. Elev (ft)         * 1708.43  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)          *    3.44  * Wt. n-Val.           *          *    0.015  *          *
* W.S. Elev (ft)         * 1704.99  * Reach Len. (ft)      *   86.82  *   86.82  *   86.82  *
* Crit W.S. (ft)         * 1705.89  * Flow Area (sq ft)    *          *  263.38  *          *
* E.G. Slope (ft/ft)     *0.004256  * Area (sq ft)         *          *  263.38  *          *
* Q Total (cfs)          * 3921.00  * Flow (cfs)           *          * 3921.00  *          *
* Top Width (ft)         *   73.57  * Top Width (ft)       *          *   73.57  *          *
* Vel Total (ft/s)       *   14.89  * Avg. Vel. (ft/s)     *          *   14.89  *          *
* Max Chl Dpth (ft)      *    4.44  * Hydr. Depth (ft)     *          *    3.58  *          *
* Conv. Total (cfs)      * 60103.7  * Conv. (cfs)          *          * 60103.7  *          *
* Length Wtd. (ft)       *   86.82  * Wetted Per. (ft)     *          *   75.33  *          *
* Min Ch El (ft)         * 1700.55  * Shear (lb/sq ft)     *          *    0.93  *          *
* Alpha                  *    1.00  * Stream Power (lb/ft s) *          *   13.83  *          *
* Frctn Loss (ft)        *    0.88  * Cum Volume (acre-ft)  *          *   14.10  *          *
* C & E Loss (ft)        *    0.13  * Cum SA (acres)        *          *    3.81  *          *
**********************************************************************************************

Warning: The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for
         additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than
         0.7 or greater than 1.4.  This may indicate the need for additional cross sections.
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section.
         This may indicate the need for additional cross sections.
Note:    Program found supercritical flow starting at this cross section.

CROSS SECTION


RIVER: Range Wash
REACH: Sloan Channel       RS: 74.1666*

INPUT
Description:
Station Elevation Data    num=       7
     Sta    Elev     Sta    Elev     Sta    Elev     Sta    Elev     Sta    Elev
```

```
*****************************************************************************
   1000 1706.92 1011.47 1700.98  1011.5 1700.96 1041.49 1700.07 1071.49 1700.96
1071.52 1700.98 1082.99 1706.92

Manning's n Values         num=       3
     Sta    n Val      Sta    n Val      Sta    n Val
***********************************************
    1000     .015     1000     .015 1082.99     .015

Bank Sta: Left    Right     Lengths: Left Channel   Right      Coeff Contr.    Expan.
          1000 1082.99                86.82   86.82   86.82              .1       .3

CROSS SECTION OUTPUT  Profile #Post-Project
*****************************************************************************************************
* E.G. Elev (ft)         * 1708.03  * Element                * Left OB *  Channel * Right OB *
* Vel Head (ft)          *    3.62  * Wt. n-Val.             *         *    0.015 *          *
* W.S. Elev (ft)         * 1704.42  * Reach Len. (ft)       *   86.82  *   86.82  *   86.82  *
* Crit W.S. (ft)         * 1705.41  * Flow Area (sq ft)     *          *  256.96  *          *
* E.G. Slope (ft/ft)     *0.004596  * Area (sq ft)          *          *  256.96  *          *
* Q Total (cfs)          * 3921.00  * Flow (cfs)           *          * 3921.00  *          *
* Top Width (ft)         *   73.32  * Top Width (ft)       *          *   73.32  *          *
* Vel Total (ft/s)       *   15.26  * Avg. Vel. (ft/s)     *          *   15.26  *          *
* Max Chl Dpth (ft)      *    4.35  * Hydr. Depth (ft)     *          *    3.50  *          *
* Conv. Total (cfs)      * 57835.1  * Conv. (cfs)          *          * 57835.1  *          *
* Length Wtd. (ft)       *   86.82  * Wetted Per. (ft)     *          *   75.03  *          *
* Min Ch El (ft)         * 1700.07  * Shear (lb/sq ft)     *          *    0.98  *          *
* Alpha                  *    1.00  * Stream Power (lb/ft s) *         *   15.00  *          *
* Frctn Loss (ft)        *    0.38  * Cum Volume (acre-ft)  *          *   13.58  *          *
* C & E Loss (ft)        *    0.02  * Cum SA (acres)        *          *    3.67  *          *
*****************************************************************************************************

CROSS SECTION


RIVER: Range Wash
REACH: Sloan Channel       RS: 73.3333*

INPUT
Description:
Station Elevation Data    num=       7
     Sta    Elev      Sta    Elev      Sta    Elev      Sta    Elev      Sta    Elev
*****************************************************************************
   1000 1706.39 1011.47 1700.49  1011.5 1700.48 1041.49 1699.58 1071.48 1700.48
1071.51 1700.49 1082.97 1706.39

Manning's n Values         num=       3
     Sta    n Val      Sta    n Val      Sta    n Val
***********************************************
    1000     .015     1000     .015 1082.97     .015

Bank Sta: Left    Right     Lengths: Left Channel   Right      Coeff Contr.    Expan.
          1000 1082.97                86.82   86.82   86.82              .1       .3

CROSS SECTION OUTPUT  Profile #Post-Project
*****************************************************************************************************
* E.G. Elev (ft)         * 1707.61  * Element                * Left OB *  Channel * Right OB *
* Vel Head (ft)          *    3.74  * Wt. n-Val.             *         *    0.015 *          *
* W.S. Elev (ft)         * 1703.87  * Reach Len. (ft)       *   86.82  *   86.82  *   86.82  *
* Crit W.S. (ft)         * 1704.92  * Flow Area (sq ft)     *          *  252.67  *          *
* E.G. Slope (ft/ft)     *0.004845  * Area (sq ft)          *          *  252.67  *          *
* Q Total (cfs)          * 3921.00  * Flow (cfs)           *          * 3921.00  *          *
* Top Width (ft)         *   73.17  * Top Width (ft)       *          *   73.17  *          *
* Vel Total (ft/s)       *   15.52  * Avg. Vel. (ft/s)     *          *   15.52  *          *
* Max Chl Dpth (ft)      *    4.29  * Hydr. Depth (ft)     *          *    3.45  *          *
* Conv. Total (cfs)      * 56331.1  * Conv. (cfs)          *          * 56331.1  *          *
* Length Wtd. (ft)       *   86.82  * Wetted Per. (ft)     *          *   74.84  *          *
* Min Ch El (ft)         * 1699.58  * Shear (lb/sq ft)     *          *    1.02  *          *
* Alpha                  *    1.00  * Stream Power (lb/ft s) *         *   15.85  *          *
* Frctn Loss (ft)        *    0.41  * Cum Volume (acre-ft)  *          *   13.07  *          *
* C & E Loss (ft)        *    0.01  * Cum SA (acres)        *          *    3.52  *          *
*****************************************************************************************************

CROSS SECTION


RIVER: Range Wash
REACH: Sloan Channel       RS: 72.5*

INPUT
Description:
Station Elevation Data    num=       7
     Sta    Elev      Sta    Elev      Sta    Elev      Sta    Elev      Sta    Elev
*****************************************************************************
   1000 1705.86 1011.47    1700 1011.49 1699.99 1041.48 1699.09 1071.47 1699.99
1071.49    1700 1082.96 1705.86

Manning's n Values         num=       3
     Sta    n Val      Sta    n Val      Sta    n Val
***********************************************
    1000     .015     1000     .015 1082.96     .015

Bank Sta: Left    Right     Lengths: Left Channel   Right      Coeff Contr.    Expan.
          1000 1082.96                86.82   86.82   86.82              .1       .3

CROSS SECTION OUTPUT  Profile #Post-Project
*****************************************************************************************************
* E.G. Elev (ft)         * 1707.17  * Element                * Left OB *  Channel * Right OB *
* Vel Head (ft)          *    3.84  * Wt. n-Val.             *         *    0.015 *          *
* W.S. Elev (ft)         * 1703.33  * Reach Len. (ft)       *   86.82  *   86.82  *   86.82  *
* Crit W.S. (ft)         * 1704.43  * Flow Area (sq ft)     *          *  249.34  *          *
* E.G. Slope (ft/ft)     *0.005052  * Area (sq ft)          *          *  249.34  *          *
* Q Total (cfs)          * 3921.00  * Flow (cfs)           *          * 3921.00  *          *
* Top Width (ft)         *   73.07  * Top Width (ft)       *          *   73.07  *          *
* Vel Total (ft/s)       *   15.73  * Avg. Vel. (ft/s)     *          *   15.73  *          *
* Max Chl Dpth (ft)      *    4.24  * Hydr. Depth (ft)     *          *    3.41  *          *
* Conv. Total (cfs)      * 55165.8  * Conv. (cfs)          *          * 55165.8  *          *
* Length Wtd. (ft)       *   86.82  * Wetted Per. (ft)     *          *   74.70  *          *
* Min Ch El (ft)         * 1699.09  * Shear (lb/sq ft)     *          *    1.05  *          *
* Alpha                  *    1.00  * Stream Power (lb/ft s) *         *   16.55  *          *
* Frctn Loss (ft)        *    0.43  * Cum Volume (acre-ft)  *          *   12.57  *          *
* C & E Loss (ft)        *    0.01  * Cum SA (acres)        *          *    3.38  *          *
*****************************************************************************************************
```

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 71.6666*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1705.33	1011.46	1699.52	1011.49	1699.51	1041.47	1698.61	1071.45	1699.51
1071.48	1699.52	1082.95	1705.33	.					

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.95	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.95	86.82	86.82	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1706.72	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.89	Wt. n-Val.		0.015	
W.S. Elev (ft)	1702.83	Reach Len. (ft)	86.82	86.82	86.82
Crit W.S. (ft)	1703.95	Flow Area (sq ft)		247.59	
E.G. Slope (ft/ft)	*0.005170	Area (sq ft)		247.59	
Q Total (cfs)	3921.00	Flow (cfs)		3921.00	
Top Width (ft)	73.07	Top Width (ft)		73.07	
Vel Total (ft/s)	15.84	Avg. Vel. (ft/s)		15.84	
Max Chl Dpth (ft)	4.22	Hydr. Depth (ft)		3.39	
Conv. Total (cfs)	54532.8	Conv. (cfs)		54532.8	
Length Wtd. (ft)	86.82	Wetted Per. (ft)		74.68	
Min Ch El (ft)	1698.61	Shear (lb/sq ft)		1.07	
Alpha	1.00	Stream Power (lb/ft s)		16.95	
Frctn Loss (ft)	0.44	Cum Volume (acre-ft)		12.08	
C & E Loss (ft)	0.01	Cum SA (acres)		3.23	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 70.8333*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1704.8	1011.46	1699.03	1011.49	1699.02	1041.47	1698.12	1071.44	1699.02
1071.47	1699.03	1082.93	1704.8						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.93	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.93	86.82	86.82	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1706.26	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.95	Wt. n-Val.		0.015	
W.S. Elev (ft)	1702.31	Reach Len. (ft)	86.82	86.82	86.82
Crit W.S. (ft)	1703.46	Flow Area (sq ft)		245.88	
E.G. Slope (ft/ft)	*0.005286	Area (sq ft)		245.88	
Q Total (cfs)	3921.00	Flow (cfs)		3921.00	
Top Width (ft)	73.04	Top Width (ft)		73.04	
Vel Total (ft/s)	15.95	Avg. Vel. (ft/s)		15.95	
Max Chl Dpth (ft)	4.19	Hydr. Depth (ft)		3.37	
Conv. Total (cfs)	53928.3	Conv. (cfs)		53928.3	
Length Wtd. (ft)	86.82	Wetted Per. (ft)		74.63	
Min Ch El (ft)	1698.12	Shear (lb/sq ft)		1.09	
Alpha	1.00	Stream Power (lb/ft s)		17.34	
Frctn Loss (ft)	0.45	Cum Volume (acre-ft)		11.59	
C & E Loss (ft)	0.01	Cum SA (acres)		3.08	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 70

INPUT
Description: PLAN STA 171+50
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1704.27	1011.46	1698.54	1041.46	1697.64	1071.46	1698.54	1082.92	1704.27

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	46.25	46.25	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1705.80	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.98	Wt. n-Val.		0.015	
W.S. Elev (ft)	1701.81	Reach Len. (ft)	46.25	46.25	46.25
Crit W.S. (ft)	1702.99	Flow Area (sq ft)		244.91	
E.G. Slope (ft/ft)	*0.005360	Area (sq ft)		244.91	
Q Total (cfs)	3921.00	Flow (cfs)		3921.00	
Top Width (ft)	73.10	Top Width (ft)		73.10	
Vel Total (ft/s)	16.01	Avg. Vel. (ft/s)		16.01	

Max Chl Dpth (ft)	4.17	Hydr. Depth (ft)		3.35			
Conv. Total (cfs)	53556.5	Conv. (cfs)		53556.5			
Length Wtd. (ft)	46.25	Wetted Per. (ft)		74.67			
Min Ch El (ft)	1697.64	Shear (lb/sq ft)		1.10			
Alpha	1.00	Stream Power (lb/ft s)		17.57			
Frctn Loss (ft)	0.46	Cum Volume (acre-ft)		11.10			
C & E Loss (ft)	0.00	Cum SA (acres)		2.94			

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 60

INPUT
Description: PLAN STA 171+96
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1710.12	1000	1704	1011.46	1698.28	1041.46	1697.38	1071.46	1698.28
1082.92	1704	1082.92	1710.12						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	90	90	.3	.5

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1705.54	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.93	Wt. n-Val.		0.015	
W.S. Elev (ft)	1701.61	Reach Len. (ft)	2.00	2.00	2.00
Crit W.S. (ft)	1702.75	Flow Area (sq ft)		249.08	
E.G. Slope (ft/ft)	*0.005204	Area (sq ft)		249.08	
Q Total (cfs)	3964.00	Flow (cfs)		3964.00	
Top Width (ft)	73.35	Top Width (ft)		73.35	
Vel Total (ft/s)	15.91	Avg. Vel. (ft/s)		15.91	
Max Chl Dpth (ft)	4.23	Hydr. Depth (ft)		3.40	
Conv. Total (cfs)	54950.2	Conv. (cfs)		54950.2	
Length Wtd. (ft)	2.00	Wetted Per. (ft)		74.94	
Min Ch El (ft)	1697.38	Shear (lb/sq ft)		1.08	
Alpha	1.00	Stream Power (lb/ft s)		17.18	
Frctn Loss (ft)	0.24	Cum Volume (acre-ft)		10.83	
C & E Loss (ft)	0.01	Cum SA (acres)		2.86	

BRIDGE

RIVER: Range Wash
REACH: Sloan Channel RS: 50

INPUT
Description: PLAN STA 171+99
Distance from Upstream XS = 2
Deck/Roadway Width = 87
Weir Coefficient = 2.6
Upstream Deck/Roadway Coordinates
num= 2

Sta Hi Cord	Lo Cord	Sta Hi Cord	Lo Cord
1000	1710.12	1704.33	1082.92	1710.12	1704.33

Upstream Bridge Cross Section Data
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1710.12	1000	1704	1011.46	1698.28	1041.46	1697.38	1071.46	1698.28
1082.92	1704	1082.92	1710.12						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Coeff Contr.	Expan.
1000	1082.92	.3	.5

Downstream Deck/Roadway Coordinates
num= 2

Sta Hi Cord	Lo Cord	Sta Hi Cord	Lo Cord
1000	1710.12	1704.33	1082.92	1710.12	1704.33

Downstream Bridge Cross Section Data
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1710.12	1000	1703.72	1011.46	1697.99	1041.46	1697.09	1071.46	1697.99
1082.92	1703.72	1082.92	1710.12						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Coeff Contr.	Expan.
1000	1082.92	.3	.5

Upstream Embankment side slope = 0 horiz. to 1.0 vertical
Downstream Embankment side slope = 0 horiz. to 1.0 vertical
Maximum allowable submergence for weir flow = .95
Elevation at which weir flow begins = 1710.12
Energy head used in spillway design =
Spillway height used in design =
Weir crest shape = Broad Crested

Number of Piers = 4

```
Pier Data
Pier Station     Upstream=1017.708    Downstream=1017.708
Upstream     num=        2
    Width   Elev    Width   Elev
*********************************
     .67    1694     .67    1705
Downstream     num=        2
    Width   Elev    Width   Elev
*********************************
     .67    1694     .67    1705

Pier Data
Pier Station     Upstream=1033.458    Downstream=1033.458
Upstream     num=        2
    Width   Elev    Width   Elev
*********************************
     .67    1694     .67    1705
Downstream     num=        2
    Width   Elev    Width   Elev
*********************************
     .67    1694     .67    1705

Pier Data
Pier Station     Upstream=1049.291    Downstream=1049.291
Upstream     num=        2
    Width   Elev    Width   Elev
*********************************
     .67    1694     .67    1705
Downstream     num=        2
    Width   Elev    Width   Elev
*********************************
     .67    1694     .67    1705

Pier Data
Pier Station     Upstream=1065.041    Downstream=1065.041
Upstream     num=        2
    Width   Elev    Width   Elev
*********************************
     .67    1694     .67    1705
Downstream     num=        2
    Width   Elev    Width   Elev
*********************************
     .67    1694     .67    1705

Number of Bridge Coefficient Sets =  1

Low Flow Methods and Data
       Energy
Selected Low Flow Methods = Highest Energy Answer

High Flow Method
       Energy Only

Additional Bridge Parameters
       Add Friction component to Momentum
       Do not add Weight component to Momentum
       Class B flow critical depth computations use critical depth
           inside the bridge at the upstream end
       Criteria to check for pressure flow = Upstream energy grade line

BRIDGE OUTPUT  Profile #Post-Project
*****************************************************************************************
* E.G. US. (ft)          *    1705.54  * Element              *Inside BR US *Inside BR DS *
* W.S. US. (ft)          *    1701.61  * E.G. Elev (ft)       *    1705.43  *    1705.26  *
* Q Total (cfs)          *    3964.00  * W.S. Elev (ft)       *    1701.99  *    1701.58  *
* Q Bridge (cfs)         *    3964.00  * Crit W.S. (ft)       *    1702.91  *    1702.60  *
* Q Weir (cfs)           *             * Max Chl Dpth (ft)     *       4.61  *       4.49  *
* Weir Sta Lft (ft)      *             * Vel Total (ft/s)      *      14.88  *      15.38  *
* Weir Sta Rgt (ft)      *             * Flow Area (sq ft)     *     266.38  *     257.68  *
* Weir Submerg           *             * Froude # Chl          *       1.37  *       1.43  *
* Weir Max Depth (ft)    *             * Specif Force (cu ft)  *    2365.30  *    2395.57  *
* Min El Weir Flow (ft)  *    1710.13  * Hydr Depth (ft)       *       3.69  *       3.59  *
* Min El Prs (ft)        *    1704.33  * W.P. Total (ft)       *     107.10  *     105.58  *
* Delta EG (ft)          *    1705.54  * Conv. Total (cfs)     *   48440.5   *   46273.2   *
* Delta WS (ft)          *      -0.47  * Top Width (ft)       *      72.20  *      71.69  *
* BR Open Area (sq ft)   *     445.75  * Frctn Loss (ft)       *       0.01  *       0.42  *
* BR Open Vel (ft/s)     *      15.38  * C & E Loss (ft)       *       0.87  *       0.62  *
* Coef of Q              *             * Shear Total (lb/sq ft) *      1.04  *       1.12  *
* Br Sel Method          *Energy only  * Power Total (lb/ft s)  *     15.47  *      17.20  *
*****************************************************************************************

Note:     Momentum answer is not valid if the water surface is above the low chord or if there is weir flow.
          The momentum answer has been disregarded.
Warning: The energy equation could not be balanced within the specified number of iterations.  The
          program selected the water surface that had the least amount of error between computed and
          assumed values.
Warning: The energy equation could not be balanced within the specified number of iterations.  The
          program selected the water surface that had the least amount of error between computed and
          assumed values.

CROSS SECTION


RIVER: Range Wash
REACH: Sloan Channel      RS: 40

INPUT
Description: PLAN STA 172+86
Station Elevation Data    num=       7
     Sta     Elev      Sta     Elev      Sta     Elev      Sta     Elev      Sta     Elev
*********************************************************************************
    1000 1710.12    1000 1703.72 1011.46 1697.99 1041.46 1697.09 1071.46 1697.99
 1082.92 1703.72 1082.92 1710.12

Manning's n Values        num=       3
     Sta   n Val      Sta   n Val      Sta   n Val
*************************************************
    1000     .015    1000     .015 1082.92     .015

Bank Sta: Left   Right    Lengths: Left Channel   Right     Coeff Contr.    Expan.
          1000 1082.92           113.64  113.64  113.64             .3        .5

CROSS SECTION OUTPUT  Profile #Post-Project
```

E.G. Elev (ft)	1704.69	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.60	Wt. n-Val.		0.015	
W.S. Elev (ft)	1702.09	Reach Len. (ft)	113.64	113.64	113.64
Crit W.S. (ft)	1702.47	Flow Area (sq ft)		306.28	
E.G. Slope (ft/ft)	*0.002772	Area (sq ft)		306.28	
Q Total (cfs)	3964.00	Flow (cfs)		3964.00	
Top Width (ft)	76.38	Top Width (ft)		76.38	
Vel Total (ft/s)	12.94	Avg. Vel. (ft/s)		12.94	
Max Chl Dpth (ft)	5.00	Hydr. Depth (ft)		4.01	
Conv. Total (cfs)	75296.6	Conv. (cfs)		75296.6	
Length Wtd. (ft)	113.64	Wetted Per. (ft)		78.34	
Min Ch El (ft)	1697.09	Shear (lb/sq ft)		0.68	
Alpha	1.00	Stream Power (lb/ft s)		8.75	
Frctn Loss (ft)	0.00	Cum Volume (acre-ft)		10.29	
C & E Loss (ft)	0.58	Cum SA (acres)		2.71	

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 30

INPUT
Description: PLAN STA 174+00
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1704.06	1011.46	1697.46	1041.46	1696.56	1071.46	1697.46	1081.36	1704.06

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	96.54	96.54	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1704.33	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.74	Wt. n-Val.		0.015	
W.S. Elev (ft)	1701.59	Reach Len. (ft)	96.54	96.54	96.54
Crit W.S. (ft)	1702.00	Flow Area (sq ft)		300.51	
E.G. Slope (ft/ft)	*0.002820	Area (sq ft)		300.51	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	72.41	Top Width (ft)		72.41	
Vel Total (ft/s)	13.28	Avg. Vel. (ft/s)		13.28	
Max Chl Dpth (ft)	5.03	Hydr. Depth (ft)		4.15	
Conv. Total (cfs)	75139.2	Conv. (cfs)		75139.2	
Length Wtd. (ft)	96.54	Wetted Per. (ft)		74.94	
Min Ch El (ft)	1696.56	Shear (lb/sq ft)		0.71	
Alpha	1.00	Stream Power (lb/ft s)		9.37	
Frctn Loss (ft)	0.32	Cum Volume (acre-ft)		9.50	
C & E Loss (ft)	0.04	Cum SA (acres)		2.52	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 29.2307*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1703.61	1011.46	1697.01	1041.46	1696.11	1071.46	1697.01	1081.36	1703.61

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	96.54	96.54	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1703.99	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.11	Wt. n-Val.		0.015	
W.S. Elev (ft)	1700.88	Reach Len. (ft)	96.54	96.54	96.54
Crit W.S. (ft)	1701.55	Flow Area (sq ft)		281.87	
E.G. Slope (ft/ft)	*0.003433	Area (sq ft)		281.87	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	71.63	Top Width (ft)		71.63	
Vel Total (ft/s)	14.16	Avg. Vel. (ft/s)		14.16	
Max Chl Dpth (ft)	4.77	Hydr. Depth (ft)		3.93	
Conv. Total (cfs)	68102.1	Conv. (cfs)		68102.1	
Length Wtd. (ft)	96.54	Wetted Per. (ft)		74.00	
Min Ch El (ft)	1696.11	Shear (lb/sq ft)		0.82	
Alpha	1.00	Stream Power (lb/ft s)		11.55	
Frctn Loss (ft)	0.30	Cum Volume (acre-ft)		8.86	
C & E Loss (ft)	0.04	Cum SA (acres)		2.36	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 28.4615*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev

```
*************************************************************************
 1001.53 1703.17 1011.46 1696.57 1041.46 1695.67 1071.46 1696.57 1081.36 1703.17

Manning's n Values         num=        3
     Sta   n Val      Sta   n Val      Sta   n Val
*********************************************
 1001.53     .015 1001.53     .015 1081.36     .015

Bank Sta: Left   Right     Lengths: Left Channel   Right      Coeff Contr.    Expan.
       1001.53 1081.36              96.54   96.54   96.54              .1        .3

CROSS SECTION OUTPUT  Profile #Post-Project
*************************************************************************************************
* E.G. Elev (ft)          * 1703.63  * Element                * Left OB * Channel * Right OB *
* Vel Head (ft)           *    3.29  * Wt. n-Val.             *         *   0.015 *          *
* W.S. Elev (ft)          * 1700.33  * Reach Len. (ft)       *   96.54  *   96.54 *   96.54  *
* Crit W.S. (ft)          * 1701.11  * Flow Area (sq ft)     *          *  273.94 *          *
* E.G. Slope (ft/ft)      *0.003748  * Area (sq ft)          *          *  273.94 *          *
* Q Total (cfs)           * 3990.00  * Flow (cfs)            *          * 3990.00 *          *
* Top Width (ft)          *   71.30  * Top Width (ft)        *          *   71.30 *          *
* Vel Total (ft/s)        *   14.57  * Avg. Vel. (ft/s)      *          *   14.57 *          *
* Max Chl Dpth (ft)       *    4.66  * Hydr. Depth (ft)      *          *    3.84 *          *
* Conv. Total (cfs)       * 65172.7  * Conv. (cfs)           *          * 65172.7 *          *
* Length Wtd. (ft)        *   96.54  * Wetted Per. (ft)      *          *   73.60 *          *
* Min Ch El (ft)          * 1695.67  * Shear (lb/sq ft)      *          *    0.87 *          *
* Alpha                   *    1.00  * Stream Power (lb/ft s) *         *   12.68 *          *
* Frctn Loss (ft)         *    0.35  * Cum Volume (acre-ft)  *          *    8.24 *          *
* C & E Loss (ft)         *    0.02  * Cum SA (acres)        *          *    2.20 *          *
*************************************************************************************************

CROSS SECTION


RIVER: Range Wash
REACH: Sloan Channel       RS: 27.6923*

INPUT
Description:
Station Elevation Data     num=        5
     Sta     Elev      Sta     Elev      Sta     Elev      Sta     Elev      Sta     Elev
*************************************************************************************
 1001.53 1702.72 1011.46 1696.12 1041.46 1695.22 1071.46 1696.12 1081.36 1702.72

Manning's n Values         num=        3
     Sta   n Val      Sta   n Val      Sta   n Val
*********************************************
 1001.53     .015 1001.53     .015 1081.36     .015

Bank Sta: Left   Right     Lengths: Left Channel   Right      Coeff Contr.    Expan.
       1001.53 1081.36              96.54   96.54   96.54              .1        .3

CROSS SECTION OUTPUT  Profile #Post-Project
*************************************************************************************************
* E.G. Elev (ft)          * 1703.24  * Element                * Left OB * Channel * Right OB *
* Vel Head (ft)           *    3.43  * Wt. n-Val.             *         *   0.015 *          *
* W.S. Elev (ft)          * 1699.80  * Reach Len. (ft)       *   96.54  *   96.54 *   96.54  *
* Crit W.S. (ft)          * 1700.66  * Flow Area (sq ft)     *          *  268.37 *          *
* E.G. Slope (ft/ft)      *0.003993  * Area (sq ft)          *          *  268.37 *          *
* Q Total (cfs)           * 3990.00  * Flow (cfs)            *          * 3990.00 *          *
* Top Width (ft)          *   71.07  * Top Width (ft)        *          *   71.07 *          *
* Vel Total (ft/s)        *   14.87  * Avg. Vel. (ft/s)      *          *   14.87 *          *
* Max Chl Dpth (ft)       *    4.58  * Hydr. Depth (ft)      *          *    3.78 *          *
* Conv. Total (cfs)       * 63139.1  * Conv. (cfs)           *          * 63139.1 *          *
* Length Wtd. (ft)        *   96.54  * Wetted Per. (ft)      *          *   73.32 *          *
* Min Ch El (ft)          * 1695.22  * Shear (lb/sq ft)      *          *    0.91 *          *
* Alpha                   *    1.00  * Stream Power (lb/ft s) *         *   13.57 *          *
* Frctn Loss (ft)         *    0.37  * Cum Volume (acre-ft)  *          *    7.64 *          *
* C & E Loss (ft)         *    0.01  * Cum SA (acres)        *          *    2.04 *          *
*************************************************************************************************

CROSS SECTION


RIVER: Range Wash
REACH: Sloan Channel       RS: 26.9230*

INPUT
Description:
Station Elevation Data     num=        5
     Sta     Elev      Sta     Elev      Sta     Elev      Sta     Elev      Sta     Elev
*************************************************************************************
 1001.53 1702.28 1011.46 1695.68 1041.46 1694.78 1071.46 1695.68 1081.36 1702.28

Manning's n Values         num=        3
     Sta   n Val      Sta   n Val      Sta   n Val
*********************************************
 1001.53     .015 1001.53     .015 1081.36     .015

Bank Sta: Left   Right     Lengths: Left Channel   Right      Coeff Contr.    Expan.
       1001.53 1081.36              96.54   96.54   96.54              .1        .3

CROSS SECTION OUTPUT  Profile #Post-Project
*************************************************************************************************
* E.G. Elev (ft)          * 1702.84  * Element                * Left OB * Channel * Right OB *
* Vel Head (ft)           *    3.52  * Wt. n-Val.             *         *   0.015 *          *
* W.S. Elev (ft)          * 1699.32  * Reach Len. (ft)       *   96.54  *   96.54 *   96.54  *
* Crit W.S. (ft)          * 1700.22  * Flow Area (sq ft)     *          *  264.93 *          *
* E.G. Slope (ft/ft)      *0.004155  * Area (sq ft)          *          *  264.93 *          *
* Q Total (cfs)           * 3990.00  * Flow (cfs)            *          * 3990.00 *          *
* Top Width (ft)          *   70.92  * Top Width (ft)        *          *   70.92 *          *
* Vel Total (ft/s)        *   15.06  * Avg. Vel. (ft/s)      *          *   15.06 *          *
* Max Chl Dpth (ft)       *    4.53  * Hydr. Depth (ft)      *          *    3.74 *          *
* Conv. Total (cfs)       * 61897.4  * Conv. (cfs)           *          * 61897.4 *          *
* Length Wtd. (ft)        *   96.54  * Wetted Per. (ft)      *          *   73.15 *          *
* Min Ch El (ft)          * 1694.78  * Shear (lb/sq ft)      *          *    0.94 *          *
* Alpha                   *    1.00  * Stream Power (lb/ft s) *         *   14.15 *          *
* Frctn Loss (ft)         *    0.39  * Cum Volume (acre-ft)  *          *    7.05 *          *
* C & E Loss (ft)         *    0.01  * Cum SA (acres)        *          *    1.88 *          *
*************************************************************************************************

CROSS SECTION
```

RIVER: Range Wash
REACH: Sloan Channel RS: 26.1538*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1701.83	1011.46	1695.23	1041.46	1694.33	1071.46	1695.23	1081.36	1701.83

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	96.54	96.54	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1702.42	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.59	Wt. n-Val.		0.015	
W.S. Elev (ft)	1698.83	Reach Len. (ft)	96.54	96.54	96.54
Crit W.S. (ft)	1699.77	Flow Area (sq ft)		262.57	
E.G. Slope (ft/ft)	*0.004272	Area (sq ft)		262.57	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	70.82	Top Width (ft)		70.82	
Vel Total (ft/s)	15.20	Avg. Vel. (ft/s)		15.20	
Max Chl Dpth (ft)	4.50	Hydr. Depth (ft)		3.71	
Conv. Total (cfs)	61047.4	Conv. (cfs)		61047.4	
Length Wtd. (ft)	96.54	Wetted Per. (ft)		73.03	
Min Ch El (ft)	1694.33	Shear (lb/sq ft)		0.96	
Alpha	1.00	Stream Power (lb/ft s)		14.57	
Frctn Loss (ft)	0.41	Cum Volume (acre-ft)		6.46	
C & E Loss (ft)	0.01	Cum SA (acres)		1.73	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 25.3846*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1701.38	1011.46	1694.78	1041.46	1693.88	1071.46	1694.78	1081.36	1701.38

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	96.54	96.54	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1701.99	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.64	Wt. n-Val.		0.015	
W.S. Elev (ft)	1698.35	Reach Len. (ft)	96.54	96.54	96.54
Crit W.S. (ft)	1699.32	Flow Area (sq ft)		260.66	
E.G. Slope (ft/ft)	*0.004369	Area (sq ft)		260.66	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	70.74	Top Width (ft)		70.74	
Vel Total (ft/s)	15.31	Avg. Vel. (ft/s)		15.31	
Max Chl Dpth (ft)	4.47	Hydr. Depth (ft)		3.68	
Conv. Total (cfs)	60362.9	Conv. (cfs)		60362.9	
Length Wtd. (ft)	96.54	Wetted Per. (ft)		72.93	
Min Ch El (ft)	1693.88	Shear (lb/sq ft)		0.97	
Alpha	1.00	Stream Power (lb/ft s)		14.92	
Frctn Loss (ft)	0.42	Cum Volume (acre-ft)		5.88	
C & E Loss (ft)	0.01	Cum SA (acres)		1.57	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 24.6153*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1700.94	1011.46	1694.34	1041.46	1693.44	1071.46	1694.34	1081.36	1700.94

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	96.54	96.54	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1701.57	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.66	Wt. n-Val.		0.015	
W.S. Elev (ft)	1697.90	Reach Len. (ft)	96.54	96.54	96.54
Crit W.S. (ft)	1698.88	Flow Area (sq ft)		259.72	
E.G. Slope (ft/ft)	*0.004418	Area (sq ft)		259.72	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	70.70	Top Width (ft)		70.70	
Vel Total (ft/s)	15.36	Avg. Vel. (ft/s)		15.36	
Max Chl Dpth (ft)	4.46	Hydr. Depth (ft)		3.67	
Conv. Total (cfs)	60026.6	Conv. (cfs)		60026.6	
Length Wtd. (ft)	96.54	Wetted Per. (ft)		72.88	
Min Ch El (ft)	1693.44	Shear (lb/sq ft)		0.98	
Alpha	1.00	Stream Power (lb/ft s)		15.10	

Frctn Loss (ft)	0.42	Cum Volume (acre-ft)		5.31				
C & E Loss (ft)	0.00	Cum SA (acres)		1.41				

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 23.8461*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1700.49	1011.46	1693.89	1041.46	1692.99	1071.46	1693.89	1081.36	1700.49

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	96.54	96.54	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1701.13	Element		0.015	
Vel Head (ft)	3.70	Wt. n-Val.		0.015	
W.S. Elev (ft)	1697.44	Reach Len. (ft)	96.54	96.54	96.54
Crit W.S. (ft)	1698.43	Flow Area (sq ft)		258.55	
E.G. Slope (ft/ft)	0.004481	Area (sq ft)		258.55	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	70.65	Top Width (ft)		70.65	
Vel Total (ft/s)	15.43	Avg. Vel. (ft/s)		15.43	
Max Chl Dpth (ft)	4.44	Hydr. Depth (ft)		3.66	
Conv. Total (cfs)	59608.0	Conv. (cfs)		59608.0	
Length Wtd. (ft)	96.54	Wetted Per. (ft)		72.82	
Min Ch El (ft)	1692.99	Shear (lb/sq ft)		0.99	
Alpha	1.00	Stream Power (lb/ft s)		15.33	
Frctn Loss (ft)	0.43	Cum Volume (acre-ft)		4.73	
C & E Loss (ft)	0.00	Cum SA (acres)		1.26	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 23.0769*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1700.04	1011.46	1693.44	1041.46	1692.54	1071.46	1693.44	1081.36	1700.04

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	96.54	96.54	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1700.70	Element		0.015	
Vel Head (ft)	3.72	Wt. n-Val.		0.015	
W.S. Elev (ft)	1696.97	Reach Len. (ft)	96.54	96.54	96.54
Crit W.S. (ft)	1697.98	Flow Area (sq ft)		257.69	
E.G. Slope (ft/ft)	0.004527	Area (sq ft)		257.69	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	70.61	Top Width (ft)		70.61	
Vel Total (ft/s)	15.48	Avg. Vel. (ft/s)		15.48	
Max Chl Dpth (ft)	4.43	Hydr. Depth (ft)		3.65	
Conv. Total (cfs)	59302.6	Conv. (cfs)		59302.6	
Length Wtd. (ft)	96.54	Wetted Per. (ft)		72.78	
Min Ch El (ft)	1692.54	Shear (lb/sq ft)		1.00	
Alpha	1.00	Stream Power (lb/ft s)		15.49	
Frctn Loss (ft)	0.43	Cum Volume (acre-ft)		4.16	
C & E Loss (ft)	0.00	Cum SA (acres)		1.10	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 22.3076*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1699.6	1011.46	1693	1041.46	1692.1	1071.46	1693	1081.36	1699.6

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	96.54	96.54	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1700.25	Element		0.015	
Vel Head (ft)	3.71	Wt. n-Val.		0.015	
W.S. Elev (ft)	1696.54	Reach Len. (ft)	96.54	96.54	96.54
Crit W.S. (ft)	1697.54	Flow Area (sq ft)		258.06	
E.G. Slope (ft/ft)	0.004507	Area (sq ft)		258.06	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	

* Top Width (ft)	* 70.63	* Top Width (ft)	*	* 70.63	*
* Vel Total (ft/s)	* 15.46	* Avg. Vel. (ft/s)	*	* 15.46	*
* Max Chl Dpth (ft)	* 4.44	* Hydr. Depth (ft)	*	* 3.65	*
* Conv. Total (cfs)	* 59432.9	* Conv. (cfs)	*	* 59432.9	*
* Length Wtd. (ft)	* 96.54	* Wetted Per. (ft)	*	* 72.80	*
* Min Ch El (ft)	* 1692.10	* Shear (lb/sq ft)	*	* 1.00	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 15.42	*
* Frctn Loss (ft)	* 0.44	* Cum Volume (acre-ft)	*	* 3.59	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 0.94	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 21.5384*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1699.15	1011.46	1692.55	1041.46	1691.65	1071.46	1692.55	1081.36	1699.15

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	96.54	96.54	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
* E.G. Elev (ft)	* 1699.81	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 3.73	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1696.08	* Reach Len. (ft)	* 96.54	* 96.54	* 96.54
* Crit W.S. (ft)	* 1697.09	* Flow Area (sq ft)	*	* 257.37	*
* E.G. Slope (ft/ft)	*0.004544	* Area (sq ft)	*	* 257.37	*
* Q Total (cfs)	* 3990.00	* Flow (cfs)	*	* 3990.00	*
* Top Width (ft)	* 70.60	* Top Width (ft)	*	* 70.60	*
* Vel Total (ft/s)	* 15.50	* Avg. Vel. (ft/s)	*	* 15.50	*
* Max Chl Dpth (ft)	* 4.43	* Hydr. Depth (ft)	*	* 3.65	*
* Conv. Total (cfs)	* 59187.5	* Conv. (cfs)	*	* 59187.5	*
* Length Wtd. (ft)	* 96.54	* Wetted Per. (ft)	*	* 72.76	*
* Min Ch El (ft)	* 1691.65	* Shear (lb/sq ft)	*	* 1.00	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 15.56	*
* Frctn Loss (ft)	* 0.44	* Cum Volume (acre-ft)	*	* 3.02	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 0.79	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 20.7692*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1698.71	1011.46	1692.11	1041.46	1691.21	1071.46	1692.11	1081.36	1698.71

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	96.54	96.54	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
* E.G. Elev (ft)	* 1699.37	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 3.73	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1695.64	* Reach Len. (ft)	* 96.54	* 96.54	* 96.54
* Crit W.S. (ft)	* 1696.65	* Flow Area (sq ft)	*	* 257.59	*
* E.G. Slope (ft/ft)	*0.004532	* Area (sq ft)	*	* 257.59	*
* Q Total (cfs)	* 3990.00	* Flow (cfs)	*	* 3990.00	*
* Top Width (ft)	* 70.61	* Top Width (ft)	*	* 70.61	*
* Vel Total (ft/s)	* 15.49	* Avg. Vel. (ft/s)	*	* 15.49	*
* Max Chl Dpth (ft)	* 4.43	* Hydr. Depth (ft)	*	* 3.65	*
* Conv. Total (cfs)	* 59267.2	* Conv. (cfs)	*	* 59267.2	*
* Length Wtd. (ft)	* 96.54	* Wetted Per. (ft)	*	* 72.77	*
* Min Ch El (ft)	* 1691.21	* Shear (lb/sq ft)	*	* 1.00	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 15.51	*
* Frctn Loss (ft)	* 0.44	* Cum Volume (acre-ft)	*	* 2.45	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 0.63	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 20

INPUT
Description: PLAN STA 186+54
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1698.26	1011.46	1691.66	1041.46	1690.76	1071.46	1691.66	1081.36	1698.26

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	260.12	280 299.88	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1698.93	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.74	Wt. n-Val.		0.015	
W.S. Elev (ft)	1695.18	Reach Len. (ft)	260.12	280.00	299.88
Crit W.S. (ft)	1696.20	Flow Area (sq ft)		257.01	
E.G. Slope (ft/ft)	0.004564	Area (sq ft)		257.01	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	70.58	Top Width (ft)		70.58	
Vel Total (ft/s)	15.52	Avg. Vel. (ft/s)		15.52	
Max Chl Dpth (ft)	4.42	Hydr. Depth (ft)		3.64	
Conv. Total (cfs)	59062.0	Conv. (cfs)		59062.0	
Length Wtd. (ft)		Wetted Per. (ft)		72.74	
Min Ch El (ft)	1690.76	Shear (lb/sq ft)		1.01	
Alpha	1.00	Stream Power (lb/ft s)		15.63	
Frctn Loss (ft)	0.44	Cum Volume (acre-ft)		1.88	
C & E Loss (ft)	0.00	Cum SA (acres)		0.48	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 10

INPUT
Description: PLAN STA 189+14
Station Elevation Data num= 4

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1700	1020	1689.5	1082	1689.5	1096	1700

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1096	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1096	0	0	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1696.51	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.31	Wt. n-Val.		0.015	
W.S. Elev (ft)	1694.20	Reach Len. (ft)			
Crit W.S. (ft)		Flow Area (sq ft)		327.16	
E.G. Slope (ft/ft)	0.002316	Area (sq ft)		327.16	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	77.22	Top Width (ft)		77.22	
Vel Total (ft/s)	12.20	Avg. Vel. (ft/s)		12.20	
Max Chl Dpth (ft)	4.70	Hydr. Depth (ft)		4.24	
Conv. Total (cfs)	82917.9	Conv. (cfs)		82917.9	
Length Wtd. (ft)		Wetted Per. (ft)		79.94	
Min Ch El (ft)	1689.50	Shear (lb/sq ft)		0.59	
Alpha	1.00	Stream Power (lb/ft s)		7.21	
Frctn Loss (ft)		Cum Volume (acre-ft)			
C & E Loss (ft)		Cum SA (acres)			

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.
Note: The user has entered a known water surface elevation at this cross section.

SUMMARY OF MANNING'S N VALUES

River:Range Wash

Reach	River Sta.	n1	n2	n3
Sloan Channel	210	.015	.015	.015
Sloan Channel	200	.015	.015	.015
Sloan Channel	197.5*	.015	.015	.015
Sloan Channel	195.*	.015	.015	.015
Sloan Channel	192.5*	.015	.015	.015
Sloan Channel	190	.015	.015	.015
Sloan Channel	180	.015	.015	.015
Sloan Channel	170	.015	.015	.015
Sloan Channel	160	.015	.015	.015
Sloan Channel	158.*	.015	.015	.015
Sloan Channel	156.*	.015	.015	.015
Sloan Channel	154.*	.015	.015	.015
Sloan Channel	152.*	.015	.015	.015
Sloan Channel	150	.015	.015	.015
Sloan Channel	148.75*	.015	.015	.015
Sloan Channel	147.5*	.015	.015	.015
Sloan Channel	146.25*	.015	.015	.015
Sloan Channel	145	.015	.015	.015
Sloan Channel	144.615*	.015	.015	.015
Sloan Channel	144.230*	.015	.015	.015
Sloan Channel	143.846*	.015	.015	.015
Sloan Channel	143.461*	.015	.015	.015
Sloan Channel	143.076*	.015	.015	.015
Sloan Channel	142.692*	.015	.015	.015
Sloan Channel	142.307*	.015	.015	.015
Sloan Channel	141.923*	.015	.015	.015
Sloan Channel	141.538*	.015	.015	.015
Sloan Channel	141.153*	.015	.015	.015
Sloan Channel	140.769*	.015	.015	.015
Sloan Channel	140.384*	.015	.015	.015
Sloan Channel	140	.015	.015	.015
Sloan Channel	130	.015	.015	.015
Sloan Channel	120	.015	.015	.015
Sloan Channel	110	.015	.015	.015
Sloan Channel	100	.015	.015	.015
Sloan Channel	90	.015	.015	.015
Sloan Channel	80	.015	.015	.015
Sloan Channel	75	.015	.015	.015
Sloan Channel	74.1666*	.015	.015	.015
Sloan Channel	73.3333*	.015	.015	.015
Sloan Channel	72.5*	.015	.015	.015

Reach	River Sta.	Left	Channel	Right
Sloan Channel	71.6666	.015	.015	.015
Sloan Channel	70.8333	.015	.015	.015
Sloan Channel	70	.015	.015	.015
Sloan Channel	60	.015	.015	.015
Sloan Channel	50	Bridge		
Sloan Channel	40	.015	.015	.015
Sloan Channel	30	.015	.015	.015
Sloan Channel	29.2307	.015	.015	.015
Sloan Channel	28.4615	.015	.015	.015
Sloan Channel	27.6923	.015	.015	.015
Sloan Channel	26.9230	.015	.015	.015
Sloan Channel	26.1538	.015	.015	.015
Sloan Channel	25.3846	.015	.015	.015
Sloan Channel	24.6153	.015	.015	.015
Sloan Channel	23.8461	.015	.015	.015
Sloan Channel	23.0769	.015	.015	.015
Sloan Channel	22.3076	.015	.015	.015
Sloan Channel	21.5384	.015	.015	.015
Sloan Channel	20.7692	.015	.015	.015
Sloan Channel	20	.015	.015	.015
Sloan Channel	10	.015	.015	.015

SUMMARY OF REACH LENGTHS

River: Range Wash

Reach	River Sta.	Left	Channel	Right
Sloan Channel	210	35.96	35.96	35.96
Sloan Channel	200	77.79	87.33	93.71
Sloan Channel	197.5	77.79	87.33	93.71
Sloan Channel	195.	77.79	87.33	93.71
Sloan Channel	192.5	77.79	87.33	93.71
Sloan Channel	190	225.65	225.65	225.65
Sloan Channel	180	100	100	100
Sloan Channel	170	51.96	51.96	51.96
Sloan Channel	160	89.2	89.2	89.2
Sloan Channel	158.	89.2	89.2	89.2
Sloan Channel	156.	89.2	89.2	89.2
Sloan Channel	154.	89.2	89.2	89.2
Sloan Channel	152.	89.2	89.2	89.2
Sloan Channel	150	72.79	72.79	72.79
Sloan Channel	148.75	72.79	72.79	72.79
Sloan Channel	147.5	72.79	72.79	72.79
Sloan Channel	146.25	72.79	72.79	72.79
Sloan Channel	145	189.27	189.27	189.27
Sloan Channel	144.615	189.27	189.27	189.27
Sloan Channel	144.230	189.27	189.27	189.27
Sloan Channel	143.846	189.27	189.27	189.27
Sloan Channel	143.461	189.27	189.27	189.27
Sloan Channel	143.076	189.27	189.27	189.27
Sloan Channel	142.692	189.27	189.27	189.27
Sloan Channel	142.307	189.27	189.27	189.27
Sloan Channel	141.923	189.27	189.27	189.27
Sloan Channel	141.538	189.27	189.27	189.27
Sloan Channel	141.153	189.27	189.27	189.27
Sloan Channel	140.769	189.27	189.27	189.27
Sloan Channel	140.384	189.27	189.27	189.27
Sloan Channel	140	50	50	50
Sloan Channel	130	129.35	129.35	129.35
Sloan Channel	120	50	50	50
Sloan Channel	110	100	100	100
Sloan Channel	100	100	100	100
Sloan Channel	90	50	50	50
Sloan Channel	80	300	300	300
Sloan Channel	75	86.82	86.82	86.82
Sloan Channel	74.1666	86.82	86.82	86.82
Sloan Channel	73.3333	86.82	86.82	86.82
Sloan Channel	72.5	86.82	86.82	86.82
Sloan Channel	71.6666	86.82	86.82	86.82
Sloan Channel	70.8333	86.82	86.82	86.82
Sloan Channel	70	46.25	46.25	46.25
Sloan Channel	60	90	90	90
Sloan Channel	50	Bridge		
Sloan Channel	40	113.64	113.64	113.64
Sloan Channel	30	96.54	96.54	96.54
Sloan Channel	29.2307	96.54	96.54	96.54
Sloan Channel	28.4615	96.54	96.54	96.54
Sloan Channel	27.6923	96.54	96.54	96.54
Sloan Channel	26.9230	96.54	96.54	96.54
Sloan Channel	26.1538	96.54	96.54	96.54
Sloan Channel	25.3846	96.54	96.54	96.54
Sloan Channel	24.6153	96.54	96.54	96.54
Sloan Channel	23.8461	96.54	96.54	96.54
Sloan Channel	23.0769	96.54	96.54	96.54
Sloan Channel	22.3076	96.54	96.54	96.54
Sloan Channel	21.5384	96.54	96.54	96.54
Sloan Channel	20.7692	96.54	96.54	96.54
Sloan Channel	20	260.12	280	299.88
Sloan Channel	10	0	0	0


SUMMARY OF CONTRACTION AND EXPANSION COEFFICIENTS
River: Range Wash


Reach	River Sta.	Contr.	Expan.
Sloan Channel	210	.1	.3
Sloan Channel	200	.1	.3
Sloan Channel	197.5	.1	.3
Sloan Channel	195.	.1	.3
Sloan Channel	192.5	.1	.3
Sloan Channel	190	.1	.3
Sloan Channel	180	.1	.3
Sloan Channel	170	.1	.3
Sloan Channel	160	.1	.3
Sloan Channel	158.	.1	.3

```
*Sloan Channel   *    156.*   *        .1*       .3*
*Sloan Channel   *    154.*   *        .1*       .3*
*Sloan Channel   *    152.*   *        .1*       .3*
*Sloan Channel   *    150     *        .1*       .3*
*Sloan Channel   *    148.75* *        .1*       .3*
*Sloan Channel   *    147.5*  *        .1*       .3*
*Sloan Channel   *    146.25* *        .1*       .3*
*Sloan Channel   *    145     *        .1*       .3*
*Sloan Channel   *    144.615**        .1*       .3*
*Sloan Channel   *    144.230**        .1*       .3*
*Sloan Channel   *    143.846**        .1*       .3*
*Sloan Channel   *    143.461**        .1*       .3*
*Sloan Channel   *    143.076**        .1*       .3*
*Sloan Channel   *    142.692**        .1*       .3*
*Sloan Channel   *    142.307**        .1*       .3*
*Sloan Channel   *    141.923**        .1*       .3*
*Sloan Channel   *    141.538**        .1*       .3*
*Sloan Channel   *    141.153**        .1*       .3*
*Sloan Channel   *    140.769**        .1*       .3*
*Sloan Channel   *    140.384**        .1*       .3*
*Sloan Channel   *    140     *        .1*       .3*
*Sloan Channel   *    130     *        .1*       .3*
*Sloan Channel   *    120     *        .1*       .3*
*Sloan Channel   *    110     *        .1*       .3*
*Sloan Channel   *    100     *        .1*       .3*
*Sloan Channel   *    90      *        .1*       .3*
*Sloan Channel   *    80      *        .1*       .3*
*Sloan Channel   *    75      *        .1*       .3*
*Sloan Channel   *    74.1666**        .1*       .3*
*Sloan Channel   *    73.3333**        .1*       .3*
*Sloan Channel   *    72.5*   *        .1*       .3*
*Sloan Channel   *    71.6666**        .1*       .3*
*Sloan Channel   *    70.8333**        .1*       .3*
*Sloan Channel   *    70      *        .1*       .3*
*Sloan Channel   *    60      *        .3*       .5*
*Sloan Channel   *    50      *Bridge  *         *
*Sloan Channel   *    40      *        .3*       .5*
*Sloan Channel   *    30      *        .1*       .3*
*Sloan Channel   *    29.2307**        .1*       .3*
*Sloan Channel   *    28.4615**        .1*       .3*
*Sloan Channel   *    27.6923**        .1*       .3*
*Sloan Channel   *    26.9230**        .1*       .3*
*Sloan Channel   *    26.1538**        .1*       .3*
*Sloan Channel   *    25.3846**        .1*       .3*
*Sloan Channel   *    24.6153**        .1*       .3*
*Sloan Channel   *    23.8461**        .1*       .3*
*Sloan Channel   *    23.0769**        .1*       .3*
*Sloan Channel   *    22.3076**        .1*       .3*
*Sloan Channel   *    21.5384**        .1*       .3*
*Sloan Channel   *    20.7692**        .1*       .3*
*Sloan Channel   *    20      *        .1*       .3*
*Sloan Channel   *    10      *        .1*       .3*
**************************************************
```

HEC-RAS Plan: Post River: Range Wash Reach: Sloan Channel Profile: Post-Project

Reach	River Sta	Profile	Q Total	Min Ch El	W.S. Elev	Crit W.S.	E.G. Elev	E.G. Slope	Vel Chnl	Flow Area	Top Width	Froude # Chl
			(cfs)	(ft)	(ft)	(ft)	(ft)	(ft/ft)	(ft/s)	(sq ft)	(ft)	
Sloan Channel	210	Post-Project	3072.00	1720.22	1724.58	1724.58	1726.32	0.002215	10.59	290.22	83.23	1.00
Sloan Channel	200	Post-Project	3072.00	1719.24	1722.56	1723.60	1726.02	0.006465	14.93	205.76	79.07	1.63
Sloan Channel	197.5*	Post-Project	3072.00	1718.89	1722.42	1723.25	1725.37	0.005029	13.78	222.93	79.93	1.45
Sloan Channel	195.*	Post-Project	3072.00	1718.54	1722.21	1722.90	1724.89	0.004310	13.12	234.20	80.50	1.36
Sloan Channel	192.5*	Post-Project	3072.00	1718.19	1721.91	1722.55	1724.50	0.004126	12.93	237.50	80.66	1.33
Sloan Channel	190	Post-Project	3072.00	1717.84	1721.56	1722.20	1724.15	0.004088	12.90	238.21	80.69	1.32
Sloan Channel	180	Post-Project	3072.00	1716.94	1720.69	1721.29	1723.23	0.003976	12.78	240.34	80.80	1.31
Sloan Channel	170	Post-Project	3072.00	1716.04	1719.99	1720.68	1722.80	0.004075	13.45	228.44	72.19	1.33
Sloan Channel	160	Post-Project	3072.00	1715.84	1719.80	1720.47	1722.59	0.004032	13.40	229.22	72.23	1.33
Sloan Channel	158.*	Post-Project	3072.00	1715.50	1719.51	1720.14	1722.22	0.003866	13.22	232.33	72.43	1.30
Sloan Channel	156.*	Post-Project	3072.00	1715.17	1719.18	1719.80	1721.89	0.003849	13.20	232.65	72.44	1.30
Sloan Channel	154.*	Post-Project	3072.00	1714.83	1718.84	1719.47	1721.55	0.003859	13.22	232.44	72.42	1.30
Sloan Channel	152.*	Post-Project	3072.00	1714.50	1718.52	1719.14	1721.21	0.003821	13.17	233.23	72.47	1.29
Sloan Channel	150	Post-Project	3072.00	1714.16	1718.18	1718.79	1720.87	0.003818	13.17	233.32	72.46	1.29
Sloan Channel	148.75*	Post-Project	3072.00	1713.94	1718.29	1718.57	1720.50	0.002810	11.91	257.85	73.80	1.12
Sloan Channel	147.5*	Post-Project	3072.00	1713.71	1718.00	1718.34	1720.28	0.002958	12.12	253.57	73.57	1.15
Sloan Channel	146.25*	Post-Project	3072.00	1713.48	1717.79	1718.12	1720.05	0.002920	12.06	254.65	73.63	1.14
Sloan Channel	145	Post-Project	3078.00	1713.26	1717.58	1717.91	1719.83	0.002902	12.05	255.50	73.67	1.14
Sloan Channel	144.615*	Post-Project	3078.00	1712.53	1716.64	1717.17	1719.20	0.003523	12.84	239.79	72.82	1.25
Sloan Channel	144.230*	Post-Project	3078.00	1711.80	1715.85	1716.44	1718.50	0.003719	13.06	235.59	72.60	1.28
Sloan Channel	143.846*	Post-Project	3078.00	1711.07	1715.10	1715.71	1717.78	0.003791	13.15	234.11	72.51	1.29
Sloan Channel	143.461*	Post-Project	3078.00	1710.34	1714.36	1714.98	1717.06	0.003828	13.19	233.34	72.47	1.30
Sloan Channel	143.076*	Post-Project	3078.00	1709.61	1713.62	1714.25	1716.33	0.003853	13.22	232.87	72.45	1.30
Sloan Channel	142.692*	Post-Project	3078.00	1708.88	1712.89	1713.52	1715.60	0.003845	13.21	233.01	72.46	1.30
Sloan Channel	142.307*	Post-Project	3078.00	1708.14	1712.15	1712.79	1714.87	0.003873	13.24	232.46	72.43	1.30
Sloan Channel	141.923*	Post-Project	3078.00	1707.41	1711.42	1712.06	1714.14	0.003864	13.23	232.64	72.44	1.30
Sloan Channel	141.538*	Post-Project	3078.00	1706.68	1710.69	1711.32	1713.41	0.003865	13.23	232.63	72.43	1.30
Sloan Channel	141.153*	Post-Project	3078.00	1705.95	1709.96	1710.59	1712.68	0.003863	13.23	232.68	72.44	1.30
Sloan Channel	140.769*	Post-Project	3078.00	1705.22	1709.23	1709.86	1711.95	0.003862	13.23	232.72	72.44	1.30
Sloan Channel	140.384*	Post-Project	3078.00	1704.49	1708.50	1709.14	1711.21	0.003858	13.22	232.82	72.45	1.30
Sloan Channel	140	Post-Project	3078.00	1703.76	1709.15	1708.42	1710.45	0.001255	9.14	336.70	77.96	0.78
Sloan Channel	130	Post-Project	3078.00	1703.57	1709.18		1710.35	0.001084	8.71	353.57	78.82	0.72
Sloan Channel	120	Post-Project	3078.00	1703.09	1709.22		1710.16	0.000773	7.78	395.80	80.93	0.62
Sloan Channel	110	Post-Project	3078.00	1702.90	1709.27		1710.10	0.000625	7.31	421.13	72.50	0.53
Sloan Channel	100	Post-Project	3891.00	1702.52	1708.37		1709.93	0.001300	10.04	387.60	72.50	0.77
Sloan Channel	90	Post-Project	3891.00	1702.14	1708.82		1709.62	0.000558	7.17	542.57	90.50	0.52
Sloan Channel	80	Post-Project	3891.00	1701.95	1707.27	1707.27	1709.43	0.002117	11.80	329.71	76.95	1.00
Sloan Channel	75	Post-Project	3921.00	1700.55	1704.99	1705.89	1708.43	0.004256	14.89	263.38	73.57	1.39
Sloan Channel	74.1666*	Post-Project	3921.00	1700.07	1704.42	1705.41	1708.03	0.004596	15.26	256.96	73.32	1.44
Sloan Channel	73.3333*	Post-Project	3921.00	1699.58	1703.87	1704.92	1707.61	0.004845	15.52	252.67	73.17	1.47
Sloan Channel	72.5*	Post-Project	3921.00	1699.09	1703.33	1704.43	1707.17	0.005052	15.73	249.34	73.07	1.50
Sloan Channel	71.6666*	Post-Project	3921.00	1698.61	1702.83	1703.95	1706.72	0.005170	15.84	247.59	73.07	1.52
Sloan Channel	70.8333*	Post-Project	3921.00	1698.12	1702.31	1703.46	1706.26	0.005286	15.95	245.88	73.04	1.53
Sloan Channel	70	Post-Project	3921.00	1697.64	1701.81	1702.99	1705.80	0.005360	16.01	244.91	73.10	1.54
Sloan Channel	60	Post-Project	3964.00	1697.38	1701.61	1702.75	1705.54	0.005204	15.91	249.08	73.35	1.52
Sloan Channel	50		Bridge									
Sloan Channel	40	Post-Project	3964.00	1697.09	1702.09	1702.47	1704.69	0.002772	12.94	306.28	76.38	1.14
Sloan Channel	30	Post-Project	3990.00	1696.56	1701.59	1702.00	1704.33	0.002820	13.28	300.51	72.41	1.15
Sloan Channel	29.2307*	Post-Project	3990.00	1696.11	1700.88	1701.55	1703.99	0.003433	14.16	281.87	71.63	1.26
Sloan Channel	28.4615*	Post-Project	3990.00	1695.67	1700.33	1701.11	1703.63	0.003748	14.57	273.94	71.30	1.31
Sloan Channel	27.6923*	Post-Project	3990.00	1695.22	1699.80	1700.66	1703.24	0.003993	14.87	268.37	71.07	1.35
Sloan Channel	26.9230*	Post-Project	3990.00	1694.78	1699.32	1700.22	1702.84	0.004155	15.06	264.93	70.92	1.37
Sloan Channel	26.1538*	Post-Project	3990.00	1694.33	1698.83	1699.77	1702.42	0.004272	15.20	262.57	70.82	1.39
Sloan Channel	25.3846*	Post-Project	3990.00	1693.88	1698.35	1699.32	1701.99	0.004369	15.31	260.66	70.74	1.41
Sloan Channel	24.6153*	Post-Project	3990.00	1693.44	1697.90	1698.88	1701.57	0.004418	15.36	259.72	70.70	1.41
Sloan Channel	23.8461*	Post-Project	3990.00	1692.99	1697.44	1698.43	1701.13	0.004481	15.43	258.55	70.65	1.42
Sloan Channel	23.0769*	Post-Project	3990.00	1692.54	1696.97	1697.98	1700.70	0.004527	15.48	257.69	70.61	1.43
Sloan Channel	22.3076*	Post-Project	3990.00	1692.10	1696.54	1697.54	1700.25	0.004507	15.46	258.06	70.63	1.43
Sloan Channel	21.5384*	Post-Project	3990.00	1691.65	1696.08	1697.09	1699.81	0.004544	15.50	257.37	70.60	1.43
Sloan Channel	20.7692*	Post-Project	3990.00	1691.21	1695.64	1696.65	1699.37	0.004532	15.49	257.59	70.61	1.43
Sloan Channel	20	Post-Project	3990.00	1690.76	1695.18	1696.20	1698.93	0.004564	15.52	257.01	70.58	1.43
Sloan Channel	10	Post-Project	3990.00	1689.50	1694.20		1696.51	0.002316	12.20	327.16	77.22	1.04



slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
Range Wash Sloan Channel
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Set WS
Elevation (ft)
1730
1725
1720
1715
1710
1705
1700
1695
1690
1685
0
1000
2000
3000
4000
5000
6000
7000
8000
Main Channel Distance (ft)
20
21.5384*
23.0769*
24.6153*
26.1538*
27.6923*
29.2307*
40
70
71.6666*
73.3333*
75
80
100
120
130
140.384*
140.769*
141.153*
141.538*
141.923*
142.307*
142.692*
143.076*
143.461*
143.846*
144.230*
144.615*
145
147.5*
150
154.*
158.*
170
190
195.*
200


slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 210 PLAN STA 118+89
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
WS Post-Project
Crit Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 200 PLAN STA 119+25
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 197.5*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta

slo_post Plan: Post-Project 12/13/2004

Geom: Post-Project Flow: Post-Project


River = Range Wash Reach = Sloan Channel RS = 195.*



slo_post Plan: Post-Project 12/13/2004

Geom: Post-Project Flow: Post-Project


River = Range Wash Reach = Sloan Channel RS = 192.5*





slo_post Plan: Post-Project 12/13/2004


Geom: Post-Project Flow: Post-Project


River = Range Wash Reach = Sloan Channel RS = 190 PLAN STA 122+74






slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 180 PLAN STA 125+00
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 170 PLAN STA 126+00
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 160 PLAN STA 126+52
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta



slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 158.*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 156.*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 154.*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta


slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 152.*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 150 PLAN STA 130+97
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 148.75*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta


slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 147.5*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 146.25*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 145
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta


slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 144.615*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 144.230*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 143.846*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta



slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 143.461*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 143.076*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 142.692*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta


slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 142.307*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 141.923*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 141.538*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta

slo_post Plan: Post-Project 12/13/2004

Geom: Post-Project Flow: Post-Project


River = Range Wash Reach = Sloan Channel RS = 141.153*



slo_post Plan: Post-Project 12/13/2004

Geom: Post-Project Flow: Post-Project


River = Range Wash Reach = Sloan Channel RS = 140.769*





slo_post Plan: Post-Project 12/13/2004


Geom: Post-Project Flow: Post-Project


River = Range Wash Reach = Sloan Channel RS = 140.384*






slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 140 PLAN STA 158+50
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
WS Post-Project
Crit Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 130 PLAN STA 159+00
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 120 PLAN STA 160+29
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
WS Post-Project
Ground
Bank Sta



slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 110 PLAN STA 160+79
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 100 PLAN STA 161+79
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 90 PLAN STA 162+79
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
WS Post-Project
Ground
Bank Sta



slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 80 PLAN STA 163+29
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
WS Post-Project
Crit Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 75
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 74.1666*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta



slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 73.3333*
.015
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
Elevation (ft)
Station (ft)
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 72.5*
.015
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
Elevation (ft)
Station (ft)
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 71.6666*
.015
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
Elevation (ft)
Station (ft)



slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 70.8333*
.015
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
Elevation (ft)
Station (ft)
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 70 PLAN STA 171+50
.015
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
Elevation (ft)
Station (ft)
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 60 PLAN STA 171+96
.015
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
Elevation (ft)
Station (ft)



slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 50 BR PLAN STA 171+99
.015
Elevation (ft)
1712
1710
1708
1706
1704
1702
1700
1698
1696
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 50 BR PLAN STA 171+99
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 40 PLAN STA 172+86
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta


slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 30 PLAN STA 174+00
.015
Elevation (ft)
1706
1704
1702
1700
1698
1696
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 29.2307*
.015
Elevation (ft)
1704
1702
1700
1698
1696
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 28.4615*
.015
Elevation (ft)
1704
1702
1700
1698
1696
1694
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta


slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 27.6923*
.015
Elevation (ft)
1704
1702
1700
1698
1696
1694
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 26.9230*
.015
Elevation (ft)
1704
1702
1700
1698
1696
1694
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 26.1538*
.015
Elevation (ft)
1704
1702
1700
1698
1696
1694
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta


slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 25.3846*
.015
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
Elevation (ft)
Station (ft)
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 24.6153*
.015
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
Elevation (ft)
Station (ft)
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 23.8461*
.015
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
Elevation (ft)
Station (ft)



slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 23.0769*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 22.3076*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 21.5384*
.015
Elevation (ft)
Station (ft)
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta


slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 20.7692*
.015
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
Elevation (ft)
Station (ft)
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 20 PLAN STA 186+54
.015
Legend
EG Post-Project
Crit Post-Project
WS Post-Project
Ground
Bank Sta
Elevation (ft)
Station (ft)
slo_post Plan: Post-Project 12/13/2004
Geom: Post-Project Flow: Post-Project
River = Range Wash Reach = Sloan Channel RS = 10 PLAN STA 189+14
.015
Legend
EG Post-Project
WS Post-Project
Ground
Bank Sta
Elevation (ft)
Station (ft)

Appendix E: Plans

F:\500-857\dwg\improv\sc_g01.dwg 03-10-04 14:06:52 RBlanchard

DEPARTMENT OF PUBLIC WORKS



Vicinity Map

NOT TO SCALE

County Commissioners

Chip Maxfield, Chairman
Myrna Williams, Vice-Chair
Yvonne Atkinson Gates
Mark A. James
Mary J. Kincaid-Chauncey
Rory Reid
Bruce L. Woodbury

SIGNATURE ON THESE PLANS WILL NOT BE CONSTRUED TO BE A PERMIT FOR OR AN APPROVAL OF ANY VIOLATION OF CLARK COUNTY SANITATION DISTRICT RULES, REGULATIONS, OR DESIGN AND CONSTRUCTION STANDARDS. THE APPROVAL OF THESE DRAWINGS DOES NOT GUARANTEE CAPACITY IN THE DISTRICT'S COLLECTION OR TREATMENT SYSTEM.

CLARK COUNTY NEVADA

"Progress as Promised"

2004
IMPROVEMENT PLANS FOR
SLOAN CHANNEL

FROM
CHARLESTON BOULEVARD TO
LAS VEGAS WASH

FUNDED BY
CLARK COUNTY REGIONAL FLOOD CONTROL DISTRICT

G.C. WALLACE, INC.
Engineers/Planners/Surveyors

County Manager

Thom Reilly

Director of Public Works

Approved:

M.J. Manning

Clark County Regional Flood Control District


Approved:

Gale Wm. Fraser II, P.E.
General Manager/
Chief Engineer

AGENCY	PLANS REVIEWED BY	DATE
SPRINT		
LAS VEGAS VALLEY WATER DISTRICT		
SOUTHWEST GAS COMPANY		
NEVADA POWER COMPANY (TRANSMISSION)		
NEVADA POWER COMPANY (DISTRIBUTION)		
CLARK COUNTY WATER RECLAMATION DISTRICT		
COX COMMUNICATIONS LAS VEGAS, INC.		

DEPARTMENT OF PUBLIC WORKS	BY	DATE
DEPUTY DIRECTOR		
CONSTRUCTION MANAGEMENT DIVISION		
DESIGN ENGINEERING DIVISION		
MAINTENANCE MANAGEMENT DIVISION		
TRAFFIC MANAGEMENT DIVISION		
COUNTY SURVEYOR'S OFFICE		

REVISIONS		
NUMBER	DESCRIPTION	DATE




DESIGN ENGINEERING DIVISION

COVER SHEET

L-1759

BID No.:



Location Map

Index of Sheets

DRAWING NO. DESCRIPTION

General Drawings


COVER SHEET
G-2 INDEX OF DRAWINGS, KEY MAP AND LOCATION MAP
G-3 GENERAL & CONSTRUCTION NOTES, LEGEND & ABBREVIATIONS
BENCHMARK, BASIS OF BEARINGS
G-4 HORIZONTAL CONTROL PLAN
G-5 ESTIMATE OF QUANTITIES
G-6 RECORD OF SURVEY

Civil Drawings

C-1 PLAN AND PROFILE STA 114+50.00 TO STA. 122+00.00
C-2 PLAN AND PROFILE STA 122+00.00 TO STA. 132+00.00
C-3 PLAN AND PROFILE STA 132+00.00 TO STA. 142+00.00
C-4 PLAN AND PROFILE STA 142+00.00 TO STA. 152+00.00
C-5 PLAN AND PROFILE STA 152+00.00 TO STA. 162+00.00
C-6 PLAN AND PROFILE STA 162+00.00 TO STA. 171+00.00
C-7 PLAN AND PROFILE STA 171+00.00 TO STA. 181+00.00
C-8 PLAN AND PROFILE STA 181+00.00 TO STA. 190+00.00
C-9 PLAN AND PROFILE (CONFLUENCE) AND LATERALS
C-10 TYPICAL CROSS SECTIONS
C-11 DETAILS
C-12 TYPICAL CROSS SECTIONS
C-13 FENCING/POST & CABLE RAILING PLAN
C-14 FENCING/POST & CABLE RAILING PLAN
C-15 ACCESS/MAINTENANCE ROAD CONTROL PLAN
C-16 ACCESS/MAINTENANCE ROAD CONTROL PLAN
C-17 DEPTH GAUGE STATION SECTIONS AND DETAILS

Structural Drawings

S-1 DETAILS
S-2 DETAILS
S-3 TYPICAL CHANNEL SECTIONS
S-4 CHANNEL TRANSITION STRUCTURES
S-5 ACCESS RAMP
S-6 ACCESS RAMP DETAILS
S-7 DETAILS



Key Map

SCALE: 1" = 400'

E	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

INDEX OF DRAWINGS, KEY MAP AND LOCATION MAP

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

NOEL C. LAUGHLIN — STATE OF NEVADA — No. 10169 — PROFESSIONAL ENGINEER — CIVIL — 3-11-04

PROJECT No: 500-857 DRAWN BY: DW
DESIGNED BY: CHECKED BY:
APPROVED BY:

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2289

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
G-2
SHT. 2 OF 30

LEGEND & ABBREVIATIONS

ABBREVIATION	LEGEND
= ASPHALTIC CONCRETE	(00.0) INV — EXIST. ELEVATION
= ASBESTOS CEMENT PIPE	00.0 INV — PROPOSED ELEVATION
= AIR VACUUM AIR RELIEF (VALVE)	(2356.1) — EXIST. SPOT ELEVATION
= BACK OF CURB	PROPERTY OR RIGHT-OF-WAY LINE
BOR = BEGIN CURB RETURN	CENTERLINE
BM = BENCHMARK	HYDRAULIC GRADE LINE (HGL)
= BACK OF WALK	ENERGY GRADE LINE (EGL)
= CABLE TELEVISION	EASEMENT
= CLARK COUNTY SANITATION DISTRICT	EXISTING TELEPHONE CABLE
= CENTERLINE	EXISTING FENCE
CSM = CONTROLLED LOW STRENGTH MATERIAL	EXISTING SANITARY SEWER LINE
CMP = CORRUGATED METAL PIPE	PROPOSED SANITARY SEWER LINE
CONC = CONCRETE	EXISTING WATER LINE
= DEPTH	PROPOSED WATER LINE
= DROP INLET	EXISTING GAS LINE
= DUCTILE IRON PIPE	EXISTING UNDERGROUND POWER
= EACH	EXISTING OVERHEAD POWER
EFF = EFFLUENT	EXISTING STORM DRAIN
EGL = ENERGY GRADE LINE	PROPOSED CHANNEL
= ELEVATION	PROPOSED STORM DRAIN
= EDGE OF PAVEMENT	EXISTING CABLE TELEVISION
= EXISTING	EXISTING CONTOUR
= FINISH FLOOR	SAWCUT LINE
FG = FINISH GRADE	EXISTING MANHOLE
FL = FLOW LINE	PROPOSED MANHOLE
FS = FINISH SURFACE	EXISTING FIRE HYDRANT
= FUTURE	EXISTING VALVE
= GAS	PROPOSED VALVE
= GRADE BREAK	PROPOSED DROP INLET
= GEOGRAPHIC INFORMATION SYSTEM	PROPOSED REUSE HYDRANT
HERCP = HORIZONTAL ELLIPTICAL REINFORCED CONCRETE PIPE	
= HYDRAULIC GRADE LINE	
= HIGH POINT	
= HIGH PRESSURE GAS	
= INSIDE DIAMETER	
INV = INVERT	
(L) LT = LEFT OF	
LF = LINEAL FEET	
= LOW POINT	
= LAS VEGAS AREA COMPUTER TRAFFIC SYSTEM	
= LAS VEGAS VALLEY WATER DISTRICT	
NAVD = NORTH AMERICAN VERTICAL DATUM	
NDOT = NEVADA DEPARTMENT OF TRANSPORTATION	
= NATURAL GRADE	
= OVERHEAD POWER	
= PLANTMIX BITUMINOUS SURFACE	
= PORTABLE PRECAST BARRIER RAIL	
PC = POINT OF CURVE	
PCC = POINT OF COMPOUND CURVE	
= POINT OF CURVE	
= POINT OF TANGENT	
= POINT REVERSE CURVE	
= PROPOSED	
PT = POINT OF TANGENT	
PVC = POLYVINYL CHLORIDE PIPE	
Q100 = 100 YEAR ULTIMATE CONDITION DESIGN FLOW	
) = RADIAL	
R = RIGHT OF	
= REINFORCED CONCRETE BOX	
RCP = REINFORCED CONCRETE PIPE	
RGRCP = RUBBER GASKET REINFORCED CONCRETE PIPE	
= RIGHT-OF-WAY	
= STORM DRAIN	
= STORM DRAIN MANHOLE	
= SOUTHERN NEVADA WATER AUTHORITY	
SS = SANITARY SEWER	
SSMH = SANITARY SEWER MANHOLE	
STA = STATION	
= STANDARD DRAWING NUMBER	
TC = TOP OF BACK OF CURB	
= TELEPHONE	
THK = THICK	
TMH = TOP OF MANHOLE	
TOE = TOE OF CHANNEL	
TP = TOP OF CHANNEL	
TW = TOP OF WALL	
= UNIFORM DESIGN AND CONSTRUCTION STANDARDS	
UNO = UNLESS NOTED OTHERWISE	
U.S. = UNITED STATES	
V.C. = VERTICAL CURVE	
VP = VITRIFIED CLAY PIPE	
W = WATER	
/ = WITH	
WWF = WELDED WIRE FABRIC	

CONSTRUCTION NOTES

1. CONSTRUCT 6' CHAIN-LINK FENCE (SEE DETAIL 9/C11)
2. CONSTRUCT 6' CHAIN-LINK GATE (SEE DETAIL 8/C11) (WIDTH OF GATE CALLED OUT IN PLAN VIEW)
3. CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)
4. CONSTRUCT 12' DRIVEWAY PER STD. DWG. NO. 224
5. INSTALL SIGN (SEE DETAIL 8/C11)
6. INSTALL SIGN (SEE DETAIL 7/C11)
7. CONSTRUCT POST AND CABLE RAILING (SEE DETAIL 10/C11)
8. PAINTED STAFF GAUGE (SEE DETAIL 5/C11)
9. CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)
10. CONSTRUCT PIPE CONNECTION (SEE DETAIL 8/S2)
11. CONSTRUCT RCB CONNECTION (SEE DETAIL 3/S7)
12. CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

1. REMOVE EXISTING BLOCK WALL AND FOOTING
2. REMOVE AND SALVAGE RIPRAP
3. REMOVE EXISTING CONCRETE SPLASH PAD
4. REMOVE EXISTING 80 FT.± CHANNEL SECTION TO EXPANSION JOINT.
5. REMOVE EXISTING CHANNEL LINING.
6. REMOVE EXISTING CONCRETE SPILLWAY.
7. REMOVE EXISTING CHAIN-LINK FENCE.

CLARK COUNTY WATER RECLAMATION DISTRICT NOTES

1. ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE DESIGN AND CONSTRUCTION STANDARDS FOR WASTE-WATER COLLECTION SYSTEMS AND THE PUBLIC WORKS CONSTRUCTION OFF SITE IMPROVEMENTS, CLARK COUNTY AREA, NEVADA, AS AMENDED, AND CLARK COUNTY SUPPLEMENT TO UNIFORM STANDARD DRAWINGS AND SPECIFICATIONS. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO BE AWARE OF THE CONTENTS OF THE ABOVE DRAWINGS AND SPECIFICATION BOOKS.
2. THESE STANDARDS SHALL APPLY TO ALL CONSTRUCTION.
3. SEWER MAINS ONLY TO BE LAID IN SEWER TRENCHES.
4. ALL LATERALS TO BE LAID AT NOT LESS THAN MINIMUM SLOPE AS SHOWN IN THESE STANDARDS.
5. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO PERFORM CONSTRUCTION AS PER PLANS. ANY ADDITIONS, DELETIONS, OR CHANGES SHALL FIRST MEET WITH THE APPROVAL OF THE CONTROLLING AGENCY.
6. SOIL TESTING SHALL BE IN ACCORDANCE WITH SECTION 3.11 OF THESE STANDARDS.
7. ALL EXFILTRATION, INFILTRATION, AIR TESTING AND TELEVISING OF LINES SHALL BE IN ACCORDANCE WITH THESE STANDARDS.
8. CUT SHEETS MUST BE SUBMITTED TO THE AGENCY BEFORE CONSTRUCTION WILL BE PERMITTED TO START.
9. ALL CONTRACTORS INSTALLING SEWER MAINS THAT WILL BE UNDER THE JURISDICTION OF THE CONTROLLING AGENCY MUST BE CLASS "A" CONTRACTORS.

CLARK COUNTY WATER RECLAMATION DISTRICT NOTES DATE

CCWRD PROJECT CONTROL NUMBER IS_____

SIGNATURE ON THESE PLANS WILL NOT BE CONSTRUED TO BE A PERMIT FOR OR AN APPROVAL OF ANY VIOLATION OF CLARK COUNTY WATER RECLAMATION DISTRICT RULES, REGULATIONS, OR DESIGN AND CONSTRUCTION STANDARDS. THE APPROVAL OF THESE DRAWINGS DOES NOT GUARANTEE CAPACITY IN THE DISTRICT'S COLLECTION OR TREATMENT SYSTEM.

LAS VEGAS VALLEY WATER DISTRICT STANDARD NOTES

LVVWD PROJECT # 25819

1. NO WORK SHALL BEGIN UNTIL THE WATER PLANS HAVE BEEN RELEASED FOR CONSTRUCTION BY THE LVVWD. FOLLOWING WATER PLAN APPROVAL, 48 HOUR NOTICE SHALL BE GIVEN TO LVVWD COMMUNICATION SUPPORT CENTER (258-7171) PRIOR TO THE START OF CONSTRUCTION. NOTICE MUST BE GIVEN BY 2:00 p.m. THE BUSINESS DAY PRIOR TO A LVVWD INSPECTION. WHEN REQUESTING INSPECTIONS, PLEASE REFER TO THE PROJECT # IDENTIFIED ABOVE.
2. ALL WORK SHALL CONFORM TO LVVWD'S STANDARD PLATES, DRAWINGS AND SPECIFICATIONS AND TO THE UNIFORM DESIGN AND CONSTRUCTION STANDARDS FOR WATER DISTRIBUTION SYSTEMS (UDACS), LATEST EDITION.
3. ALL WORK, EXCEPT AS MODIFIED BY THESE PLANS OR BY NOTE 2, SHALL BE DONE IN ACCORDANCE WITH THE MOST CURRENT DRAFT OR EDITION OF THE UNIFORM STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION OFFSITE IMPROVEMENT, CLARK COUNTY AREA.
4. A SINGLE PIPE MATERIAL SHALL BE USED THROUGHOUT THE PROJECT UNLESS OTHERWISE APPROVED BY THE LVVWD.
5. ALL SERVICE LATERALS TWO (2) INCHES IN DIAMETER AND SMALLER SHALL BE COPPER TUBING WITH LVVWD APPROVED SERVICE SADDLES.
6. ALL WATER METER BOXES SHALL BE LOCATED OUTSIDE OF DRIVEWAY AREAS.
7. ALL VALVES SHALL BE LOCATED OUTSIDE OF DRIVEWAY, VALLEY AND CURB GUTTERS.
8. THE FOLLOWING REQUIREMENTS MUST BE MET IN THE EVENT A WATER LINE AND SANITARY OR STORM SEWER LINE CROSS:

   A MINIMUM EIGHTEEN (18) INCH VERTICAL SEPARATION (OUTSIDE TO OUTSIDE) MUST BE MAINTAINED WHEN THE WATER LINE IS INSTALLED OVER THE SANITARY OR STORM SEWER LINE. IF THE VERTICAL SEPARATION CANNOT BE MAINTAINED OR THE WATER LINE MUST BE PLACED UNDER THE SANITARY OR STORM SEWER LINE, THE SANITARY OR STORM SEWER LINE MUST BE CONSTRUCTED WITH ONE OF THE FOLLOWING OR, AS SHOWN ON THESE PLANS:

   A. POTABLE WATER SUPPLY QUALITY MATERIAL,
   B. ENCASEMENT, WITH FOUR (4) INCH CONCRETE (MINIMUM),
   C. SLEEVING WITH POTABLE WATER SUPPLY QUALITY PIPE.

   EACH PROVISION MUST EXTEND ALONG THE SANITARY OR STORM SEWER, ON EITHER SIDE OF THE MAIN, A MINIMUM 10 FOOT DISTANCE PERPENDICULAR TO THE WATER MAIN EXTERIOR.
9. WARNING TAPE SHALL BE REQUIRED OVER ALL MAINS, ALL SIX (6) INCH DIAMETER AND LARGER SERVICE LATERALS, AND ANY SERVICE LATERAL NOT INSTALLED PERPENDICULAR TO THE MAIN IN ACCORDANCE WITH STANDARD PLATE NO. 27.
10. ALL WATER FACILITIES SHALL BE FILLED, DISINFECTED, PRESSURE TESTED, FLUSHED, FILLED AND AN ACCEPTABLE WATER SAMPLE OBTAINED, PRIOR TO CONNECTION TO THE LVVWD'S DISTRIBUTION SYSTEM.
11. THE CONTRACTOR MUST OBTAIN ALL METERS TWO (2) INCHES AND SMALLER FROM LVVWD CENTRAL STORES. TELEPHONE 258-3152 FORTY-EIGHT (48) HOURS PRIOR TO PICKUP.
12. CONSTRUCTION MAY INTERRUPT SERVICE, WITH LVVWD APPROVAL AND PROPER NOTIFICATION, BETWEEN THE HOURS OF 10 PM AND 6 AM, SUNDAY THROUGH THURSDAY. CIRCUMSTANCES MAY REQUIRE TEMPORARY SERVICE FEEDS BE INSTALLED, WITHOUT LVVWD REIMBURSEMENT. ANY TEMPORARY SERVICE FEED MUST HAVE PRIOR LVVWD APPROVAL.
13. ALL WATER FACILITY CONSTRUCTION MATERIALS USED MUST BE AS LISTED ON THE LVVWD'S PRE-APPROVED MATERIALS AND MANUFACTURER'S LISTING FOR NEW FACILITIES, LATEST REVISION, OR SPECIFICALLY APPROVED ON THESE PLANS.

APPROVED FOR CONSTRUCTION

_____

LAS VEGAS VALLEY WATER DISTRICT DATE

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES

1. CONTRACTOR SHALL FIELD LOCATE AND PROTECT ALL SNWA/SNWS APPURTENANCES INCLUDING, BUT NOT LIMITED TO AV/AR, ACCESS MANWAYS AND CATHODIC PROTECTION SYSTEMS. ALL ABOVE GROUND STRUCTURES AND AT GRADE STRUCTURES MUST BE ADJUSTED TO NEW GRADE AT CONTRACTOR'S EXPENSE. CATHODIC PROTECTION TEST STATIONS, RECTIFIERS, AND AV/AR'S MUST BE RELOCATED TO THE SIDEWALK PER SNWA STANDARDS AND AT THE CONTRACTOR'S EXPENSE. CONTRACTOR TO NOTIFY SOUTHERN NEVADA WATER AUTHORITY DEVELOPMENT PLAN REVIEW, AT (702) 862-3444 AT LEAST 48 HOURS PRIOR TO CONSTRUCTION ACTIVITY.
2. NO BUILDINGS, STRUCTURES, FENCES OR TREES SHALL BE PLACED UPON, OVER OR UNDER SAID PARCEL OF LAND FOR THE DURATION OF THIS EASEMENT EXCEPT THAT SAID PARCEL MAY BE IMPROVED AND USED FOR STREET, ROAD OR DRIVEWAY PURPOSES AND FOR OTHER UTILITIES, INSOFAR AS SUCH USE DOES NOT INTERFERE WITH ITS USE BY SNWA FOR THE PURPOSES FOR WHICH IT IS GRANTED.
3. SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.

AVOID HITTING OVERHEAD POWER LINES. IT'S EASY.
CALL BEFORE YOU DO OVERHEAD
1-702-593-6111

Avoid striking underground utility lines. It's easy.
Call before you Dig.
1-800-227-2600
(NEVADA ONLY)

BASIS OF BEARINGS

SOUTH 00°18'40" EAST - BEING THE WEST LINE OF SOUTHWEST QUARTER (SW 1/4) OF SECTION 3, TOWNSHIP 21 SOUTH, RANGE 62 EAST, M.D.M., AS SHOWN BY A MAP THEREOF ON FILE IN FILE 36, PAGE 6 OF SURVEYS IN THE CLARK COUNTY RECORDER'S OFFICE, CLARK COUNTY, NEVADA.

PROJECT BENCHMARK

CLARK COUNTY BM - 6C02 33SW16

RIVET AND SQUARE ALUMINUM PLATE IN TOP OF CURB, IN NORTHEAST CORNER OF NELLIS BLVD. AND BELPORT DR. NEAR THE PC OF NELLIS BLVD.

ELEVATION - 531.863 (M) NAVD 88
1744.954 (FT) NAVD 88

GENERAL NOTES

1. ALL CONSTRUCTION AND MATERIALS FOR THIS PROJECT SHALL BE IN ACCORDANCE WITH THE "UNIFORM STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION", CLARK COUNTY AREA, NEVADA LATEST EDITION, AND THE "UNIFORM DRAWINGS FOR PUBLIC WORKS CONSTRUCTION", CLARK COUNTY AREA, NEVADA LATEST EDITION, UNLESS OTHERWISE SPECIFIED BY NOTE ON THE PLANS AND/OR SPECIAL PROVISIONS. THE IMPROVEMENT STANDARDS WILL HEREAFTER BE REFERRED TO AS "CLARK COUNTY AREA STANDARD DRAWINGS.
2. 48 HOURS PRIOR TO START OF CONSTRUCTION, THE CONTRACTOR SHALL CONTACT

NEVADA POWER COMPANY	PHONE	1-800-227-2600
SPRINT-CENTRAL TELEPHONE COMPANY	PHONE	1-800-227-2600
SOUTHWEST GAS CORPORATION	PHONE	1-800-227-2600
COX COMMUNICATIONS LAS VEGAS, INC.	PHONE	384-8084
LAS VEGAS VALLEY WATER DIST.	PHONE	870-4194
CLARK COUNTY TRAFFIC MGMT. DIV.	PHONE	455-7511
CLARK COUNTY WATER RECLAMATION DISTRICT	PHONE	434-8000
SOUTHERN NEVADA WATER AUTHORITY	PHONE	862-3444

3. LOCATIONS OF UNDERGROUND UTILITIES SHOWN ON THE DRAWINGS WERE OBTAINED FROM INFORMATION RECEIVED FROM THE AFFECTABLE UTILITY COMPANIES NEITHER THE OWNER NOR ENGINEER ASSUMES ANY RESPONSIBILITY FOR UTILITIES OR STRUCTURES NOT SHOWN, OR FOR UTILITIES OR STRUCTURES NOT SHOWN AT ACTUAL LOCATIONS ON THE DRAWINGS. EXISTING SERVICE LATERALS ARE NOT SHOWN ON THESE DRAWINGS. CONTRACTOR TO VERIFY THE EXACT LOCATION OF UTILITIES PRIOR TO START OF CONSTRUCTION. THE CONTRACTOR'S RESPONSIBILITY REGARDING UTILITIES SHALL BE AS REQUIRED UNDER SECTION 107.17 OF THE UNIFORM STANDARD SPECIFICATIONS FOR CLARK COUNTY AREA, NEVADA AND AS PROVIDED IN THE SPECIFICATIONS.
4. THE CONTRACTOR SHALL NOT REMOVE TREES, SHRUBS, LAWNS, WALLS, FENCES, SIGNS, STRUCTURES, LIGHTS, OR ANY EXISTING IMPROVEMENTS OUTSIDE OF STREET RIGHT-OF-WAY, EXCEPT WHERE REQUIRED TO DO SO BY THE CONTRACT DRAWINGS OF BY THE ENGINEER.
5. REPLACEMENT, RELOCATION, OR RECONSTRUCTION OF ALL EXISTING IMPROVEMENTS INCLUDING SPRINKLER SYSTEMS, LAWNS, FENCES, WALLS, SIGNS, STEPS, SIDEWALK, DRIVEWAYS, LAWN LIGHTS, AND ALL OTHER ITEMS APPLICABLE TO THIS CONTRACT SHALL BE AS REQUIRED BY THE ENGINEER.
6. THE CONTRACTOR SHALL BACKFILL AND FINE GRADE ALL CUT OR FILL SLOPES TO MATCH EXISTING CONDITIONS TO THE SATISFACTION OF THE ENGINEER. WHERE EXISTING LAWNS ARE DAMAGED BY THE CONTRACTOR'S OPERATIONS THE CONTRACTOR SHALL SOD THE AFFECTED AREA TO A CONDITION EQUAL TO, OR BETTER TO THAT WHICH EXISTED PRIOR TO CONSTRUCTION.
7. ALL BARRICADING AND TEMPORARY TRAFFIC CONTROL DEVICES OR METHODS USED DURING CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE "NEVADA TRAFFIC CONTROL MANUAL", 1986 (OR LATEST REVISION), PUBLISHED BY THE STATE OF NEVADA DEPARTMENT OF TRANSPORTATION AND THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", EXCEPT AS OTHERWISE PROVIDED IN THE CONTRACT SPECIFICATIONS OR AS REQUIRED BY THE ENGINEER.
8. REMOVAL OR RELOCATIONS OF POWER POLES, TELEPHONE POLES, JOINTLY-OWNED POLES, AND APPURTENANCES WHICH INTERFERE WITH IMPROVEMENTS REQUIRED TO BE CONSTRUCTED UNDER THIS CONTRACT, SHALL BE THE RESPONSIBILITY OF THE RESPECTIVE UTILITY COMPANY. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATION WITH THE UTILITY COMPANIES FAR ENOUGH IN ADVANCE AS TO NOT IMPACT THE SCHEDULE.
9. UNLESS OTHERWISE SHOWN ON THE CONTRACT DRAWINGS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OF, RELOCATION OF ALL WATER SERVICES AND METERS WHICH INTERFERE WITH IMPROVEMENTS SHOWN ON THE CONTRACT DRAWINGS.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE VERTICAL ADJUSTMENT OF ALL EXISTING SANITARY, WATER AND STORM SEWER MANHOLES TO THE FINAL FINISH GRADES IN ACCORDANCE WITH SECTIONS 608 AND 630 OF THE "STANDARD SPECIFICATIONS".
11. SPRINT TELEPHONE COMPANY SHALL BE RESPONSIBLE FOR THE VERTICAL OR HORIZONTAL ADJUSTMENT OF ALL TELEPHONE FACILITIES WHICH INTERFERE WITH IMPROVEMENTS SHOWN ON THE CONTRACT DRAWINGS.
12. THE SOUTHWEST GAS CORPORATION SHALL BE RESPONSIBLE FOR THE REMOVAL OR RELOCATION OF ALL GAS LINES AND APPURTENANCES WHICH INTERFERE WITH IMPROVEMENTS SHOWN ON THE CONTRACT DRAWINGS.
13. ALL EXISTING TRAFFIC SIGNS, STREET LIGHTS & SIGNS TO BE REMOVED SHALL BE SALVAGED BY THE CONTRACTOR AND DELIVERED TO THE CLARK COUNTY TRAFFIC OPERATIONS DIVISION LOCATED AT 5821 E. FLAMINGO ROAD, LAS VEGAS, NEVADA WITHIN 48 HOURS OF THEIR REMOVAL.
14. EXACT LOCATIONS OF ALL SAWCUT LINES SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER. SAWCUTS, LONGITUDINAL TO THE ROADWAY, MAY BE WHEEL CUT WITH EQUIPMENT AS APPROVED BY THE ENGINEER. ALL OTHER SAWCUT SHALL BE MADE BY A ROTARY SAW.
15. ALL SANITARY SEWER CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CLARK COUNTY SANITATION DISTRICT DESIGN AND CONSTRUCTION STANDARDS.
16. THE PLANS DO NOT SHOW ALL SEWER LATERALS, SEWER FORCE MAINS AND WATER SERVICE LATERALS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY REPAIRS OR RELOCATIONS OF LATERALS BROKEN OR IN CONFLICT WITH THE PROPOSED CHANNEL, STORM DRAIN OR ROADWAY CONSTRUCTION.
17. CONTRACTOR SHALL MAINTAIN CONTINUOUS SEWER SERVICE TO ALL CCSD CUSTOMERS. SEWER LATERALS CUT DURING CONSTRUCTION SHALL BE REPAIRED BY CONTRACTOR PER CCSD DESIGN AND CONSTRUCTION STANDARDS. CONTRACTOR SHALL IMMEDIATELY REPORT ANY SANITARY SEWER OR SEWER LATERALS THAT CANNOT BE RECONNECTED TO SEWER MAIN DUE TO STORM DRAIN CONFLICT. CLARK COUNTY SHALL BE RESPONSIBLE FOR PROVIDING DESUBMITTED APPROVED MAIN LINE SEWER EXTENSION PLANS TO PROVIDE NEW MAIN TO REROUTE ANY SEWERS THAT CANNOT BE RECONNECTED.
18. THE NEVADA POWER COMPANY SHALL BE RESPONSIBLE FOR THE RELOCATION OF UNDERGROUND OR OVERHEAD POWER LINES THAT INTERFERE WITH THE REQUIRED IMPROVEMENTS AS SHOWN ON THE PLANS.
19. IF THE IMPROVEMENTS NECESSITATE THE OBLITERATION, TEMPORARY OBSTRUCTION, TEMPORARY REMOVAL, OR RELOCATION OF ANY EXISTING TRAFFIC PAVEMENT MARKING, SUCH PAVEMENT MARKING SHALL BE RESTORED OR REPLACED WITH LIKE MATERIALS TO THE SATISFACTION OF THE COUNTY TRAFFIC MANAGER.
20. LVACTS INTERCONNECT CABLE POLICY IS IN EFFECT. INTERCONNECT CABLE MUST BE MAINTAINED AT ALL TIMES. CONTRACTOR SHALL PROVIDE TEMPORARY OVERHEAD INTERCONNECT CABLE WHILE PAVEMENT CABLE IS BEING RELOCATED. TEMPORARY AERIAL INSTALLATION MUST BE ACCEPTABLE TO THE COUNTY TRAFFIC MANAGER AND TO LVACTS. ANY DAMAGE TO THIS CABLE IS DEEMED AN EMERGENCY BY LVACTS, CITY OF LAS VEGAS, CLARK COUNTY AND NDOT AND MUST BE REPAIRED IMMEDIATELY TO LVACTS' ACCEPTANCE. $2,500 PER DAY DAMAGES WILL BE ASSESSED AFTER TWENTY-FOUR (24) HOURS HAS ELAPSED FROM THE TIME OF BREAK OR DAMAGE.
21. THE CONTRACTOR SHALL DETERMINE THE LOCATION AND DEPTH OF SUSPECTED UTILITY INTERFERENCES, AND SHALL FURNISH INFORMATION ON THE SAME TO THE ENGINEER, NOT LESS THAN TEN (10) DAY PRIOR TO THE ANTICIPATED IMPACT OF THESE SUSPECTED INTERFERENCES ON HIS WORK. IF CONFLICTS EXIST, THE CONTRACTOR WILL IMMEDIATELY CONTACT THE ENGINEER AND PROVIDE THE ENGINEER WITH ALL THE NECESSARY DATA SUCH AS ELEVATIONS, HORIZONTAL LOCATIONS, ETC., AND PROVIDE THE ENGINEER WITH SKETCHES INDICATING THE PROPOSED IMPROVEMENT AND THE UTILITY CONFLICT. THE ENGINEER WILL EXAMINE AND REVIEW ALL THE DATA AND SKETCHES PROVIDED, AND WILL PROVIDE THE CONTRACTOR WITH AN ALTERNATIVE DESIGN WITHIN FIVE (5) DAYS AFTER RECEIPT OF DATA AND SKETCHES.
22. THE FOLLOWING DENSITIES WERE USED IN CALCULATING QUANTITIES FOR ASPHALT CONCRETE PAVEMENT.
    PLANTMIX BITUMINOUS SURFACING 155 LB/CF
    PLANTMIX BITUMINOUS OPEN-GRADED SURFACE 140 LB/CF

DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

GENERAL & CONSTRUCTION NOTES, LEGEND AND ABBREVIATIONS, BENCHMARK, BASIS OF BEARINGS

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER — STATE OF NEVADA — NOEL C. LAUGHLIN — No. 10165 — CIVIL — 3-11-04


PROJECT No: 500.857 DRAWN BY: ____
DESIGNED BY: ____ CHECKED BY: ____
APPROVED BY ____

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE (702) 804-2000 • FAX (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
G-3
SHT. 3 OF 30


F:\500-857\dwg\improv\sc_g04.dwg 03-11-04 12:04:56 RBlanchard



LINE TABLE		
No.	Bearing	Distance
L2	N 89°37'02" E	41.00'

CHANNEL & LINE TABLE		
No.	Bearing	Distance
L1	N 00°00'06" W	150.00'
L3	N 00°22'58" E	20.22'
L4	N 66°00'50" E	75.33'
L5	N 00°22'58" W	109.59'
L6	N 00°02'58" W	50.00'

CHANNEL ℄ CURVE TABLE				
No.	Radius	Delta	Length	Tangent
C1	807.70'	27°20'22"	385.40'	196.44'
C2	800.00'	31°55'40"	445.80'	228.85'
C3	462.47'	42°11'02"	340.49'	178.38'
C4	50.00'	66°23'48"	57.94'	32.72'



BASIS OF BEARINGS

SOUTH 00°18'40" EAST, BEING THE WEST LINE OF THE SOUTHWEST QUARTER (SW 1/4) OF SECTION 3, TOWNSHIP 21 SOUTH, RANGE 62 EAST, M.D.M., CLARK COUNTY, NEVADA, AS SHOWN BY FILE 36, PAGE 6 OF SURVEYS IN THE CLARK COUNTY RECORDER'S OFFICE CLARK COUNTY, NEVADA.

BENCHMARK

CLARK COUNTY BM – 6C02 335WW6

RIVET AND SQUARE ALUMINUM PLATE IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND BELPORT DR. NEAR THE PC OF NELLIS BLVD.

ELEVATION: 531.863 METERS (NAVD 88)
1744.854 FEET (NAVD 88)

LEGEND

- ◉ FOUND MONUMENTATION AS SHOWN AND DESCRIBED
- × CALCULATED POINT
- —— —— SECTION LINE
- —— — —— QUARTER LINE
- —— — — —— 1/16 LINE

REFERENCES

FILE 36, PAGE 6 OF SURVEYS
FILE 122, PAGE 76 OF SURVEYS

NO.	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
HORIZONTAL CONTROL PLAN

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL LAND SURVEYOR – STATE OF NEVADA
DANNY E. HILL EXP. 6/30/05 NO. 9389

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: 1" = 500'
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
G-4
SHT. 4 OF 30

BASE BID SCHEDULE
Estimate of Quantities

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTALS
100.01	CONSTRUCTION OFFICE	LS	1
105.01	ON-SITE MATERIAL TESTING FOR QUALITY CONTROL	LS	1
107.01	TRAFFIC CONTROL	LS	1
109.01	OWNER CAUSED DELAY ALLOWANCE	DAY	20
109.02	OWNER CAUSED DELAY ALLOWANCE ABOVE $500/DAY	DAY	20
109.03	CONSTRUCTION CONFLICTS AND ADDITIONAL WORK	LS	1
200.01	MOBILIZATION	LS	1
201.01	CLEARING AND GRUBBING	LS	1
202.01	REMOVE EXISTING SPLASH PADS (5 EACH)	LS	1
202.02	REMOVE EXISTING CHANNEL LINING FROM STA. 163+66 (RT) TO STA. 171+98 (RT)	LS	1
202.03	REMOVE EXISTING CHANNEL LINING FROM STA. 186+54 TO STA. 186+18	LS	1
202.04	REMOVE AND SALVAGE EXISTING RIPRAP ON WEST BANK FROM STA. 118+89 TO STA. 132+00	LS	1
202.05	REMOVE EXISTING BLOCK WALL AND FOOTING	LF	73
202.06	REMOVE EXISTING CHAIN-LINK FENCE	LF	515
203.01	CHANNEL EXCAVATION	CY	73,000
205.01	DEWATERING	LS	1
209.01	2-INCH DRAIN BACKFILL	CY	16,310
301.01	SELECTED MATERIAL BASE	CY	29,000
302.01	TYPE II AGGREGATE BASE	CY	4,100
302.02	TYPE II AGGREGATE BASE MAINTENANCE ROAD	CY	1,500
502.01	TRAPEZOIDAL TO TRAPEZOIDAL TRANSITION STA. 118+88.78 TO STA. 119+25	LS	1
502.02	TRAPEZOIDAL CHANNEL LINING STA. 119+38.78 TO STA. 122+58.37	LF	319.59
502.03	TRAPEZOIDAL CHANNEL TRANSITION STA. 122+58.37 TO STA. 123+00	LS	1
502.04	TRAPEZOIDAL CHANNEL LINING STA. 123+00 TO STA. 158+50	LF	3,550
502.05	TRAPEZOIDAL CHANNEL TRANSITION STA. 158+50 TO STA. 159+00	LS	1
502.06	TRAPEZOIDAL CHANNEL LINING STA. 159+00 TO STA. 160+29.41	LF	129.41
502.07	TRAPEZOIDAL TO RECTANGULAR TRANSITION STA. 160+29.41 TO STA. 160+79.41	LS	1
502.08	CONFLUENCE STRUCTURE STA. 160+79.41 TO STA. 162+79.41	LS	1
502.09	RECTANGULAR TO TRAPEZOIDAL TRANSITION STA. 162+79.41 TO STA. 163+29.41	LS	1
502.10	TRAPEZOIDAL CHANNEL LINING STA. 163+29.41 TO STA. 171+98.47; STA. 172+86.31 TO STA. 174+50; STA. 176+00 TO STA. 179+00	LF	1,332.75
502.11	CCRFCD CHANNEL GAUGE STATION	LS	1
502.12	TRAPEZOIDAL CHANNEL LINING WITH MAINTENANCE RAMP STA. 174+50 TO STA. 176+00	LS	1
502.13	MODIFIED TRAPEZOIDAL CHANNEL STA. 179+00 TO STA. 186+54.94	LF	755
502.14	TRAPEZOIDAL TO TRAPEZOIDAL TRANSITION STA. 186+54.94 TO STA. 187+18	LS	1
502.15	MAINTENANCE ROAD CROSSING STA. 130+71	LS	1
502.16	MAINTENANCE ROAD CROSSING STA. 165+68	LS	1
502.17	MAINTENANCE ROAD CROSSING STA. 184+79	LS	1
611.01	3-INCH CONCRETE SLOPE PAVEMENT	SY	34,113
616.01	6-FOOT CHAIN LINK FENCE	LF	160
616.02	POST AND CABLE RAILING	LF	2,000
627.01	PERMANENT SIGNS	EA	2
637.01	DUST PALLIATIVE	AC	13
637.02	DUST CONTROL	LS	1

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTALS

NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
ESTIMATE OF QUANTITIES

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


REGISTERED PROFESSIONAL ENGINEER STATE OF NEVADA NOEL C. LAUGHLIN No. 10165 CIVIL 3-11-04

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY:

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
G-5
SHT. 5 OF 30



SURVEYOR'S CERTIFICATE

I, DANNY E. HILL, A PROFESSIONAL LAND SURVEYOR LICENSED IN THE STATE OF NEVADA, CERTIFY THAT THIS MAP IS AN ACCURATE REPRESENTATION OF THE LANDS SURVEYED UNDER MY DIRECT SUPERVISION AT THE INSTANCE OF CLARK COUNTY PUBLIC WORKS. ALL SURVEY MONUMENTS FOUND OR SET ARE CORRECTLY SHOWN, OCCUPY THE POSITIONS INDICATED AND ARE SUFFICIENT TO ENABLE THE RETRACEMENT OF THE SURVEY WHICH WAS COMPLETED ON APRIL 16, 2002. THIS SURVEY PLAT DOES NOT CONSTITUTE A SUBDIVISION AS DEFINED BY NEVADA STATE LAW. THE LANDS LIE WITHIN SECTIONS 3 AND 10 TOWNSHIP 21 SOUTH, RANGE 62 EAST, M.D.M., CLARK COUNTY, NEVADA. THIS RECORD OF SURVEY IS FILED IN COMPLIANCE WITH PROVISIONS OF N.R.S. CHAPTER 278.325 AND WITH PROVISIONS OF N.R.S. CHAPTER 625.340.

DANNY E. HILL
PROFESSIONAL LAND SURVEYOR
NEVADA LICENSE NO. 9389



07 JUNE 2002
EXP. 06-30-03

BASIS OF BEARINGS

SOUTH 00°18'40" EAST, BEING THE WEST LINE OF THE SOUTHWEST QUARTER (SW 1/4) OF SECTION 3, TOWNSHIP 21 SOUTH, RANGE 62 EAST, M.D.M., CLARK COUNTY, NEVADA, AS SHOWN BY FILE 36, PAGE 6 OF SURVEYS IN THE CLARK COUNTY RECORDER'S OFFICE, CLARK COUNTY, NEVADA.

NOTE:

THIS FIELD SURVEY WAS PERFORMED TO ESTABLISH AND MEMORIALIZE THE LEGAL RIGHT-OF-WAY AND/OR BOUNDARY LIMITS FOR THE CONSTRUCTION OF THE PROJECT SO THAT ALL INTERSECTIONS AND OTHER CONTROL POINTS FOR THE PROJECT CAN BE MONUMENTED IN ACCORDANCE WITH APPLICABLE STATE STATUTES AND LOCAL ORDINANCES AT THE COMPLETION OF CONSTRUCTION.

RECORDER'S NOTE:

ANY SUBSEQUENT CHANGES TO THIS MAP SHOULD BE EXAMINED AND MAY BE DETERMINED BY REFERENCE TO THE COUNTY RECORDER'S CUMULATIVE MAP INDEX.
N.R.S. 278.5695

LEGEND


- ◎ FOUND MONUMENTATION AS SHOWN AND DESCRIBED
- x CALCULATED POINT
- —— —— SECTION LINE
- — — — QUARTER LINE
- ——— 1/16 LINE

LINE	BEARING	DISTANCE
L1	S89°37'24"W	200.01'
L2	S09°37'24"W	189.63'
L3	N89°43'35"E	136.48'
L4	N01°26'00"W	48.81'
L5	N01°26'00"W	51.30'
L6	S00°18'25"E	20.00'
L7	S89°43'35"W	250.11'
L8	S00°22'28"E	20.00'
L9	N31°11'20"W	409.00'
L10	S88°41'29"E	16.68'
L11	N00°22'58"W	107.78'
L12	S00°22'58"E	111.42'
L13	N00°22'58"W	2665.90'
L14	S00°26'46"E	1295.01'
L15	N88°41'29"W	18.11'
L16	N00°22'58"W	1369.09'
L17	N89°32'44"W	12.00'
L18	S00°22'58"E	1319.26'
L19	N00°22'58"W	1320.90'
L20	N89°36'56"E	112.00'
L21	N89°36'56"E	120.00'
L22	S00°02'58"E	1411.47'
L23	S00°02'58"E	1412.17'
L24	S84°21'34"E	180.49'
L25	S00°16'25"E	30.00'

REFERENCE MAPS

[1] FILE 36, PAGE 6 OF SURVEYS

CURVE	DELTA	RADIUS	LENGTH	TANGENT
C1	29°45'20"	738.00'	383.27'	196.06'
C2	29°45'20"	862.00'	447.66'	229.00'
C3	30°48'22"	862.00'	463.47'	237.48'
C4	30°48'22"	738.00'	396.80'	203.32'
C5	34°49'33"	527.97'	320.91'	163.59'
C6	51°31'45"	407.97'	366.91'	196.91'



500.857
SLOAN CHANNEL

SHEET 1 OF 1

RECORD OF SURVEY
FOR
CLARK COUNTY PUBLIC WORKS
SLOAN CHANNEL


THOSE PORTIONS OF LAND LYING WITHIN SECTIONS 3, AND 10, TOWNSHIP 21 SOUTH, RANGE 62 EAST, M.D.M., CLARK COUNTY, NEVADA.

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146

INSTRUMENT NO. 00924
OFFICIAL RECORDS
BOOK NO. 20020607
FILED AT THE REQUEST OF
G.C. WALLACE INC.
DATE 6-7-02 AT 10:39
FILE 122 PAGE 0076
OF SURVEYS
CLARK COUNTY, NEVADA RECORDS
JUDITH A. VANDEVER, RECORDER
FEE $ 0.00 DEPUTY SH


FILE 122 PAGE 0076


F:\500-857\dwg\improv\sc_c01.dwg 03-11-04 12:05:54 RBlanchard



CHANNEL ℄ CURVE TABLE

CURVE TABLE				
CURVE	DELTA	RADIUS	LENGTH	TANGENT
C1	27°20'55"	807.70'	385.53'	196.51'





CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)
(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)
(10) CONSTRUCT PIPE CONNECTION (SEE DETAIL 9/S2)

REMOVAL NOTES


[2] REMOVE AND SALVAGE RIPRAP
[6] REMOVE EXISTING CONCRETE SPILLWAY

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

Avoid working underground utility lines. It's costly. Call before you Dig. 1-800-227-2600 UNDERGROUND SERVICE (USA)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY. CALL BEFORE YOU DO OVERHEAD 1-702-593-6111



Key Map

SCALE: NOT TO SCALE

NO.	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

PLAN AND PROFILE

STA. 114+50.00 TO STA. 122+00.00

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER STATE OF NEVADA NOEL C. LAUGHLIN No. 10165 CIVIL

PROJECT No: 500.857 DRAWN BY: DVJ
DESIGNED BY: CHECKED BY:
APPROVED BY:

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2288

SCALE	
HORIZ:	1" = 40'
VERT:	1" = 4'
FIELD BOOK	

L-1759
DRAWING NO.
C-1
SHT. 7 OF 30


F:\500-857\dwg\improv\ac_c02.dwg 03-11-04 12:07:11 RStanchard

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES

SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.

SOUTHERN NEVADA WATER AUTHORITY DATE

NOTE: SEE SHEET C-3 FOR SNWA CONSTRUCTION NOTES.



CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)
(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)
(10) CONSTRUCT PIPE CONNECTION (SEE DETAIL 9/S2)
(11) CONSTRUCT RCB CONNECTION (SEE DETAIL 3/S7)

REMOVAL NOTES

[2] REMOVE AND SALVAGE RIPRAP
[6] REMOVE EXISTING CONCRETE SPILLWAY

CHANNEL ℄ CURVE TABLE


CURVE TABLE				
CURVE	DELTA	RADIUS	LENGTH	TANGENT
C1	27°20'55"	807.70'	385.53'	196.51'
C2	31°55'41"	800.00'	445.80'	228.85'


NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

Avoid cutting underground utility lines in your area
Call before you Dig.
1-800-227-2600
(NEVADA ONLY)

AVOID WIRING OVERHEAD POWER LINES. IT'S COSTLY
CALL BEFORE YOU DO OVERHEAD
1-702-593-6111





DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

PLAN AND PROFILE

STA. 122+00.00 TO STA. 132+00.00

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER STATE OF NEVADA NOEL C. LAUGHLIN No. 10185 CIVIL 3-11-04


PROJECT No: 500.857 DRAWN BY: DWJ
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK

L-1759
DRAWING NO.
C-2
SHT. 8 OF 30

F:\500-857\dwg\Improv\sc_c03.dwg 03-11-04 12:08:40 RBlanchard



SLOAN CHANNEL



CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(12) CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

[2] REMOVE AND SALVAGE RIPRAP

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES


SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.

SOUTHERN NEVADA WATER AUTHORITY DATE

NOTE: SEE SHEET C-3 FOR SNWA CONSTRUCTION NOTES.

Avoid digging underground utility lines. It's costly.
Call before you Dig.
1-800-227-2600

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY
CALL BEFORE YOU DIG OVERHEAD
1-702-593-6111



Key Map
SCALE: NOT TO SCALE

NO.	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
PLAN AND PROFILE
STA. 132+00.00 TO STA. 142+00.00
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


NICOL LAUGHLIN No. 10165 STATE OF NEVADA PROFESSIONAL ENGINEER CIVIL 10/31/2005

PROJECT No: 500.857 DRAWN BY: DVJ
DESIGNED BY: _____ CHECKED BY: _____
APPROVED BY _____

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2298

SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK

L-1759
DRAWING NO.
C-3
SHT. 9 OF 30



NORTH
SCALE 1" = 40'

40 0 40 80
SCALE FEET

CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

REMOVAL NOTES

[3] REMOVE EXISTING CONCRETE SPLASH PAD

NOTE:


SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES

SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.


SOUTHERN NEVADA WATER AUTHORITY DATE

NOTE: SEE SHEET C-3 FOR SNWA CONSTRUCTION NOTES.



Avoid striking underground utility lines. It's easy. Call before you Dig. 1-800-227-2600 (Underground Service Alert)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY. CALL BEFORE YOU DO OVERHEAD 1-702-593-6111



Key Map
SCALE: NOT TO SCALE

NO.	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
PLAN AND PROFILE
STA. 142+00.00 TO STA. 152+00.00
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


ROBERT LAUGHLIN No. 10185 PROFESSIONAL ENGINEER STATE OF NEVADA 3-11-04

PROJECT No: 500/857 DRAWN BY: DVJ
DESIGNED BY: _____ CHECKED BY: _____
APPROVED BY: _____

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2286

SCALE	
HORIZ:	1" = 40'
VERT:	1" = 4'
FIELD BOOK	

L-1759
DRAWING NO. C-4
SHT. 10 OF 30



NORTH

SCALE 1" = 40'

40 0 40 80

SCALE FEET

CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(12) CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

[1] REMOVE EXISTING BLOCK WALL AND FOOTING

[3] REMOVE EXISTING CONCRETE SPLASH PAD

[5] REMOVE EXISTING CHANNEL LINING.

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES

SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.


SOUTHERN NEVADA WATER AUTHORITY DATE


NOTE: SEE SHEET G-3 FOR SNWA CONSTRUCTION NOTES.

Avoid cutting underground utility lines. It's costly. Call before you Dig. 1-800-227-2600 (Underground Service Alert)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY. CALL BEFORE YOU DO OVERHEAD. 1-702-593-6111

SLOAN CHANNEL





Key Map

SCALE: NOT TO SCALE

NO.	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

PLAN AND PROFILE

STA. 152+00.00 TO STA. 162+50.00

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER STATE OF NEVADA NOEL C. LAUGHLIN No. 10165 CIVIL 3-4-04

PROJECT No: 500-857 DRAWN BY: DW

DESIGNED BY: CHECKED BY:

APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE	
HORIZ:	1" = 40'
VERT:	1" = 4'
FIELD BOOK	


L-1759

DRAWING NO. C-5

SHT. 11 OF 30

F:\500-857\dwg\improv\sc_c06.dwg 03-11-04 13:11:04 RBlanchard





NORTH SCALE 1" = 40'

SCALE 40 0 40 80 FEET

CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(11) CONSTRUCT RCB CONNECTION (SEE DETAIL 3/S7)

(12) CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

[3] REMOVE EXISTING CONCRETE SPLASH PAD

[5] REMOVE EXISTING CHANNEL LINING.

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES


SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.

SOUTHERN NEVADA WATER AUTHORITY DATE

NOTE: SEE SHEET G-3 FOR SNWA CONSTRUCTION NOTES.

Avoid working underground utility lines. It's costly. Call before you Dig. 1-800-227-2600 UNDERGROUND SERVICE (UNA)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY! CALL BEFORE YOU DO OVERHEAD 1-702-593-6111



Key Map
SCALE: NOT TO SCALE

DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
PLAN AND PROFILE
STA. 162+50.00 TO STA. 171+00.00
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER STATE OF NEVADA JOHN E. LAUGHLIN No. 10165 CIVIL 3-11-04

PROJECT No: 500-857 DRAWN BY: DVJ
DESIGNED BY: _____ CHECKED BY: _____
APPROVED BY _____

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89145
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2288

SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK

L-1759
DRAWING NO.
C-6
SHT. 12 OF 30

F:\500-857\dwg\improv\sc_c07.dwg 03-11-04 13:11:54 RBlanchard

MATCH LINE – STA. 171+00.00 SEE SHEET C-8

MATCH LINE – STA. 181+00.00 SEE SHEET C-8

NORTH

SCALE 1" = 40'

40 0 40 80

SCALE FEET

CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(4) CONSTRUCT 12' DRIVEWAY PER STD. DWG. NO. 224

(8) PAINTED STAFF GAUGE (SEE DETAIL 5/C11)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(12) CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

[5] REMOVE EXISTING CHANNEL LINING.

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

CONTRACTOR TO EXCERCISE EXTREME CARE WHEN EXCAVATING WITHIN 10 FEET (HORIZONTAL) OF SNWA WATERLINE. SNWA TO BE PRESENT DURING EXCAVATION WITHIN AFOREMENTIONED LIMITS.

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES

SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.


SOUTHERN NEVADA WATER AUTHORITY DATE

LAS VEGAS VALLEY WATER DISTRICT DATE

NOTE: SEE SHEET C-3 FOR SNWA CONSTRUCTION NOTES.

Avoid hitting underground utility lines. It's costly. Call before you Dig. 1-800-227-2600 UNDERGROUND SERVICE (UNR)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY. CALL BEFORE YOU DO OVERHEAD 1-702-593-6111



Key Map

SCALE: NOT TO SCALE

SLOAN CHANNEL

171+98.47, CHANNEL ON RIGHT SIDE EXISTING FROM TOE OF SLOPE TO TOP OF SLOPE

SLOPE PAVING LEFT SIDE

TOP OF CHANNEL BOTH SIDES

SAHARA AVENUE

SLOPE PAVING RIGHT SIDE

HGL

6.5' BOTH SIDES

ACCESS RAMP LEFT SIDE

EXIST CULVERT

97.89 FL

-0.53%

97.37 FL

-(0.32%)

97.09 FL

Q_{ult} 100=4416 cfs

-0.46%

PROPOSED FLOWLINE CHANNEL

EX. 78" SNWA WATERLINE

EXIST. GRADE ℄ CHANNEL

17.5 BOTH SIDES

-0.46%

93.33 FL

STA. 171+17± 66.1'± LT 1694.3± INV

STA. 171+89± 65.8'± LT 1680.8± INV

EXIST. CONC. ENCASED SEWER SIPHON INV.= 89.4'±

12" 10" 8" 6"

EX. 78" SNWA WATERLINE

STA. 171+98.47 MATCH EXISTING GRADE BREAK (1697.37) FL SEE SHEET S-2

EX. 18" DIP W/ 30" STL CASING. 1691.5± TOP CASING

STA. 172+96.31 MATCH EXISTING GRADE BREAK (1697.09) FL SEE SHEET S-2

STA. 173+19± 65.0'± LT 1680.5± INV

STA. 173+72± 64.7'± LT 1693.5± INV

STA. 173+76± "SNWA" STA. 85+40± 69.3'± LT EX. BLOW OFF ASSEMBLY

STA. 173+86± "SNWA" STA. 85+40± 69.1'± LT EX. BLOW OFF ASSEMBLY

STA. 173+10± "SNWA" STA. 86+11± 68.7'± LT EX. MANWAY W/ ACCESS AND BLOWOFF

STA. 177+65± "SNWA" STA. 81+50± 62.9'± LT EX. MANWAY W/ ACCESS

STA = 178+50.00 BEGIN HEIGHT TRANSITION (LEFT SIDE) 1694.48 FL

STA = 179+00.00 BEGIN HEIGHT TRANSITION (LEFT SIDE) 1694.25 FL

1712 1704 1696 1688 1680

171+00 172+00 173+00 174+00 175+00 176+00 177+00 178+00 179+00 180+00 181+00

NO.	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

PLAN AND PROFILE

STA. 171+00.00 TO STA. 181+00.00

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER STATE OF NEVADA No. 10163 DALE LAUGHON CIVIL

PROJECT No: 500.857 DRAWN BY: DVJ

DESIGNED BY: _____ CHECKED BY: _____

APPROVED BY _____

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89145
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE	
HORIZ:	1" = 40'
VERT:	1" = 4'
FIELD BOOK	


L-1759

DRAWING NO. C-7

SHT. 13 OF 30

F:\500-857\dwg\improv\sc_c08.dwg 03-11-04 13:15:56 RBlanchard





CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)
(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)
(10) CONSTRUCT PIPE CONNECTION (SEE DETAIL 9/S2)
(11) CONSTRUCT RCB CONNECTION (SEE DETAIL J/S7)
(12) CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

[3] REMOVE EXISTING CONCRETE SPLASH PAD
[4] REMOVE EXISTING 60 FT.± CHANNEL SECTION TO EXPANSION JOINT.

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

CONTRACTOR TO EXERCISE EXTREME CARE WHEN EXCAVATING WITHIN 10 FEET (HORIZONTAL) OF SNWA WATERLINE. SNWA TO BE PRESENT DURING EXCAVATION WITHIN AFOREMENTIONED LIMITS.

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES

SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.

SOUTHERN NEVADA WATER AUTHORITY DATE


NOTE: SEE SHEET C-3 FOR SNWA CONSTRUCTION NOTES.


CHANNEL ℄ CURVE TABLE

CURVE TABLE				
CURVE	DELTA	RADIUS	LENGTH	TANGENT
C3	51°57'23"	462.47'	419.37'	225.34'

Call before you Dig. 1-800-227-2600
1-702-593-6111

SLOAN CHANNEL





NO.	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

PLAN AND PROFILE

STA. 181+00.00 TO STA. 190+00.00

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA NOEL C. LAUGHLIN No. 10165 Exp. 12/31/2005 CIVIL


PROJECT No: 500.857 DRAWN BY: DW
DESIGNED BY: CHECKED BY:
APPROVED BY:

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE	
HORIZ:	1" = 40'
VERT:	1" = 4'
FIELD BOOK	


L-1759
DRAWING NO. C-8
SHT. 14 OF 30


ORCHARDS FL CHANNEL
FOR TRANSITION DETAIL SEE SECTIONS A & B, SHEET S-6
FOR CHANNEL DETAIL SEE SECTION C, SHEET S-6
12' ACCESS MAINTENANCE ROAD
TOP OF CHANNEL BANK
TOE
FL
L1
L2
L3
L4
L5
L6
L7
L8
L9
L10
L11
L12
L13
L14
L15
L16
L17
L18
L19
L20
L21
L22
L23
L24
L25
L26
L27
L28
L29
L30
L31
L32
L33
L34
L35
L36
L37
L38
L39
L40
L41
L42
L43
L44
L45
L46
L47
L48
L49
L50
L51
L52
L53
L54
L55
L56
L57
L58
L59
L60
L61
L62
L63
L64
L65
L66
L67
L68
L69
L70
L71
L72
L73
L74
L75
L76
L77
L78
L79
L80
L81
L82
L83
L84
L85
L86
L87
L88
L89
L90
L91
L92
L93
L94
L95
L96
L97
L98
L99
L100
L101
L102
L103
L104
L105
L106
L107
L108
L109
L110
L111
L112
L113
L114
L115
L116
L117
L118
L119
L120
L121
L122
L123
L124
L125
L126
L127
L128
L129
L130
L131
L132
L133
L134
L135
L136
L137
L138
L139
L140
L141
L142
L143
L144
L145
L146
L147
L148
L149
L150
L151
L152
L153
L154
L155
L156
L157
L158
L159
L160
L161
L162
L163
L164
L165
L166
L167
L168
L169
L170
L171
L172
L173
L174
L175
L176
L177
L178
L179
L180
L181
L182
L183
L184
L185
L186
L187
L188
L189
L190
L191
L192
L193
L194
L195
L196
L197
L198
L199
L200
L201
L202
L203
L204
L205
L206
L207
L208
L209
L210
L211
L212
L213
L214
L215
L216
L217
L218
L219
L220
L221
L222
L223
L224
L225
L226
L227
L228
L229
L230
L231
L232
L233
L234
L235
L236
L237
L238
L239
L240
L241
L242
L243
L244
L245
L246
L247
L248
L249
L250
L251
L252
L253
L254
L255
L256
L257
L258
L259
L260
L261
L262
L263
L264
L265
L266
L267
L268
L269
L270
L271
L272
L273
L274
L275
L276
L277
L278
L279
L280
L281
L282
L283
L284
L285
L286
L287
L288
L289
L290
L291
L292
L293
L294
L295
L296
L297
L298
L299
L300
L301
L302
L303
L304
L305
L306
L307
L308
L309
L310
L311
L312
L313
L314
L315
L316
L317
L318
L319
L320
L321
L322
L323
L324
L325
L326
L327
L328
L329
L330
L331
L332
L333
L334
L335
L336
L337
L338
L339
L340
L341
L342
L343
L344
L345
L346
L347
L348
L349
L350
L351
L352
L353
L354
L355
L356
L357
L358
L359
L360
L361
L362
L363
L364
L365
L366
L367
L368
L369
L370
L371
L372
L373
L374
L375
L376
L377
L378
L379
L380
L381
L382
L383
L384
L385
L386
L387
L388
L389
L390
L391
L392
L393
L394
L395
L396
L397
L398
L399
L400
L401
L402
L403
L404
L405
L406
L407
L408
L409
L410
L411
L412
L413
L414
L415
L416
L417
L418
L419
L420
L421
L422
L423
L424
L425
L426
L427
L428
L429
L430
L431
L432
L433
L434
L435
L436
L437
L438
L439
L440
L441
L442
L443
L444
L445
L446
L447
L448
L449
L450
L451
L452
L453
L454
L455
L456
L457
L458
L459
L460
L461
L462
L463
L464
L465
L466
L467
L468
L469
L470
L471
L472
L473
L474
L475
L476
L477
L478
L479
L480
L481
L482
L483
L484
L485
L486
L487
L488
L489
L490
L491
L492
L493
L494
L495
L496
L497
L498
L499
L500
L501
L502
L503
L504
L505
L506
L507
L508
L509
L510
L511
L512
L513
L514
L515
L516
L517
L518
L519
L520
L521
L522
L523
L524
L525
L526
L527
L528
L529
L530
L531
L532
L533
L534
L535
L536
L537
L538
L539
L540
L541
L542
L543
L544
L545
L546
L547
L548
L549
L550
L551
L552
L553
L554
L555
L556
L557
L558
L559
L560
L561
L562
L563
L564
L565
L566
L567
L568
L569
L570
L571
L572
L573
L574
L575
L576
L577
L578
L579
L580
L581
L582
L583
L584
L585
L586
L587
L588
L589
L590
L591
L592
L593
L594
L595
L596
L597
L598
L599
L600
L601
L602
L603
L604
L605
L606
L607
L608
L609
L610
L611
L612
L613
L614
L615
L616
L617
L618
L619
L620
L621
L622
L623
L624
L625
L626
L627
L628
L629
L630
L631
L632
L633
L634
L635
L636
L637
L638
L639
L640
L641
L642
L643
L644
L645
L646
L647
L648
L649
L650
L651
L652
L653
L654
L655
L656
L657
L658
L659
L660
L661
L662
L663
L664
L665
L666
L667
L668
L669
L670
L671
L672
L673
L674
L675
L676
L677
L678
L679
L680
L681
L682
L683
L684
L685
L686
L687
L688
L689
L690
L691
L692
L693
L694
L695
L696
L697
L698
L699
L700
L701
L702
L703
L704
L705
L706
L707
L708
L709
L710
L711
L712
L713
L714
L715
L716
L717
L718
L719
L720
L721
L722
L723
L724
L725
L726
L727
L728
L729
L730
L731
L732
L733
L734
L735
L736
L737
L738
L739
L740
L741
L742
L743
L744
L745
L746
L747
L748
L749
L750
L751
L752
L753
L754
L755
L756
L757
L758
L759
L760
L761
L762
L763
L764
L765
L766
L767
L768
L769
L770
L771
L772
L773
L774
L775
L776
L777
L778
L779
L780
L781
L782
L783
L784
L785
L786
L787
L788
L789
L790
L791
L792
L793
L794
L795
L796
L797
L798
L799
L800
L801
L802
L803
L804
L805
L806
L807
L808
L809
L810
L811
L812
L813
L814
L815
L816
L817
L818
L819
L820
L821
L822
L823
L824
L825
L826
L827
L828
L829
L830
L831
L832
L833
L834
L835
L836
L837
L838
L839
L840
L841
L842
L843
L844
L845
L846
L847
L848
L849
L850
L851
L852
L853
L854
L855
L856
L857
L858
L859
L860
L861
L862
L863
L864
L865
L866
L867
L868
L869
L870
L871
L872
L873
L874
L875
L876
L877
L878
L879
L880
L881
L882
L883
L884
L885
L886
L887
L888
L889
L890
L891
L892
L893
L894
L895
L896
L897
L898
L899
L900
L901
L902
L903
L904
L905
L906
L907
L908
L909
L910
L911
L912
L913
L914
L915
L916
L917
L918
L919
L920
L921
L922
L923
L924
L925
L926
L927
L928
L929
L930
L931
L932
L933
L934
L935
L936
L937
L938
L939
L940
L941
L942
L943
L944
L945
L946
L947
L948
L949
L950
L951
L952
L953
L954
L955
L956
L957
L958
L959
L960
L961
L962
L963
L964
L965
L966
L967
L968
L969
L970
L971
L972
L973
L974
L975
L976
L977
L978
L979
L980
L981
L982
L983
L984
L985
L986
L987
L988
L989
L990
L991
L992
L993
L994
L995
L996
L997
L998
L999
L1000
L1001
L1002
L1003
L1004
L1005
L1006
L1007
L1008
L1009
L1010
L1011
L1012
L1013
L1014
L1015
L1016
L1017
L1018
L1019
L1020
L1021
L1022
L1023
L1024
L1025
L1026
L1027
L1028
L1029
L1030
L1031
L1032
L1033
L1034
L1035
L1036
L1037
L1038
L1039
L1040
L1041
L1042
L1043
L1044
L1045
L1046
L1047
L1048
L1049
L1050
L1051
L1052
L1053
L1054
L1055
L1056
L1057
L1058
L1059
L1060
L1061
L1062
L1063
L1064
L1065
L1066
L1067
L1068
L1069
L1070
L1071
L1072
L1073
L1074
L1075
L1076
L1077
L1078
L1079
L1080
L1081
L1082
L1083
L1084
L1085
L1086
L1087
L1088
L1089
L1090
L1091
L1092
L1093
L1094
L1095
L1096
L1097
L1098
L1099
L1100
L1101
L1102
L1103
L1104
L1105
L1106
L1107
L1108
L1109
L1110
L1111
L1112
L1113
L1114
L1115
L1116
L1117
L1118
L1119
L1120
L1121
L1122
L1123
L1124
L1125
L1126
L1127
L1128
L1129
L1130
L1131
L1132
L1133
L1134
L1135
L1136
L1137
L1138
L1139
L1140
L1141
L1142
L1143
L1144
L1145
L1146
L1147
L1148
L1149
L1150
L1151
L1152
L1153
L1154
L1155
L1156
L1157
L1158
L1159
L1160
L1161
L1162
L1163
L1164
L1165
L1166
L1167
L1168
L1169
L1170
L1171
L1172
L1173
L1174
L1175
L1176
L1177
L1178
L1179
L1180
L1181
L1182
L1183
L1184
L1185
L1186
L1187
L1188
L1189
L1190
L1191
L1192
L1193
L1194
L1195
L1196
L1197
L1198
L1199
L1200
L1201
L1202
L1203
L1204
L1205
L1206
L1207
L1208
L1209
L1210
L1211
L1212
L1213
L1214
L1215
L1216
L1217
L1218
L1219
L1220
L1221
L1222
L1223
L1224
L1225
L1226
L1227
L1228
L1229
L1230
L1231
L1232
L1233
L1234
L1235
L1236
L1237
L1238
L1239
L1240
L1241
L1242
L1243
L1244
L1245
L1246
L1247
L1248
L1249
L1250
L1251
L1252
L1253
L1254
L1255
L1256
L1257
L1258
L1259
L1260
L1261
L1262
L1263
L1264
L1265
L1266
L1267
L1268
L1269
L1270
L1271
L1272
L1273
L1274
L1275
L1276
L1277
L1278
L1279
L1280
L1281
L1282
L1283
L1284
L1285
L1286
L1287
L1288
L1289
L1290
L1291
L1292
L1293
L1294
L1295
L1296
L1297
L1298
L1299
L1300
L1301
L1302
L1303
L1304
L1305
L1306
L1307
L1308
L1309
L1310
L1311
L1312
L1313
L1314
L1315
L1316
L1317
L1318
L1319
L1320
L1321
L1322
L1323
L1324
L1325
L1326
L1327
L1328
L1329
L1330
L1331
L1332
L1333
L1334
L1335
L1336
L1337
L1338
L1339
L1340
L1341
L1342
L1343
L1344
L1345
L1346
L1347
L1348
L1349
L1350
L1351
L1352
L1353
L1354
L1355
L1356
L1357
L1358
L1359
L1360
L1361
L1362
L1363
L1364
L1365
L1366
L1367
L1368
L1369
L1370
L1371
L1372
L1373
L1374
L1375
L1376
L1377
L1378
L1379
L1380
L1381
L1382
L1383
L1384
L1385
L1386
L1387
L1388
L1389
L1390
L1391
L1392
L1393
L1394
L1395
L1396
L1397
L1398
L1399
L1400
L1401
L1402
L1403
L1404
L1405
L1406
L1407
L1408
L1409
L1410
L1411
L1412
L1413
L1414
L1415
L1416
L1417
L1418
L1419
L1420
L1421
L1422
L1423
L1424
L1425
L1426
L1427
L1428
L1429
L1430
L1431
L1432
L1433
L1434
L1435
L1436
L1437
L1438
L1439
L1440
L1441
L1442
L1443
L1444
L1445
L1446
L1447
L1448
L1449
L1450
L1451
L1452
L1453
L1454
L1455
L1456
L1457
L1458
L1459
L1460
L1461
L1462
L1463
L1464
L1465
L1466
L1467
L1468
L1469
L1470
L1471
L1472
L1473
L1474
L1475
L1476
L1477
L1478
L1479
L1480
L1481
L1482
L1483
L1484
L1485
L1486
L1487
L1488
L1489
L1490
L1491
L1492
L1493
L1494
L1495
L1496
L1497
L1498
L1499
L1500
L1501
L1502
L1503
L1504
L1505
L1506
L1507
L1508
L1509
L1510
L1511
L1512
L1513
L1514
L1515
L1516
L1517
L1518
L1519
L1520
L1521
L1522
L1523
L1524
L1525
L1526
L1527
L1528
L1529
L1530
L1531
L1532
L1533
L1534
L1535
L1536
L1537
L1538
L1539
L1540
L1541
L1542
L1543
L1544
L1545
L1546
L1547
L1548
L1549
L1550
L1551
L1552
L1553
L1554
L1555
L1556
L1557
L1558
L1559
L1560
L1561
L1562
L1563
L1564
L1565
L1566
L1567
L1568
L1569
L1570
L1571
L1572
L1573
L1574
L1575
L1576
L1577
L1578
L1579
L1580
L1581
L1582
L1583
L1584
L1585
L1586
L1587
L1588
L1589
L1590
L1591
L1592
L1593
L1594
L1595
L1596
L1597
L1598
L1599
L1600
L1601
L1602
L1603
L1604
L1605
L1606
L1607
L1608
L1609
L1610
L1611
L1612
L1613
L1614
L1615
L1616
L1617
L1618
L1619
L1620
L1621
L1622
L1623
L1624
L1625
L1626
L1627
L1628
L1629
L1630
L1631
L1632
L1633
L1634
L1635
L1636
L1637
L1638
L1639
L1640
L1641
L1642
L1643
L1644
L1645
L1646
L1647
L1648
L1649
L1650
L1651
L1652
L1653
L1654
L1655
L1656
L1657
L1658
L1659
L1660
L1661
L1662
L1663
L1664
L1665
L1666
L1667
L1668
L1669
L1670
L1671
L1672
L1673
L1674
L1675
L1676
L1677
L1678
L1679
L1680
L1681
L1682
L1683
L1684
L1685
L1686
L1687
L1688
L1689
L1690
L1691
L1692
L1693
L1694
L1695
L1696
L1697
L1698
L1699
L1700
L1701
L1702
L1703
L1704
L1705
L1706
L1707
L1708
L1709
L1710
L1711
L1712
L1713
L1714
L1715
L1716
L1717
L1718
L1719
L1720
L1721
L1722
L1723
L1724
L1725
L1726
L1727
L1728
L1729
L1730
L1731
L1732
L1733
L1734
L1735
L1736
L1737
L1738
L1739
L1740
L1741
L1742
L1743
L1744
L1745
L1746
L1747
L1748
L1749
L1750
L1751
L1752
L1753
L1754
L1755
L1756
L1757
L1758
L1759
L1760
L1761
L1762
L1763
L1764
L1765
L1766
L1767
L1768
L1769
L1770
L1771
L1772
L1773
L1774
L1775
L1776
L1777
L1778
L1779
L1780
L1781
L1782
L1783
L1784
L1785
L1786
L1787
L1788
L1789
L1790
L1791
L1792
L1793
L1794
L1795
L1796
L1797
L1798
L1799
L1800
L1801
L1802
L1803
L1804
L1805
L1806
L1807
L1808
L1809
L1810
L1811
L1812
L1813
L1814
L1815
L1816
L1817
L1818
L1819
L1820
L1821
L1822
L1823
L1824
L1825
L1826
L1827
L1828
L1829
L1830
L1831
L1832
L1833
L1834
L1835
L1836
L1837
L1838
L1839
L1840
L1841
L1842
L1843
L1844
L1845
L1846
L1847
L1848
L1849
L1850
L1851
L1852
L1853
L1854
L1855
L1856
L1857
L1858
L1859
L1860
L1861
L1862
L1863
L1864
L1865
L1866
L1867
L1868
L1869
L1870
L1871
L1872
L1873
L1874
L1875
L1876
L1877
L1878
L1879
L1880
L1881
L1882
L1883
L1884
L1885
L1886
L1887
L1888
L1889
L1890
L1891
L1892
L1893
L1894
L1895
L1896
L1897
L1898
L1899
L1900
L1901
L1902
L1903
L1904
L1905
L1906
L1907
L1908
L1909
L1910
L1911
L1912
L1913
L1914
L1915
L1916
L1917
L1918
L1919
L1920
L1921
L1922
L1923
L1924
L1925
L1926
L1927
L1928
L1929
L1930
L1931
L1932
L1933
L1934
L1935
L1936
L1937
L1938
L1939
L1940
L1941
L1942
L1943
L1944
L1945
L1946
L1947
L1948
L1949
L1950
L1951
L1952
L1953
L1954
L1955
L1956
L1957
L1958
L1959
L1960
L1961
L1962
L1963
L1964
L1965
L1966
L1967
L1968
L1969
L1970
L1971
L1972
L1973
L1974
L1975
L1976
L1977
L1978
L1979
L1980
L1981
L1982
L1983
L1984
L1985
L1986
L1987
L1988
L1989
L1990
L1991
L1992
L1993
L1994
L1995
L1996
L1997
L1998
L1999
L2000
L2001
L2002
L2003
L2004
L2005
L2006
L2007
L2008
L2009
L2010
L2011
L2012
L2013
L2014
L2015
L2016
L2017
L2018
L2019
L2020
L2021
L2022
L2023
L2024
L2025
L2026
L2027
L2028
L2029
L2030
L2031
L2032
L2033
L2034
L2035
L2036
L2037
L2038
L2039
L2040
L2041
L2042
L2043
L2044
L2045
L2046
L2047
L2048
L2049
L2050
L2051
L2052
L2053
L2054
L2055
L2056
L2057
L2058
L2059
L2060
L2061
L2062
L2063
L2064
L2065
L2066
L2067
L2068
L2069
L2070
L2071
L2072
L2073
L2074
L2075
L2076
L2077
L2078
L2079
L2080
L2081
L2082
L2083
L2084
L2085
L2086
L2087
L2088
L2089
L2090
L2091
L2092
L2093
L2094
L2095
L2096
L2097
L2098
L2099
L2100
L2101
L2102
L2103
L2104
L2105
L2106
L2107
L2108
L2109
L2110
L2111
L2112
L2113
L2114
L2115
L2116
L2117
L2118
L2119
L2120
L2121
L2122
L2123
L2124
L2125
L2126
L2127
L2128
L2129
L2130
L2131
L2132
L2133
L2134
L2135
L2136
L2137
L2138
L2139
L2140
L2141
L2142
L2143
L2144
L2145
L2146
L2147
L2148
L2149
L2150
L2151
L2152
L2153
L2154
L2155
L2156
L2157
L2158
L2159
L2160
L2161
L2162
L2163
L2164
L2165
L2166
L2167
L2168
L2169
L2170
L2171
L2172
L2173
L2174
L2175
L2176
L2177
L2178
L2179
L2180
L2181
L2182
L2183
L2184
L2185
L2186
L2187
L2188
L2189
L2190
L2191
L2192
L2193
L2194
L2195
L2196
L2197
L2198
L2199
L2200
L2201
L2202
L2203
L2204
L2205
L2206
L2207
L2208
L2209
L2210
L2211
L2212
L2213
L2214
L2215
L2216
L2217
L2218
L2219
L2220
L2221
L2222
L2223
L2224
L2225
L2226
L2227
L2228
L2229
L2230
L2231
L2232
L2233
L2234
L2235
L2236
L2237
L2238
L2239
L2240
L2241
L2242
L2243
L2244
L2245
L2246
L2247
L2248
L2249
L2250
L2251
L2252
L2253
L2254
L2255
L2256
L2257
L2258
L2259
L2260
L2261
L2262
L2263
L2264
L2265
L2266
L2267
L2268
L2269
L2270
L2271
L2272
L2273
L2274
L2275
L2276
L2277
L2278
L2279
L2280
L2281
L2282
L2283
L2284
L2285
L2286
L2287
L2288
L2289
L2290
L2291
L2292
L2293
L2294
L2295
L2296
L2297
L2298
L2299
L2300
L2301
L2302
L2303
L2304
L2305
L2306
L2307
L2308
L2309
L2310
L2311
L2312
L2313
L2314
L2315
L2316
L2317
L2318
L2319
L2320
L2321
L2322
L2323
L2324
L2325
L2326
L2327
L2328
L2329
L2330
L2331
L2332
L2333
L2334
L2335
L2336
L2337
L2338
L2339
L2340
L2341
L2342
L2343
L2344
L2345
L2346
L2347
L2348
L2349
L2350
L2351
L2352
L2353
L2354
L2355
L2356
L2357
L2358
L2359
L2360
L2361
L2362
L2363
L2364
L2365
L2366
L2367
L2368
L2369
L2370
L2371
L2372
L2373
L2374
L2375
L2376
L2377
L2378
L2379
L2380
L2381
L2382
L2383
L2384
L2385
L2386
L2387
L2388
L2389
L2390
L2391
L2392
L2393
L2394
L2395
L2396
L2397
L2398
L2399
L2400
L2401
L2402
L2403
L2404
L2405
L2406
L2407
L2408
L2409
L2410
L2411
L2412
L2413
L2414
L2415
L2416
L2417
L2418
L2419
L2420
L2421
L2422
L2423
L2424
L2425
L2426
L2427
L2428
L2429
L2430
L2431
L2432
L2433
L2434
L2435
L2436
L2437
L2438
L2439
L2440
L2441
L2442
L2443
L2444
L2445
L2446
L2447
L2448
L2449
L2450
L2451
L2452
L2453
L2454
L2455
L2456
L2457
L2458
L2459
L2460
L2461
L2462
L2463
L2464
L2465
L2466
L2467
L2468
L2469
L2470
L2471
L2472
L2473
L2474
L2475
L2476
L2477
L2478
L2479
L2480
L2481
L2482
L2483
L2484
L2485
L2486
L2487
L2488
L2489
L2490
L2491
L2492
L2493
L2494
L2495
L2496
L2497
L2498
L2499
L2500
L2501
L2502
L2503
L2504
L2505
L2506
L2507
L2508
L2509
L2510
L2511
L2512
L2513
L2514
L2515
L2516
L2517
L2518
L2519
L2520
L2521
L2522
L2523
L2524
L2525
L2526
L2527
L2528
L2529
L2530
L2531
L2532
L2533
L2534
L2535
L2536
L2537
L2538
L2539
L2540
L2541
L2542
L2543
L2544
L2545
L2546
L2547
L2548
L2549
L2550
L2551
L2552
L2553
L2554
L2555
L2556
L2557
L2558
L2559
L2560
L2561
L2562
L2563
L2564
L2565
L2566
L2567
L2568
L2569
L2570
L2571
L2572
L2573
L2574
L2575
L2576
L2577
L2578
L2579
L2580
L2581
L2582
L2583
L2584
L2585
L2586
L2587
L2588
L2589
L2590
L2591
L2592
L2593
L2594
L2595
L2596
L2597
L2598
L2599
L2600
L2601
L2602
L2603
L2604
L2605
L2606
L2607
L2608
L2609
L2610
L2611
L2612
L2613
L2614
L2615
L2616
L2617
L2618
L2619
L2620
L2621
L2622
L2623
L2624
L2625
L2626
L2627
L2628
L2629
L2630
L2631
L2632
L2633
L2634
L2635
L2636
L2637
L2638
L2639
L2640
L2641
L2642
L2643
L2644
L2645
L2646
L2647
L2648
L2649
L2650
L2651
L2652
L2653
L2654
L2655
L2656
L2657
L2658
L2659
L2660
L2661
L2662
L2663
L2664
L2665
L2666
L2667
L2668
L2669
L2670
L2671
L2672
L2673
L2674
L2675
L2676
L2677
L2678
L2679
L2680
L2681
L2682
L2683
L2684
L2685
L2686
L2687
L2688
L2689
L2690
L2691
L2692
L2693
L2694
L2695
L2696
L2697
L2698
L2699
L2700
L2701
L2702
L2703
L2704
L2705
L2706
L2707
L2708
L2709
L2710
L2711
L2712
L2713
L2714
L2715
L2716
L2717
L2718
L2719
L2720
L2721
L2722
L2723
L2724
L2725
L2726
L2727
L2728
L2729
L2730
L2731
L2732
L2733
L2734
L2735
L2736
L2737
L2738
L2739
L2740
L2741
L2742
L2743
L2744
L2745
L2746
L2747
L2748
L2749
L2750
L2751
L2752
L2753
L2754
L2755
L2756
L2757
L2758
L2759
L2760
L2761
L2762
L2763
L2764
L2765
L2766
L2767
L2768
L2769
L2770
L2771
L2772
L2773
L2774
L2775
L2776
L2777
L2778
L2779
L2780
L2781
L2782
L2783
L2784
L2785
L2786
L2787
L2788
L2789
L2790
L2791
L2792
L2793
L2794
L2795
L2796
L2797
L2798
L2799
L2800
L2801
L2802
L2803
L2804
L2805
L2806
L2807
L2808
L2809
L2810
L2811
L2812
L2813
L2814
L2815
L2816
L2817
L2818
L2819
L2820
L2821
L2822
L2823
L2824
L2825
L2826
L2827
L2828
L2829
L2830
L2831
L2832
L2833
L2834
L2835
L2836
L2837
L2838
L2839
L2840
L2841
L2842
L2843
L2844
L2845
L2846
L2847
L2848
L2849
L2850
L2851
L2852
L2853
L2854
L2855
L2856
L2857
L2858
L2859
L2860
L2861
L2862
L2863
L2864
L2865
L2866
L2867
L2868
L2869
L2870
L2871
L2872
L2873
L2874
L2875
L2876
L2877
L2878
L2879
L2880
L2881
L2882
L2883
L2884
L2885
L2886
L2887
L2888
L2889
L2890
L2891
L2892
L2893
L2894
L2895
L2896
L2897
L2898
L2899
L2900
L2901
L2902
L2903
L2904
L2905
L2906
L2907
L2908
L2909
L2910
L2911
L2912
L2913
L2914
L2915
L2916
L2917
L2918
L2919
L2920
L2921
L2922
L2923
L2924
L2925
L2926
L2927
L2928
L2929
L2930
L2931
L2932
L2933
L2934
L2935
L2936
L2937
L2938
L2939
L2940
L2941
L2942
L2943
L2944
L2945
L2946
L2947
L2948
L2949
L2950
L2951
L2952
L2953
L2954
L2955
L2956
L2957
L2958
L2959
L2960
L2961
L2962
L2963
L2964
L2965
L2966
L2967
L2968
L2969
L2970
L2971
L2972
L2973
L2974
L2975
L2976
L2977
L2978
L2979
L2980
L2981
L2982
L2983
L2984
L2985
L2986
L2987
L2988
L2989
L2990
L2991
L2992
L2993
L2994
L2995
L2996
L2997
L2998
L2999
L3000
L3001
L3002
L3003
L3004
L3005
L3006
L3007
L3008
L3009
L3010
L3011
L3012
L3013
L3014
L3015
L3016
L3017
L3018
L3019
L3020
L3021
L3022
L3023
L3024
L3025
L3026
L3027
L3028
L3029
L3030
L3031
L3032
L3033
L3034
L3035
L3036
L3037
L3038
L3039
L3040
L3041
L3042
L3043
L3044
L3045
L3046
L3047
L3048
L3049
L3050
L3051
L3052
L3053
L3054
L3055
L3056
L3057
L3058
L3059
L3060
L3061
L3062
L3063
L3064
L3065
L3066
L3067
L3068
L3069
L3070
L3071
L3072
L3073
L3074
L3075
L3076
L3077
L3078
L3079
L3080
L3081
L3082
L3083
L3084
L3085
L3086
L3087
L3088
L3089
L3090
L3091
L3092
L3093
L3094
L3095
L3096
L3097
L3098
L3099
L3100
L3101
L3102
L3103
L3104
L3105
L3106
L3107
L3108
L3109
L3110
L3111
L3112
L3113
L3114
L3115
L3116
L3117
L3118
L3119
L3120
L3121
L3122
L3123
L3124
L3125
L3126
L3127
L3128
L3129
L3130
L3131
L3132
L3133
L3134
L3135
L3136
L3137
L3138
L3139
L3140
L3141
L3142
L3143
L3144
L3145
L3146
L3147
L3148
L3149
L3150
L3151
L3152
L3153
L3154
L3155
L3156
L3157
L3158
L3159
L3160
L3161
L3162
L3163
L3164
L3165
L3166
L3167
L3168
L3169
L3170
L3171
L3172
L3173
L3174
L3175
L3176
L3177
L3178
L3179
L3180
L3181
L3182
L3183
L3184
L3185
L3186
L3187
L3188
L3189
L3190
L3191
L3192
L3193
L3194
L3195
L3196
L3197
L3198
L3199
L3200
L3201
L3202
L3203
L3204
L3205
L3206
L3207
L3208
L3209
L3210
L3211
L3212
L3213
L3214
L3215
L3216
L3217
L3218
L3219
L3220
L3221
L3222
L3223
L3224
L3225
L3226
L3227
L3228
L3229
L3230
L3231
L3232
L3233
L3234
L3235
L3236
L3237
L3238
L3239
L3240
L3241
L3242
L3243
L3244
L3245
L3246
L3247
L3248
L3249
L3250
L3251
L3252
L3253
L3254
L3255
L3256
L3257
L3258
L3259
L3260
L3261
L3262
L3263
L3264
L3265
L3266
L3267
L3268
L3269
L3270
L3271
L3272
L3273
L3274
L3275
L3276
L3277
L3278
L3279
L3280
L3281
L3282
L3283
L3284
L3285
L3286
L3287
L3288
L3289
L3290
L3291
L3292
L3293
L3294
L3295
L3296
L3297
L3298
L3299
L3300
L3301
L3302
L3303
L3304
L3305
L3306
L3307
L3308
L3309
L3310
L3311
L3312
L3313
L3314
L3315
L3316
L3317
L3318
L3319
L3320
L3321
L3322
L3323
L3324
L3325
L3326
L3327
L3328
L3329
L3330
L3331
L3332
L3333
L3334
L3335
L3336
L3337
L3338
L3339
L3340
L3341
L3342
L3343
L3344
L3345
L3346
L3347
L3348
L3349
L3350
L3351
L3352
L3353
L3354
L3355
L3356
L3357
L3358
L3359
L3360
L3361
L3362
L3363
L3364
L3365
L3366
L3367
L3368
L3369
L3370
L3371
L3372
L3373
L3374
L3375
L3376
L3377
L3378
L3379
L3380
L3381
L3382
L3383
L3384
L3385
L3386
L3387
L3388
L3389
L3390
L3391
L3392
L3393
L3394
L3395
L3396
L3397
L3398
L3399
L3400
L3401
L3402
L3403
L3404
L3405
L3406
L3407
L3408
L3409
L3410
L3411
L3412
L3413
L3414
L3415
L3416
L3417
L3418
L3419
L3420
L3421
L3422
L3423
L3424
L3425
L3426
L3427
L3428
L3429
L3430
L3431
L3432
L3433
L3434
L3435
L3436
L3437
L3438
L3439
L3440
L3441
L3442
L3443
L3444
L3445
L3446
L3447
L3448
L3449
L3450
L3451
L3452
L3453
L3454
L3455
L3456
L3457
L3458
L3459
L3460
L3461
L3462
L3463
L3464
L3465
L3466
L3467
L3468
L3469
L3470
L3471
L3472
L3473
L3474
L3475
L3476
L3477
L3478
L3479
L3480
L3481
L3482
L3483
L3484
L3485
L3486
L3487
L3488
L3489
L3490
L3491
L3492
L3493
L3494
L3495
L3496
L3497
L3498
L3499
L3500
L3501
L3502
L3503
L3504
L3505
L3506
L3507
L3508
L3509
L3510
L3511
L3512
L3513
L3514
L3515
L3516
L3517
L3518
L3519
L3520
L3521
L3522
L3523
L3524
L3525
L3526
L3527
L3528
L3529
L3530
L3531
L3532
L3533
L3534
L3535
L3536
L3537
L3538
L3539
L3540
L3541
L3542
L3543
L3544
L3545
L3546
L3547
L3548
L3549
L3550
L3551
L3552
L3553
L3554
L3555
L3556
L3557
L3558
L3559
L3560
L3561
L3562
L3563
L3564
L3565
L3566
L3567
L3568
L3569
L3570
L3571
L3572
L3573
L3574
L3575
L3576
L3577
L3578
L3579
L3580
L3581
L3582
L3583
L3584
L3585
L3586
L3587
L3588
L3589
L3590
L3591
L3592
L3593
L3594
L3595
L3596
L3597
L3598
L3599
L3600
L3601
L3602
L3603
L3604
L3605
L3606
L3607
L3608
L3609
L3610
L3611
L3612
L3613
L3614
L3615
L3616
L3617
L3618
L3619
L3620
L3621
L3622
L3623
L3624
L3625
L3626
L3627
L3628
L3629
L3630
L3631
L3632
L3633
L3634
L3635
L3636
L3637
L3638
L3639
L3640
L3641
L3642
L3643
L3644
L3645
L3646
L3647
L3648
L3649
L3650
L3651
L3652
L3653
L3654
L3655
L3656
L3657
L3658
L3659
L3660
L3661
L3662
L3663
L3664
L3665
L3666
L3667
L3668
L3669
L3670
L3671
L3672
L3673
L3674
L3675
L3676
L3677
L3678
L3679
L3680
L3681
L3682
L3683
L3684
L3685
L3686
L3687
L3688
L3689
L3690
L3691
L3692
L3693
L3694
L3695
L3696
L3697
L3698
L3699
L3700
L3701
L3702
L3703
L3704
L3705
L3706
L3707
L3708
L3709
L3710
L3711
L3712
L3713
L3714
L3715
L3716
L3717
L3718
L3719
L3720
L3721
L3722
L3723
L3724
L3725
L3726
L3727
L3728
L3729
L3730
L3731
L3732
L3733
L3734
L3735
L3736
L3737
L3738
L3739
L3740
L3741
L3742
L3743
L3744
L3745
L3746
L3747
L3748
L3749
L3750
L3751
L3752
L3753
L3754
L3755
L3756
L3757
L3758
L3759
L3760
L3761
L3762
L3763
L3764
L3765
L3766
L3767
L3768
L3769
L3770
L3771
L3772
L3773
L3774
L3775
L3776
L3777
L3778
L3779
L3780
L3781
L3782
L3783
L3784
L3785
L3786
L3787
L3788
L3789
L3790
L3791
L3792
L3793
L3794
L3795
L3796
L3797
L3798
L3799
L3800
L3801
L3802
L3803
L3804
L3805
L3806
L3807
L3808
L3809
L3810
L3811
L3812
L3813
L3814
L3815
L3816
L3817
L3818
L3819
L3820
L3821
L3822
L3823
L3824
L3825
L3826
L3827
L3828
L3829
L3830
L3831
L3832
L3833
L3834
L3835
L3836
L3837
L3838
L3839
L3840
L3841
L3842
L3843
L3844
L3845
L3846
L3847
L3848
L3849
L3850
L3851
L3852
L3853
L3854
L3855
L3856
L3857
L3858
L3859
L3860
L3861
L3862
L3863
L3864
L3865
L3866
L3867
L3868
L3869
L3870
L3871
L3872
L3873
L3874
L3875
L3876
L3877
L3878
L3879
L3880
L3881
L3882
L3883
L3884
L3885
L3886
L3887
L3888
L3889
L3890
L3891
L3892
L3893
L3894
L3895
L3896
L3897
L3898
L3899
L3900
L3901
L3902
L3903
L3904
L3905
L3906
L3907
L3908
L3909
L3910
L3911
L3912
L3913
L3914
L3915
L3916
L3917
L3918
L3919
L3920
L3921
L3922
L3923
L3924
L3925
L3926
L3927
L3928
L3929
L3930
L3931
L3932
L3933
L3934
L3935
L3936
L3937
L3938
L3939
L3940
L3941
L3942
L3943
L3944
L3945
L3946
L3947
L3948
L3949
L3950
L3951
L3952
L3953
L3954
L3955
L3956
L3957
L3958
L3959
L3960
L3961
L3962
L3963
L3964
L3965
L3966
L3967
L3968
L3969
L3970
L3971
L3972
L3973
L3974
L3975
L3976
L3977
L3978
L3979
L3980
L3981
L3982
L3983
L3984
L3985
L3986
L3987
L3988
L3989
L3990
L3991
L3992
L3993
L3994
L3995
L3996
L3997
L3998
L3999
L4000
L4001
L4002
L4003
L4004
L4005
L4006
L4007
L4008
L4009
L4010
L4011
L4012
L4013
L4014
L4015
L4016
L4017
L4018
L4019
L4020
L4021
L4022
L4023
L4024
L4025
L4026
L4027
L4028
L4029
L4030
L4031
L4032
L4033
L4034
L4035
L4036
L4037
L4038
L4039
L4040
L4041
L4042
L4043
L4044
L4045
L4046
L4047
L4048
L4049
L4050
L4051
L4052
L4053
L4054
L4055
L4056
L4057
L4058
L4059
L4060
L4061
L4062
L4063
L4064
L4065
L4066
L4067
L4068
L4069
L4070
L4071
L4072
L4073
L4074
L4075
L4076
L4077
L4078
L4079
L4080
L4081
L4082
L4083
L4084
L4085
L4086
L4087
L4088
L4089
L4090
L4091
L4092
L4093
L4094
L4095
L4096
L4097
L4098
L4099
L4100
L4101
L4102
L4103
L4104
L4105
L4106
L4107
L4108
L4109
L4110
L4111
L4112
L4113
L4114
L4115
L4116
L4117
L4118
L4119
L4120
L4121
L4122
L4123
L4124
L4125
L4126
L4127
L4128
L4129
L4130
L4131
L4132
L4133
L4134
L4135
L4136
L4137
L4138
L4139
L4140
L4141
L4142
L4143
L4144
L4145
L4146
L4147
L4148
L4149
L4150
L4151
L4152
L4153
L4154
L4155
L4156
L4157
L4158
L4159
L4160
L4161
L4162
L4163
L4164
L4165
L4166
L4167
L4168
L4169
L4170
L4171
L4172
L4173
L4174
L4175
L4176
L4177
L4178
L4179
L4180
L4181
L4182
L4183
L4184
L4185
L4186
L4187
L4188
L4189
L4190
L4191




(STA. 163+29.41 TO STA. 165+00.00)
SECTION (STA. 166+27.37 TO STA. 167+50.00)
NOT TO SCALE

12 C-10




SECTION (STA. 176+00.00 TO STA. 178+50.00)
NOT TO SCALE

8 C-10




SECTION (STA. 132+09.50 TO STA. 145+03.96)
NOT TO SCALE

4 C-10




SECTION
NOT TO SCALE

11 C-10




SECTION (STA. 173+70.00 TO STA. 174+00.00)
NOT TO SCALE

7 C-10




SECTION (STA. 126+67.44 TO STA. 130+80.42)
NOT TO SCALE

3 C-10




(STA. 182+17.17 TO STA. 184+00.00)
SECTION (STA. 185+50.00 TO STA. 186+54.00)
NOT TO SCALE

10 C-10




SECTION (STA. 168+00.00 TO STA. 171+33.63)
NOT TO SCALE

6 C-10




SECTION (STA. 122+98.37 TO STA. 125+00.00)
NOT TO SCALE

2 C-10




SECTION (STA. 179+00.00 TO STA. 182+17.17)
NOT TO SCALE

9 C-10



SECTION (STA. 145+03.96 TO STA. 158+50.00)
NOT TO SCALE

5 C-10



SECTION (STA. 119+38.78 TO STA. 122+58.37)
NOT TO SCALE

1 C-10

NO.	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
SECTIONS

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


JOEL C. LAUGHLIN — No. 10165 — STATE OF NEVADA — REGISTERED PROFESSIONAL ENGINEER — Exp. 12/31/2005 CIVIL

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE (702) 804-2000 • FAX: (702) 804-2250

SCALE	
HORIZ:	NONE
VERT:	NONE
FIELD BOOK	


L-1759
DRAWING NO.
C-10
SHT. 16 OF 30




ST AND CABLE RAILING DETAILS (10/C11)
SCALE




WARNING SIGN - FLOOD CHANNEL DETAIL (7/C11)
NOT TO SCALE



PERMANENT CHANNEL SIGN DETAIL (6/C11)
NOT TO SCALE



SLOPE PAVING DETAIL (3/C11)
NOT TO SCALE




CHAIN LINK FENCE DETAIL (9/C11)
NOT TO SCALE


TABLE I
FOR 6' HIGH CHAIN LINK FENCE

LOCATION	MIN. SIZE	MIN. WEIGHT
END, CORNER AND PULL	2.351 O.D.	3.10
LINE	2.00 O.D.	2.72
BRACES	1.83 O.D.	2.27
TOP RAIL	1.83 O.D.	2.27

NOTES:
1. FENCING SHALL BE CHAIN LINK AND SHALL CONSIST OF GALVANIZED CHAINLINK FABRIC ON STEEL POSTS.
(A) ALL POST TOPS SHALL BE FITTED WITH SUITABLE FINIALS.
(B) BRACES SHALL BE SPACED APPROXIMATELY 12' BELOW TOP OF TERMINAL POSTS AND SHALL EXTEND FROM END, GATE, OR CORNER POSTS TO FIRST ADJACENT LINE POST.
(C) ALL FITTINGS SHALL BE HOT DIPPED GALVANIZED MALLEABLE, CAST IRON, OR PRESSED STEEL.
(D) TOP AND BOTTOM SELVAGES OF THE FENCE SHALL HAVE A TWISTED AND BARBED FINISH.



FENCE PLAN (TYPICAL)




PAINTED STAFF GAUGE (5/C11)
NOT TO SCALE

TYPICAL LETTERING DIMENSIONS
NOTE: UNITS SHALL BE IN FEET AND BE GRADUATED IN IN TENTHS OF FEET


STAFF GAUGE LOCATIONS

STATIONS	
LT	RT
173+00.00	171+75.00
	177+50.00




SLOPE PAVING DETAIL (2/C11)
NOT TO SCALE

CHAIN LINK GATE DETAIL (8/C11)
NOT TO SCALE



MANWAY DETAIL (4/C11)
NOT TO SCALE



POST AND CABLE RAILING POLE MOUNT (1/C11)
NOT TO SCALE

DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
DETAILS

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA NOEL LAUGHLIN No. 10185 CIVIL 3-11-04

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE (702) 804-2000 • FAX: (702) 804-2299


SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
C-11
SHT. 17 OF 30




SECTION (STA. 162+25.00 TO STA. 162+79.41)
NOT TO SCALE

3
C-12



SECTION (STA. 160+79.41 TO STA. 161+59.19)
NOT TO SCALE

2
C-12



SECTION (STA. 159+00.00 TO STA. 160+29.41)
NOT TO SCALE

1
C-12

DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
SECTIONS

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA — No. 10165 — 3-11-04


PROJECT No: 500-857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-3000 • FAX: (702) 804-3288

SCALE	
HORIZ:	NONE
VERT:	NONE
FIELD BOOK	

L-1759
DRAWING NO.
C-12
SHT. 18 OF 30







CONSTRUCTION NOTES

1. CONSTRUCT 6' CHAIN-LINK FENCE (SEE DETAIL 9/C11)
2. CONSTRUCT 6' CHAIN-LINK GATE (SEE DETAIL 8/C11) (WIDTH OF GATE CALLED OUT IN PLAN VIEW)
5. INSTALL SIGN (SEE DETAIL 6/C11)
6. INSTALL SIGN (SEE DETAIL 7/C11)
7. CONSTRUCT POST AND CABLE RAILING (SEE DETAIL 10/C11)

REMOVAL NOTES

7. REMOVE EXISTING CHAIN-LINK FENCE.

POST AND CABLE CURVE TABLE


CURVE TABLE				
CURVE	DELTA	RADIUS	LENGTH	TANGENT
C15	22°40'28"	855.50'	338.56'	171.52'
C16	01°09'50"	861.63'	17.50'	8.75'
C17	66°23'48"	58.50'	67.79'	38.28'
C18	66°23'48"	41.50'	48.09'	27.16'
C16	01°09'50"	848.80'	17.24'	8.62'

POST AND CABLE LINE TABLE

LINE TABLE		
LINE	BEARING	LENGTH
L39	N02°31'07"E	52.38'
L40	N39°02'59"W	41.25'
L42	N25°32'04"E	26.11'
L43	N66°00'50"E	28.64'
L44	N23°59'10"W	17.00'
L45	N73°30'24"W	26.11'
L46	N66°00'50"E	10.50'
L47	N00°22'58"W	120.26'
L48	N08°08'53"E	50.60'
L49	N15°28'19"E	51.91'
L50	N00°22'58"W	99.93'
L51	N04°36'54"W	50.12'
L52	N00°22'58"W	249.98'
L53	N00°02'58"W	50.00'

FENCE LINE TABLE

LINE TABLE		
LINE	BEARING	LENGTH
L35	N08°30'51"W	30.45'
L36	N89°33'09"E	16.00'
L37	N09°23'22"E	18.85'
L38	N43°12'16"E	21.62'



DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
FENCING/POST AND CABLE RAILING PLAN

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA ROBERT E. LAUGHLIN No. 10165 CIVIL 11-04


PROJECT No: 500.857 DRAWN BY: DM
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2286

SCALE
HORIZ: 1" = 40'
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
C-13
SHT. 19 OF 30






POST AND CABLE LINE TABLE

LINE TABLE		
LINE	BEARING	LENGTH
L65	N07°01'09"E	50.35'
L66	N00°02'58"W	753.89'
L67	N16°19'46"W	59.16'
L68	N00°02'58"W	50.00'
L69	N00°02'58"W	436.83'
L70	N01°48'00"W	70.06'
L71	S89°57'02"W	4.50'
L72	S00°02'58"E	7.83'
L73	S89°57'02"W	4.50'

FENCE LINE TABLE

LINE TABLE		
LINE	BEARING	LENGTH
L54	N89°36'24"E	66.37'
L55	N00°27'55"W	26.40'
L56	N89°32'05"E	17.26'
L57	N58°30'46"E	19.47'
L58	N00°22'58"W	28.89'
L59	N89°56'23"E	1.37'
L60	N83°53'00"W	4.45'
L61	N83°45'44"E	40.84'
L62	N00°02'58"W	29.68'
L63	N62°55'16"E	14.01'
L64	N00°02'58"W	21.80'



CONSTRUCTION NOTES

1. CONSTRUCT 6' CHAIN-LINK FENCE (SEE DETAIL 9/C11)
2. CONSTRUCT 6' CHAIN-LINK GATE (SEE DETAIL 8/C11) (WIDTH OF GATE CALLED OUT IN PLAN VIEW)
5. INSTALL SIGN (SEE DETAIL 6/C11)
6. INSTALL SIGN (SEE DETAIL 7/C11)
7. CONSTRUCT POST AND CABLE RAILING (SEE DETAIL 10/C11)

CONSTRUCTION NOTES

[7] REMOVE EXISTING CHAIN-LINK FENCE.

NO.	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
FENCING/POST AND CABLE RAILING PLAN

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER STATE OF NEVADA ROBERT LAUGHLIN No. 10185 CIVIL


PROJECT No: 500.857 DRAWN BY: DKJ
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE (702) 804-2000 • FAX (702) 804-2280

SCALE
HORIZ: 1" = 40'
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
C-14
SHT. 20 OF 30

F:\500-857\dwg\improv\ac_c15.dwg 03-11-04 13:29:31 RBlanchard



ACCESS/ MAINTENANCE ROAD ℄ LINE TABLE

LINE TABLE		
LINE	BEARING	LENGTH
L3	S00°49'42"W	48.17'
L4	S23°55'17"E	22.80'
L5	S32°18'38"E	225.35'
L6	S32°53'00"E	100.03'
L7	S32°18'38"E	51.79'
L8	S02°48'57"E	77.41'
L9	S01°58'00"E	36.30'
L10	S00°02'58"E	20.23'
L11	S02°28'47"W	20.02'
L12	S00°22'58"E	940.87'
L13	S02°06'04"E	20.01'
L35	S00°22'58"E	20.18'
L36	S01°20'08"E	20.01'
L37	S00°22'58"E	924.87'
L38	S07°58'39"E	30.27'
L39	S00°22'58"E	30.80'
L40	S07°12'43"E	30.27'
L41	S00°02'58"E	582.12'
L42	S03°23'36"W	50.11'
L43	S00°22'58"E	119.19'
L44	S23°59'10"E	95.58'

ACCESS/ MAINTENANCE ROAD ℄ CURVE TABLE

CURVE TABLE				
CURVE	DELTA	RADIUS	LENGTH	TANGENT
C5	22°03'58"	750.40'	289.00'	146.31'
C6	31°53'55"	855.30'	476.17'	244.43'
C7	23°36'12"	56.00'	23.07'	11.70'

NO.	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

ACCESS/MAINTENANCE CONTROL PLAN
STA. 118+82.26 TO STA. 161+00.00
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER STATE OF NEVADA No. 10165 NOEL C. LAUGHLIN Exp. 12/31/2005 CIVIL 5-11-04


PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY:


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2220


SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK


L-1759
DRAWING NO.
C-15
SHT. 21 OF 30

F:\500-857\dwg\improv\ac_c16.dwg 03-11-04 13:30:29 RBlanchard









ACCESS/ MAINTENANCE ROAD ℄ LINE TABLE

LINE TABLE		
LINE	BEARING	LENGTH
L13	S23°59'10"E	55.22'
L14	S00°02'58"E	53.46'
L15	S00°22'58"E	138.98'
L16	S00°02'58"E	31.72'
L17	N04°06'16"W	42.21'
L18	S00°02'58"E	50.47'
L19	S04°50'32"E	35.18'
L20	S01°11'43"E	122.31'
L21	S00°02'58"E	333.69'
L22	S00°23'04"E	5.89'
L23	S00°35'33"W	39.05'
L24	S00°02'58"E	30.60'
L25	S11°28'07"E	51.91'
L26	S00°49'43"W	148.58'
L27	S00°02'58"E	250.32'
L28	S07°01'09"W	50.36'
L29	S00°02'58"E	499.52'
L30	S02°10'18"E	54.01'
L31	S00°02'58"E	50.24'
L32	S02°26'19"W	46.07'
L33	S00°02'58"E	103.32'
L34	S08°39'47"E	57.00'

ACCESS/ MAINTENANCE ROAD ℄ CURVE TABLE

CURVE TABLE				
CURVE	DELTA	RADIUS	LENGTH	TANGENT
C8	23°56'12"	56.00'	23.40'	11.87'
C9	41°05'27"	94.00'	67.41'	35.23'
C10	41°25'26"	94.00'	67.96'	35.54'
C11	31°26'16"	56.00'	30.73'	15.76'
C12	31°06'10"	56.00'	30.40'	15.58'
C13	67°38'26"	24.00'	28.33'	16.08'
C14	68°16'57"	24.00'	28.60'	16.27'

DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

ACCESS/MAINTENANCE ROAD CONTROL PLAN
STA. 161+00.00 TO STA. 181+82.26
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA No. 10165 LAUGHLIN CIVIL 3-11-04

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK


L-1759
DRAWING NO.
C-16
SHT. 22 OF 30




LOCKING BAR GUIDE
NOT TO SCALE




PLAN
NOT TO SCALE




DETAIL A
NOT TO SCALE




SECTION B-B
(STRUCTURAL REINFORCING BETWEEN MANHOLES)
NOT TO SCALE



SECTION A-A
NOT TO SCALE



SECTION C-C
NOT TO SCALE



GAUGING STATION STENCIL DETAIL
(VIEW FROM INSIDE OF GAUGING STATION)
NOT TO SCALE

DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
GAUGING STATION
SECTION AND DETAILS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA — NOEL LAUGHLIN — No. 10165 — CIVIL — 03/31/2008

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
C-17
SHT. 23 OF 30




WALL EXPANSION JOINT DETAIL (8)
NOT TO SCALE




(*) UNLESS OTHERWISE NOTED


SLAB EXPANSION JOINT DETAIL (5)
NOT TO SCALE



WALL JOINT DETAIL (9)
NOT TO SCALE




CAP DETAIL




NOTES:
1. WEAKENED PLANE JOINTS TO BE CENTERED WITH WEEPHOLES WHEN JOINTS OCCUR.
2. IN CURVED ALIGNMENT SECTIONS, TRANSVERSE JOINTS SHALL BE NORMAL TO CENTERLINE AND SHALL NOT EXCEED 60' MAX SPACING.

PLAN - CONCRETE LINED TRAPEZOIDAL CHANNEL (1)
NOT TO SCALE




WALL CONTRACTION JOINT DETAIL (10)
NOT TO SCALE




SECTION

SLAB WEEPHOLE DETAIL (6)
NOT TO SCALE




NOTE:
SPRAY GALVANIZE REINFORCING BARS 9" EACH SIDE OF WEAKENED PLANE JOINT

WEAKENED PLANE JOINT DETAIL (2)
NOT TO SCALE




CONSTRUCTION JOINT DETAIL (7)
NOT TO SCALE



SEALANT DETAIL (3)
NOT TO SCALE

STRUCTURE NOTES

1. DESIGN SPECIFICATIONS: AASHTO "STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, 1996" AND INTERIMS THROUGH 2000. REINFORCED CONCRETE DESIGN BASED ON LOAD FACTOR DESIGN.
2. CONSTRUCTION SPECIFICATIONS: UNIFORM STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, OFF-SITE IMPROVEMENTS, CLARK COUNTY AREA, NEVADA.
3. LIVE LOAD: STANDARD AASHTO HS20-44 TRUCK LOADING AND TRAFFIC SURCHARGE FROM MAINTENANCE VEHICLES (2' OF SOIL)
4. SEISMIC LOAD: ACCELERATION COEFFICIENT 0.15 g
5. CONCRETE: ALL CONCRETE SHALL BE CLASS A MODIFIED (MAJOR) EXCEPT FOR WALLS WHICH SHALL BE CLASS D MODIFIED (MAJOR). ONLY TYPE V CEMENT SHALL BE USED FOR CONCRETE IN CONTACT WITH SOIL. CONCRETE COMPRESSIVE MINIMUM STRENGTH AT 28 DAYS SHALL BE, f'c=4,500 PSI AND A MAXIMUM WATER TO CEMENT RATIO, BY WEIGHT, OF 0.45.
6. REINFORCING STEEL: ALL REINFORCING STEEL SHALL BE ASTM A615 REINFORCING STEEL STRENGTH, Fy = 60,000 PSI.
7. ALL EXPOSED EDGES OF CONCRETE SHALL BE CHAMFERED 3/4" UNLESS OTHERWISE INDICATED.
8. TRANSVERSE AND LONGITUDINAL JOINTS IN INVERT SLAB AND SIDE SLOPE SLAB OF PAVED TRAPEZOIDAL CHANNELS AND WALLS FOR RECTANGULAR CHANNELS WILL BE REQUIRED AT THE END OF EACH CONTINUOUS POURING OPERATION. SEE TYPICAL CONSTRUCTION JOINT DETAIL. TRANSVERSE CONSTRUCTION JOINTS SHALL NOT BE PLACED WITHIN 3-FEET OF A MANHOLE, WITHIN 10-FEET OF JUNCTION STRUCTURE OPENINGS, OR WITHIN 50 FEET OF AN EXPANSION JOINT.
9. ALL TRANSVERSE JOINTS IN WALLS AND SLABS (CONSTRUCTION, WEAKENED CONTRACTION AND EXPANSION) SHALL BE IN THE SAME PLANE. NO STAGGERING OF JOINTS WILL BE PERMITTED UNLESS SHOWN OTHERWISE. TRANSVERSE CONSTRUCTION JOINTS SHALL BE NORMAL OR RADIAL TO CENTERLINE OF CONSTRUCTION.
10. ALL SINGLE LAYER REINFORCEMENT SHALL BE PLACED IN THE CENTER OF CONCRETE UNLESS NOTED OTHERWISE.
11. IN CURVED CHANNEL SECTIONS TRANSVERSE BARS SHALL BE PLACED NORMAL TO THE CHANNEL CENTERLINE.
12. IN CURVED CHANNEL SECTIONS, THE MAXIMUM SPACING OF BARS SHALL NOT EXCEED THAT SHOWN FOR TYPICAL SECTIONS. STEEL SHALL BE PLACED RADIALLY FROM THE MAXIMUM SPACING.
13. AT THE BEGINNING AND ENDING OF ALL POURS, A COMPLETE CURTAIN OF MAIN REINFORCEMENT SHALL BE PLACED 3-INCHES FROM THE TRANSVERSE CONSTRUCTION, CONTRACTION AND EXPANSION JOINTS.
14. NO WELDING WILL BE PERMITTED ON ANY REINFORCEMENT.
15. CHANNEL ELEVATIONS: FOR CHANNEL INVERT ELEVATIONS REFER TO THE CHANNEL PLAN AND PROFILE SHEETS LOCATED ELSEWHERE IN THIS DRAWING SET.
16. EXCAVATION AND BACKFILL: THE LIMITS OF EXCAVATION AND BACKFILL SHALL BE AS SHOWN IN THE STATE OF NEVADA, "STANDARD PLANS FOR ROAD AND BRIDGE CONSTRUCTION, JANUARY 2001," UNLESS OTHERWISE NOTED.
17. WEEPHOLES: WEEPHOLES WILL BE REQUIRED AT 30-FEET O.C. PER THE TYPICAL WEEPHOLE DETAIL FOR ALL OPEN CHANNEL STRUCTURES.
18. BEDDING MATERIALS: UNLESS NOTED OTHERWISE ALL BEDDING MATERIAL SHALL BE 3-INCHES OF TYPE II AGGREGATE BASE OVER 12 INCHES OF 2 INCH DRAIN ROCK COMPACTED TO 90% OF THE MAXIMUM DRY DENSITY AS ESTABLISHED BY ASTM TEST METHOD D-1557.



NOTES:
1. CUTOFF WALL TO BE SPACED @ 180' OC FOR TRAPEZOIDAL CHANNELS AND 180' OC FOR RECTANGULAR CHANNELS ACROSS THE ENTIRE WIDTH OF THE CHANNEL LINING.
2. CONTRACTOR TO VERIFY THAT ALL DOWELS ARE IN PLANE AND PERPINDICULAR TO JOINT PRIOR TO POURING CONCRETE.

TRANSVERSE CUT-OFF WALL EXPANSION DETAIL (4)
NOT TO SCALE

NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES DETAILS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


RIMAH NAZZAL — Exp. 12/31/2006 — CIVIL / STRUCTURAL — STATE OF NEVADA — PROFESSIONAL ENGINEER — No. 12971
3/11/04

PROJECT No: 500.857 DRAWN BY: NO/M
DESIGNED BY: RN CHECKED BY: RN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-1
SHT. 24 OF 30




* SEE CHANNEL PLAN AND PROFILE SHEETS FOR RCP LOCATIONS

REINFORCING AROUND PIPE

NOT TO SCALE

10




NOTE:
1. FOR INFORMATION NOT SHOWN, SEE 4/S-1
2. CONTRACTOR TO VERIFY THAT ALL DOWELS ARE IN PLACE AND PERPINDICULAR TO JOINT PRIOR TO POURING CONCRETE.

EXPANSION JOINT AND CUT-OFF WALL

NOT TO SCALE

7




NOTE: CONTRACTOR MAY USE ALTERNATE JOINT CONFIGURATION WITH WRITTEN APPROVAL FROM OWNER

KEY JOINT DETAIL

NOT TO SCALE


4



TRAPEZOIDAL CHANNEL WEEPHOLE

NOT TO SCALE

1




STEP LOCATIONS

STATIONS	
LT	RT
119+60.00	119+00.00
125+60.00	125+00.00
131+60.00	131+00.00
137+60.00	137+00.00
143+60.00	143+00.00
149+60.00	149+00.00
155+60.00	155+00.00
161+40.00	161+00.00
167+60.00	167+00.00
173+60.00	173+00.00
179+60.00	179+00.00
185+60.00	185+00.00

CHANNEL STEP DETAILS

NOT TO SCALE

11




NOTES:
1. THE INFORMATION SHOWN FOR THE SAHARA AVE CULVERT IS BASED ON THE DESIGN DRAWINGS FOR SID #94. CONTRACTOR TO VERIFY THE GEOMETRY & CONDITION OF THE CULVERT TIE IN LOCATIONS.
2. EXPANSION JOINT DETAIL IS SIMILAR AT BOTH UPSTREAM AND DOWNSTREAM ENDS OF BRIDGE AT SAHARA AVE.

EXPANSION JOINT

NOT TO SCALE


8



CONNECTION JOINT

NOT TO SCALE


5



RECTANGULAR CHANNEL WEEPHOLE

NOT TO SCALE


2



PIPE CONNECTION

NOT TO SCALE


9



APRON AT CHARLESTON BLVD BRIDGE

NOT TO SCALE

6



APRON AT ORCHARDS CHANNEL

NOT TO SCALE

3

DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

CHANNEL STRUCTURES DETAILS

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER — RIMAH I. NAZZAL — Exp. 12/31/2005 — CIVIL / STRUCTURAL — No. 12977 — STATE OF NEVADA


3/11/04

PROJECT No: 500-857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2291


SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-2
SHT. 25 OF 30



KEYED JOINT (1)
NOT TO SCALE





RECTANGULAR CHANNEL SECTION (STA 161+79.41, 41.00' LT TO STA 161+09.37, 80.14' LT) (STA 161+02.56, 95.72' LT TO STA 160+91.22, 121.68' LT) (B)
NOT TO SCALE

CHANNEL REACH	L1	L2	L3	L4	H1	H2
STA. 118+88.78 TO STA. 119+38.78	VARIES LINEARLY FROM 10.94' TO 7.3'	VARIES LINEARLY FROM 32.47' TO 30'	VARIES LINEARLY FROM 35.99' TO 30'	VARIES LINEARLY FROM 20.51' TO 12.3'	VARIES LINEARLY FROM 0' TO 2.37'	–
STA. 119+38.78 TO STA. 120+68.17	17.3'	30'	30'	12.3'	VARIES LINEARLY FROM 2.37' TO 1.63'	–
STA. 120+68.17 TO STA. 120+74.33	17.3'	30'	30'	VARIES LINEARLY FROM 12.3' TO 9.93'	VARIES LINEARLY FROM 1.63' TO 1.59'	–
STA. 120+74.33 TO STA. 120+96.22	17.3'	30'	30'	9.93'	VARIES LINEARLY FROM 1.59' TO 1.47'	–
STA. 120+96.22 TO STA. 121+02.78	17.3'	30'	30'	VARIES LINEARLY FROM 9.93' TO 12.3'	VARIES LINEARLY FROM 1.47' TO 1.43'	–
STA. 121+02.78 TO STA. 122+58.37	17.3'	30'	30'	12.3'	VARIES LINEARLY FROM 1.43' TO 0.54'	–
STA. 122+58.37 TO STA. 122+98.37	VARIES LINEARLY FROM 17.3' TO 12.3'	30'	30'	12.3'	VARIES LINEARLY FROM 0.54' TO 0'	–
STA. 122+98.37 TO STA. 130+97.58	12.3'	30'	30'	12.3'	–	–
STA. 130+97.58 TO STA. 131+75.00	VARIES LINEARLY FROM 12.3' TO 11.5'	30'	30'	VARIES LINEARLY FROM 12.3' TO 11.5'	–	–
STA. 131+75.00 TO STA. 158+50.00	11.5'	30'	30'	11.5'	–	–
STA. 158+50.00 TO STA. 159+00.00	VARIES LINEARLY FROM 11.5' TO 15.2'	30'	30'	VARIES LINEARLY FROM 11.5' TO 15.2'	–	–
STA. 159+00.00 TO STA. 160+29.41	15.2'	30'	30'	15.2'	–	–
STA. 160+29.41 TO STA. 160+62.41	VARIES LINEARLY FROM 15.2' TO 5.17'	VARIES LINEARLY FROM 30' TO 37.59'	VARIES LINEARLY FROM 30' TO 30.66'	VARIES LINEARLY FROM 15.2' TO 5.17'	VARIES LINEARLY FROM 0' TO 4.79'	VARIES LINEARLY FROM 0' TO 5'
STA. 163+29.41 TO STA. 165+61.82	11.5'	30'	30'	11.5'	–	–
STA. 165+61.82 TO STA. 165+72.82	11.5'	30'	30'	10.36'	–	–
STA. 165+72.82 TO STA. 171+98.47	11.5'	30'	30'	11.5'	–	–
STA. 172+86.31 TO STA. 174+00.00	13.2'	30'	30'	13.2'	–	–
STA. 174+00.00 TO STA. 174+50.00	13.2'	30'	30'	VARIES LINEARLY FROM 13.2' TO 11.63'	–	–
STA. 176+00.00 TO STA. 178+50.00	13.2'	30'	30'	13.2'	–	–
STA. 178+50.00 TO STA. 179+00.00	13.2'	30'	30'	VARIES LINEARLY FROM 13.2' TO 7'	–	VARIES LINEARLY FROM 0' TO 3.1'
STA. 179+00.00 TO STA. 182+17.17	13.2'	30'	30'	7'	–	3.1'
STA. 182+17.17 TO STA. 185+17.69	13.2'	30'	30'	7'	VARIES LINEARLY FROM 0' TO 2.7'	3.1'
STA. 185+17.69 TO STA. 186+54.00	13.2'	30'	30'	7'	VARIES LINEARLY FROM 2.7' TO 1.43'	3.1'
STA. 186+54.00 TO STA. 187+17.89	VARIES LINEARLY FROM 13.2' TO 15.9'	30'	30'	VARIES LINEARLY FROM 7' TO 19.67'	VARIES LINEARLY FROM 1.43' TO 0'	VARIES LINEARLY FROM 3.1' TO 0'

TYPICAL TRAPEZOIDAL CHANNEL SECTION (A)
NOT TO SCALE

DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES
TYPICAL CHANNEL SECTIONS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


RIMAH I. NAZZAL No. 12971 CIVIL STRUCTURAL — 3/11/04

PROJECT NAME: SLOAN DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-3
SHT. 26 OF 30



NOTE:
WEAKENED PLANE JOINTS AND VERTICAL WALL CONTRACTION JOINTS ARE NOT SHOWN BUT WILL BE REQUIRED AT MAXIMUM 60'-0" OC SPACING.


TYPICAL TRANSITION BETWEEN TRAPEZOIDAL AND RECTANGULAR CHANNEL (1)
1/8" = 1'-0"



NOTE:
FOR WEAKENED PLANE JOINTS & CUT OFF WALLS SEE DETAILS 2/S-1 4/S-1


CHANNEL REACH	L1	L2	L3	L4	H1	H2
STA. 160+62.41 TO STA. 160+71.41	VARIES LINEARLY FROM 5.17' TO 2.43'	VARIES LINEARLY FROM 37.59' TO 39.66'	VARIES LINEARLY FROM 30.66' TO 30.84'	VARIES LINEARLY FROM 5.17' TO 2.43'	VARIES LINEARLY FROM 4.79' TO 6.09'	VARIES LINEARLY FROM 5' TO 6.36'

TYPICAL TRANSITION SECTION (A)
3/8" = 1'-0"



CHANNEL REACH	L1	L2	L3	L4	H1	H2
STA. 162+79.41 TO STA. 163+29.41	VARIES LINEARLY FROM 0' TO 11.5'	VARIES LINEARLY FROM 41.5' TO 30'	VARIES LINEARLY FROM 49' TO 30'	VARIES LINEARLY FROM 0' TO 11.5'	VARIES LINEARLY FROM 7.25' TO 0'	VARIES LINEARLY FROM 8.53' TO 0'

PICAL TRANSITION SECTION (C)
= 3/8"



CHANNEL REACH	L1	L2	L3	L4	H1	H2
STA. 160+71.41 TO STA. 160+79.41	VARIES LINEARLY FROM 2.43' TO 0'	VARIES LINEARLY FROM 39.66' TO 41.5'	VARIES LINEARLY FROM 30.84' TO 31'	VARIES LINEARLY FROM 2.43' TO 0'	VARIES LINEARLY FROM 6.09' TO 7.25'	VARIES LINEARLY FROM 6.36' TO 7.57'

TYPICAL TRANSITION SECTION (B)
3/8" = 1'-0"

DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES
CHANNEL TRANSITION STRUCTURES
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA
RIMAH I. NAZZAL
No. 12977
Exp. 12/31/2005
CIVIL / STRUCTURAL
3/11/04

PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK


L-1759
DRAWING NO.
S-4
SHT. 27 OF 30



SECTION
3/8" = 1'-0"


* SEE DETAIL (2/—)

(B/—)



DETAIL
1/4" = 1'-0"


(2/—)



POINT	Ⓐ	Ⓑ	Ⓒ	Ⓓ	Ⓔ	Ⓕ	Ⓖ
RAMP 1	STA: 174+50.99	STA. 174+52.04	STA. 174+63.24	STA. 175+25.23	STA. 175+23.35	STA. 176+00.00	STA. 176+00.00
	OFFSET: 41.47' LT	OFFSET: 54.47' LT	OFFSET: 52.69' LT	OFFSET: 41.85' LT	OFFSET: 30.00' LT	OFFSET: 30.00' LT	OFFSET: 43.20' LT
	EL = 1703.83	EL = 1704.07	EL = 1703.62	EL = 1700.83 TW EL = 1697.13 TOE	EL = 1696.89	EL = 1696.54	EL = 1703.14

PLAN - TRAPEZOIDAL CHANNEL ACCESS RAMP
1/16" = 1'-0"


(1/—)



CHANNEL REACH	L1	L2	H1	H2
STA. 160+79.41 TO STA. 161+59.19	41.5'	31'	7.25'	VARIES LINEARLY FROM 7.57' TO 7.96'
STA. 161+59.19 TO STA. 161+79.41	41.5'	31'	7.25'	VARIES LINEARLY FROM 7.96' TO 7.76'
STA. 161+79.41 TO STA. 162+25.00	41.5'	49'	7.25'	VARIES LINEARLY FROM 7.76' TO 8.53'
STA. 162+25.00 TO STA. 162+79.41	41.5'	49'	7.25'	8.53'

RECTANGULAR CHANNEL SECTION
3/8" = 1'-0"

(A/—)



CHANNEL TRANSITION SECTION
1/2" = 1'-0"

(C/—)

DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES
ACCESS RAMP
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA — RIMAH I. NAZZAL — Exp. 12/31/2005 — CIVIL / STRUCTURAL — No. 12971
3/11/04

PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-5
SHT. 28 OF 30




TRANSITION SECTION
3/8" = 1'-0"


STA 160+89.62, 125.34'LT TO STA 160+91.22, 121.68'LT (C)



SECTION
1/2" = 1'-0" (D)




HEADWALL DETAIL 1
1/2" = 1'-0"



TRANSITION SECTION
3/8" = 1'-0"

STA 160+83.21, 140.01'LT TO STA 160+88.02, 129.01'LT (A)



TRANSITION SECTION
3/8" = 1'-0"

STA 160+88.02, 129.01'LT TO STA 160+89.62, 125.34'LT (B)

DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
ACCESS RAMP
DETAILS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


RIMAH I. NAZZAL — Exp. 12/31/2004 — CIVIL / STRUCTURAL — No. 12971 — STATE OF NEVADA — PROFESSIONAL ENGINEER
3/11/04

PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RN CHECKED BY: RIN
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE	
HORIZ:	NONE
VERT:	NONE
FIELD BOOK	

L-1759
DRAWING NO. S-6
SHT. 29 OF 30




SECTION D-D



RCB INLET DETAILS

NOT TO SCALE


3



DETAIL

NOT TO SCALE

B




SIDE DRAIN	L1	L2	L3	L4
1	29.15' TO 28.40'	10.00'	10.00'	29.10' TO 28.40'
2	24.20' TO 25.21'	17.05' TO 18.66'	18.72' TO 20.23'	22.07' TO 24.21'

CHANNEL SECTION

NOT TO SCALE

A




PLAN - TYPE 2 SIDE DRAIN

NOT TO SCALE

2

NOTE:
SEE CIVIL DRAWINGS FOR ELEVATIONS AND INFORMATION NOT SHOWN

	STA "A"	BEARING "A"	BEARING "B"
SIDE DRAIN 1	120+84.85	N 71°07'11" E (R)	N 71°50'27" E
SIDE DRAIN 2	127+33.01	N 63°30'25" E (R)	N 63°33'08" E



PLAN - TYPE 1 SIDE DRAIN

NOT TO SCALE

1

DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES
DETAILS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER STATE OF NEVADA
RIMAH I. NAZZAL
Exp. 12/31/2005
CIVIL STRUCTURAL
No. 12977
3/11/04

PROJECT No: 500.857 DRAWN BY: RB/MD/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-7
SHT. 30 OF 30

Appendix F: Reference Material

CC NV INCORPORATED AREAS Volume I

TECHNICAL SUPPORT DATA NOTEBOOK

for

CLARK COUNTY, NEVADA AND INCORPORATED AREAS
INCLUDING:
CITY OF NORTH LAS VEGAS
AND
UNINCORPORATED AREAS OF CLARK COUNTY


RANGE WASH
FLOOD INSURANCE STUDY RESTUDY

VOLUME 1

SECTION 1 GENERAL DOCUMENTATION
SECTION 2 ENGINEERING ANALYSES
SECTION 3 DRAFT FIS REPORT TEXT
SECTION 4 MAPPING INFORMATION
SECTION 5 REFERENCE MATERIALS
Data Collection Summary Memorandum
& Photo Log

Submitted by:	**Clark County Regional Flood Control District**
Study Contractor:	**Post, Buckley, Schuh & Jernigan, Inc.**
Date Submitted:	**February 27, 1996**

FIGURE 5A: Drainage Basins



LEGEND

Drainage Basins

Detention Basins

Concentration Point ID


49A-M Basin ID

GRAPHIC SCALE

2 1.5 1 0.5 0 1 2


(IN MILES)

SCALE:1 Inch = 7800 feet



LIMITS OF STUDY AREA

POST, BUCKLEY, SCHUH & JERNIGAN



DFIRM 1995

POST, BUCKLEY, SCHUH & JERNIGAN
ENGINEERING • PLANNING • SURVEYING • CONSTRUCTION SERVICES

RFIS-CC.OUT

```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10
          *DIAGRAM
** FREE ***
    1     ID                    RANGE WASH - FLOOD INSURANCE RESTUDY
    2     ID              FOR: CLARK COUNTY REGIONAL FLOOD CONTROL DISTRICT
    3     ID                  BY: POST, BUCKLEY, SCHUH & JERNIGAN, INC.
    4     ID                              JOB. NO. 51804
    5     ID                          HEC-1 FILE: RFIS-CC.DAT
    6     ID                               DECEMBER 1995
    7     ID
    8     ID                    EXISTING CONDITIONS DOWNSTREAM OF THE
    9     ID           CONFLUENCE DETENTION BASIN, CURRENTLY UNDER CONSTRUCTION.
   10     ID         STORM CENTERING FOR NODE V2, AT SLOAN CHANNEL DOWNSTREAM OF STEWART,
   11     ID         AND FOR NODE CC, AT THE SLOAN CHANNEL AND LAS VEGAS WASH CONFLUENCE.
   12     ID
   13     ID    ********************************************************************************
   14     ID    *              FROM: CCRFCD LAS VEGAS VALLEY MASTER PLAN UPDATE                  *
   15     ID    *                           RANGE WASH WATERSHED                                 *
   16     ID    *                JAMES M. MONTGOMERY, CONSULTING ENGINEERS, INC.                 *
   17     ID    *                                 JANUARY 1991                                   *
   18     ID    *                  PRESENT CONDITIONS, EXISTING FACILITIES                      *
   19     ID    *                   BASED ON RANGE WASH FACILITIES STUDY                        *
   20     ID    *                      BOYLE ENGINEERS CORP-JULY 1989                           *
   21     ID    *                                                                               *
   22     ID    *                   (CONVERTED RK TO RM IN UPLAND SUBAREAS)                     *
   23     ID    *MODIFIED TO REMOVE SUBAREAS TRIBUTARY TO WEST RANGE DIVERSION DIKE (1/91)*
   24     ID    ********************************************************************************
   25     ID    *                        100-YEAR, 6-HOUR STORM, AMC 2.0                         *
   26     ID    ********************************************************************************
   27     ID    * STORM DISTRIBUTION 5 (SDN 5) FOR TOTAL BASIN AREA GREATER THAN 10 SQ.MI.*
   28     ID    *  ONLY FOR DRAINAGE BASINS DOWNSTREAM OF CONFLUENCE THE DETENTION BASIN, *
   29     ID    *  JR DARF RATIO 0.85 FOR NODE V2, AT SLOAN CHANNEL DOWNSTREAM OF STEWART *
   30     ID    *  AND 0.82 FOR NODE CC, AT THE SLOAN CHANNEL/LAS VEGAS WASH CONFLUENCE.  *
   31     ID    ********************************************************************************
   32     ID
   33     IT      05       0       0     200
   34     IO       5       0       0
   35     JR    PREC    0.85    0.82

   36     KK    318C
   37     KM    BASIN 318C CONTRIBUTES FLOW TO NODE M1.
   38     KM    NODE M1 GIVES THE TOTAL FLOW IN THE SLOAN CHANNEL JUST UPSTREAM OF
   39     KM    THE CONFLUENCE WITH THE RANGE WASH CHANNEL.
   40     BA     1.28
   41     PB     2.93
   42     PC    .000    .020    .059    .080    .110    .144    .150    .160    .168    .171
   43     PC    .180    .182    .187    .190    .197    .202    .210    .220    .230    .241
   44     PC    .250    .259    .265    .280    .290    .300    .305    .309    .310    .317
   45     PC    .321    .327    .333    .346    .361    .381    .408    .430    .477    .514
   46     PC    .561    .630    .710    .720    .731    .752    .779    .790    .795    .804
   47     PC    .810    .820    .826    .840    .859    .889    .910    .938    .966    .970
   48     PC    .974    .979    .981    .983    .985    .989    .990    .992    .993    .996
   49     PC    .997    .999   1.00
   50     LS      0      79
   51     UD   0.75
          *
```

```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

  52      KK   321-M
  53      KM   BASIN 321-M CONTRIBUTES FLOW TO THE RANGE WASH CHANNEL UPSTREAM OF
  54      KM   ITS CONFLUENCE WITH THE SLOAN CHANNEL.
  55      BA   0.691
  56      PB    2.77
  57      LS       0      67
  58      UD    1.66
          *

  59      KK NODE.M3
  60      KM   COMBINE FLOWS FROM M1 AND M2 AT NODE M3.
  61      KM   NODE M3 IS THE TOTAL FLOW AT THE CONFLUENCE OF THE SLOAN CHANNEL
  62      KM   AND THE RANGE WASH CHANNEL AT SLOAN AND CAREY AVENUE.
  63      HC       2
          *

  64      KK   M3-S1
  65      KM   ROUTE FLOW FROM NODE M3 THROUGH THE SLOAN CHANNEL TO NODE S1.
  66      RK    2640   0.004   0.015       0    TRAP       40       3
          *

  67      KK   48A-M
  68      KM   BASIN 48A-M CONTRIBUTES FLOW TO NODE S1.
  69      BA   0.715
  70      PB    2.93
  71      LS       0      83
  72      UD    0.44
          *

  73      KK      S1
  74      KM   COMBINE FLOW FROM M3 WITH FLOW FROM BASIN 48A-M.
  75      KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL AT LAKE MEAD BLVD.
  76      HC       2
          *

  77      KK   S1-S2
  78      KM   ROUTE FLOW FROM S1 THROUGH THE SLOAN CHANNEL TO S2.
  79      RK    2640   0.002   0.015       0    TRAP       50       2
          *

  80      KK     48B
  81      KM   BASIN 48B CONTRIBUTES FLOW TO NODE R.
  82      BA   1.142
  83      PB    3.10
  84      LS       0      89
  85      UD    0.51
          *

  86      KK    R-S2
  87      KM   ROUTE FLOW FROM R THROUGH BASIN 49A-M TO NODE S2.
  88      RK   10500   0.022    0.02       0    TRAP       10      20
          *
```

```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

  89      KK   49A-M
  90      KM   BASIN 49A-M CONTRIBUTES FLOW TO NODE S2.
  91      BA   0.693
  92      PB    2.85
  93      LS       0      79
  94      UD    0.49
          *

  95      KK NODE.S2
  96      KM   COMBINE FLOW FROM NODES S1 AND R WITH FLOW FROM BASIN 49A-M AT NODE S2.
  97      KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL AT OWENS AVENUE.
  98      HC       3
          *

  99      KK   S2-S3
 100      KM   ROUTE FLOW FROM S2 THROUGH THE SLOAN CHANNEL TO S3.
 101      RK    2640   0.004   0.014       0    TRAP      60       2
          *

 102      KK     49C
 103      KM   BASIN 49C CONTRIBUTES FLOW TO NODE S3.
 104      BA   0.426
 105      PB    2.85
 106      LS       0      76
 107      UD    0.53
          *

 108      KK NODE.S3
 109      KM   COMBINE FLOW FROM S2 WITH FLOW FROM BASIN 49C AT NODE S3.
 110      KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL AT WASHINGTON AVE.
 111      HC       2
          *

 112      KK   49B-M
 113      KM   BASIN 49B-M CONTRIBUTES FLOW TO NODE T1.
 114      KM   NODE T1 REPRESENTS THE TOTAL FLOW TO THE DIVERSION CHANNEL ALONG
 115      KM   WASHINGTON AVE. JUST UPSTREAM OF THE SLOAN CHANNEL.
 116      BA   1.977
 117      PB    3.00
 118      LS       0      85
 119      UD    0.61
          *

 120      KK NODE.S4
 121      KM   COMBINE FLOW FROM S3 WITH FLOW FROM T1 AT NODE S4.
 122      KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL AT HARRIS AVE.
 123      HC       2
          *
```

```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

  124     KK   50B-M
  125     KM   BASIN 50B-M CONTRIBUTES FLOW TO NODE V1.
  126     BA   0.628
  127     PB    3.00
  128     LS       0      80
  129     UD    0.39
          *

  130     KK NODE.V1
  131     KM   COMBINE FLOW FROM S4 WITH FLOW FROM BASIN 50B-M AT NODE V1.
  132     KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL AT BONANZA RD.
  133     HC       2
          *

  134     KK   V1-V2
  135     KM   ROUTE FLOWS FROM V1 THROUGH THE SLOAN CHANNEL TO NODE V2.
  136     RK    2640   0.008   0.014       0    TRAP      60       2
          *

  137     KK   50A-M
  138     KM   BASIN 50A-M CONTRIBUTES FLOW TO NODE V2.
  139     BA   0.207
  140     PB    2.85
  141     LS       0      73
  142     UD    0.46
          *

  143     KK NODE.V2
  144     KM   COMBINE FLOW FROM V1 WITH FLOW FROM BASIN 50A-M AT NODE V2.
  145     KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL AT STEWART AVE.
  146     HC       2
          *

  147     KK   324-M
  148     KM   BASIN 324-M CONTRIBUTES FLOW TO NODE V3.
  149     BA   3.026
  150     PB    2.85
  151     LS       0      72
  152     UD    0.77
          *

  153     KK    STEW
  154     KM   DIVERT FLOWS WHICH CONTINUE IN CHRISTY & LINN LANES, ETC
  155     KM   FLOW IN STEWART GOES TO SLOAN CHANNEL
  156     KM   FLOW IN CHRISTY GOES TOWARD LAS VEGAS WASH
  157     DT      CL
  158     DI       0      15     600
  159     DQ       0       0     330
          *
```

```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

  160     KK NODE.V3
  161     KM   COMBINE FLOW FROM V2 WITH FLOW FROM BASIN 324-M AT NODE V3.
  162     KM   GIVES TOTAL FLOW IN THE SLOAN CHANNEL
  163     KM   SOUTH OF STEWART AVE.
  164     HC       2
          *

  165     KK   V3-V4
  166     KM   ROUTE V3 THROUGH THE SLOAN CHANNEL TO V4.
  167     RK    2000   0.003    0.03       0    TRAP      80       2
          *

  168     KK     CLR
  169     KM   RETREIVE FLOW IN CHRISTY AND LINN LANES
  170     DR      CL
          *

  171     KK    LINN
  172     KM   FLOW IN LINN LANE GOES TO BASIN 326-A THEN TO SLOAN CHANNEL
  173     KM   FLOW IN CHRISTY GOES TO LAS VEGAS WASH
  174     DT   CHRIS
  175     DI       0     100     500
  176     DQ       0      78     390
          *

  177     KK   326-A
  178     KM   BASIN 326-A CONTRIBUTES FLOW TO NODE V4.
  179     KM   GIVES TOTAL FLOW IN THE SECTION OF CHARLESTON BLVD. WEST OF SLOAN CHANNEL.
  180     BA   0.231
  181     PB    2.85
  182     LS       0      79
  183     UD    0.39
          *

  184     KK  326-AL
  185     KM   BASIN 326-A AND FLOW IN LINN LANE
  186     HC       2
          *

  187     KK    OR-1
  188     KM   ORCHARDS OFFSITE DRAINAGE BASIN 01; CONTRIBUTES FLOW TO NODE X1.
  189     KM   * BASINS WITH THE "OR" PREFIX ARE TAKEN FROM THE "CONCEPTUAL MASTER        *
  190     KM   * DRAINAGE STUDY FOR LEWIS HOMES - ORCHARDS," BY PENTACORE, JANUARY, 1992. *
  191     KM   * THE MAJORITY OF THE ORCHARDS SITE IS CONSTRUCTED; HOWEVER, THE PLANNED   *
  192     KM   * ORCHARDS DETENTION BASIN IS NOT CONSTRUCTED. HYDROLOGY FROM THE ORCHARDS *
  193     KM   * DRAINAGE STUDY HAS BEEN MODIFIED TO REPRESENT APPROXIMATE EXISTING       *
  194     KM   * CONDITIONS, RATHER THAN FULLY DEVELOPED CONDITIONS.                      *
  195     PB    3.00
  196     BA   0.279
  197     LS       0      89
  198     UD    0.18
          *
```

```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

  199     KK   X1-X2
  200     KM   ROUTE X1 THROUGH BASIN OR-2 TO NODE X2.
  201     RK   10000   0.033    0.02       0    TRAP      20       10
          *

  202     KK    OR-2
  203     KM   ORCHARDS OFFSITE DRAINAGE BASIN 02; CONTRIBUTES FLOW TO NODE X2.
  204     BA   1.206
  205     PB    2.93
  206     LS       0       75
  207     UD    0.60
          *

  208     KK NODE.X2
  209     KM   COMBINE FLOW FROM X1 AND BASIN OR-2 AT NODE X2.
  210     KM   GIVES TOTAL FLOW IN THE SECTION OF CHARLESTON BLVD. EAST OF SLOAN CHANNEL.
  211     HC       2
          *

  212     KK NODE.V4
  213     KM   COMBINE FLOW FROM V3, X2 AND BASIN 326-A.
  214     KM   GIVES TOTAL FLOW TO THE SLOAN CHANNEL AT CHARLESTON BLVD.
  215     HC       3
          *

  216     KK   OR-11
  217     KM   ORCHARDS ONSITE BASIN OR-11 CONTRIBUTES FLOW TO NODE V5.
  218     BA  0.0428
  219     PB    2.85
  220     LS       0       75
  221     UD    0.20
          *

  222     KK NODE.V5
  223     KM   COMBINE FLOW FROM V4 AND BASIN OR-11.
  224     KM   TOTAL FLOW TO THE SLOAN CHANNEL APPROX. 1500 FT. SOUTH OF CHARLESTON BLVD.
  225     HC       2
          *

  226     KK   V5-Z2
  227     KM   ROUTE V5 THROUGH SLOAN CHANNEL TO THE ORCHARDS CHANNEL CONFLUENCE AT Z2.
  228     RK    2800   0.005    0.03       0    TRAP      60       2
          *

  229     KK    OR-3
  230     KM   ORCHARDS OFFSITE DRAINAGE BASIN 03.
  231     KM   GIVES FLOW TO NODE Y1, LOCATED AT CHARLESTON WEST OF HOLLYWOOD.
  232     BA   0.205
  233     PB    3.00
  234     LS       0       82
  235     UD    0.42
          *
```

```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

  236     KK   Y1-Z1
  237     KM   ROUTE NODE Y1 THROUGH BASIN OR-12 TO NODE Z1.
  238     RK    5500   0.011   0.016       0    TRAP      50       1
          *

  239     KK    OR-4
  240     KM   ORCHARDS OFFSITE DRAINAGE BASIN 04.
  241     KM   CONTRIBUTES FLOW TO NODE Y2.
  242     BA   0.448
  243     PB    3.00
  244     LS       0      88
  245     UD    0.29
          *

  246     KK   Y2-Y3
  247     KM   ROUTE NODE Y2 THROUGH BASIN OR-5 TO NODE Y3.
  248     RM       4    0.33    0.15
          *

  249     KK    OR-5
  250     KM   ORCHARDS OFFSITE DRAINAGE BASIN 05.
  251     KM   CONTRIBUTES FLOW TO NODE Y3.
  252     BA   0.373
  253     PB    3.00
  254     LS       0      77
  255     UD    0.44
          *

  256     KK      Y3
  257     KM   COMBINE FLOWS FROM Y2 AND BASIN OR-5 AT HOLLYWOOD.
  258     HC       2
          *

  259     KK   Y3-Z1
  260     KM   ROUTE Y3 THROUGH BASIN OR-12 TO NODE Z1.
  261     RK    5000   0.012   0.016       0    TRAP      50       1
          *

  262     KK   OR-6A
  263     KM   ORCHARDS OFFSITE DRAINAGE BASIN 06A.
  264     BA   0.264
  265     PB    3.00
  266     LS       0      88
  267     UD     .13
          *

  268     KK   OR-6B
  269     KM   ORCHARDS OFFSITE DRAINAGE BASIN 06B,
  270     BA   0.160
  271     PB    3.00
  272     LS       0      89
  273     UD     .14
          *
```

```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

  274     KK   OR-6C
  275     KM   ORCHARDS OFFSITE DRAINAGE BASIN 06C.
  276     BA   0.191
  277     PB    3.00
  278     LS      0      87
  279     UD    .18
          *

  280     KKNODE.AA1
  281     KM   COMBINE FLOWS FROM BASINS OR-6A, OR-6B & OR-6C.
  282     HC      3
          *

  283     KK AA1-AA2
  284     KM   ROUTE AA1 THROUGH BASIN OR-7 TO NODE AA2.
  285     RM      4    0.32    0.15
          *

  286     KK    OR-7
  287     KM   ORCHARDS OFFSITE DRAINAGE BASIN 07.
  288     BA   0.613
  289     PB    3.00
  290     LS      0      77
  291     UD    0.49
          *

  292     KKNODE.AA2
  293     KM   COMBINE AA1 WITH FLOW FROM BASIN OR-7 AT NODE AA2.
  294     HC      2
          *

  295     KK  AA2-Z1
  296     KM   ROUTE AA2 THROUGH BASIN OR-12 TO NODE Z1.
  297     RK    4500   0.013   0.016      0    TRAP      50       1
          *

  298     KK    OR-8
  299     KM   ORCHARDS OFFSITE BASIN 08; CONTRIBUTES FLOW TO NODE AA3.
  300     BA   0.017
  301     PB    3.00
  302     LS      0      77
  303     UD   0.18
          *

  304     KK  R8-AA3
  305     KM   ROUTE FLOW FROM BASIN OR-8 THROUGH BASIN OR-9 TO NODE AA3 AT HOLLYWOOD.
  306     RM     10    0.82    0.15
          *
```

```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

  307     KK    OR-9
  308     KM   ORCHARDS OFFSITE DRAINAGE BASIN 09; CONTRIBUTES FLOW TO NODE AA3.
  309     BA   0.278
  310     PB    3.00
  311     LS       0      77
  312     UD    0.65
          *

  313     KKNODE.AA3
  314     KM   COMBINE FLOWS FROM BASINS OR-8 AND OR-9 AT NODE AA3.
  315     HC       2
          *

  316     KK  AA3-Z1
  317     KM   ROUTE AA3 THROUGH BASIN OR-12 TO NODE Z1.
  318     RK    4500   0.012   0.016       0    TRAP      50       1
          *

  319     KK   OR-12
  320     KM   ORCHARDS ONSITE DRAINAGE BASIN 12; CONTRIBUTES FLOW TO NODE Z1.
  321     BA   0.525
  322     PB    2.85
  323     LS       0      76
  324     UD    0.39
          *

  325     KK NODE.Z1
  326     KM   COMBINE FLOW FROM NODES Y1, Y3, AA2, AA3 AND BASIN OR-12 AT NODE Z1.
  327     KM   NODE Z1 REPRESENTS THE TOTAL FLOW IN THE CONCRETE-LINED ORCHARDS CHANNEL
  328     KM   TRIBUTARY TO THE SLOAN CHANNEL.
  329     HC       5
          *

  330     KK NODE.Z2
  331     KM   COMBINE FLOW FROM NODES V5 AND Z1.
  332     KM   TOTAL FLOW IN THE SLOAN CHANNEL AT ITS CONFLUENCE WITH THE ORCHARDS CHANNEL.
  333     HC       2
          *

  334     KK   OR-13
  335     KM   ORCHARDS ONSITE DRAINAGE BASIN OR-13; CONTRIBUTES FLOW TO NODE Z3.
  336     BA   0.120
  337     PB    2.85
  338     LS       0      84
  339     UD    0.29
          *

  340     KK NODE.Z3
  341     KM   COMBINE FLOW FROM NODES Z2 AND BASIN OR-13 AT NODE Z3.
  342     KM   NODE Z3 IS THE TOTAL FLOW IN THE SLOAN CHANNEL AT APPROXIMATELY
  343     KM   450 FEET SOUTH OF THE ORCHARDS CHANNEL CONFLUENCE.
  344     HC       2
          *
```

```
LINE      ID.....1.....2.....3.....4.....5.....6.....7.....8.....9.....10

  345     KK   OR-10
  346     KM   ORCHARDS OFFSITE DRAINAGE BASIN O10.
  347     KM   CONTRIBUTES FLOW TO NODE BB1, LOCATED AT THE HOLLYWOOD/SAHARA INTERSECTION.
  348     BA  0.0984
  349     PB   3.00
  350     LS      0      77
  351     UD   0.45
          *

  352     KK BB1-BB2
  353     KM   ROUTE BB1 THROUGH SAHARA AVENUE TO NODE BB2.
  354     RK    4000   0.014   0.016       0    TRAP     100       1
          *

  355     KK   OR-14
  356     KM   ORCHARDS ONSITE DRAINAGE BASIN 14; CONTRIBUTES FLOW TO NODE BB2.
  357     BA  0.0937
  358     PB   2.85
  359     LS      0      75
  360     UD   0.33
          *

  361     KKNODE.BB2
  362     KM   NODE BB2 REPRESENTS THE TOTAL FLOW IN SAHARA AVE. EAST OF THE SLOAN CHANNEL.
  363     HC      2
          *

  364     KKNODE.BB3
  365     KM   COMBINE FLOW FROM Z3 WITH FLOW FROM BB2.
  366     KM   NODE BB3 IS THE TOTAL FLOW IN SLOAN CHANNEL AT SAHARA AVE.
  367     HC      2
          *

  368     KK  BB3-CC
  369     KM   ROUTE BB3 THROUGH THE SLOAN CHANNEL TO NODE CC.
  370     RK    1700   0.006   0.025       0    TRAP      80       2
          *

  371     KK   52A-M
  372     KM   BASIN 52A-M CONTRIBUTES FLOW TO NODE CC.
  373     BA   0.286
  374     PB   2.85
  375     LS      0      73
  376     UD   0.84
          *


  377     KK NODE.CC
  378     KM   COMBINE FLOW FROM  NODE BB3 WITH FLOW FROM BASINS 326-B AND 52A-M.
  379     KM   NODE CC REPRESENTS THE TOTAL FLOW IN THE SLOAN CHANNEL JUST UPSTREAM OF
  380     KM   ITS CONFLUENCE WITH THE LAS VEGAS WASH.
  381     HC      2
          *
  382     ZZ
```


1


SCHEMATIC DIAGRAM OF STREAM NETWORK

INPUT LINE NO.

(V) ROUTING
(.) CONNECTOR
(---->) DIVERSION OR PUMP FLOW
(<----) RETURN OF DIVERTED OR PUMPED FLOW




157
153
STEW
CL
160
NODE.V3
165
V3-V4
170
168
CLR
CL
174
171
LINN
CHRIS
177
326-A
184
326-AL
187
OR-1
199
X1-X2
202
OR-2
208
NODE.X2
212
NODE.V4
216
OR-11
222
NODE.V5
226
V5-Z2
229
OR-3
236
Y1-Z1
239
OR-4
246
Y2-Y3
249
OR-5
256
Y3
259
Y3-Z1


262
OR-6A
268
OR-6B
274
OR-6C
280
NODE.AA1
283
AA1-AA2
286
OR-7
292
NODE.AA2
295
AA2-Z1
298
OR-8
304
R8-AA3
307
OR-9
313
NODE.AA3
316
AA3-Z1
319
OR-12
325
NODE.Z1
330
NODE.Z2
334
OR-13
340
NODE.Z3
345
OR-10
352
BB1-BB2
355
OR-14
361
NODE.BB2
364
NODE.BB3
368
BB3-CC

```
                .
371             .       52A-M
                .         .
                .         .
377     NODE.CC.............
```

(***) RUNOFF ALSO COMPUTED AT THIS LOCATION

```
*****************************************
*                                       *
*   FLOOD HYDROGRAPH PACKAGE  (HEC-1)   *
*             SEPTEMBER 1990            *
*              VERSION 4.0              *
*                                       *
*   RUN DATE  01/12/1996  TIME  09:54:56 *
*                                       *
*****************************************
```


```
*****************************************
*                                       *
*    U.S. ARMY CORPS OF ENGINEERS       *
*    HYDROLOGIC ENGINEERING CENTER      *
*          609 SECOND STREET            *
*       DAVIS, CALIFORNIA 95616         *
*          (916) 756-1104               *
*                                       *
*****************************************
```


RANGE WASH - FLOOD INSURANCE RESTUDY
FOR: CLARK COUNTY REGIONAL FLOOD CONTROL DISTRICT
BY: POST, BUCKLEY, SCHUH & JERNIGAN, INC.
JOB. NO. 51804
HEC-1 FILE: RFIS-CC.DAT
DECEMBER 1995

EXISTING CONDITIONS DOWNSTREAM OF THE
CONFLUENCE DETENTION BASIN, CURRENTLY UNDER CONSTRUCTION.
STORM CENTERING FOR NODE V2, AT SLOAN CHANNEL DOWNSTREAM OF STEWART,
AND FOR NODE CC, AT THE SLOAN CHANNEL AND LAS VEGAS WASH CONFLUENCE.

```
*************************************************************************
*             FROM: CCRFCD LAS VEGAS VALLEY MASTER PLAN UPDATE          *
*                          RANGE WASH WATERSHED                         *
*                 JAMES M. MONTGOMERY, CONSULTING ENGINEERS, INC.       *
*                          JANUARY 1991                                 *
*                   PRESENT CONDITIONS, EXISTING FACILITIES             *
*                    BASED ON RANGE WASH FACILITIES STUDY               *
*                       BOYLE ENGINEERS CORP-JULY 1989                  *
*                                                                       *
*                   (CONVERTED RK TO RM IN UPLAND SUBAREAS)             *
*MODIFIED TO REMOVE SUBAREAS TRIBUTARY TO WEST RANGE DIVERSION DIKE (1/91)*
*************************************************************************
*                      100-YEAR, 6-HOUR STORM, AMC 2.0                  *
*************************************************************************
* STORM DISTRIBUTION 5 (SDN 5) FOR TOTAL BASIN AREA GREATER THAN 10 SQ.MI.*
*  ONLY FOR DRAINAGE BASINS DOWNSTREAM OF CONFLUENCE THE DETENTION BASIN, *
*  JR DARF RATIO 0.85 FOR NODE V2, AT SLOAN CHANNEL DOWNSTREAM OF STEWART *
*  AND 0.82 FOR NODE CC, AT THE SLOAN CHANNEL/LAS VEGAS WASH CONFLUENCE.  *
*************************************************************************
```

```
34 IO          OUTPUT CONTROL VARIABLES
                    IPRNT          5  PRINT CONTROL
                    IPLOT          0  PLOT CONTROL
                    QSCAL          0.  HYDROGRAPH PLOT SCALE

   IT          HYDROGRAPH TIME DATA
                     NMIN          5  MINUTES IN COMPUTATION INTERVAL
                    IDATE      1   0  STARTING DATE
                    ITIME       0000  STARTING TIME
                       NQ        200  NUMBER OF HYDROGRAPH ORDINATES
                   NDDATE      1   0  ENDING DATE
                   NDTIME       1635  ENDING TIME
                    ICENT         19  CENTURY MARK

                 COMPUTATION INTERVAL      .08 HOURS
                      TOTAL TIME BASE    16.58 HOURS

       ENGLISH UNITS
            DRAINAGE AREA         SQUARE MILES
            PRECIPITATION DEPTH   INCHES
            LENGTH, ELEVATION     FEET
            FLOW                  CUBIC FEET PER SECOND
            STORAGE VOLUME        ACRE-FEET
            SURFACE AREA          ACRES
            TEMPERATURE           DEGREES FAHRENHEIT

   JP          MULTI-PLAN OPTION
                    NPLAN          1  NUMBER OF PLANS

   JR          MULTI-RATIO OPTION
                   RATIOS OF PRECIPITATION
                   .85       .82
```

1

PEAK FLOW AND STAGE (END-OF-PERIOD) SUMMARY FOR MULTIPLE PLAN-RATIO ECONOMIC COMPUTATIONS
FLOWS IN CUBIC FEET PER SECOND, AREA IN SQUARE MILES
TIME TO PEAK IN HOURS

OPERATION	STATION	AREA	PLAN		RATIOS APPLIED TO PRECIPITATION RATIO 1 .85	RATIO 2 .82
HYDROGRAPH AT						
+	318C	1.28	1	FLOW	312.	290.
				TIME	4.25	4.25
HYDROGRAPH AT						
+	321-M	.69	1	FLOW	45.	41.
				TIME	5.92	5.92
2 COMBINED AT						
+	NODE.M3	1.97	1	FLOW	323.	299.
				TIME	4.25	4.25
ROUTED TO						
+	M3-S1	1.97	1	FLOW	322.	298.
				TIME	4.25	4.25
HYDROGRAPH AT						
+	48A-M	.71	1	FLOW	290.	272.
				TIME	3.83	3.83
2 COMBINED AT						
+	S1	2.69	1	FLOW	545.	507.
				TIME	4.00	4.08
ROUTED TO						
+	S1-S2	2.69	1	FLOW	545.	507.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	48B	1.14	1	FLOW	627.	596.
				TIME	3.92	3.92
ROUTED TO						
+	R-S2	1.14	1	FLOW	621.	589.
				TIME	4.00	4.08
HYDROGRAPH AT						
+	49A-M	.69	1	FLOW	200.	185.
				TIME	3.92	3.92
3 COMBINED AT						
+	NODE.S2	4.52	1	FLOW	1352.	1268.
				TIME	4.00	4.08
ROUTED TO						
+	S2-S3	4.52	1	FLOW	1351.	1268.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	49C	.43	1	FLOW	96.	88.
				TIME	4.00	4.00
2 COMBINED AT						
+	NODE.S3	4.95	1	FLOW	1445.	1355.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	49B-M	1.98	1	FLOW	788.	742.
				TIME	4.00	4.00

2 COMBINED AT						
+	NODE.S4	6.92	1	FLOW	2225.	2090.
				TIME	4.08	4.08
HYDROGRAPH AT						
•	50B-M	.63	1	FLOW	237.	221.
				TIME	3.75	3.75
2 COMBINED AT						
•	NODE.V1	7.55	1	FLOW	2420.	2270.
				TIME	4.00	4.00
ROUTED TO						
+	V1-V2	7.55	1	FLOW	2409.	2262.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	50A-M	.21	1	FLOW	40.	36.
				TIME	3.92	3.92
2 COMBINED AT						
•	NODE.V2	7.76	1	FLOW	2446.	2296.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	324-M	3.03	1	FLOW	407.	368.
				TIME	4.33	4.33
DIVERSION TO						
•	CL	3.03	1	FLOW	221.	199.
				TIME	4.33	4.33
HYDROGRAPH AT						
+	STEW	3.03	1	FLOW	186.	169.
				TIME	4.33	4.33
2 COMBINED AT						
+	NODE.V3	10.78	1	FLOW	2618.	2450.
				TIME	4.08	4.08
ROUTED TO						
+	V3-V4	10.78	1	FLOW	2610.	2442.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	CLR	.00	1	FLOW	221.	199.
				TIME	4.33	4.33
DIVERSION TO						
+	CHRIS	.00	1	FLOW	172.	155.
				TIME	4.33	4.33
HYDROGRAPH AT						
+	LINN	.00	1	FLOW	49.	44.
				TIME	4.33	4.33
HYDROGRAPH AT						
+	326-A	.23	1	FLOW	74.	68.
				TIME	3.75	3.75
2 COMBINED AT						
+	326-AL	.23	1	FLOW	106.	97.
				TIME	3.92	3.92
HYDROGRAPH AT						
•	OR-1	.28	1	FLOW	231.	220.
				TIME	3.58	3.58
ROUTED TO						
+	X1-X2	.28	1	FLOW	220.	206.
				TIME	3.75	3.75

HYDROGRAPH AT						
•	OR-2	1.21	1	FLOW	254.	233.
				TIME	4.08	4.08
2 COMBINED AT						
+	NODE.X2	1.49	1	FLOW	408.	376.
				TIME	3.75	3.75
3 COMBINED AT						
•	NODE.V4	12.50	1	FLOW	3072.	2870.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	OR-11	.04	1	FLOW	14.	13.
				TIME	3.58	3.58
2 COMBINED AT						
+	NODE.V5	12.54	1	FLOW	3078.	2876.
				TIME	4.08	4.08
ROUTED TO						
+	V5-Z2	12.54	1	FLOW	3060.	2855.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	OR-3	.20	1	FLOW	84.	79.
				TIME	3.83	3.83
ROUTED TO						
+	Y1-Z1	.20	1	FLOW	83.	77.
				TIME	3.92	3.92
HYDROGRAPH AT						
+	OR-4	.45	1	FLOW	293.	278.
				TIME	3.67	3.67
ROUTED TO						
+	Y2-Y3	.45	1	FLOW	258.	245.
				TIME	4.00	4.00
HYDROGRAPH AT						
+	OR-5	.37	1	FLOW	111.	102.
				TIME	3.83	3.83
2 COMBINED AT						
•	Y3	.82	1	FLOW	362.	342.
				TIME	4.00	4.00
ROUTED TO						
•	Y3-Z1	.82	1	FLOW	359.	339.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	OR-6A	.26	1	FLOW	223.	212.
				TIME	3.58	3.58
HYDROGRAPH AT						
+	OR-6B	.16	1	FLOW	140.	133.
				TIME	3.58	3.58
HYDROGRAPH AT						
+	OR-6C	.19	1	FLOW	146.	138.
				TIME	3.58	3.58
3 COMBINED AT						
+	NODE.AA1	.62	1	FLOW	508.	483.
				TIME	3.58	3.58
ROUTED TO						
+	AA1-AA2	.62	1	FLOW	408.	387.

				TIME	3.83	3.83
HYDROGRAPH AT						
+	OR-7	.61	1	FLOW	173.	160.
				TIME	3.92	3.92
2 COMBINED AT						
+	NODE.AA2	1.23	1	FLOW	578.	544.
				TIME	3.83	3.83
ROUTED TO						
+	AA2-Z1	1.23	1	FLOW	572.	539.
				TIME	3.92	3.92
HYDROGRAPH AT						
+	OR-8	.02	1	FLOW	8.	7.
				TIME	3.58	3.58
ROUTED TO						
+	R8-AA3	.02	1	FLOW	5.	5.
				TIME	4.42	4.42
HYDROGRAPH AT						
+	OR-9	.28	1	FLOW	68.	63.
				TIME	4.08	4.08
2 COMBINED AT						
+	NODE.AA3	.29	1	FLOW	72.	66.
				TIME	4.17	4.17
ROUTED TO						
+	AA3-Z1	.29	1	FLOW	71.	66.
				TIME	4.25	4.25
HYDROGRAPH AT						
+	OR-12	.52	1	FLOW	137.	126.
				TIME	3.83	3.83
5 COMBINED AT						
+	NODE.Z1	3.07	1	FLOW	1177.	1101.
				TIME	3.92	3.92
2 COMBINED AT						
+	NODE.Z2	15.62	1	FLOW	4163.	3891.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	OR-13	.12	1	FLOW	60.	56.
				TIME	3.67	3.67
2 COMBINED AT						
+	NODE.Z3	15.74	1	FLOW	4195.	3921.
				TIME	4.08	4.08
HYDROGRAPH AT						
•	OR-10	.10	1	FLOW	29.	27.
				TIME	3.83	3.83
ROUTED TO						
•	BB1-BB2	.10	1	FLOW	29.	27.
				TIME	4.00	4.08
HYDROGRAPH AT						
+	OR-14	.09	1	FLOW	25.	23.
				TIME	3.75	3.75
2 COMBINED AT						
+	NODE.BB2	.19	1	FLOW	48.	44.
				TIME	3.92	4.00
2 COMBINED AT						

+	NODE.883	15.93	1	FLOW	4241.	3964.
				TIME	4.08	4.08
ROUTED TO						
+	BB3-CC	15.93	1	FLOW	4237.	3959.
				TIME	4.08	4.08
HYDROGRAPH AT						
+	52A-M	.29	1	FLOW	40.	36.
				TIME	4.33	4.42
2 COMBINED AT						
+	NODE.CC	16.22	1	FLOW	4272.	3990.
				TIME	4.08	4.08

SUMMARY OF KINEMATIC WAVE - MUSKINGUM-CUNGE ROUTING
(FLOW IS DIRECT RUNOFF WITHOUT BASE FLOW)

ISTAQ	ELEMENT	DT	PEAK	TIME TO PEAK	VOLUME	INTERPOLATED TO COMPUTATION INTERVAL DT	PEAK	TIME TO PEAK	VOLUME
		(MIN)	(CFS)	(MIN)	(IN)	(MIN)	(CFS)	(MIN)	(IN)
FOR PLAN = 1 RATIO= .85									
M3-S1	MANE	1.68	322.74	257.86	.64	5.00	321.79	255.00	.64

CONTINUITY SUMMARY (AC-FT) - INFLOW= .6771E+02 EXCESS= .0000E+00 OUTFLOW= .6772E+02 BASIN STORAGE= .9168E-03 PERCENT ERROR= .0

FOR PLAN = 1 RATIO= .82									
M3-S1	MANE	1.73	298.79	257.22	.60	5.00	297.91	255.00	.60

CONTINUITY SUMMARY (AC-FT) - INFLOW= .6258E+02 EXCESS= .0000E+00 OUTFLOW= .6259E+02 BASIN STORAGE= .8285E-03 PERCENT ERROR= .0

FOR PLAN = 1 RATIO= .85									
S1-S2	MANE	1.72	544.60	244.89	.75	5.00	544.60	245.00	.75

CONTINUITY SUMMARY (AC-FT) - INFLOW= .1077E+03 EXCESS= .0000E+00 OUTFLOW= .1077E+03 BASIN STORAGE= .6011E-02 PERCENT ERROR= .0

FOR PLAN = 1 RATIO= .82									
S1-S2	MANE	1.73	506.81	245.43	.70	5.00	506.78	245.00	.70

CONTINUITY SUMMARY (AC-FT) - INFLOW= .1001E+03 EXCESS= .0000E+00 OUTFLOW= .1001E+03 BASIN STORAGE= .5599E-02 PERCENT ERROR= .0

FOR PLAN = 1 RATIO= .85									
R-S2	MANE	4.46	624.64	240.81	1.58	5.00	621.18	240.00	1.58

CONTINUITY SUMMARY (AC-FT) - INFLOW= .9583E+02 EXCESS= .0000E+00 OUTFLOW= .9603E+02 BASIN STORAGE= .2964E-03 PERCENT ERROR= -.2

FOR PLAN = 1 RATIO= .82									
R-S2	MANE	4.54	593.72	241.41	1.49	5.00	589.08	245.00	1.49

CONTINUITY SUMMARY (AC-FT) - INFLOW= .9084E+02 EXCESS= .0000E+00 OUTFLOW= .9100E+02 BASIN STORAGE= .3480E-03 PERCENT ERROR= -.2

FOR PLAN = 1 RATIO= .85									
S2-S3	MANE	.99	1351.53	242.33	.97	5.00	1351.22	245.00	.97

CONTINUITY SUMMARY (AC-FT) - INFLOW= .2328E+03 EXCESS= .0000E+00 OUTFLOW= .2329E+03 BASIN STORAGE= .9229E-02 PERCENT ERROR= .0

FOR PLAN = 1 RATIO= .82									
S2-S3	MANE	.99	1268.16	245.48	.90	5.00	1268.07	245.00	.90

CONTINUITY SUMMARY (AC-FT) - INFLOW= .2181E+03 EXCESS= .0000E+00 OUTFLOW= .2181E+03 BASIN STORAGE= .8398E-02 PERCENT ERROR= .0

FOR PLAN = 1 RATIO= .85									
V1-V2	MANE	.67	2419.16	241.61	1.01	5.00	2409.21	245.00	1.01

CONTINUITY SUMMARY (AC-FT) - INFLOW= .4070E+03 EXCESS= .0000E+00 OUTFLOW= .4070E+03 BASIN STORAGE= .1041E-01 PERCENT ERROR= .0

```
          FOR PLAN = 1  RATIO=  .82
            V1-V2  MANE          .61   2269.59    241.59       .95      5.00   2262.06    245.00         .95

CONTINUITY SUMMARY (AC-FT) - INFLOW= .3815E+03 EXCESS= .0000E+00 OUTFLOW= .3815E+03 BASIN STORAGE= .1066E-01 PERCENT ERROR=    .0

          FOR PLAN = 1  RATIO=  .85
            V3-V4  MANE          1.18   2614.11    247.01       .78      5.00   2610.32    245.00         .78

CONTINUITY SUMMARY (AC-FT) - INFLOW= .4507E+03 EXCESS= .0000E+00 OUTFLOW= .4508E+03 BASIN STORAGE= .2760E-01 PERCENT ERROR=    .0

          FOR PLAN = 1  RATIO=  .82
            V3-V4  MANE          1.20   2447.30    247.22       .73      5.00   2441.87    245.00         .73

CONTINUITY SUMMARY (AC-FT) - INFLOW= .4216E+03 EXCESS= .0000E+00 OUTFLOW= .4217E+03 BASIN STORAGE= .2788E-01 PERCENT ERROR=    .0

          FOR PLAN = 1  RATIO=  .85
            X1-X2  MANE          4.27    229.82    223.45      1.51      5.00    219.70    225.00        1.51

CONTINUITY SUMMARY (AC-FT) - INFLOW= .2230E+02 EXCESS= .0000E+00 OUTFLOW= .2254E+02 BASIN STORAGE= .2110E-03 PERCENT ERROR=  -1.1

          FOR PLAN = 1  RATIO=  .82
            X1-X2  MANE          4.24    209.83    221.69      1.43      5.00    205.56    225.00        1.43

CONTINUITY SUMMARY (AC-FT) - INFLOW= .2113E+02 EXCESS= .0000E+00 OUTFLOW= .2129E+02 BASIN STORAGE= .1659E-03 PERCENT ERROR=   -.8

          FOR PLAN = 1  RATIO=  .85
            V5-Z2  MANE          1.18   3075.27    247.18       .80      5.00   3060.30    245.00         .80

CONTINUITY SUMMARY (AC-FT) - INFLOW= .5348E+03 EXCESS= .0000E+00 OUTFLOW= .5350E+03 BASIN STORAGE= .3889E-01 PERCENT ERROR=   -.1

          FOR PLAN = 1  RATIO=  .82
            V5-Z2  MANE          1.12   2873.14    247.49       .75      5.00   2854.86    245.00         .75

CONTINUITY SUMMARY (AC-FT) - INFLOW= .4997E+03 EXCESS= .0000E+00 OUTFLOW= .4999E+03 BASIN STORAGE= .3920E-01 PERCENT ERROR=   -.1

          FOR PLAN = 1  RATIO=  .85
            Y1-Z1  MANE          3.99     83.27    238.87      1.04      5.00     83.14    235.00        1.04

CONTINUITY SUMMARY (AC-FT) - INFLOW= .1131E+02 EXCESS= .0000E+00 OUTFLOW= .1134E+02 BASIN STORAGE= .1712E-02 PERCENT ERROR=   -.3

          FOR PLAN = 1  RATIO=  .82
            Y1-Z1  MANE          4.04     77.97    235.57       .97      5.00     77.49    235.00         .97

CONTINUITY SUMMARY (AC-FT) - INFLOW= .1059E+02 EXCESS= .0000E+00 OUTFLOW= .1063E+02 BASIN STORAGE= .1776E-02 PERCENT ERROR=   -.4

          FOR PLAN = 1  RATIO=  .85
            Y3-Z1  MANE          2.13    360.97    242.90      1.13      5.00    359.37    245.00        1.13

INUITY SUMMARY (AC-FT) - INFLOW= .4939E+02 EXCESS= .0000E+00 OUTFLOW= .4946E+02 BASIN STORAGE= .1313E-02 PERCENT ERROR=   -.2
```

```
          FOR PLAN = 1  RATIO=  .82
            Y3-Z1  MANE          2.17    340.80    244.17      1.06      5.00    338.70    245.00        1.06

 CONTINUITY SUMMARY (AC-FT) - INFLOW= .4642E+02 EXCESS= .0000E+00 OUTFLOW= .4650E+02 BASIN STORAGE= .1471E-02 PERCENT ERROR=   -.2

          FOR PLAN = 1  RATIO=  .85
            AA2-Z1  MANE         1.52    576.80    232.93      1.10      5.00    572.49    235.00        1.10

 CONTINUITY SUMMARY (AC-FT) - INFLOW= .7186E+02 EXCESS= .0000E+00 OUTFLOW= .7197E+02 BASIN STORAGE= .1299E-02 PERCENT ERROR=   -.2

          FOR PLAN = 1  RATIO=  .82
            AA2-Z1  MANE         1.63    540.39    234.43      1.03      5.00    539.02    235.00        1.03

 CONTINUITY SUMMARY (AC-FT) - INFLOW= .6749E+02 EXCESS= .0000E+00 OUTFLOW= .6759E+02 BASIN STORAGE= .1101E-02 PERCENT ERROR=   -.1

          FOR PLAN = 1  RATIO=  .85
            AA3-Z1  MANE         3.45     71.41    256.18       .77      5.00     71.33    255.00         .77

 CONTINUITY SUMMARY (AC-FT) - INFLOW= .1214E+02 EXCESS= .0000E+00 OUTFLOW= .1216E+02 BASIN STORAGE= .1216E-02 PERCENT ERROR=   -.2

          FOR PLAN = 1  RATIO=  .82
            AA3-Z1  MANE         3.45     66.15    256.72       .72      5.00     65.98    255.00         .72

 CONTINUITY SUMMARY (AC-FT) - INFLOW= .1126E+02 EXCESS= .0000E+00 OUTFLOW= .1127E+02 BASIN STORAGE= .1284E-02 PERCENT ERROR=   -.1

          FOR PLAN = 1  RATIO=  .85
            BB1-BB2  MANE        5.00     28.84    240.58       .78      5.00     28.66    240.00         .78

 CONTINUITY SUMMARY (AC-FT) - INFLOW= .4051E+01 EXCESS= .0000E+00 OUTFLOW= .4070E+01 BASIN STORAGE= .1893E-02 PERCENT ERROR=   -.5

          FOR PLAN = 1  RATIO=  .82
            BB1-BB2  MANE        5.00     26.55    244.95       .72      5.00     26.54    245.00         .72

 CONTINUITY SUMMARY (AC-FT) - INFLOW= .3754E+01 EXCESS= .0000E+00 OUTFLOW= .3767E+01 BASIN STORAGE= .2057E-02 PERCENT ERROR=   -.4

          FOR PLAN = 1  RATIO=  .85
            BB3-CC  MANE          .55   4239.29    245.74       .84      5.00   4237.45    245.00         .84

 CONTINUITY SUMMARY (AC-FT) - INFLOW= .7117E+03 EXCESS= .0000E+00 OUTFLOW= .7118E+03 BASIN STORAGE= .3026E-01 PERCENT ERROR=    .0

          FOR PLAN = 1  RATIO=  .82
            BB3-CC  MANE          .64   3961.05    245.72       .78      5.00   3958.59    245.00         .78

 CONTINUITY SUMMARY (AC-FT) - INFLOW= .6655E+03 EXCESS= .0000E+00 OUTFLOW= .6655E+03 BASIN STORAGE= .2962E-01 PERCENT ERROR=    .0



 *** NORMAL END OF HEC-1 ***
```

Appendix G: Data CD

05-09-0577R

RESPONSE TO COMMENTS
SLOAN CHANNEL IMPROVEMENTS
REQUEST FOR
CONDITIONAL LETTER OF MAP REVISION

Case No.: 05-09-0577R
Community: Clark County, Nevada
Community No.: 320003

Prepared for:

Clark County Regional Flood Control District
500 South Grand Central Parkway
Las Vegas, NV 89155

Prepared by:

PBS&J
2270 Corporate Circle, Suite 100
Henderson, Nevada 89074

Reference Number: 511606.00
March, 2005

March 28, 2005

Ms. Sheila M. Norlin
National LOMC Manager
Michael Baker Jr., Inc.
3601 Eisenhower Avenue
Alexandria, Virginia 22304-6425

RE: CASE NO.: 05-09-0577R
COMMUNITY: CLARK COUNTY, NV
COMMUNITY NO.: 320003

Dear Ms. Norlin:

Submitted for your review is the Response to Comments for the Sloan Channel Improvements Request for Conditional Letter of Map Revision.

If you have any questions regarding this report, please contact our office at (702) 263-7275.

Sincerely,

PBS&J



3/28/05

Brian K. Loffman, CFM
Hydrologist

Matt Baird, P.E., CFM
Sr. Program Manager

The response to comments in a letter dated March 8, 2005 from Michael Baker Jr., Inc. (MBJ) are included below, see Appendix A for a copy of the comment letter.

Comment 1: **The starting water surface elevation (WSEL) for a tributary should be based on the slope-area method at a cross section on the tributary located just upstream of the confluence with the main stream. The submitted proposed conditions HEC-RAS model for Range Wash uses a known WSEL for the starting WSEL. Please provide a HEC-RAS hydraulic model for Range Wash with the starting WSEL computed by the slope-area method at a cross section on Range Wash located just upstream of the confluence with Las Vegas Wash.**

Response 1: As described in the original submittal (dated January 2005) the WSEL used in the HEC-RAS model at the downstream end (1694.20') was interpolated from the BFE's at the confluence of the proposed channel and Las Vegas Wash. A normal depth section taken at the downstream portion of the proposed channel (Section 10) shows a WSEL of 1693.40 and is 0.80' lower than the WSEL obtained from the BFE's. Therefore, the HEC-RAS model presented in the original submittal is actually more conservative. Please refer to Appendix B for the Flowmaster normal depth calculation for cross-section 10. PBS&J recommends the use of the higher starting WSEL to ensure that all future development in the area is properly elevated above the 100-year WSEL. However, PBS&J has revised the HEC-RAS model as requested using a starting WSEL (1693.40) obtained from the normal depth calculation.

It should also be noted that an error in the HEC-RAS model was discovered during the preparation of this report. The error is limited to cross-section 10 at the downstream end of the model and is located in the existing concrete channel section as shown on Sheet C-8 of the design plans. The geometry for the cross-section was taken from the 1-foot contours and a channel bottom width of 62 feet was used in the model. However, the bottom width of the proposed channel has a constant width of 60-feet. It is unlikely a change in the bottom width occurred at the transition from the proposed to existing channel. Therefore, PBS&J has revised the bottom width of cross-section 10 to 60-feet to match the design plans. The model revision did not result in a change to the WSEL at cross-section 10 or any of the upstream cross-sections.

A CD containing the electronic files for the revised HEC-RAS models has been included in Appendix C.

Comment 2: **The submitted design plans for Sloan Channel are not shown at an accurate scale, and the scale reduction is not exact. Please provide the design plans for Sloan Channel, certified by a registered professional engineer or land surveyor, at an accurate scale.**

Response 2: Please refer to appendix C for a complete full size set of the Sloan Channel Improvement Plans and a CD containing a PDF set of the approved design plans.

Appendix A: Comment Letter

NATIONAL FLOOD INSURANCE PROGRAM
FEMA MAP COORDINATION CONTRACTOR

March 8, 2005

Mr. Kevin Eubanks, P.E., CFM
Assistant General Manager
Clark County Regional Flood Control District
600 South Grand Central Parkway, Suite 300
Las Vegas, NV 89106

IN REPLY REFER TO:
Case No.: 05-09-0577R
Community: Clark County, NV
Community No.: 320003

316-AD

Dear Mr. Eubanks:

This responds to your request dated February 14, 2005, that the Department of Homeland Security's Federal Emergency Management Agency (FEMA) issue a conditional revision to the Flood Insurance Rate Map (FIRM) for Clark County, Nevada and Incorporated Areas. Pertinent information about the request is listed below.

Identifier:	Range Wash Channelization – Charleston Boulevard to Las Vegas Wash
Flooding Source:	Range Wash
FIRM Panel(s) Affected:	32003C2195 E

The data required to complete our review, which must be submitted within 90 days of the date of this letter, are listed on the enclosed summary.

If we do not receive the required data within 90 days, we will suspend our processing of your request. Any data submitted after 90 days will be treated as an original submittal and will be subject to all submittal/payment procedures, including the flat review and processing fee for requests of this type established by the current fee schedule.

If you are unable to meet the 90-day deadline for submittal of required items, and would like us to continue processing your request, you must request an extension of the deadline. This request must be submitted to us in writing and must provide (1) the reason why the data cannot be submitted within the requested timeframe, and (2) a new date for the submittal of the data. FEMA receives a very large volume of requests and cannot maintain inactive requests for an indefinite period of time. Therefore, the fees will be forfeited for any request for which neither the requested data nor a written extension request is received within 90 days.

If you have general questions about your request, FEMA policy, or the National Flood Insurance Program, please call the FEMA Map Assistance Center, toll free, at 1-877-FEMA MAP (1-877-336-2627). If you

have specific questions concerning your request, please call the Revisions Coordinator for your State, Mr. Sacha Tohme, CFM, who may be reached at (703) 960-8800, ext. 3028.

Sincerely,

Sheila M. Norlin, CFM
National LOMC Manager
Michael Baker Jr., Inc.

Enclosures

cc: Mr. Dave Betley, P.E.
Principal Engineer
Civil Engineering Division
Department of Development Services
Clark County

Mr. Mathew S. Baird, P.E., CFM
Senior Program Manager
PBS&J

NATIONAL FLOOD INSURANCE PROGRAM
FEMA MAP COORDINATION CONTRACTOR

Summary of Additional Data Required to Support a
Conditional Letter of Map Revision

Case No.: 05-09-0577R

Requester: Mr. Kevin Eubanks, P.E., CFM

Community: Clark County, NV

Community No.: 320003

The issues listed below must be addressed before we can continue the review of your request.

1. The starting water-surface elevation (WSEL) for a tributary should be based on the slope-area method at a cross section on the tributary located just upstream of the confluence with the main stream. The submitted proposed conditions HEC-RAS model for Range Wash uses a known WSEL for the starting WSEL. Please provide a HEC-RAS hydraulic model for Range Wash with the starting WSEL computed by the slope-area method at a cross section on Range Wash located just upstream of the confluence with Las Vegas Wash.

2. The submitted design plans for Sloan Channel are not shown at an accurate scale, and the scale reduction is not exact. Please provide the design plans for Sloan Channel, certified by a registered professional engineer or land surveyor, at an accurate scale.

Please send the required data directly to us at the address shown at the bottom of this page. For identification purposes, please include the case number referenced above on all correspondence.

Effective September 1, 2002, FEMA revised the fee schedule for reviewing and processing requests for conditional and final modifications to published flood information and maps. A copy of the notice summarizing the current fee schedule, which was published in the *Federal Register*, is enclosed for your information. In accordance with this schedule, the fee for your request is $4,000 and must be submitted before we can continue processing your request. Payment of this fee must be made in the form of a check or money order, payable in U.S. funds to the National Flood Insurance Program, or a credit card payment. For identification purposes, the case number referenced above must be included on the check or money order. We will not perform a detailed technical review of your request until we receive this payment.

Payment must be forwarded to one of the addresses listed below.

Using U.S. Postal Service:
Federal Emergency Management Agency
Fee-Charge System Administrator
P.O. Box 22787
Alexandria, VA 22304

Using overnight service:
FEMA Fee-Charge System Administrator
c/o Michael Baker Jr., Inc.
3601 Eisenhower Avenue
Alexandria, VA 22304

Appendix B: Flowmaster Calculation Worksheet

Worksheet for Cross-Section 10

Project Description		
Flow Element:	Irregular Section	
Friction Method:	Manning Formula	
Solve For:	Normal Depth	

Input Data		
Channel Slope:	0.46000	%
Discharge:	3990.00	ft^3/s

Options		
Current Roughness Weighted Meth	ImprovedLotters	
Open Channel Weighted Roughnes	ImprovedLotters	
Closed Channel Weighted Roughne	Hortons	

Results		
Roughness Coefficient:	0.015	
Water Surface Elevation:	1693.40	ft
Elevation Range:	1689.50 to 1700.00 ft	
Flow Area:	260.29	ft^2
Wetted Perimeter:	75.53	ft
Top Width:	73.38	ft
Normal Depth:	3.90	ft
Critical Depth:	4.91	ft
Critical Slope:	0.00210	ft/ft
Velocity:	15.33	ft/s
Velocity Head:	3.65	ft
Specific Energy:	7.55	ft
Froude Number:	1.43	
Flow Type:	Supercritical	

Segment Roughness

Start Station	End Station	Roughness Coefficient
(0+00, 1700.00)	(0+96, 1700.00)	0.015

Section Geometry

Station	Elevation
0+00	1700.00
0+21	1689.50


Worksheet for Cross-Section 10


Station	Elevation
0+81	1689.50
0+96	1700.00

Cross Section for Cross-Section 10

Project Description		
Flow Element:	Irregular Section	
Friction Method:	Manning Formula	
Solve For:	Normal Depth	


Section Data		
Roughness Coefficient:	0.015	
Channel Slope:	0.46000	%
Normal Depth:	3.90	ft
Elevation Range:	1689.50 to 1700.00 ft	
Discharge:	3990.00	ft^3/s





Appendix C: Sloan Channel Plans & CD

DEPARTMENT OF PUBLIC WORKS



Vicinity Map

NOT TO SCALE

CLARK COUNTY NEVADA

"Progress as Promised"

2004 IMPROVEMENT PLANS FOR SLOAN CHANNEL

FROM CHARLESTON BOULEVARD TO LAS VEGAS WASH

FUNDED BY

CLARK COUNTY REGIONAL FLOOD CONTROL DISTRICT

County Manager

Thom Reilly

Director of Public Works

Approved:

M.J. Manning

Clark County Regional Flood Control District

Approved:

Gale Wm. Fraser II, P.E.
General Manager/
Chief Engineer

County Commissioners

Chip Maxfield, Chairman
Myrna Williams, Vice-Chair
Yvonne Atkinson Gates
Mark A. James
Mary J. Kincaid-Chauncey
Rory Reid
Bruce L. Woodbury

SIGNATURE ON THESE PLANS WILL NOT BE CONSTRUED TO BE A PERMIT FOR OR AN APPROVAL OF ANY VIOLATION OF CLARK COUNTY SANITATION DISTRICT RULES, REGULATIONS, OR DESIGN AND CONSTRUCTION STANDARDS. THE APPROVAL OF THESE DRAWINGS DOES NOT GUARANTEE CAPACITY IN THE DISTRICT'S COLLECTION OR TREATMENT SYSTEM.

NEVADA POWER COMPANY ACKNOWLEDGES THAT WE HAVE RECEIVED YOUR PLANS AND WILL PROVIDE SERVICE TO ALL ELECTRICAL NEEDS ASSOCIATED WITH THIS PROJECT. NEVADA POWER COMPANY RESERVES THE RIGHT TO ADDRESS ANY EXISTING OR FUTURE CONFLICTS ONCE THE FINAL DESIGN IS COMPLETED. THE NEW FACILITY AND THE RESOLUTION OF ANY CONFLICTS WILL BE ACCOMPLISHED PURSUANT TO THE NEVADA PUBLIC UTILITY COMMISSION'S RULES AND REGULATIONS.

"The affixed Sprint Nevada approval does not assume or guarantee liability for known or unknown conflicts with existing or proposed improvements. Resolution of any conflict will be accomplished pursuant to Local Ordinances, Nevada Revised Statutes and/or Public Utility Commission Rules and Regulations."

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146

AGENCY	PLANS REVIEWED BY	DATE
SPRINT		9-3-04
LAS VEGAS VALLEY WATER DISTRICT		4/5/04
SOUTHWEST GAS COMPANY	Thomas Crum	4-4-4
NEVADA POWER COMPANY (TRANSMISSION)		9/3/04
NEVADA POWER COMPANY (DISTRIBUTION)		9-8-04
CLARK COUNTY WATER RECLAMATION DISTRICT		3/12/04
COX COMMUNICATIONS LAS VEGAS, INC.		9/9/04

DEPARTMENT OF PUBLIC WORKS	BY	DATE
DEPUTY DIRECTOR		3-16-2004
CONSTRUCTION MANAGEMENT DIVISION		3/16/04
DESIGN ENGINEERING DIVISION		3-16-04
MAINTENANCE MANAGEMENT DIVISION		3-16-04
TRAFFIC MANAGEMENT DIVISION		3/16/04
COUNTY SURVEYOR'S OFFICE		3/16/2004

REVISIONS NUMBER	DESCRIPTION	DATE

PROFESSIONAL ENGINEER STATE OF NEVADA NOEL LAUGHLIN Exp. 12/31/2005 CIVIL No. 10165


3-12-04

DESIGN ENGINEERING DIVISION

COVER SHEET

L-1759

BID No.: 5524-04



Location Map

Index of Sheets

DRAWING NO. **DESCRIPTION**

General Drawings


	COVER SHEET
G-2	INDEX OF DRAWINGS, KEY MAP AND LOCATION MAP
G-3	GENERAL & CONSTRUCTION NOTES, LEGEND & ABBREVIATIONS BENCHMARK, BASIS OF BEARINGS
G-4	HORIZONTAL CONTROL PLAN
G-5	ESTIMATE OF QUANTITIES
G-6	RECORD OF SURVEY

Civil Drawings

C-1	PLAN AND PROFILE STA. 114+50.00 TO STA. 122+00.00
C-2	PLAN AND PROFILE STA. 122+00.00 TO STA. 132+00.00
C-3	PLAN AND PROFILE STA. 132+00.00 TO STA. 142+00.00
C-4	PLAN AND PROFILE STA. 142+00.00 TO STA. 152+00.00
C-5	PLAN AND PROFILE STA. 152+00.00 TO STA. 162+00.00
C-6	PLAN AND PROFILE STA. 162+00.00 TO STA. 171+00.00
C-7	PLAN AND PROFILE STA. 171+00.00 TO STA. 181+00.00
C-8	PLAN AND PROFILE STA. 181+00.00 TO STA. 190+00.00
C-9	PLAN AND PROFILE (CONFLUENCE) AND LATERALS
C-10	TYPICAL CROSS SECTIONS
C-11	DETAILS
C-12	TYPICAL CROSS SECTIONS
C-13	FENCING/POST & CABLE RAILING PLAN
C-14	FENCING/POST & CABLE RAILING PLAN
C-15	ACCESS/MAINTENANCE ROAD CONTROL PLAN
C-16	ACCESS/MAINTENANCE ROAD CONTROL PLAN
C-17	DEPTH GAUGE STATION SECTIONS AND DETAILS

Structural Drawings

S-1	DETAILS
S-2	DETAILS
S-3	TYPICAL CHANNEL SECTIONS
S-4	CHANNEL TRANSITION STRUCTURES
S-5	ACCESS RAMP
S-6	ACCESS RAMP DETAILS
S-7	DETAILS



Key Map

SCALE: 1" = 400'

REV. NO. | DATE | DESCRIPTION | APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

INDEX OF DRAWINGS, KEY MAP AND LOCATION MAP

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

NOEL C. LAUGHLIN — Exp. 12/31/2005 — CIVIL — No. 10165 — PROFESSIONAL ENGINEER — STATE OF NEVADA — 4-5-04

PROJECT No: 500.857 DRAWN BY: DVJ
DESIGNED BY: _____ CHECKED BY: _____
APPROVED BY _____

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
G-2
SHT. 2 OF 30

LEGEND & ABBREVIATIONS

ABBREVIATION

AC = ASPHALTIC CONCRETE
ACP = ASBESTOS CEMENT PIPE
AVAR = AIR VACUUM AIR RELIEF (VALVE)
BC = BACK OF CURB
BCR = BEGIN CURB RETURN
BM = BENCHMARK
BW = BACK OF WALK
CATV = CABLE TELEVISION
CCSD = CLARK COUNTY SANITATION DISTRICT
CL/℄ = CENTERLINE
CLSM = CONTROLLED LOW STRENGTH MATERIAL
CMP = CORRUGATED METAL PIPE
CONC. = CONCRETE
D = DEPTH
DI = DROP INLET
DIP = DUCTILE IRON PIPE
EA. = EACH
EFF = EFFLUENT
EGL = ENERGY GRADE LINE
ELEV./ EL = ELEVATION
EP = EDGE OF PAVEMENT
EXIST./ EX = EXISTING
FF = FINISH FLOOR
FG = FINISH GRADE
FL = FLOW LINE
FS = FINISH SURFACE
FUT = FUTURE
G = GAS
GB = GRADE BREAK
GIS = GEOGRAPHIC INFORMATION SYSTEM
HERCP = HORIZONTAL ELLIPTICAL REINFORCED CONCRETE PIPE
HGL = HYDRAULIC GRADE LINE
HP = HIGH POINT
HPG = HIGH PRESSURE GAS
I.D. = INSIDE DIAMETER
INV = INVERT
L / LT = LEFT OF
LF = LINEAR FEET
LP = LOW POINT
LVACTS = LAS VEGAS AREA COMPUTER TRAFFIC SYSTEM
LVVWD = LAS VEGAS VALLEY WATER DISTRICT
NAVD = NORTH AMERICAN VERTICAL DATUM
NDOT = NEVADA DEPARTMENT OF TRANSPORTATION
NG = NATURAL GRADE
OHP = OVERHEAD POWER
PBS = PLANTMIX BITUMINOUS SURFACE
PBCBR = PORTABLE PRECAST BARRIER RAIL
PC = POINT OF CURVE
PCC = POINT OF COMPOUND CURVE
POC = POINT OF CURVE
POT = POINT OF TANGENT
PRC = POINT REVERSE CURVE
PROP = PROPOSED
PT = POINT OF TANGENT
PVC = POLYVINYL CHLORIDE PIPE
$Q_{ult}100$ = 100 YEAR ULTIMATE CONDITION DESIGN FLOW
(R) = RADIAL
R / RT = RIGHT OF
RCB = REINFORCED CONCRETE BOX
RCP = REINFORCED CONCRETE PIPE
RGRCP = RUBBER GASKET REINFORCED CONCRETE PIPE
R/W = RIGHT-OF-WAY
SD = STORM DRAIN
SDMH = STORM DRAIN MANHOLE
SNWA = SOUTHERN NEVADA WATER AUTHORITY
SS = SANITARY SEWER
SSMH = SANITARY SEWER MANHOLE
STA = STATION
STD.DWG.NO. = STANDARD DRAWING NUMBER
TC = TOP OF BACK OF CURB
TEL = TELEPHONE
THK = THICK
TMH = TOP OF MANHOLE
TOE = TOE OF CHANNEL
TOP = TOP OF CHANNEL
TW = TOP OF WALL
UDACS = UNIFORM DESIGN AND CONSTRUCTION STANDARDS
UNO = UNLESS NOTED OTHERWISE
U.S. = UNITED STATES
V.C. = VERTICAL CURVE
VCP = VERIFIED CLAY PIPE
W = WATER
W/ = WITH
WWF = WELDED WIRE FABRIC

LEGEND

(650.61) / INV — EXIST. ELEVATION
00.0 / INV — PROPOSED ELEVATION
(23.67) / S — EXIST. SPOT ELEVATION
PROPERTY OR RIGHT-OF-WAY LINE
CENTERLINE
HYDRAULIC GRADE LINE (HGL)
ENERGY GRADE LINE (EGL)
EASEMENT
T — EXISTING TELEPHONE CABLE
EXISTING FENCE
SS — EXISTING SANITARY SEWER LINE
SS — PROPOSED SANITARY SEWER LINE
W — EXISTING WATER LINE
W — PROPOSED WATER LINE
G — EXISTING GAS LINE
UGE — EXISTING UNDERGROUND POWER
OHP — EXISTING OVERHEAD POWER
SD — EXISTING STORM DRAIN
CHANNEL — PROPOSED CHANNEL
SD — PROPOSED STORM DRAIN
CATV — EXISTING CABLE TELEVISION
EXISTING CONTOUR
SAWCUT LINE
EXISTING MANHOLE
PROPOSED MANHOLE
EXISTING FIRE HYDRANT
EXISTING VALVE
PROPOSED VALVE
PROPOSED DROP INLET
PROPOSED REUSE HYDRANT

CONSTRUCTION NOTES

1. CONSTRUCT 6' CHAIN-LINK FENCE (SEE DETAIL 9/C11)
2. CONSTRUCT 6' CHAIN-LINK GATE (SEE DETAIL 8/C11) (WIDTH OF GATE CALLED OUT IN PLAN VIEW)
3. CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)
4. CONSTRUCT 12' DRIVEWAY PER STD. DWG. NO. 224
5. INSTALL SIGN (SEE DETAIL 6/C11)
6. INSTALL SIGN (SEE DETAIL 7/C11)
7. CONSTRUCT POST AND CABLE RAILING (SEE DETAIL 10/C11)
8. PAINTED STAFF GAUGE (SEE DETAIL 5/C11)
9. CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)
10. CONSTRUCT PIPE CONNECTION (SEE DETAIL 9/S2)
11. CONSTRUCT RCB CONNECTION (SEE DETAIL 3/S7)
12. CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

1. REMOVE EXISTING BLOCK WALL AND FOOTING
2. REMOVE AND SALVAGE RIPRAP
3. REMOVE EXISTING CONCRETE SPLASH PAD
4. REMOVE EXISTING 60 FT.± CHANNEL SECTION TO EXPANSION JOINT.
5. REMOVE EXISTING CHANNEL LINING.
6. REMOVE EXISTING CONCRETE SPILLWAY.
7. REMOVE EXISTING CHAIN-LINK FENCE.

CLARK COUNTY WATER RECLAMATION DISTRICT NOTES

1. ALL CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF THE DESIGN AND CONSTRUCTION STANDARDS FOR WASTE-WATER COLLECTION SYSTEMS AND THE PUBLIC WORKS CONSTRUCTION OFF SITE IMPROVEMENTS, CLARK COUNTY AREA, NEVADA, AS AMENDED, AND CLARK COUNTY SUPPLEMENT TO UNIFORM STANDARD DRAWINGS AND SPECIFICATIONS. IT WILL BE THE RESPONSIBILITY OF THE CONTRACTOR TO BE AWARE OF THE CONTENTS OF THE ABOVE DRAWINGS AND SPECIFICATION BOOKS.
2. THESE STANDARDS SHALL APPLY TO ALL CONSTRUCTION.
3. SEWER MAINS ONLY TO BE LAID IN SEWER TRENCHES.
4. ALL LATERALS TO BE LAID AT NOT LESS THAN MINIMUM SLOPE AS SHOWN IN THESE STANDARDS.
5. IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO PERFORM CONSTRUCTION AS PER PLANS. ANY ADDITIONS, DELETIONS, OR CHANGES SHALL FIRST MEET WITH THE APPROVAL OF THE CONTROLLING AGENCY.
6. SOIL TESTING SHALL BE IN ACCORDANCE WITH SECTION 3.11 OF THESE STANDARDS.
7. ALL EXFILTRATION, INFILTRATION, AIR TESTING AND TELEVISING OF LINES SHALL BE IN ACCORDANCE WITH THESE STANDARDS.
8. CUT SHEETS MUST BE SUBMITTED TO THE AGENCY BEFORE CONSTRUCTION WILL BE PERMITTED TO START.
9. ALL CONTRACTORS INSTALLING SEWER MAINS THAT WILL BE UNDER THE JURISDICTION OF THE CONTROLLING AGENCY MUST BE CLASS "A" CONTRACTORS.

CLARK COUNTY WATER RECLAMATION DISTRICT NOTES DATE

CCWRD PROJECT CONTROL NUMBER IS_____.

SIGNATURE ON THESE PLANS WILL NOT BE CONSTRUED TO BE A PERMIT FOR OR AN APPROVAL OF ANY VIOLATION OF CLARK COUNTY WATER RECLAMATION DISTRICT RULES, REGULATIONS, OR DESIGN AND CONSTRUCTION STANDARDS. THE APPROVAL OF THESE DRAWINGS DOES NOT GUARANTEE CAPACITY IN THE DISTRICT'S COLLECTION OR TREATMENT SYSTEM.

LAS VEGAS VALLEY WATER DISTRICT STANDARD NOTES

LVVWD PROJECT # 25819

1. NO WORK SHALL BEGIN UNTIL THE WATER PLANS HAVE BEEN RELEASED FOR CONSTRUCTION BY THE LVVWD. FOLLOWING WATER PLAN APPROVAL, 48 HOUR NOTICE SHALL BE GIVEN TO LVVWD COMMUNICATION SUPPORT CENTER (258-7171) PRIOR TO THE START OF CONSTRUCTION. NOTICE MUST BE GIVEN BY 2:00 p.m. THE BUSINESS DAY PRIOR TO A LVVWD INSPECTION. WHEN REQUESTING INSPECTIONS, PLEASE REFER TO THE PROJECT # IDENTIFIED ABOVE.
2. ALL WORK SHALL CONFORM TO LVVWD'S STANDARD PLATES, DRAWINGS AND SPECIFICATIONS AND TO THE UNIFORM DESIGN AND CONSTRUCTION STANDARDS FOR WATER DISTRIBUTION SYSTEMS (UDACS), LATEST EDITION.
3. ALL WORK, EXCEPT AS MODIFIED BY THESE PLANS OR BY NOTE 2, SHALL BE DONE IN ACCORDANCE WITH THE MOST CURRENT DRAFT OR EDITION OF THE UNIFORM STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION OFFSITE IMPROVEMENT, CLARK COUNTY AREA.
4. A SINGLE PIPE MATERIAL SHALL BE USED THROUGHOUT THE PROJECT UNLESS OTHERWISE APPROVED BY THE LVVWD.
5. ALL SERVICE LATERALS TWO (2) INCHES IN DIAMETER AND SMALLER SHALL BE COPPER TUBING WITH LVVWD APPROVED SERVICE SADDLES.
6. ALL WATER METER BOXES SHALL BE LOCATED OUTSIDE OF DRIVEWAY AREAS.
7. ALL VALVES SHALL BE LOCATED OUTSIDE OF DRIVEWAY, VALLEY AND CURB GUTTERS.
8. THE FOLLOWING REQUIREMENTS MUST BE MET IN THE EVENT A WATER LINE AND SANITARY OR STORM SEWER LINE CROSS:

   A MINIMUM EIGHTEEN (18) INCH VERTICAL SEPARATION (OUTSIDE TO OUTSIDE) MUST BE MAINTAINED WHEN THE WATER LINE IS INSTALLED OVER THE SANITARY OR STORM SEWER LINE. IF THE VERTICAL SEPARATION CANNOT BE MAINTAINED OR THE WATER LINE MUST BE PLACED UNDER THE SANITARY OR STORM SEWER LINE, THE SANITARY OR STORM SEWER LINE MUST BE CONSTRUCTED WITH ONE OF THE FOLLOWING OR, AS SHOWN ON THESE PLANS:

   A. POTABLE WATER SUPPLY QUALITY MATERIAL,
   B. ENCASEMENT, WITH FOUR (4) INCH CONCRETE (MINIMUM),
   C. SLEEVING WITH POTABLE WATER SUPPLY QUALITY PIPE.

   EACH PROVISION MUST EXTEND ALONG THE SANITARY OR STORM SEWER, ON EITHER SIDE OF THE MAIN, A MINIMUM 10 FOOT DISTANCE PERPENDICULAR TO THE WATER MAIN EXTERIOR.
9. WARNING TAPE SHALL BE REQUIRED OVER ALL MAINS, ALL SIX (6) INCH DIAMETER AND LARGER SERVICE LATERALS, AND ANY SERVICE LATERAL NOT INSTALLED PERPENDICULAR TO THE MAIN IN ACCORDANCE WITH STANDARD PLATE NO. 27.
10. ALL WATER FACILITIES SHALL BE FILLED, DISINFECTED, PRESSURE TESTED, FLUSHED, FILLED AND AN ACCEPTABLE WATER SAMPLE OBTAINED, PRIOR TO CONNECTION TO THE LVVWD'S DISTRIBUTION SYSTEM.
11. THE CONTRACTOR MUST OBTAIN ALL METERS TWO (2) INCHES AND SMALLER FROM LVVWD CENTRAL STORES. TELEPHONE 258-3152 FORTY-EIGHT (48) HOURS PRIOR TO PICKUP.
12. CONSTRUCTION MAY INTERRUPT SERVICE, WITH LVVWD APPROVAL AND PROPER NOTIFICATION, BETWEEN THE HOURS OF 10 PM AND 6 AM, SUNDAY THROUGH THURSDAY. CIRCUMSTANCES MAY REQUIRE TEMPORARY SERVICE FEEDS BE INSTALLED, WITHOUT LVVWD REIMBURSEMENT. ANY TEMPORARY SERVICE FEED MUST HAVE PRIOR LVVWD APPROVAL.
13. ALL WATER FACILITY CONSTRUCTION MATERIALS USED MUST BE AS LISTED ON THE LVVWD'S PRE-APPROVED MATERIALS AND MANUFACTURER'S LISTING FOR NEW FACILITIES, LATEST REVISION, OR SPECIFICALLY APPROVED ON THESE PLANS.

APPROVED FOR CONSTRUCTION

Robert J. Morgan 4/5/04

LAS VEGAS VALLEY WATER DISTRICT DATE

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES

1. CONTRACTOR SHALL FIELD LOCATE AND PROTECT ALL SNWA/SNWS APPURTENANCES INCLUDING, BUT NOT LIMITED TO AV/AR, ACCESS MANWAYS AND CATHODIC PROTECTION SYSTEMS. ALL ABOVE GROUND STRUCTURES AND AT GRADE STRUCTURES MUST BE ADJUSTED TO NEW GRADE AT CONTRACTOR'S EXPENSE. CATHODIC PROTECTION TEST STATIONS, RECTIFIERS, AND AV/AR'S MUST BE RELOCATED TO THE SIDEWALK PER SNWA STANDARDS AND AT THE CONTRACTOR'S EXPENSE. CONTRACTOR TO NOTIFY SOUTHERN NEVADA WATER AUTHORITY DEVELOPMENT PLAN REVIEW, AT (702) 862-3444 AT LEAST 48 HOURS PRIOR TO CONSTRUCTION ACTIVITY.
2. NO BUILDINGS, STRUCTURES, FENCES OR TREES SHALL BE PLACED UPON, OVER OR UNDER SAID PARCEL OF LAND FOR THE DURATION OF THIS EASEMENT EXCEPT THAT SAID PARCEL MAY BE IMPROVED AND USED FOR STREET, ROAD OR DRIVEWAY PURPOSES AND FOR OTHER UTILITIES, INSOFAR AS SUCH USE DOES NOT INTERFERE WITH ITS USE BY SNWA FOR THE PURPOSES FOR WHICH IT IS GRANTED.
3. SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.



BASIS OF BEARINGS

SOUTH 00°18'40" EAST - BEING THE WEST LINE OF SOUTHWEST QUARTER (SW 1/4) OF SECTION 3, TOWNSHIP 21 SOUTH, RANGE 62 EAST, M.D.M. AS SHOWN BY A MAP THEREOF ON FILE IN FILE 36, PAGE 6 OF SURVEYS IN THE CLARK COUNTY RECORDER'S OFFICE, CLARK COUNTY, NEVADA.

Avoid cutting underground utility lines. It's costly.
Call before you Dig.
1-800-227-2600
UNDERGROUND SERVICE (USA)

PROJECT BENCHMARK

CLARK COUNTY BM - 6C02 33SW16

RIVET AND SQUARE ALUMINUM PLATE IN TOP OF CURB, IN NORTHEAST CORNER OF NELLIS BLVD. AND BELPORT DR. NEAR THE PC OF NELLIS BLVD.

ELEVATION - 531.863 (M) NAVD 88
1744.954 (FT) NAVD 88

GENERAL NOTES

1. ALL CONSTRUCTION AND MATERIALS FOR THIS PROJECT SHALL BE IN ACCORDANCE WITH THE "UNIFORM STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION", CLARK COUNTY AREA, NEVADA LATEST EDITION, AND THE "UNIFORM DRAWINGS FOR PUBLIC WORKS CONSTRUCTION", CLARK COUNTY AREA, NEVADA LATEST EDITION, UNLESS OTHERWISE SPECIFIED BY NOTE ON THE PLANS AND/OR SPECIAL PROVISIONS. THE IMPROVEMENT STANDARDS WILL HEREAFTER BE REFERRED TO AS "CLARK COUNTY AREA STANDARD DRAWINGS.
2. 48 HOURS PRIOR TO START OF CONSTRUCTION, THE CONTRACTOR SHALL CONTACT

NEVADA POWER COMPANY	PHONE	1-800-227-2600
SPRINT-CENTRAL TELEPHONE COMPANY	PHONE	1-800-227-2600
SOUTHWEST GAS CORPORATION	PHONE	1-800-227-2600
COX COMMUNICATIONS LAS VEGAS, INC.	PHONE	384-8084
LAS VEGAS VALLEY WATER DIST.	PHONE	870-4194
CLARK COUNTY TRAFFIC MGMT. DIV.	PHONE	455-7511
CLARK COUNTY WATER RECLAMATION DISTRICT	PHONE	434-8000
SOUTHERN NEVADA WATER AUTHORITY	PHONE	862-3444

3. LOCATIONS OF UNDERGROUND UTILITIES SHOWN ON THE DRAWINGS WERE OBTAINED FROM INFORMATION RECEIVED FROM THE APPLICABLE UTILITY COMPANIES NEITHER THE OWNER NOR ENGINEER ASSUMES ANY RESPONSIBILITY FOR UTILITIES OR STRUCTURES NOT SHOWN, OR FOR UTILITIES OR STRUCTURES NOT SHOWN AT ACTUAL LOCATIONS ON THE DRAWINGS. EXISTING SERVICE LATERALS ARE NOT SHOWN ON THESE DRAWINGS. CONTRACTOR TO VERIFY THE EXACT LOCATION OF UTILITIES PRIOR TO START OF CONSTRUCTION. THE CONTRACTOR'S RESPONSIBILITY REGARDING UTILITIES SHALL BE AS REQUIRED UNDER SECTION 107.17 OF THE UNIFORM STANDARD SPECIFICATIONS FOR CLARK COUNTY AREA, NEVADA AND AS PROVIDED IN THE SPECIFICATIONS.
4. THE CONTRACTOR SHALL NOT REMOVE TREES, SHRUBS, LAWNS, WALLS, FENCES, SIGNS, STRUCTURES, LIGHTS, OR ANY EXISTING IMPROVEMENTS OUTSIDE OF STREET RIGHT-OF-WAY, EXCEPT WHERE REQUIRED TO DO SO BY THE CONTRACT DRAWINGS OR BY THE ENGINEER.
5. REPLACEMENT, RELOCATION, OR RECONSTRUCTION OF ALL EXISTING IMPROVEMENTS INCLUDING SPRINKLER SYSTEMS, LAWNS, FENCES, WALLS, SIGNS, STEPS, SIDEWALK, DRIVEWAYS, LAWN LIGHTS, AND ALL OTHER ITEMS APPLICABLE TO THIS CONTRACT SHALL BE AS REQUIRED BY THE ENGINEER.
6. THE CONTRACTOR SHALL BACKFILL AND FINE GRADE ALL CUT OR FILL SLOPES TO MATCH EXISTING CONDITIONS TO THE SATISFACTION OF THE ENGINEER, WHERE EXISTING LAWNS ARE DAMAGED BY THE CONTRACTOR'S OPERATIONS THE CONTRACTOR SHALL SOD THE AFFECTED AREA TO A CONDITION EQUAL TO, OR BETTER TO THAT WHICH EXISTED PRIOR TO CONSTRUCTION.
7. ALL BARRICADING AND TEMPORARY TRAFFIC CONTROL DEVICES OR METHODS USED DURING CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE "NEVADA TRAFFIC CONTROL MANUAL", 1986 (OR LATEST REVISION), PUBLISHED BY THE STATE OF NEVADA DEPARTMENT OF TRANSPORTATION AND THE "MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES", EXCEPT AS OTHERWISE PROVIDED IN THE CONTRACT SPECIFICATIONS OR AS REQUIRED BY THE ENGINEER.
8. REMOVAL OR RELOCATIONS OF POWER POLES, TELEPHONE POLES, JOINTLY-OWNED POLES, AND APPURTENANCES WHICH INTERFERE WITH IMPROVEMENTS REQUIRED TO BE CONSTRUCTED UNDER THIS CONTRACT, SHALL BE THE RESPONSIBILITY OF THE RESPECTIVE UTILITY COMPANY. THE CONTRACTOR IS RESPONSIBLE FOR COORDINATION WITH THE UTILITY COMPANIES FAR ENOUGH IN ADVANCE AS TO NOT IMPACT THE SCHEDULE.
9. UNLESS OTHERWISE SHOWN ON THE CONTRACT DRAWINGS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE REMOVAL OR RELOCATION OF ALL WATER SERVICES AND METERS WHICH INTERFERE WITH IMPROVEMENTS SHOWN ON THE CONTRACT DRAWINGS.
10. THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE VERTICAL ADJUSTMENT OF ALL EXISTING SANITARY, WATER AND STORM SEWER MANHOLES TO THE FINAL FINISH GRADES IN ACCORDANCE WITH SECTIONS 609 AND 630 OF THE "STANDARD SPECIFICATIONS".
11. SPRINT TELEPHONE COMPANY SHALL BE RESPONSIBLE FOR THE VERTICAL OR HORIZONTAL ADJUSTMENT OF ALL TELEPHONE FACILITIES WHICH INTERFERE WITH IMPROVEMENTS SHOWN ON THE CONTRACT DRAWINGS.
12. ALL EXISTING TRAFFIC SIGNS, STREET LIGHTS & SIGNS TO BE REMOVED SHALL BE SALVAGED BY THE CONTRACTOR AND DELIVERED TO THE CLARK COUNTY TRAFFIC OPERATIONS DIVISION LOCATED AT 5821 E. FLAMINGO ROAD, LAS VEGAS, NEVADA WITHIN 48 HOURS OF THEIR REMOVAL.
13. EXACT LOCATIONS OF ALL SAWCUT LINES SHALL BE DETERMINED IN THE FIELD BY THE ENGINEER. SAWCUTS, LONGITUDINAL TO THE ROADWAY, MAY BE WHEEL CUT WITH EQUIPMENT AS APPROVED BY THE ENGINEER. ALL OTHER SAWCUT SHALL BE MADE BY A ROTARY SAW.
14. ALL SANITARY SEWER CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE CLARK COUNTY SANITATION DISTRICT DESIGN AND CONSTRUCTION STANDARDS.
15. THE PLANS DO NOT SHOW ALL SEWER LATERALS, SEWER FORCE MAINS AND WATER SERVICE LATERALS, THE CONTRACTOR SHALL BE RESPONSIBLE FOR ANY REPAIRS OR RELOCATIONS OF LATERALS BROKEN OR IN CONFLICT WITH THE PROPOSED CHANNEL, STORM DRAIN OR ROADWAY CONSTRUCTION.
16. CONTRACTOR SHALL MAINTAIN CONTINUOUS SEWER SERVICE TO ALL CCSD CUSTOMERS. SEWER LATERALS CUT DURING CONSTRUCTION SHALL BE REPAIRED BY CONTRACTOR PER CCSD DESIGN AND CONSTRUCTION STANDARDS. CONTRACTOR SHALL IMMEDIATELY REPORT ANY SANITARY SEWER OR SEWER LATERALS THAT CANNOT BE RECONNECTED TO SEWER MAIN DUE TO STORM DRAIN CONFLICT. CLARK COUNTY SHALL BE RESPONSIBLE FOR PROVIDING RESUBMITTED APPROVED MAIN LINE SEWER EXTENSION PLANS TO PROVIDE NEW MAIN TO REROUTE ANY SEWERS THAT CANNOT BE RECONNECTED.
17. THE NEVADA POWER COMPANY SHALL BE RESPONSIBLE FOR THE RELOCATION OF UNDERGROUND OR OVERHEAD POWER LINES THAT INTERFERE WITH THE REQUIRED IMPROVEMENTS AS SHOWN ON THE PLANS.
18. IF THE IMPROVEMENTS NECESSITATE THE OBLITERATION, TEMPORARY OBSTRUCTION, TEMPORARY REMOVAL, OR RELOCATION OF ANY EXISTING TRAFFIC PAVEMENT MARKING, SUCH PAVEMENT MARKING SHALL BE RESTORED OR REPLACED WITH LIKE MATERIALS TO THE SATISFACTION OF THE COUNTY TRAFFIC MANAGER.
19. LVACTS INTERCONNECT CABLE POLICY IS IN EFFECT. INTERCONNECT CABLE MUST BE MAINTAINED AT ALL TIMES. CONTRACTOR SHALL PROVIDE TEMPORARY OVERHEAD INTERCONNECT CABLE WHILE PAVEMENT CABLE IS BEING RELOCATED. TEMPORARY AERIAL INSTALLATION MUST BE ACCEPTABLE TO THE COUNTY TRAFFIC MANAGER AND TO LVACTS. ANY DAMAGE TO THIS CABLE IS DEEMED AN EMERGENCY BY LVACTS, CITY OF LAS VEGAS, CLARK COUNTY AND NDOT AND MUST BE REPAIRED IMMEDIATELY TO LVACTS' ACCEPTANCE. $2,500 PER DAY DAMAGES WILL BE ASSESSED AFTER TWENTY-FOUR (24) HOURS HAS ELAPSED FROM THE TIME OF BREAK OR DAMAGE.
20. THE CONTRACTOR SHALL DETERMINE THE LOCATION AND DEPTH OF SUSPECTED UTILITY INTERFERENCES, AND SHALL FURNISH INFORMATION ON THE SAME TO THE ENGINEER, NOT LESS THAN TEN (10) DAY PRIOR TO THE ANTICIPATED IMPACT OF THESE SUSPECTED INTERFERENCES ON HIS WORK. IF CONFLICTS EXIST, THE CONTRACTOR WILL IMMEDIATELY CONTACT THE ENGINEER AND PROVIDE THE ENGINEER WITH ALL THE NECESSARY DATA SUCH AS ELEVATIONS, HORIZONTAL LOCATIONS, ETC., AND PROVIDE THE ENGINEER WITH SKETCHES INDICATING THE PROPOSED IMPROVEMENT AND THE UTILITY CONFLICT. THE ENGINEER WILL EXAMINE AND REVIEW ALL THE DATA AND SKETCHES PROVIDED, AND WILL PROVIDE THE CONTRACTOR WITH AN ALTERNATIVE DESIGN WITHIN FIVE (5) DAYS AFTER RECEIPT OF DATA AND SKETCHES.
21. THE FOLLOWING DENSITIES WERE USED IN CALCULATING QUANTITIES FOR ASPHALT CONCRETE PAVEMENT.
    PLANTMIX BITUMINOUS SURFACING 155 LB/CF
    PLANTMIX BITUMINOUS OPEN-GRADED SURFACE 140 LB/CF

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

GENERAL & CONSTRUCTION NOTES, LEGEND AND ABBREVIATIONS, BENCHMARK, BASIS OF BEARINGS

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


NOEL G. LAUGHLIN — Exp. 12/31/2005 — CIVIL — No. 10165 — STATE OF NEVADA — PROFESSIONAL ENGINEER — 4-5-04

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
G-3
SHT. 3 OF 30



LINE TABLE		
No.	Bearing	Distance
L2	N 89°37'02" E	41.00'

CHANNEL ℄ LINE TABLE		
No.	Bearing	Distance
L1	N 00°00'06" W	150.00'
L3	N 00°22'58" E	20.22'
L4	N 66°00'50" E	75.33'
L5	N 00°22'58" W	109.59'
L6	N 00°02'58" W	50.00'

CHANNEL ℄ CURVE TABLE				
No	Radius	Delta	Length	Tangent
C1	807.70'	27°20'22"	385.40'	196.44'
C2	800.00'	31°55'40"	445.80'	228.85'
C3	462.47'	42°11'02"	340.49'	178.38'
C4	50.00'	66°23'48"	57.94'	32.72'

NORTH

SCALE 1" = 500'

500 0 500 1000

SCALE FEET

BASIS OF BEARINGS

SOUTH 00°18'40" EAST, BEING THE WEST LINE OF THE SOUTHWEST QUARTER (SW 1/4) OF SECTION 3, TOWNSHIP 21 SOUTH, RANGE 62 EAST, M.D.M., CLARK COUNTY, NEVADA. AS SHOWN BY FILE 36, PAGE 6 OF SURVEYS IN THE CLARK COUNTY RECORDER'S OFFICE CLARK COUNTY, NEVADA.

BENCHMARK

CLARK COUNTY BM – 6C02 33SWW6

RIVET AND SQUARE ALUMINUM PLATE IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND BELPORT DR. NEAR THE PC OF NELLIS BLVD.

ELEVATION: 531.863 METERS (NAVD 88)
1744.954 FEET (NAVD 88)

LEGEND

- ◉ FOUND MONUMENTATION AS SHOWN AND DESCRIBED
- × CALCULATED POINT
- —— —— SECTION LINE
- — — — QUARTER LINE
- — — — — 1/16 LINE

REFERENCES

FILE 36, PAGE 6 OF SURVEYS
FILE 122, PAGE 76 OF SURVEYS

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
HORIZONTAL CONTROL PLAN

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

LAND SURVEYOR DANNY E. HILL EXP.6/30/05 STATE OF NEVADA NO. 9389
5 APRIL 2004

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: 1" = 500'
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
G-4
SHT. 4 OF 30

BASE BID SCHEDULE
Estimate of Quantities

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTALS
100.01	CONSTRUCTION OFFICE	LS	1
105.01	ON-SITE MATERIAL TESTING FOR QUALITY CONTROL	LS	1
107.01	TRAFFIC CONTROL	LS	1
109.01	OWNER CAUSED DELAY ALLOWANCE	DAY	20
109.02	OWNER CAUSED DELAY ALLOWANCE ABOVE $500/DAY	DAY	20
109.03	CONSTRUCTION CONFLICTS AND ADDITIONAL WORK	LS	1
200.01	MOBILIZATION	LS	1
201.01	CLEARING AND GRUBBING	LS	1
202.01	REMOVE EXISTING SPLASH PADS (5 EACH)	LS	1
202.02	REMOVE EXISTING CHANNEL LINING FROM STA. 163+66 (RT) TO STA. 171+98 (RT)	LS	1
202.03	REMOVE EXISTING CHANNEL LINING FROM STA. 186+54 TO STA. 186+18	LS	1
202.04	REMOVE AND SALVAGE EXISTING RIPRAP ON WEST BANK FROM STA. 118+89 TO STA. 132+00	LS	1
202.05	REMOVE EXISTING BLOCK WALL AND FOOTING	LF	73
202.06	REMOVE EXISTING CHAIN-LINK FENCE	LF	515
203.01	CHANNEL EXCAVATION	CY	73,000
205.01	DEWATERING	LS	1
209.01	2-INCH DRAIN BACKFILL	CY	16,310
301.01	SELECTED MATERIAL BASE	CY	29,000
302.01	TYPE II AGGREGATE BASE	CY	4,100
302.02	TYPE II AGGREGATE BASE MAINTENANCE ROAD	CY	1,500
502.01	TRAPEZOIDAL TO TRAPEZOIDAL TRANSITION STA. 118+88.78 TO STA. 119+25	LS	1
502.02	TRAPEZOIDAL CHANNEL LINING STA. 119+38.78 TO STA. 122+58.37	LF	319.59
502.03	TRAPEZOIDAL CHANNEL TRANSITION STA. 122+58.37 TO STA. 123+00	LS	1
502.04	TRAPEZOIDAL CHANNEL LINING STA. 123+00 TO STA. 158+50	LF	3,550
502.05	TRAPEZOIDAL CHANNEL TRANSITION STA. 158+50 TO STA. 159+00	LS	1
502.06	TRAPEZOIDAL CHANNEL LINING STA. 159+00 TO STA. 160+29.41	LF	129.41
502.07	TRAPEZOIDAL TO RECTANGULAR TRANSITION STA. 160+29.41 TO STA. 160+79.41	LS	1
502.08	CONFLUENCE STRUCTURE STA. 160+79.41 TO STA. 162+79.41	LS	1
502.09	RECTANGULAR TO TRAPEZOIDAL TRANSITION STA. 162+79.41 TO STA. 163+29.41	LS	1
502.10	TRAPEZOIDAL CHANNEL LINING STA. 163+29.41 TO STA. 171+98.47; STA. 172+86.31 TO STA. 174+50; STA. 176+00 TO STA. 179+00	LF	1,332.75
502.11	CCRFCD CHANNEL GAUGE STATION	LS	1
502.12	TRAPEZOIDAL CHANNEL LINING WITH MAINTENANCE RAMP STA. 174+50 TO STA. 176+00	LS	1
502.13	MODIFIED TRAPEZOIDAL CHANNEL STA. 179+00 TO STA. 186+54.94	LF	755
502.14	TRAPEZOIDAL TO TRAPEZOIDAL TRANSITION STA. 186+54.94 TO STA. 187+18	LS	1
502.15	MAINTENANCE ROAD CROSSING STA. 130+71	LS	1
502.16	MAINTENANCE ROAD CROSSING STA. 165+68	LS	1
502.17	MAINTENANCE ROAD CROSSING STA. 184+79	LS	1
611.01	3-INCH CONCRETE SLOPE PAVEMENT	SY	34,113
616.01	6-FOOT CHAIN LINK FENCE	LF	160
616.02	POST AND CABLE RAILING	LF	2,000
627.01	PERMANENT SIGNS	EA	2
637.01	DUST PALLIATIVE	AC	13
637.02	DUST CONTROL	LS	1

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTALS

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
ESTIMATE OF QUANTITIES

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA
NOEL C. LAUGHLIN
Exp. 12/31/2005
CIVIL
No. 10165
4-5-04

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
G-5
SHT. 5 OF 30



SURVEYOR'S CERTIFICATE

I, DANNY E. HILL, A PROFESSIONAL LAND SURVEYOR LICENSED IN THE STATE OF NEVADA, CERTIFY THAT THIS MAP IS AN ACCURATE REPRESENTATION OF THE LANDS SURVEYED UNDER MY DIRECT SUPERVISION AT THE INSTANCE OF CLARK COUNTY PUBLIC WORKS. ALL SURVEY MONUMENTS FOUND OR SET ARE CORRECTLY SHOWN, OCCUPY THE POSITIONS INDICATED AND ARE SUFFICIENT TO ENABLE THE RETRACEMENT OF THE SURVEY WHICH WAS COMPLETED ON APRIL 16, 2002. THIS SURVEY PLAT DOES NOT CONSTITUTE A SUBDIVISION AS DEFINED BY NEVADA STATE LAW, THE LANDS LIE WITHIN SECTIONS 3 AND 10 TOWNSHIP 21 SOUTH, RANGE 62 EAST, M.D.M., CLARK COUNTY, NEVADA. THIS RECORD OF SURVEY IS FILED IN COMPLIANCE WITH PROVISIONS OF N.R.S. CHAPTER 278.325 AND WITH PROVISIONS OF N.R.S. CHAPTER 625.340.

DANNY E. HILL
PROFESSIONAL LAND SURVEYOR
NEVADA LICENSE NO. 9389

PROFESSIONAL LAND SURVEYOR — DANNY E. HILL — NO. 9389 — STATE OF NEVADA

07 JUNE 2002
EXP. 06-30-03

BASIS OF BEARINGS

SOUTH 00°18'40" EAST, BEING THE WEST LINE OF THE SOUTHWEST QUARTER (SW 1/4) OF SECTION 3, TOWNSHIP 21 SOUTH, RANGE 62 EAST, M.D.M., CLARK COUNTY, NEVADA. AS SHOWN BY FILE 36, PAGE 6 OF SURVEYS IN THE CLARK COUNTY RECORDER'S OFFICE, CLARK COUNTY, NEVADA.

NOTE:

THIS FIELD SURVEY WAS PERFORMED TO ESTABLISH AND MEMORIALIZE THE LEGAL RIGHT-OF-WAY AND/OR BOUNDARY LIMITS FOR THE CONSTRUCTION OF THE PROJECT SO THAT ALL INTERSECTIONS AND OTHER CONTROL POINTS FOR THE PROJECT CAN BE MONUMENTED IN ACCORDANCE WITH APPLICABLE STATE STATUTES AND LOCAL ORDINANCES AT THE COMPLETION OF CONSTRUCTION.

RECORDER'S NOTE:

ANY SUBSEQUENT CHANGES TO THIS MAP SHOULD BE EXAMINED AND MAY BE DETERMINED BY REFERENCE TO THE COUNTY RECORDER'S CUMULATIVE MAP INDEX.
N.R.S. 278.5695

LEGEND


- ◉ FOUND MONUMENTATION AS SHOWN AND DESCRIBED
- × CALCULATED POINT
- —— —— SECTION LINE
- — — — QUARTER LINE
- — — — — 1/16 LINE

LINE	BEARING	DISTANCE
L1	S89°37'24"W	200.01'
L2	S89°37'24"W	189.63'
L3	N89°43'35"E	136.48'
L4	N01°26'00"W	48.81'
L5	N01°26'00"W	51.30'
L6	S00°16'25"E	20.00'
L7	S89°43'35"W	250.11'
L8	S00°22'58"E	20.00'
L9	N31°11'20"W	409.00'
L10	S88°41'29"E	16.68'
L11	N00°22'58"W	107.76'
L12	S00°22'58"E	111.42'
L13	N00°22'58"W	2665.90'
L14	S00°26'46"E	1295.01'
L15	N88°41'29"W	18.11'
L16	N00°22'58"W	1369.09'
L17	N89°32'44"W	12.00'
L18	S00°22'58"E	1319.28'
L19	N00°22'58"W	1320.90'
L20	N89°36'56"E	112.00'
L21	N89°36'56"E	120.00'
L22	S00°02'58"E	1411.47'
L23	S00°02'58"E	1412.17'
L24	S84°21'34"E	180.49'
L25	S00°16'25"E	30.00'

REFERENCE MAPS

[1] FILE 36, PAGE 6 OF SURVEYS

CURVE	DELTA	RADIUS	LENGTH	TANGENT
C1	29°45'20"	738.00'	383.27'	196.06'
C2	29°45'20"	882.00'	447.66'	229.00'
C3	30°48'22"	882.00'	463.47'	237.48'
C4	30°48'22"	738.00'	396.80'	203.32'
C5	34°49'33"	527.97'	320.91'	165.59'
C6	51°31'45"	407.97'	366.91'	196.91'



500.857
SLOAN CHANNEL

SHEET 1 OF 1

RECORD OF SURVEY
FOR
CLARK COUNTY PUBLIC WORKS
SLOAN CHANNEL

THOSE PORTIONS OF LAND LYING WITHIN SECTIONS 3, AND 10, TOWNSHIP 21 SOUTH, RANGE 62 EAST, M.D.M., CLARK COUNTY, NEVADA.


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146

INSTRUMENT NO. 00924
OFFICIAL RECORDS
BOOK NO. 20020607
FILED AT THE REQUEST OF
G.C. WALLACE INC.
DATE 6-7-02 AT 10:39
FILE 122 PAGE 0076
OF SURVEYS
CLARK COUNTY, NEVADA RECORDS
JUDITH A. VANDEVER, RECORDER
FEE $ 0.00 DEPUTY GX

JOB# 500.857

FILE 122 PAGE 0076


F:\500-857\dwg\improv\sc_c01.dwg 04-05-04 08:10:57 RBlanchard




CHANNEL ℄ CURVE TABLE

CURVE TABLE

CURVE	DELTA	RADIUS	LENGTH	TANGENT
C1	27°20'55"	807.70'	385.53'	196.51'





CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(10) CONSTRUCT PIPE CONNECTION (SEE DETAIL 9/S2)

REMOVAL NOTES

[2] REMOVE AND SALVAGE RIPRAP


[6] REMOVE EXISTING CONCRETE SPILLWAY

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

Avoid cutting underground utility lines. It's costly.
Call before you Dig.
1-800-227-2600
UNDERGROUND SERVICE (USA)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY.
CALL BEFORE YOU DO OVERHEAD
1-702-593-6111



REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

PLAN AND PROFILE

STA. 114+50.00 TO STA. 122+00.00

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER NOEL C. LAUGHLIN Exp. 12/31/2005 CIVIL No. 10158 STATE OF NEVADA 4-5-04

PROJECT No: 500.857 DRAWN BY: DVJ

DESIGNED BY: _____ CHECKED BY: _____

APPROVED BY _____

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK

L-1759
DRAWING NO.
C-1
SHT. 7 OF 30

F:\500-857\dwg\improv\sc_c02.dwg 04-05-04 08:20:23 RBlanchard

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES


SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.


SOUTHERN NEVADA WATER AUTHORITY — 04/15/04 DATE

NOTE: SEE SHEET G-3 FOR SNWA CONSTRUCTION NOTES.

NORTH SCALE 1" = 40'

SCALE 40 0 40 80 FEET





CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(10) CONSTRUCT PIPE CONNECTION (SEE DETAIL 9/S2)

(11) CONSTRUCT RCB CONNECTION (SEE DETAIL 3/S7)

REMOVAL NOTES

[2] REMOVE AND SALVAGE RIPRAP

[6] REMOVE EXISTING CONCRETE SPILLWAY

CHANNEL ℄ CURVE TABLE


CURVE TABLE				
CURVE	DELTA	RADIUS	LENGTH	TANGENT
C1	27°20'55"	807.70'	385.53'	196.51'
C2	31°55'41"	800.00'	445.80'	228.85'

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

Avoid cutting underground utility lines. It's costly. Call before you Dig. 1-800-227-2600 UNDERGROUND SERVICE (USA)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY. CALL BEFORE YOU DO OVERHEAD 1-702-593-6111



REV. NO.	DATE	DESCRIPTION	APPROVED

SLOAN CHANNEL
PLAN AND PROFILE
STA. 122+00.00 TO STA. 132+00.00
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

NOEL C. LAUGHLIN Exp. 12/31/2005 CIVIL No. 10165 STATE OF NEVADA 4-5-04


PROJECT No: 500.857 DRAWN BY: DWJ
DESIGNED BY: _____ CHECKED BY: _____
APPROVED BY _____

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK

L-1759
DRAWING NO.
C-2
SHT. 8 OF 30

F:\500-857\dwg\improv\sc_c03.dwg 04-05-04 08:55:16 RBlanchard



SLOAN CHANNEL



CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(12) CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

[2] REMOVE AND SALVAGE RIPRAP

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES

SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.


Manson 04/15/04

SOUTHERN NEVADA WATER AUTHORITY DATE

NOTE: SEE SHEET G-3 FOR SNWA CONSTRUCTION NOTES.

Avoid cutting underground utility lines. It's costly. Call before you Dig. 1-800-227-2600 UNDERGROUND SERVICE (USA)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY. CALL BEFORE YOU DO OVERHEAD 1-702-593-6111



Key Map

SCALE: NOT TO SCALE

REV. NO.	DATE	DESCRIPTION	APPROVED

SLOAN CHANNEL

PLAN AND PROFILE

STA. 132+00.00 TO STA. 142+00.00

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

NOEL C. LAUGHLIN Exp. 12/31/2005 CIVIL No. 10165 PROFESSIONAL ENGINEER STATE OF NEVADA 4-5-04

PROJECT No: 500.857 DRAWN BY: DWJ


DESIGNED BY: _____ CHECKED BY: _____


APPROVED BY _____


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK

L-1759
DRAWING NO.
C-3
SHT. 9 OF 30







CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(12) CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

[3] REMOVE EXISTING CONCRETE SPLASH PAD

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES


SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.

SOUTHERN NEVADA WATER AUTHORITY — DATE 04/15/04

NOTE: SEE SHEET G-3 FOR SNWA CONSTRUCTION NOTES.

Avoid cutting underground utility lines. It's costly.
Call before you Dig.
1-800-227-2600
UNDERGROUND SERVICE (USA)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY
CALL BEFORE YOU DO OVERHEAD
1-702-593-6111



REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
PLAN AND PROFILE
STA. 142+00.00 TO STA. 152+00.00
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER — NOEL LAUGHLIN — Exp. 12/31/2005 — CIVIL — No. 10169 — STATE OF NEVADA — 4-5-04


PROJECT No: 500.857 DRAWN BY: DWJ
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK


L-1759
DRAWING NO.
C-4
SHT. 10 OF 30

F:\500-857\dwg\improv\sc_c05.dwg 04-05-04 08:23:31 RBlanchard



SLOAN CHANNEL





CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(12) CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

[1] REMOVE EXISTING BLOCK WALL AND FOOTING

[3] REMOVE EXISTING CONCRETE SPLASH PAD

[5] REMOVE EXISTING CHANNEL LINING.

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES


SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.

SOUTHERN NEVADA WATER AUTHORITY 04/15/04 DATE

NOTE: SEE SHEET G-3 FOR SNWA CONSTRUCTION NOTES.

Avoid cutting underground utility lines. It's costly.
Call before you Dig.
1-800-227-2600
UNDERGROUND SERVICE (USA)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY
CALL BEFORE YOU DO OVERHEAD
1-702-593-6111



REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
PLAN AND PROFILE
STA. 152+00.00 TO STA. 162+50.00
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


NOEL C. LAUGHLIN Exp. 12/31/2005 CIVIL No. 10165 STATE OF NEVADA PROFESSIONAL ENGINEER 4-5-04


PROJECT No: 500.857 DRAWN BY: DVJ
DESIGNED BY: _____ CHECKED BY: _____
APPROVED BY _____


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK

L-1759
DRAWING NO.
C-5
SHT. 11 OF 30







CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(11) CONSTRUCT RCB CONNECTION (SEE DETAIL 3/S7)

(12) CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

[3] REMOVE EXISTING CONCRETE SPLASH PAD

[5] REMOVE EXISTING CHANNEL LINING.

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES


SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.

SOUTHERN NEVADA WATER AUTHORITY — DATE 04/15/04

NOTE: SEE SHEET G-3 FOR SNWA CONSTRUCTION NOTES.

Avoid cutting underground utility lines. It's costly.
Call before you Dig.
1-800-227-2600
UNDERGROUND SERVICE (USA)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY.
CALL BEFORE YOU DO OVERHEAD
1-702-593-6111



REV. NO.	DATE	DESCRIPTION	APPROVED

SLOAN CHANNEL
PLAN AND PROFILE
STA. 162+50.00 TO STA. 171+00.00
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

NOEL LAUGHLIN — PROFESSIONAL ENGINEER — STATE OF NEVADA — Exp. 12/31/2005 — No. 10165 — CIVIL — 4-5-04

PROJECT No: 500.857 DRAWN BY: DVJ
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK

L-1759
DRAWING NO.
C-6
SHT. 12 OF 30

F:\500-857\dwg\improv\sc_c07.dwg 04-05-04 08:57:42 RBlanchard

MATCH LINE – STA. 171+00.00 SEE SHEET C-6

MATCH LINE – STA. 181+00.00 SEE SHEET C-8

42+63.48 ℄ SAHARA AVE.

172+42.15 ℄ SLOAN CHANNEL

N89°36'24"E

100.00' SAHARA AVE. R/W

12' ACCESS/ MAINTENANCE ROAD

ACCESS RAMP SEE SHEETS S-5 AND S-6 FOR DETAILS AND SECTIONS.

STA 177+50.00 49.70' LT CONSTRUCT DISTRICT GAUGING STATION, SEE DETAILS SHEET C-17

SN.W.A. EASEMENT 980714:01468 980911:01363

FIBER OPTICS CONDUIT

4" FIBER OPTICS CONDUIT

16TH LINE EASEMENT LINE

℄ CHANNEL

S 00°02'58" E

0.46%

0.53%

5' MANWAY

SAHARA AVENUE

35' NEVADA POWER CO. EASEMENT

EASEMENT LINE

100.00' SAHARA AVE. R/W

N89°36'56"E

27" SS

3" PVC

172+00 173+00 174+00 175+00 176+00 177+00 178+00 179+00 180+00 181

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES

SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.

SOUTHERN NEVADA WATER AUTHORITY — DATE 04/15/04

LAS VEGAS VALLEY WATER DISTRICT — DATE 4/5/04

NOTE: SEE SHEET G-3 FOR SNWA CONSTRUCTION NOTES.

NORTH

SCALE 1" = 40'

40 0 40 80

SCALE FEET

CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(4) CONSTRUCT 12' DRIVEWAY PER STD. DWG. NO. 224

(8) PAINTED STAFF GAUGE (SEE DETAIL 5/C11)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(12) CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

[5] REMOVE EXISTING CHANNEL LINING.

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

CONTRACTOR TO EXERCISE EXTREME CARE WHEN EXCAVATING WITHIN 10 FEET (HORIZONTAL) OF SNWA WATERLINE. SNWA TO BE PRESENT DURING EXCAVATION WITHIN AFOREMENTIONED LIMITS.

Avoid cutting underground utility lines. It's costly.
Call before you Dig.
1-800-227-2600
UNDERGROUND SERVICE (USA)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY
CALL BEFORE YOU DO OVERHEAD
1-702-593-6111

SLOAN CHANNEL

1712 1704 1696 1688 1680

171+98.47, CHANNEL ON RIGHT SIDE EXISTING FROM TOE OF SLOPE TO TOP OF SLOPE

SAHARA AVENUE

SLOPE PAVING LEFT SIDE

TOP OF CHANNEL BOTH SIDES

SLOPE PAVING RIGHT SIDE

ACCESS RAMP LEFT SIDE

HGL

6.65' BOTH SIDES

17.5' BOTH SIDES

EXIST CULVERT

97.90 FL

(97.37) FL

(97.09) FL

-0.53%

-(0.32%)

-0.46%

$Q_{ult\,100}$=4416 cfs

PROPOSED FLOWLINE CHANNEL

EX. 78" SNWA WATERLINE

EXIST. GRADE ℄ CHANNEL

93.33 FL

STA. 171+17± 66.1'± LT 1694.3± INV.

STA. 171+69± 65.8'± LT 1680.8± INV

12" 18" 8" 6"

EXIST. CONC. ENCASED SEWER SIPHON INV.= 89.4'±

STA. 173+19± 65.0'± LT 1680.5± INV

STA. 173+72± 64.7'± LT 1693.5± INV

STA. 173+76± SNWA STA. 85+40± 69.3'± LT EX. BLOW OFF ASSEMBLY

STA. 173+86± SNWA STA. 85+40± 68.1'± LT EX. BLOW OFF ASSEMBLY

STA. 177+65± SNWA STA. 81+50± 62.9'± LT EX. MANWAY W/ ACCESS

STA. 178+50.00 BEGIN HEIGHT TRANSITION (LEFT SIDE) 1694.48 FL

STA. 179+00.00 BEGIN HEIGHT TRANSITION (LEFT SIDE) 1694.25 FL


STA = 171+98.47 MATCH EXISTING/ GRADE BREAK (1697.37) FL SEE SHEET S-2

EX. 18" DIP W/ 30" STL CASING 1691.5± TOP CASING

STA = 172+98.31 MATCH EXISTING/ GRADE BREAK (1697.09) FL SEE SHEET S-2

STA. 173+10± "SNWA" STA. 86+11± 68.7'± LT EX. MANWAY W/ ACCESS AND BLOWOFF

171+00 172+00 173+00 174+00 175+00 176+00 177+00 178+00 179+00 180+00 181+00



Key Map
SCALE: NOT TO SCALE

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
PLAN AND PROFILE
STA. 171+00.00 TO STA. 181+00.00
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

NOEL C. LAUGHLIN Exp. 12/31/2005 CIVIL No. 10165 STATE OF NEVADA PROFESSIONAL ENGINEER 4-5-04


PROJECT No: 500.857 DRAWN BY: DWJ
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK

L-1759
DRAWING NO. C-7
SHT. 13 OF 30

F:\500-857\dwg\improv\sc_c08.dwg 04-05-04 09:00:50 RBlanchard



NORTH
SCALE 1" = 40'

40 0 40 80
SCALE FEET

CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(10) CONSTRUCT PIPE CONNECTION (SEE DETAIL 9/S2)

(11) CONSTRUCT RCB CONNECTION (SEE DETAIL 3/S7)

(12) CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

[3] REMOVE EXISTING CONCRETE SPLASH PAD

[4] REMOVE EXISTING 60 FT.± CHANNEL SECTION TO EXPANSION JOINT.

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

CONTRACTOR TO EXERCISE EXTREME CARE WHEN EXCAVATING WITHIN 10 FEET (HORIZONTAL) OF SNWA WATERLINE. SNWA TO BE PRESENT DURING EXCAVATION WITHIN AFOREMENTIONED LIMITS.

SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES

SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.

SOUTHERN NEVADA WATER AUTHORITY — DATE 04/15/04

NOTE: SEE SHEET G-3 FOR SNWA CONSTRUCTION NOTES.


SLOAN CHANNEL


CHANNEL ℄ CURVE TABLE

CURVE TABLE				
CURVE	DELTA	RADIUS	LENGTH	TANGENT
C3	51°57'23"	462.47'	419.37'	225.34'

Avoid cutting underground utility lines. It's costly. Call before you Dig. 1-800-227-2600 UNDERGROUND SERVICE (USA)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY. CALL BEFORE YOU DO OVERHEAD 1-702-593-6111





REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
PLAN AND PROFILE
STA. 181+00.00 TO STA. 190+00.00
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


NOEL C. LAUGHLIN Exp. 12/31/2005 CIVIL No. 10165 STATE OF NEVADA PROFESSIONAL ENGINEER 4-5-04

PROJECT No: 500.857 DRAWN BY: DVJ
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK

L-1759
DRAWING NO.
C-8
SHT. 14 OF 30




SOUTHERN NEVADA WATER AUTHORITY CONSTRUCTION NOTES

SNWA APPROVAL IS VALID FOR ONE (1) YEAR FROM THE SIGNATURE DATE. IF CONSTRUCTION WITHIN THE EASEMENT OR RESTRICTED PIPE SAFETY ZONE IS NOT COMPLETE, PLANS MUST BE RESUBMITTED TO SNWA FOR APPROVAL.


SOUTHERN NEVADA WATER AUTHORITY — 04/15/04 DATE


NOTE: SEE SHEET G-3 FOR SNWA CONSTRUCTION NOTES.



STORM DRAIN LATERAL (STA. 165+67.32)


NOT TO SCALE — 2 / C9






STORM DRAIN LATERAL (STA. 184+78.98)

NOT TO SCALE — 3 / C9



STORM DRAIN LATERAL (STA. 130+86.62)

NOT TO SCALE — 1 / C9



CONSTRUCTION NOTES

(3) CONSTRUCT CHANNEL ACCESS STEPS (SEE DETAIL 11/S2)

(9) CONSTRUCT SLOPE PAVING (SEE DETAIL 3/C11)

(12) CONTRACTOR SHALL FIELD VERIFY AND FLAG ALL SNWA APPURTENANCES AND PROTECT FROM DAMAGE AND BEING BURIED.

REMOVAL NOTES

[1] REMOVE EXISTING BLOCK WALL AND FOOTING


[5] REMOVE EXISTING CHANNEL LINING.

NOTE:

SEE SHEETS C-13 AND C-14 FOR FENCING/POST & CABLE RAILING PLAN.

Avoid cutting underground utility lines. It's costly.
Call before you Dig.
1-800-227-2600
UNDERGROUND SERVICE (USA)

AVOID HITTING OVERHEAD POWER LINES. IT'S COSTLY.
CALL BEFORE YOU DO OVERHEAD
1-702-593-6111



REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
PLAN AND PROFILE (CONFLUENCE) AND LATERALS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA — NOEL C. LAUGHLIN — Exp. 12/31/2005 — CIVIL — No. 10165 — 4-5-04

PROJECT No: 500.857 DRAWN BY: DVJ
DESIGNED BY: _____ CHECKED BY: _____
APPROVED BY _____

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE	
HORIZ:	1" = 40'
VERT:	1" = 4'
FIELD BOOK	


L-1759
DRAWING NO.
C-9
SHT. 15 OF 30



SECTION (STA. 163+29.41 TO STA. 165+00.00)
(STA. 166+27.37 TO STA. 167+50.00)

NOT TO SCALE


12 C-10



SECTION

NOT TO SCALE

11 C-10



SECTION (STA. 182+17.17 TO STA. 184+00.00)
(STA. 185+50.00 TO STA. 186+54.00)


NOT TO SCALE

10 C-10

SECTION (STA. 179+00.00 TO STA. 182+17.17)

NOT TO SCALE


9 C-10



SECTION (STA. 176+00.00 TO STA. 178+50.00)

NOT TO SCALE


8 C-10



SECTION (STA. 173+70.00 TO STA. 174+00.00)

NOT TO SCALE

7 C-10



SECTION (STA. 168+00.00 TO STA. 171+33.63)


NOT TO SCALE

6 C-10

SECTION (STA. 145+03.96 TO STA. 158+50.00)

NOT TO SCALE


5 C-10



SECTION (STA. 132+51.17 TO STA. 145+03.96)

NOT TO SCALE


4 C-10



SECTION (STA. 126+67.44 TO STA. 129+63.93)

NOT TO SCALE


3 C-10



SECTION (STA. 122+98.37 TO STA. 125+00.00)

NOT TO SCALE

2 C-10



SECTION (STA. 119+38.78 TO STA. 122+58.37)

NOT TO SCALE

1 C-10

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
SECTIONS

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA NOEL C. LAUGHLIN Exp. 12/31/2005 CIVIL No. 10165 4-5-04

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE	
HORIZ:	NONE
VERT:	NONE
FIELD BOOK	

L-1759
DRAWING NO.
C-10
SHT. 16 OF 30




POST AND CABLE RAILING DETAILS

NOT TO SCALE — 10 C11




WARNING SIGN - FLOOD CHANNEL DETAIL

NOT TO SCALE — 7 C11



PERMANENT CHANNEL SIGN DETAIL

NOT TO SCALE — 6 C11



SLOPE PAVING DETAIL

NOT TO SCALE — 3 C11





TABLE I FOR 6' HIGH CHAIN LINK FENCE		
LOCATION	MIN. SIZE	MIN. WEIGHT
END, CORNER AND PULL	2.351 O.D.	3.10
LINE	2.00 O.D.	2.72
BRACES	1.63 O.D.	2.27
TOP RAIL	1.63 O.D.	2.27

NOTES:
1. FENCING SHALL BE CHAIN LINK AND SHALL CONSIST OF GALVANIZED CHAINLINK FABRIC ON STEEL POSTS.
(A) ALL POST TOPS SHALL BE FITTED WITH SUITABLE FINIALS.
(B) BRACES SHALL BE SPACED APPROXIMATELY 12" BELOW TOP OF TERMINAL POSTS AND SHALL EXTEND FROM END, GATE, OR CORNER POSTS TO FIRST ADJACENT LINE POST.
(C) ALL FITTINGS SHALL BE HOT DIPPED GALVANIZED MALLEABLE, CAST IRON, OR PRESSED STEEL
(D) TOP AND BOTTOM SELVAGES OF THE FENCE SHALL HAVE A TWISTED AND BARBED FINISH.

CHAIN LINK FENCE DETAIL

NOT TO SCALE — 9 C11

FENCE PLAN (TYPICAL)



PAINTED STAFF GAUGE


NOT TO SCALE — 5 C11

TYPICAL LETTERING DIMENSIONS

NOTE: UNITS SHALL BE IN FEET AND BE GRADUATED IN IN TENTHS OF FEET

STAFF GAUGE LOCATIONS


STATIONS	
LT	RT
173+00.00	171+75.00
	177+50.00



SLOPE PAVING DETAIL

NOTE: WEAKENED PLANE JOINTS ARE NOT SEALED.

NOT TO SCALE — 2 C11




GATE SWING POST DIA.	
GATE SIZE	PIPE DIA.
6' AND LESS	3"O.D.-5.79 LB/ FT
6' - 10'	4"O.D.-9.10 LB/ FT

CHAIN LINK GATE DETAIL


NOT TO SCALE — 8 C11

GATE SWING POST DIA.	
GATE SIZE	PIPE DIA.
6' AND LESS	3"O.D.-5.79 LB/ FT
6' - 10'	4"O.D.-9.10 LB/ FT



MANWAY DETAIL

NOT TO SCALE — 4 C11



POST AND CABLE RAILING POLE MOUNT

NOT TO SCALE — 1 C11

REV. NO.	DATE	DESCRIPTION	APPROVED

SLOAN CHANNEL
DETAILS


CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
C-11
SHT. 17 OF 30




SECTION (STA. 162+25.00 TO STA. 162+79.41) — 3 / C-12

NOT TO SCALE



SECTION (STA. 160+79.41 TO STA. 161+59.19) — 2 / C-12

NOT TO SCALE



SECTION (STA. 159+00.00 TO STA. 160+29.41) — 1 / C-12

NOT TO SCALE

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
SECTIONS

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA — NOEL C. LAUGHLIN — Exp. 12/31/2005 — CIVIL — No. 10185 — 4-5-04


PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
C-12
SHT. 18 OF 30








CONSTRUCTION NOTES

1. CONSTRUCT 6' CHAIN-LINK FENCE (SEE DETAIL 9/C11)
2. CONSTRUCT 6' CHAIN-LINK GATE (SEE DETAIL 8/C11) (WIDTH OF GATE CALLED OUT IN PLAN VIEW)
5. INSTALL SIGN (SEE DETAIL 6/C11)
6. INSTALL SIGN (SEE DETAIL 7/C11)
7. CONSTRUCT POST AND CABLE RAILING (SEE DETAIL 10/C11)

REMOVAL NOTES

7. REMOVE EXISTING CHAIN-LINK FENCE.



POST AND CABLE CURVE TABLE

CURVE TABLE				
CURVE	DELTA	RADIUS	LENGTH	TANGENT
C15	22°40'28"	855.50'	338.56'	171.52'
C16	01°09'50"	861.63'	17.50'	8.75'
C17	66°23'48"	58.50'	67.79'	38.28'
C18	66°23'48"	41.50'	48.09'	27.16'
C16	01°09'50"	848.80'	17.24'	8.62'

POST AND CABLE LINE TABLE

LINE TABLE		
LINE	BEARING	LENGTH
L39	N02°31'07"E	52.38'
L40	N39°02'59"W	41.25'
L42	N25°32'04"E	26.11'
L43	N66°00'50"E	28.64'
L44	N23°59'10"W	17.00'
L45	N73°30'24"W	26.11'
L46	N66°00'50"E	10.50'
L47	N00°22'58"W	120.26'
L48	N08°08'53"E	50.60'
L49	N15°28'19"E	51.91'
L50	N00°22'58"W	99.93'
L51	N04°36'54"W	50.12'
L52	N00°22'58"W	249.98'
L53	N00°02'58"W	50.00'

FENCE LINE TABLE

LINE TABLE		
LINE	BEARING	LENGTH
L35	N08°30'51"W	30.45'
L36	N89°33'09"E	16.00'
L37	N09°23'22"E	18.85'
L38	N43°12'16"E	21.62'

REV. NO.	DATE	DESCRIPTION	APPROVED

SLOAN CHANNEL
FENCING/POST AND CABLE RAILING PLAN

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA NOEL C. LAUGHLIN Exp. 12/31/2005 CIVIL No. 10165 4-5-04


PROJECT No: 500.857 DRAWN BY: DWJ
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: 1" = 40'
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
C-13
SHT. 19 OF 30





POST AND CABLE LINE TABLE

LINE TABLE		
LINE	BEARING	LENGTH
L65	N07°01'09"E	50.35'
L66	N00°02'58"W	753.89'
L67	N16°19'46"W	59.16'
L68	N00°02'58"W	50.00'
L69	N00°02'58"W	436.83'
L70	N01°48'00"W	70.06'
L71	S89°57'02"W	4.50'
L72	S00°02'58"E	7.83'
L73	S89°57'02"W	4.50'

FENCE LINE TABLE

LINE TABLE		
LINE	BEARING	LENGTH
L54	N89°36'24"E	66.37'
L55	N00°27'55"W	26.40'
L56	N89°32'05"E	17.26'
L57	N58°30'46"E	19.47'
L58	N00°22'58"W	28.89'
L59	N89°56'23"E	1.37'
L60	N83°53'00"W	4.45'
L61	N83°45'44"E	40.84'
L62	N00°02'58"W	29.68'
L63	N62°55'16"E	14.01'
L64	N00°02'58"W	21.80'

NORTH

SCALE 1" = 40'

40 0 40 80

SCALE FEET

CONSTRUCTION NOTES

1. CONSTRUCT 6' CHAIN-LINK FENCE (SEE DETAIL 9/C11)
2. CONSTRUCT 6' CHAIN-LINK GATE (SEE DETAIL 8/C11) (WIDTH OF GATE CALLED OUT IN PLAN VIEW)
5. INSTALL SIGN (SEE DETAIL 6/C11)
6. INSTALL SIGN (SEE DETAIL 7/C11)
7. CONSTRUCT POST AND CABLE RAILING (SEE DETAIL 10/C11)

CONSTRUCTION NOTES

7. REMOVE EXISTING CHAIN-LINK FENCE.

REV. NO.	DATE	DESCRIPTION	APPROVED

SLOAN CHANNEL

FENCING/POST AND CABLE RAILING PLAN

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER STATE OF NEVADA NOEL C. LAUGHLIN Exp. 12/31/2005 CIVIL No. 10165 4-5-04

PROJECT No: 500.857 DRAWN BY: DVJ

DESIGNED BY: CHECKED BY:

APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE

HORIZ: 1" = 40'

VERT: NONE

FIELD BOOK


L-1759

DRAWING NO.

C-14

SHT. 20 OF 30

F:\500-857\dwg\improv\sc_c15.dwg 04-05-04 09:03:38 RBlanchard



40 0 40 80
SCALE FEET

ACCESS/ MAINTENANCE ROAD ℄ LINE TABLE

LINE TABLE		
LINE	BEARING	LENGTH
L3	S00°49'42"W	48.17'
L4	S23°55'17"E	22.80'
L5	S32°18'38"E	225.35'
L6	S32°53'00"E	100.03'
L7	S32°18'38"E	51.79'
L8	S02°48'57"E	77.41'
L9	S01°58'00"E	36.30'
L10	S00°02'58"E	20.23'
L11	S02°28'47"W	20.02'
L12	S00°22'58"E	940.87'
L13	S02°06'04"E	20.01'
L35	S00°22'58"E	20.18'
L36	S01°20'08"E	20.01'
L37	S00°22'58"E	924.87'
L38	S07°58'39"E	30.27'
L39	S00°22'58"E	30.80'
L40	S07°12'43"E	30.27'
L41	S00°02'58"E	582.12'
L42	S03°23'36"W	50.11'
L43	S00°22'58"E	119.19'
L44	S23°59'10"E	95.58'

ACCESS/ MAINTENANCE ROAD ℄ CURVE TABLE

CURVE TABLE				
CURVE	DELTA	RADIUS	LENGTH	TANGENT
C5	22°03'58"	750.40'	289.00'	146.31'
C6	31°53'55"	855.30'	476.17'	244.43'
C7	23°36'12"	56.00'	23.07'	11.70'

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

ACCESS/MAINTENANCE CONTROL PLAN

STA. 118+82.26 TO STA. 161+00.00

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER STATE OF NEVADA
NOEL C. LAUGHLIN
Exp. 12/31/2005
CIVIL
No. 10185
4-5-04


PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE (702) 804-2000 • FAX: (702) 804-2299


SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK


L-1759
DRAWING NO.
C-15
SHT. 21 OF 30

F:\500-857\dwg\improv\sc_c16.dwg 04-05-04 09:04:07 RBlanchard









ACCESS/ MAINTENANCE ROAD ℄ LINE TABLE

LINE TABLE		
LINE	BEARING	LENGTH
L13	S23°59'10"E	55.22'
L14	S00°02'58"E	53.46'
L15	S00°22'58"E	138.98'
L16	S00°02'58"E	31.72'
L17	N04°06'16"W	42.21'
L18	S00°02'58"E	50.47'
L19	S04°50'32"E	35.18'
L20	S01°11'43"E	122.31'
L21	S00°02'58"E	333.69'
L22	S00°23'04"E	5.89'
L23	S00°35'33"W	39.05'
L24	S00°02'58"E	30.60'
L25	S11°28'07"E	51.91'
L26	S00°49'43"W	148.58'
L27	S00°02'58"E	250.32'
L28	S07°01'09"W	50.38'
L29	S00°02'58"E	499.52'
L30	S02°10'18"E	54.01'
L31	S00°02'58"E	50.24'
L32	S02°26'19"W	46.07'
L33	S00°02'58"E	103.32'
L34	S08°39'47"E	57.00'

ACCESS/ MAINTENANCE ROAD ℄ CURVE TABLE

CURVE TABLE				
CURVE	DELTA	RADIUS	LENGTH	TANGENT
C8	23°56'12"	56.00'	23.40'	11.87'
C9	41°05'27"	94.00'	67.41'	35.23'
C10	41°25'26"	94.00'	67.96'	35.54'
C11	31°26'16"	56.00'	30.73'	15.76'
C12	31°06'10"	56.00'	30.40'	15.58'
C13	67°38'26"	24.00'	28.33'	16.08'
C14	68°16'57"	24.00'	28.60'	16.27'

REV. NO.	DATE	DESCRIPTION	APPROVED

SLOAN CHANNEL

ACCESS/MAINTENANCE ROAD CONTROL PLAN
STA. 161+00.00 TO STA. 181+82.26
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA NOEL O. LAUGHLIN Exp. 12/31/2005 CIVIL No. 10165 4-5-04

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY:


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: 1" = 40'
VERT: 1" = 4'
FIELD BOOK


L-1759
DRAWING NO.
C-16
SHT. 22 OF 30




LOCKING BAR GUIDE
NOT TO SCALE




PLAN
NOT TO SCALE




DETAIL A
NOT TO SCALE




SECTION B-B
(STRUCTURAL REINFORCING BETWEEN MANHOLES)
NOT TO SCALE



SECTION A-A
NOT TO SCALE



SECTION C-C
NOT TO SCALE



GAUGING STATION STENCIL DETAIL
(VIEW FROM INSIDE OF GAUGING STATION)
NOT TO SCALE

REV. NO.	DATE	DESCRIPTION	APPROVED

SLOAN CHANNEL
GAUGING STATION
SECTION AND DETAILS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


NOEL C. LAUGHLIN — Exp. 12/31/2005 — CIVIL — No. 10165 — STATE OF NEVADA — REGISTERED ENGINEER
4-5-04

PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE	
HORIZ:	NONE
VERT:	NONE
FIELD BOOK	

L-1759
DRAWING NO. C-17
SHT. 23 OF 30




WALL EXPANSION JOINT DETAIL (8)
NOT TO SCALE





(*) UNLESS OTHERWISE NOTED

SLAB EXPANSION JOINT DETAIL (5)
NOT TO SCALE



WALL JOINT DETAIL (9)
NOT TO SCALE






NOTES:
1. WEAKENED PLANE JOINTS TO BE CENTERED WITH WEEPHOLES WHEN JOINTS OCCUR.
2. IN CURVED ALIGNMENT SECTIONS, TRANSVERSE JOINTS SHALL BE NORMAL TO CENTERLINE AND SHALL NOT EXCEED 60' MAX SPACING.


PLAN - CONCRETE LINED TRAPEZOIDAL CHANNEL (1)
NOT TO SCALE

STRUCTURE NOTES

1. DESIGN SPECIFICATIONS: AASHTO "STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, 1996" AND INTERIMS THROUGH 2000. REINFORCED CONCRETE DESIGN BASED ON LOAD FACTOR DESIGN.
2. CONSTRUCTION SPECIFICATIONS: UNIFORM STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, OFF-SITE IMPROVEMENTS, CLARK COUNTY AREA, NEVADA.
3. LIVE LOAD: STANDARD AASHTO HS20-44 TRUCK LOADING AND TRAFFIC SURCHARGE FROM MAINTENANCE VEHICLES (2' OF SOIL)
4. SEISMIC LOAD: ACCELERATION COEFFICIENT 0.15 g
5. CONCRETE: ALL CONCRETE SHALL BE CLASS A MODIFIED (MAJOR) EXCEPT FOR WALLS WHICH SHALL BE CLASS D MODIFIED (MAJOR). ONLY TYPE V CEMENT SHALL BE USED FOR CONCRETE IN CONTACT WITH SOIL. CONCRETE COMPRESSIVE MINIMUM STRENGTH AT 28 DAYS SHALL BE, f'c=4,500 PSI AND A MAXIMUM WATER TO CEMENT RATIO, BY WEIGHT, OF 0.45.
6. REINFORCING STEEL: ALL REINFORCING STEEL SHALL BE ASTM A615 REINFORCING STEEL STRENGTH, Fy = 60,000 PSI.
7. ALL EXPOSED EDGES OF CONCRETE SHALL BE CHAMFERED 3/4" UNLESS OTHERWISE INDICATED.
8. TRANSVERSE AND LONGITUDINAL JOINTS IN INVERT SLAB AND SIDE SLOPE SLAB OF PAVED TRAPEZOIDAL CHANNELS AND WALLS FOR RECTANGULAR CHANNELS WILL BE REQUIRED AT THE END OF EACH CONTINUOUS POURING OPERATION. SEE TYPICAL CONSTRUCTION JOINT DETAIL. TRANSVERSE CONSTRUCTION JOINTS SHALL NOT BE PLACED WITHIN 3-FEET OF A MANHOLE, WITHIN 10-FEET OF JUNCTION STRUCTURE OPENINGS, OR WITHIN 50 FEET OF AN EXPANSION JOINT.
9. ALL TRANSVERSE JOINTS IN WALLS AND SLABS (CONSTRUCTION, WEAKENED CONTRACTION AND EXPANSION) SHALL BE IN THE SAME PLANE. NO STAGGERING OF JOINTS WILL BE PERMITTED UNLESS SHOWN OTHERWISE. TRANSVERSE CONSTRUCTION JOINTS SHALL BE NORMAL OR RADIAL TO CENTERLINE OF CONSTRUCTION.
10. ALL SINGLE LAYER REINFORCEMENT SHALL BE PLACED IN THE CENTER OF CONCRETE UNLESS NOTED OTHERWISE.
11. IN CURVED CHANNEL SECTIONS TRANSVERSE BARS SHALL BE PLACED NORMAL TO THE CHANNEL CENTERLINE.
12. IN CURVED CHANNEL SECTIONS, THE MAXIMUM SPACING OF BARS SHALL NOT EXCEED THAT SHOWN FOR TYPICAL SECTIONS. STEEL SHALL BE PLACED RADIALLY FROM THE MAXIMUM SPACING.
13. AT THE BEGINNING AND ENDING OF ALL POURS, A COMPLETE CURTAIN OF MAIN REINFORCEMENT SHALL BE PLACED 3-INCHES FROM THE TRANSVERSE CONSTRUCTION, CONTRACTION AND EXPANSION JOINTS.
14. NO WELDING WILL BE PERMITTED ON ANY REINFORCEMENT.
15. CHANNEL ELEVATIONS: FOR CHANNEL INVERT ELEVATIONS REFER TO THE CHANNEL PLAN AND PROFILE SHEETS LOCATED ELSEWHERE IN THIS DRAWING SET.
16. EXCAVATION AND BACKFILL: THE LIMITS OF EXCAVATION AND BACKFILL SHALL BE AS SHOWN IN THE STATE OF NEVADA, "STANDARD PLANS FOR ROAD AND BRIDGE CONSTRUCTION, JANUARY 2001," UNLESS OTHERWISE NOTED.
17. WEEPHOLES: WEEPHOLES WILL BE REQUIRED AT 30-FEET O.C. PER THE TYPICAL WEEPHOLE DETAIL FOR ALL OPEN CHANNEL STRUCTURES.
18. BEDDING MATERIALS: UNLESS NOTED OTHERWISE ALL BEDDING MATERIAL SHALL BE 3-INCHES OF TYPE II AGGREGATE BASE OVER 12 INCHES OF 2 INCH DRAIN ROCK COMPACTED TO 90% OF THE MAXIMUM DRY DENSITY AS ESTABLISHED BY ASTM TEST METHOD D-1557.




WALL CONTRACTION JOINT DETAIL (10)
NOT TO SCALE




SECTION

SLAB WEEPHOLE DETAIL (6)
NOT TO SCALE




NOTE:
SPRAY GALVANIZE REINFORCING BARS 9" EACH SIDE OF WEAKENED PLANE JOINT


WEAKENED PLANE JOINT DETAIL (2)
NOT TO SCALE



CONSTRUCTION JOINT DETAIL (7)
NOT TO SCALE



SEALANT DETAIL (3)
NOT TO SCALE



NOTES:
1. CUTOFF WALL TO BE SPACED @ 180' OC FOR TRAPEZOIDAL CHANNELS AND 180' OC FOR RECTANGULAR CHANNELS ACROSS THE ENTIRE WIDTH OF THE CHANNEL LINING.
2. CONTRACTOR TO VERIFY THAT ALL DOWELS ARE IN PLANE AND PERPINDICULAR TO JOINT PRIOR TO POURING CONCRETE.

TRANSVERSE CUT-OFF WALL EXPANSION DETAIL (4)
NOT TO SCALE

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES DETAILS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA
RIMAH I. NAZZAL
Exp. 12/31/2005
CIVIL / STRUCTURAL
No. 12977
4/5/04

PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-1
SHT. 24 OF 30




* SEE CHANNEL PLAN AND PROFILE SHEETS FOR RCP LOCATIONS

REINFORCING AROUND PIPE

NOT TO SCALE

10




NOTE:
1. FOR INFORMATION NOT SHOWN, SEE 4/S-1
2. CONTRACTOR TO VERIFY THAT ALL DOWELS ARE IN PLACE AND PERPINDICULAR TO JOINT PRIOR TO POURING CONCRETE.

EXPANSION JOINT AND CUT-OFF WALL

NOT TO SCALE

7




NOTE: CONTRACTOR MAY USE ALTERNATE JOINT CONFIGURATION WITH WRITTEN APPROVAL FROM OWNER

KEY JOINT DETAIL

NOT TO SCALE


4



TRAPEZOIDAL CHANNEL WEEPHOLE

NOT TO SCALE

1




STEP LOCATIONS

STATIONS	
LT	RT
119+60.00	119+00.00
125+60.00	125+00.00
131+60.00	131+00.00
137+60.00	137+00.00
143+60.00	143+00.00
149+60.00	149+00.00
155+60.00	155+00.00
161+40.00	161+00.00
167+60.00	167+00.00
173+60.00	173+00.00
179+60.00	179+00.00
185+60.00	185+00.00

CHANNEL STEP DETAILS

NOT TO SCALE

11




NOTES:
1. THE INFORMATION SHOWN FOR THE SAHARA AVE CULVERT IS BASED ON THE DESIGN DRAWINGS FOR SID #94. CONTRACTOR TO VERIFY THE GEOMETRY & CONDITION OF THE CULVERT TIE IN LOCATIONS.
2. EXPANSION JOINT DETAIL IS SIMILAR AT BOTH UPSTREAM AND DOWNSTREAM ENDS OF BRIDGE AT SAHARA AVE.

EXPANSION JOINT

NOT TO SCALE


8



CONNECTION JOINT

NOT TO SCALE


5



RECTANGULAR CHANNEL WEEPHOLE

NOT TO SCALE


2



PIPE CONNECTION

NOT TO SCALE

9



APRON AT CHARLESTON BLVD BRIDGE

NOT TO SCALE

6

APRON AT ORCHARDS CHANNEL

NOT TO SCALE

3

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

CHANNEL STRUCTURES DETAILS

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA
RIMAH NAZZAL
Exp. 12/31/2005
CIVIL / STRUCTURAL
No. 12977
4/5/04

PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK


L-1759
DRAWING NO.
S-2
SHT. 25 OF 30



KEYED JOINT (1)
NOT TO SCALE



NOTE:
FOR WEAKENED PLANE JOINTS & CUT OFF WALLS SEE DETAILS 2/S-1 4/S-1



RECTANGULAR CHANNEL SECTION (STA 161+79.41, 41.00' LT TO STA 161+09.37, 80.14' LT) (STA 161+02.56, 95.72' LT TO STA 160+91.22, 121.68' LT) (B)
NOT TO SCALE


CHANNEL REACH	L1	L2	L3	L4	H1	H2
STA. 118+88.78 TO STA. 119+38.78	VARIES LINEARLY FROM 10.94' TO 17.3'	VARIES LINEARLY FROM 32.47' TO 30'	VARIES LINEARLY FROM 35.99' TO 30'	VARIES LINEARLY FROM 20.51' TO 12.3'	VARIES LINEARLY FROM 0' TO 2.37'	–
STA. 119+38.78 TO STA. 120+68.17	17.3'	30'	30'	12.3'	VARIES LINEARLY FROM 2.37' TO 1.63'	–
STA. 120+68.17 TO STA. 120+74.33	17.3'	30'	30'	VARIES LINEARLY FROM 12.3' TO 9.93'	VARIES LINEARLY FROM 1.63' TO 1.59'	–
STA. 120+74.33 TO STA. 120+96.22	17.3'	30'	30'	9.93'	VARIES LINEARLY FROM 1.59' TO 1.47'	–
STA. 120+96.22 TO STA. 121+02.78	17.3'	30'	30'	VARIES LINEARLY FROM 9.93' TO 12.3'	VARIES LINEARLY FROM 1.47' TO 1.43'	–
STA. 121+02.78 TO STA. 122+58.37	17.3'	30'	30'	12.3'	VARIES LINEARLY FROM 1.43' TO 0.54'	–
STA. 122+58.37 TO STA. 122+98.37	VARIES LINEARLY FROM 17.3' TO 12.3'	30'	30'	12.3'	VARIES LINEARLY FROM 0.54' TO 0'	–
STA. 122+98.37 TO STA. 130+97.58	12.3'	30'	30'	12.3'	–	–
STA. 130+97.58 TO STA. 131+75.00	VARIES LINEARLY FROM 12.3' TO 11.5'	30'	30'	VARIES LINEARLY FROM 12.3' TO 11.5'	–	–
STA. 131+75.00 TO STA. 158+50.00	11.5'	30'	30'	11.5'	–	–
STA. 158+50.00 TO STA. 159+00.00	VARIES LINEARLY FROM 11.5' TO 15.2'	30'	30'	VARIES LINEARLY FROM 11.5' TO 15.2'	–	–
STA. 159+00.00 TO STA. 160+29.41	15.2'	30'	30'	15.2'	–	–
STA. 160+29.41 TO STA. 160+62.41	VARIES LINEARLY FROM 15.2' TO 5.17'	VARIES LINEARLY FROM 30' TO 37.59'	VARIES LINEARLY FROM 30' TO 30.66'	VARIES LINEARLY FROM 15.2' TO 5.17'	VARIES LINEARLY FROM 0' TO 4.79'	VARIES LINEARLY FROM 0' TO 5'
STA. 163+29.41 TO STA. 165+61.82	11.5'	30'	30'	11.5'	–	–
STA. 165+61.82 TO STA. 165+72.82	11.5'	30'	30'	10.36'	–	–
STA. 165+72.82 TO STA. 171+98.47	11.5'	30'	30'	11.5'	–	–
STA. 172+86.31 TO STA. 174+00.00	13.2'	30'	30'	13.2'	–	–
STA. 174+00.00 TO STA. 174+50.00	13.2'	30'	30'	VARIES LINEARLY FROM 13.2' TO 11.63'	–	–
STA. 176+00.00 TO STA. 178+50.00	13.2'	30'	30'	13.2'	–	–
STA. 178+50.00 TO STA. 179+00.00	13.2'	30'	30'	VARIES LINEARLY FROM 13.2' TO 7'	–	VARIES LINEARLY FROM 0' TO 3.1'
STA. 179+00.00 TO STA. 182+17.17	13.2'	30'	30'	7'	–	3.1'
STA. 182+17.17 TO STA. 185+17.69	13.2'	30'	30'	7'	VARIES LINEARLY FROM 0' TO 2.7'	3.1'
STA. 185+17.69 TO STA. 186+54.00	13.2'	30'	30'	7'	VARIES LINEARLY FROM 2.7' TO 1.43'	3.1'
STA. 186+54.00 TO STA. 187+17.89	VARIES LINEARLY FROM 13.2' TO 15.9'	30'	30'	VARIES LINEARLY FROM 7' TO 19.67'	VARIES LINEARLY FROM 1.43' TO 0'	VARIES LINEARLY FROM 3.1' TO 0'

TYPICAL TRAPEZOIDAL CHANNEL SECTION (A)
NOT TO SCALE

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES
TYPICAL CHANNEL SECTIONS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS




PROJECT No's: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK


L-1759
DRAWING NO.
S-3
SHT. 26 OF 30



NOTE:
WEAKENED PLANE JOINTS AND VERTICAL WALL CONTRACTION JOINTS ARE NOT SHOWN BUT WILL BE REQUIRED AT MAXIMUM 60'-0" OC SPACING.

TYPICAL TRANSITION BETWEEN TRAPEZOIDAL AND RECTANGULAR CHANNEL 1

1/8" = 1'-0"




NOTE:
FOR WEAKENED PLANE JOINTS & CUT OFF WALLS SEE DETAILS 2/S-1 4/S-1

CHANNEL REACH	L1	L2	L3	L4	H1	H2
STA. 160+62.41 TO STA. 160+71.41	VARIES LINEARLY FROM 5.17' TO 2.43'	VARIES LINEARLY FROM 37.59' TO 39.66'	VARIES LINEARLY FROM 30.66' TO 30.84'	VARIES LINEARLY FROM 5.17' TO 2.43'	VARIES LINEARLY FROM 4.79' TO 6.09'	VARIES LINEARLY FROM 5' TO 6.36'

TYPICAL TRANSITION SECTION A


3/8" = 1'-0"



CHANNEL REACH	L1	L2	L3	L4	H1	H2
STA. 162+79.41 TO STA. 163+29.41	VARIES LINEARLY FROM 0' TO 11.5'	VARIES LINEARLY FROM 41.5' TO 30'	VARIES LINEARLY FROM 49' TO 30'	VARIES LINEARLY FROM 0' TO 11.5'	VARIES LINEARLY FROM 7.25' TO 0'	VARIES LINEARLY FROM 8.53' TO 0'

TYPICAL TRANSITION SECTION C

3/8" = 1'-0"



CHANNEL REACH	L1	L2	L3	L4	H1	H2
STA. 160+71.41 TO STA. 160+79.41	VARIES LINEARLY FROM 2.43' TO 0'	VARIES LINEARLY FROM 39.66' TO 41.5'	VARIES LINEARLY FROM 30.84' TO 31'	VARIES LINEARLY FROM 2.43' TO 0'	VARIES LINEARLY FROM 6.09' TO 7.25'	VARIES LINEARLY FROM 6.36' TO 7.57'

TYPICAL TRANSITION SECTION B

3/8" = 1'-0"

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES
CHANNEL TRANSITION STRUCTURES
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA
RIMAH I. NAZZAL
Exp. 12/31/2005
CIVIL / STRUCTURAL
No. 12977
4/5/2004

PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-4
SHT. 27 OF 30




SECTION
3/8" = 1'-0"

B/—



DETAIL
1/4" = 1'-0"

2/—




NOTE: PROVIDE WEEPHOLES AS SPECIFIED ON

POINT	A	B	C	D	E	F	G
RAMP 1	STA: 174+50.99	STA. 174+52.04	STA. 174+63.24	STA. 175+25.23	STA. 175+23.35	STA. 176+00.00	STA. 176+00.00
	OFFSET: 41.47' LT	OFFSET: 54.47' LT	OFFSET: 52.69' LT	OFFSET: 41.85' LT	OFFSET: 30.00' LT	OFFSET: 30.00' LT	OFFSET: 43.20' LT
	EL = 1703.83	EL = 1704.07	EL = 1703.62	EL = 1700.83 TW EL = 1697.13 TOE	EL = 1696.89	EL = 1696.54	EL = 1703.14

PLAN - TRAPEZOIDAL CHANNEL ACCESS RAMP
1/16" = 1'-0"


1/—



CHANNEL REACH	L1	L2	H1	H2
STA. 160+79.41 TO STA. 161+59.19	41.5'	31'	7.25'	VARIES LINEARLY FROM 7.57' TO 7.96'
STA. 161+59.19 TO STA. 161+79.41	41.5'	31'	7.25'	VARIES LINEARLY FROM 7.96' TO 7.76'
STA. 161+79.41 TO STA. 162+25.00	41.5'	49'	7.25'	VARIES LINEARLY FROM 7.76' TO 8.53'
STA. 162+25.00 TO STA. 162+79.41	41.5'	49'	7.25'	8.53'

RECTANGULAR CHANNEL SECTION
3/8" = 1'-0"

A/—



CHANNEL TRANSITION SECTION
1/2" = 1'-0"

C/—

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES
ACCESS RAMP
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

STATE OF NEVADA — REGISTERED ENGINEER — RIMAH I. NAZZAL — Exp. 12/31/2005 — CIVIL / STRUCTURAL — No. 12977 — 4/5/04


PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-5
SHT. 28 OF 30

F:\500-857\dwg\improv\sc_s06.dwg 04-05-04 12:15:04 RBlanchard




* THESE DIMENSIONS AND VALUES VARY LINEARLY FROM MATCHING EXISTING ORCHARDS CHANNEL TO FINAL VALUES NOTES AT STA 160+91.22,121.68'LT

TRANSITION SECTION C

3/8" = 1'-0"

STA 160+89.62, 125.34'LT TO STA 160+91.22, 121.68'LT




NOTE:
FOR CUT OFF WALL SEE DETAIL 3 S-2

* THESE DIMENSIONS AND VALUES VARY LINEARLY FROM MATCHING EXISTING ORCHARDS CHANNEL TO FINAL VALUES NOTES AT STA 160+91.22,121.68'LT

TRANSITION SECTION A


3/8" = 1'-0"

STA 160+83.21, 140.01'LT TO STA 160+88.02, 129.01'LT




HEADWALL DETAIL 1

1/2" = 1'-0"



SECTION D

1/2" = 1'-0"



* THESE DIMENSIONS AND VALUES VARY LINEARLY FROM MATCHING EXISTING ORCHARDS CHANNEL TO FINAL VALUES NOTES AT STA 160+91.22,121.68'LT

TRANSITION SECTION B

3/8" = 1'-0"

STA 160+88.02, 129.01'LT TO STA 160+89.62, 125.34'LT

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
ACCESS RAMP
DETAILS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER — RIMAH I. NAZZAL, Exp. 12/31/2005, CIVIL / STRUCTURAL, No. 12971, STATE OF NEVADA
4/5/04

PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-6
SHT. 29 OF 30




WALL EXPANSION JOINT DETAIL 8
NOT TO SCALE





(*) UNLESS OTHERWISE NOTED

SLAB EXPANSION JOINT DETAIL 5
NOT TO SCALE




WALL JOINT DETAIL 9
NOT TO SCALE






NOTES:
1. WEAKENED PLANE JOINTS TO BE CENTERED WITH WEEPHOLES WHEN JOINTS OCCUR.
2. IN CURVED ALIGNMENT SECTIONS, TRANSVERSE JOINTS SHALL BE NORMAL TO CENTERLINE AND SHALL NOT EXCEED 60' MAX SPACING.


PLAN - CONCRETE LINED TRAPEZOIDAL CHANNEL 1
NOT TO SCALE




WALL CONTRACTION JOINT DETAIL 10
NOT TO SCALE



SLAB WEEPHOLE DETAIL 6
NOT TO SCALE




CONSTRUCTION JOINT DETAIL 7
NOT TO SCALE



NOTE:
SPRAY GALVANIZE REINFORCING BARS 9" EACH SIDE OF WEAKENED PLANE JOINT


WEAKENED PLANE JOINT DETAIL 2
NOT TO SCALE



SEALANT DETAIL 3
NOT TO SCALE

STRUCTURE NOTES

1. DESIGN SPECIFICATIONS: AASHTO "STANDARD SPECIFICATIONS FOR HIGHWAY BRIDGES, 1996" AND INTERIMS THROUGH 2000. REINFORCED CONCRETE DESIGN BASED ON LOAD FACTOR DESIGN.
2. CONSTRUCTION SPECIFICATIONS: UNIFORM STANDARD SPECIFICATIONS FOR PUBLIC WORKS CONSTRUCTION, OFF-SITE IMPROVEMENTS, CLARK COUNTY AREA, NEVADA.
3. LIVE LOAD: STANDARD AASHTO HS20-44 TRUCK LOADING AND TRAFFIC SURCHARGE FROM MAINTENANCE VEHICLES (2' OF SOIL)
4. SEISMIC LOAD: ACCELERATION COEFFICIENT 0.15 g
5. CONCRETE: ALL CONCRETE SHALL BE CLASS A MODIFIED (MAJOR) EXCEPT FOR WALLS WHICH SHALL BE CLASS D MODIFIED (MAJOR). ONLY TYPE V CEMENT SHALL BE USED FOR CONCRETE IN CONTACT WITH SOIL. CONCRETE COMPRESSIVE MINIMUM STRENGTH AT 28 DAYS SHALL BE, f'c=4,500 PSI AND A MAXIMUM WATER TO CEMENT RATIO, BY WEIGHT, OF 0.45.
6. REINFORCING STEEL: ALL REINFORCING STEEL SHALL BE ASTM A615 REINFORCING STEEL STRENGTH, Fy = 60,000 PSI.
7. ALL EXPOSED EDGES OF CONCRETE SHALL BE CHAMFERED 3/4" UNLESS OTHERWISE INDICATED.
8. TRANSVERSE AND LONGITUDINAL JOINTS IN INVERT SLAB AND SIDE SLOPE SLAB OF PAVED TRAPEZOIDAL CHANNELS AND WALLS FOR RECTANGULAR CHANNELS WILL BE REQUIRED AT THE END OF EACH CONTINUOUS POURING OPERATION. SEE TYPICAL CONSTRUCTION JOINT DETAIL. TRANSVERSE CONSTRUCTION JOINTS SHALL NOT BE PLACED WITHIN 3-FEET OF A MANHOLE, WITHIN 10-FEET OF JUNCTION STRUCTURE OPENINGS, OR WITHIN 50 FEET OF AN EXPANSION JOINT.
9. ALL TRANSVERSE JOINTS IN WALLS AND SLABS (CONSTRUCTION, WEAKENED CONTRACTION AND EXPANSION) SHALL BE IN THE SAME PLANE. NO STAGGERING OF JOINTS WILL BE PERMITTED UNLESS SHOWN OTHERWISE. TRANSVERSE CONSTRUCTION JOINTS SHALL BE NORMAL OR RADIAL TO CENTERLINE OF CONSTRUCTION.
10. ALL SINGLE LAYER REINFORCEMENT SHALL BE PLACED IN THE CENTER OF CONCRETE UNLESS NOTED OTHERWISE.
11. IN CURVED CHANNEL SECTIONS TRANSVERSE BARS SHALL BE PLACED NORMAL TO THE CHANNEL CENTERLINE.
12. IN CURVED CHANNEL SECTIONS, THE MAXIMUM SPACING OF BARS SHALL NOT EXCEED THAT SHOWN FOR TYPICAL SECTIONS. STEEL SHALL BE PLACED RADIALLY FROM THE MAXIMUM SPACING.
13. AT THE BEGINNING AND ENDING OF ALL POURS, A COMPLETE CURTAIN OF MAIN REINFORCEMENT SHALL BE PLACED 3-INCHES FROM THE TRANSVERSE CONSTRUCTION, CONTRACTION AND EXPANSION JOINTS.
14. NO WELDING WILL BE PERMITTED ON ANY REINFORCEMENT.
15. CHANNEL ELEVATIONS: FOR CHANNEL INVERT ELEVATIONS REFER TO THE CHANNEL PLAN AND PROFILE SHEETS LOCATED ELSEWHERE IN THIS DRAWING SET.
16. EXCAVATION AND BACKFILL: THE LIMITS OF EXCAVATION AND BACKFILL SHALL BE AS SHOWN IN THE STATE OF NEVADA, "STANDARD PLANS FOR ROAD AND BRIDGE CONSTRUCTION, JANUARY 2001," UNLESS OTHERWISE NOTED.
17. WEEPHOLES: WEEPHOLES WILL BE REQUIRED AT 30-FEET O.C. PER THE TYPICAL WEEPHOLE DETAIL FOR ALL OPEN CHANNEL STRUCTURES.
18. BEDDING MATERIALS: UNLESS NOTED OTHERWISE ALL BEDDING MATERIAL SHALL BE 3-INCHES OF TYPE II AGGREGATE BASE OVER 12 INCHES OF 2 INCH DRAIN ROCK COMPACTED TO 90% OF THE MAXIMUM DRY DENSITY AS ESTABLISHED BY ASTM TEST METHOD D-1557.



NOTES:
1. CUTOFF WALL TO BE SPACED @ 180' OC FOR TRAPEZOIDAL CHANNELS AND 180' OC FOR RECTANGULAR CHANNELS ACROSS THE ENTIRE WIDTH OF THE CHANNEL LINING.
2. CONTRACTOR TO VERIFY THAT ALL DOWELS ARE IN PLANE AND PERPINDICULAR TO JOINT PRIOR TO POURING CONCRETE.

TRANSVERSE CUT-OFF WALL EXPANSION DETAIL 4
NOT TO SCALE

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES DETAILS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA
RIMAH I. NAZZAL
Exp. 12/31/2005
No. 12977
CIVIL / STRUCTURAL
9/8/04

PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-1
SHT. 24 OF 30



* SEE CHANNEL PLAN AND PROFILE SHEETS FOR RCP LOCATIONS


REINFORCING AROUND PIPE
NOT TO SCALE — 10



STEP LOCATIONS


STATIONS	
LT	RT
119+60.00	119+00.00
125+60.00	125+00.00
131+60.00	131+00.00
137+60.00	137+00.00
143+60.00	143+00.00
149+60.00	149+00.00
155+60.00	155+00.00
161+40.00	161+00.00
167+60.00	167+00.00
173+60.00	173+00.00
179+60.00	179+00.00
185+60.00	185+00.00

CHANNEL STEP DETAILS
NOT TO SCALE — 11




NOTE:
1. FOR INFORMATION NOT SHOWN, SEE 4/S-1
2. CONTRACTOR TO VERIFY THAT ALL DOWELS ARE IN PLACE AND PERPINDICULAR TO JOINT PRIOR TO POURING CONCRETE.

EXPANSION JOINT AND CUT-OFF WALL
NOT TO SCALE — 7




NOTES:
1. THE INFORMATION SHOWN FOR THE SAHARA AVE CULVERT IS BASED ON THE DESIGN DRAWINGS FOR SID #94. CONTRACTOR TO VERIFY THE GEOMETRY & CONDITION OF THE CULVERT TIE IN LOCATIONS.
2. EXPANSION JOINT DETAIL IS SIMILAR AT BOTH UPSTREAM AND DOWNSTREAM ENDS OF BRIDGE AT SAHARA AVE.

EXPANSION JOINT
NOT TO SCALE — 8




PIPE CONNECTION
NOT TO SCALE — 9




NOTE: CONTRACTOR MAY USE ALTERNATE JOINT CONFIGURATION WITH WRITTEN APPROVAL FROM OWNER


KEY JOINT DETAIL
NOT TO SCALE — 4




CONNECTION JOINT
NOT TO SCALE — 5




APRON AT CHARLESTON BLVD BRIDGE
NOT TO SCALE — 6



TRAPEZOIDAL CHANNEL WEEPHOLE
NOT TO SCALE — 1



RECTANGULAR CHANNEL WEEPHOLE
NOT TO SCALE — 2




APRON AT ORCHARDS CHANNEL
NOT TO SCALE — 3

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES
DETAILS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS




PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-2
SHT. 25 OF 30



KEYED JOINT (1)
NOT TO SCALE





RECTANGULAR CHANNEL SECTION (STA 161+79.41, 41.00' LT TO STA 161+09.37, 80.14' LT) (STA 161+02.56, 95.72' LT TO STA 160+91.22, 121.68' LT) (B)
NOT TO SCALE

CHANNEL REACH	L1	L2	L3	L4	H1	H2
STA. 118+88.78 TO STA. 119+38.78	VARIES LINEARLY FROM 10.94' TO 17.3'	VARIES LINEARLY FROM 32.47' TO 30'	VARIES LINEARLY FROM 35.99' TO 30'	VARIES LINEARLY FROM 20.51' TO 12.3'	VARIES LINEARLY FROM 0' TO 2.37'	–
STA. 119+38.78 TO STA. 120+68.17	17.3'	30'	30'	12.3'	VARIES LINEARLY FROM 2.37' TO 1.63'	–
STA. 120+68.17 TO STA. 120+74.33	17.3'	30'	30'	VARIES LINEARLY FROM 12.3' TO 9.93'	VARIES LINEARLY FROM 1.63' TO 1.59'	–
STA. 120+74.33 TO STA. 120+96.22	17.3'	30'	30'	9.93'	VARIES LINEARLY FROM 1.59' TO 1.47'	–
STA. 120+96.22 TO STA. 121+02.78	17.3'	30'	30'	VARIES LINEARLY FROM 9.93' TO 12.3'	VARIES LINEARLY FROM 1.47' TO 1.43'	–
STA. 121+02.78 TO STA. 122+58.37	17.3'	30'	30'	12.3'	VARIES LINEARLY FROM 1.43' TO 0.54'	–
STA. 122+58.37 TO STA. 122+98.37	VARIES LINEARLY FROM 17.3' TO 12.3'	30'	30'	12.3'	VARIES LINEARLY FROM 0.54' TO 0'	–
STA. 122+98.37 TO STA. 130+97.58	12.3'	30'	30'	12.3'	–	–
STA. 130+97.58 TO STA. 131+75.00	VARIES LINEARLY FROM 12.3' TO 11.5'	30'	30'	VARIES LINEARLY FROM 12.3' TO 11.5'	–	–
STA. 131+75.00 TO STA. 158+50.00	11.5'	30'	30'	11.5'	–	–
STA. 158+50.00 TO STA. 159+00.00	VARIES LINEARLY FROM 11.5' TO 15.2'	30'	30'	VARIES LINEARLY FROM 11.5' TO 15.2'	–	–
STA. 159+00.00 TO STA. 160+29.41	15.2'	30'	30'	15.2'	–	–
STA. 160+29.41 TO STA. 160+62.41	VARIES LINEARLY FROM 15.2' TO 5.17'	VARIES LINEARLY FROM 30' TO 37.59'	VARIES LINEARLY FROM 30' TO 30.66'	VARIES LINEARLY FROM 15.2' TO 5.17'	VARIES LINEARLY FROM 0' TO 4.79'	VARIES LINEARLY FROM 0' TO 5'
STA. 163+29.41 TO STA. 165+61.82	11.5'	30'	30'	11.5'	–	–
STA. 165+61.82 TO STA. 165+72.82	11.5'	30'	30'	10.36'	–	–
STA. 165+72.82 TO STA. 171+98.47	11.5'	30'	30'	11.5'	–	–
STA. 172+86.31 TO STA. 174+00.00	13.2'	30'	30'	13.2'	–	–
STA. 174+00.00 TO STA. 174+50.00	13.2'	30'	30'	VARIES LINEARLY FROM 13.2' TO 11.63'	–	–
STA. 176+00.00 TO STA. 178+50.00	13.2'	30'	30'	13.2'	–	–
STA. 178+50.00 TO STA. 179+00.00	13.2'	30'	30'	VARIES LINEARLY FROM 13.2' TO 7'	–	VARIES LINEARLY FROM 0' TO 3.1'
STA. 179+00.00 TO STA. 182+17.17	13.2'	30'	30'	7'	–	3.1'
STA. 182+17.17 TO STA. 185+17.69	13.2'	30'	30'	7'	VARIES LINEARLY FROM 0' TO 2.7'	3.1'
STA. 185+17.69 TO STA. 186+54.00	13.2'	30'	30'	7'	VARIES LINEARLY FROM 2.7' TO 1.43'	3.1'
STA. 186+54.00 TO STA. 187+17.89	VARIES LINEARLY FROM 13.2' TO 15.9'	30'	30'	VARIES LINEARLY FROM 7' TO 19.67'	VARIES LINEARLY FROM 1.43' TO 0'	VARIES LINEARLY FROM 3.1' TO 0'

TYPICAL TRAPEZOIDAL CHANNEL SECTION (A)
NOT TO SCALE

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES
TYPICAL CHANNEL SECTIONS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


RIMAH NAZZAL Exp. 12/31/2005 CIVIL / STRUCTURAL No. 12977 STATE OF NEVADA
9/8/04

PROJECT No's: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK


L-1759
DRAWING NO.
S-3
SHT. 26 OF 30



NOTE:
WEAKENED PLANE JOINTS AND VERTICAL WALL CONTRACTION JOINTS ARE NOT SHOWN BUT WILL BE REQUIRED AT MAXIMUM 60'-0" OC SPACING.

TYPICAL TRANSITION BETWEEN TRAPEZOIDAL AND RECTANGULAR CHANNEL 1

1/8" = 1'-0"




NOTE:
FOR WEAKENED PLANE JOINTS & CUT OFF WALLS SEE DETAILS 2 S-1 4 S-1

CHANNEL REACH	L1	L2	L3	L4	H1	H2
STA. 160+62.41 TO STA. 160+71.41	VARIES LINEARLY FROM 5.17' TO 2.43'	VARIES LINEARLY FROM 37.59' TO 39.66'	VARIES LINEARLY FROM 30.66' TO 30.84'	VARIES LINEARLY FROM 5.17' TO 2.43'	VARIES LINEARLY FROM 4.79' TO 6.09'	VARIES LINEARLY FROM 5' TO 6.36'

TYPICAL TRANSITION SECTION A


3/8" = 1'-0"



CHANNEL REACH	L1	L2	L3	L4	H1	H2
STA. 162+79.41 TO STA. 163+29.41	VARIES LINEARLY FROM 0' TO 11.5'	VARIES LINEARLY FROM 41.5' TO 30'	VARIES LINEARLY FROM 49' TO 30'	VARIES LINEARLY FROM 0' TO 11.5'	VARIES LINEARLY FROM 7.25' TO 0'	VARIES LINEARLY FROM 8.53' TO 0'

TYPICAL TRANSITION SECTION C

3/8" = 1'-0"



CHANNEL REACH	L1	L2	L3	L4	H1	H2
STA. 160+71.41 TO STA. 160+79.41	VARIES LINEARLY FROM 2.43' TO 0'	VARIES LINEARLY FROM 39.66' TO 41.5'	VARIES LINEARLY FROM 30.84' TO 31'	VARIES LINEARLY FROM 2.43' TO 0'	VARIES LINEARLY FROM 6.09' TO 7.25'	VARIES LINEARLY FROM 6.36' TO 7.57'

TYPICAL TRANSITION SECTION B

3/8" = 1'-0"

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES
CHANNEL TRANSITION STRUCTURES
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA
RIMAH H. NAZZAL
Exp. 12/31/2006
CIVIL / STRUCTURAL
No. 12977
9/8/04

PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299


SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-4
SHT. 27 OF 30




SECTION
3/8" = 1'-0"

* SEE DETAIL (2) — B




DETAIL
1/4" = 1'-0" — 2




POINT	(A)	(B)	(C)	(D)	(E)	(F)	(G)
RAMP 1	STA: 174+50.99	STA. 174+52.04	STA. 174+63.24	STA. 175+25.23	STA. 175+23.35	STA. 176+00.00	STA. 176+00.00
	OFFSET: 41.47' LT	OFFSET: 54.47' LT	OFFSET: 52.69' LT	OFFSET: 41.85' LT	OFFSET: 30.00' LT	OFFSET: 30.00' LT	OFFSET: 43.20' LT
	EL = 1703.83	EL = 1704.07	EL = 1703.62	EL = 1700.83 TW EL = 1697.13 TOE	EL = 1696.89	EL = 1696.54	EL = 1703.14

PLAN - TRAPEZOIDAL CHANNEL ACCESS RAMP
1/16" = 1'-0" — 1



CHANNEL TRANSITION SECTION
1/2" = 1'-0" — C



CHANNEL REACH	L1	L2	H1	H2
STA. 160+79.41 TO STA. 161+59.19	41.5'	31'	7.25'	VARIES LINEARLY FROM 7.57' TO 7.96'
STA. 161+59.19 TO STA. 161+79.41	41.5'	31'	7.25'	VARIES LINEARLY FROM 7.96' TO 7.76'
STA. 161+79.41 TO STA. 162+25.00	41.5'	49'	7.25'	VARIES LINEARLY FROM 7.76' TO 8.53'
STA. 162+25.00 TO STA. 162+79.41	41.5'	49'	7.25'	8.53'

RECTANGULAR CHANNEL SECTION
3/8" = 1'-0" — A

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
CHANNEL STRUCTURES
ACCESS RAMP
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA
RIMAH N. NAZZAL
Exp. 12/31/2005
CIVIL / STRUCTURAL
No. 12977
9/8/04

PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: NONE
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
S-5
SHT. 28 OF 30




* THESE DIMENSIONS AND VALUES VARY LINEARLY FROM MATCHING EXISTING ORCHARDS CHANNEL TO FINAL VALUES NOTES AT STA 160+91.22,121.68'LT

TRANSITION SECTION C

3/8" = 1'-0"

STA 160+89.62, 125.34'LT TO STA 160+91.22, 121.68'LT




NOTE:
FOR CUT OFF WALL SEE DETAIL 3/S-2

* THESE DIMENSIONS AND VALUES VARY LINEARLY FROM MATCHING EXISTING ORCHARDS CHANNEL TO FINAL VALUES NOTES AT STA 160+91.22,121.68'LT

TRANSITION SECTION A


3/8" = 1'-0"

STA 160+83.21, 140.01'LT TO STA 160+88.02, 129.01'LT




SECTION D

1/2" = 1'-0"



HEADWALL DETAIL 1

1/2" = 1'-0"



* THESE DIMENSIONS AND VALUES VARY LINEARLY FROM MATCHING EXISTING ORCHARDS CHANNEL TO FINAL VALUES NOTES AT STA 160+91.22,121.68'LT

TRANSITION SECTION B

3/8" = 1'-0"

STA 160+88.02, 129.01'LT TO STA 160+89.62, 125.34'LT

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL
ACCESS RAMP
DETAILS
CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS


PROFESSIONAL ENGINEER STATE OF NEVADA
RIMAH NAZZAL
Exp. 12/31/2005
CIVIL / STRUCTURAL
No. 12977
9/8/04

PROJECT No: 500.857 DRAWN BY: NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY


G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE	
HORIZ:	NONE
VERT:	NONE
FIELD BOOK	

L-1759
DRAWING NO.
S-6
SHT. 29 OF 30



SECTION D-D




SECTION C

RCB INLET DETAILS

NOT TO SCALE


3



DETAIL

NOT TO SCALE

B



SIDE DRAIN	L1	L2	L3	L4
1	29.15' TO 28.40'	10.00'	10.00'	29.10' TO 28.40'
2	24.20' TO 25.21'	17.05' TO 18.66'	18.72' TO 20.23'	22.07' TO 24.21'

CHANNEL SECTION

NOT TO SCALE

A


PLAN - TYPE 2 SIDE DRAIN

NOT TO SCALE

2

NOTE:
SEE CIVIL DRAWINGS FOR ELEVATIONS AND INFORMATION NOT SHOWN

	STA "A"	BEARING "A"	BEARING "B"
SIDE DRAIN 1	120+84.85	N 71°07'11" E (R)	N 71°50'27" E
SIDE DRAIN 2	127+33.01	N 63°30'25" E (R)	N 63°33'08" E



PLAN - TYPE 1 SIDE DRAIN

NOT TO SCALE

1

REV. NO.	DATE	DESCRIPTION	APPROVED

CLARK COUNTY NEVADA

SLOAN CHANNEL

CHANNEL STRUCTURES DETAILS

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

PROFESSIONAL ENGINEER STATE OF NEVADA
RIMAH NAZZAL
Exp. 12/31/2005
CIVIL / STRUCTURAL
No. 12977
9/6/04

PROJECT No: 500.857 DRAWN BY: RB/NO/AL
DESIGNED BY: RIN CHECKED BY: RIN
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE	
HORIZ:	NONE
VERT:	NONE
FIELD BOOK	

L-1759

DRAWING NO.

S-7

SHT. 30 OF 30

November 20, 2006

Mr. Kevin Eubanks, P.E., CFM
Clark County Regional Flood Control District
600 South Grand Central Parkway, Ste 300
Las Vegas, Nevada 89155


RE: SLOAN CHANNEL LETTER OF MAP REVISION

Dear Mr. Eubanks,

At your request, PBS&J has prepared a revised hydraulic model for the Sloan Channel improvements. The HEC-RAS model was extended upstream of the Charleston Boulevard bridge by appending the Sloan Channel CLOMR model with HEC-2 cross-sections taken from the Range Wash FIS.

Sincerely,

PBS&J



Matthew S. Baird, P.E., CFM
Lic. 13684, Nevada

Model Methodology

Hydraulic modeling of the Sloan Channel was performed using the U.S. Army Corps of Engineers' River Analysis System (HEC-RAS), version 3.1.3. The hydraulic modeling conforms to local standards that are specified in the CCRFCD Hydrologic Criteria and Drainage Design Manual.

Datum Conversion

The hydraulic model prepared for the Range Wash Flood Insurance Study (FIS) was prepared using HEC-2 and used elevations based on National Geodetic Vertical Datum of 1929 (NGVD 29). The Sloan Channel improvement plans and the HEC-RAS model submitted in the CLOMR used elevations based on North American Vertical Datum of 1988 (NAVD 88). The HEC-2 cross-section data extracted from the Range Wash FIS was converted to NAVD 88 by adding 2.46 feet. The datum conversion is based on a comparison of published NAVD 88 and NGVD 29 elevations for Clark County Benchmark 6C02 33SWW6. Please refer to this Appendix for the detailed datum conversion process.

Model Description

The hydraulic model prepared for the Sloan Channel CLOMR was revised per the condition in the CLOMR approval letter dated June 16, 2005 under Case No. 05-09-0577R. The condition stated that the LOMR submittal must include a revised hydraulic model that extended the analysis upstream through the bridge at Charleston Boulevard until a hydraulic tie-in was achieved. The CLOMR HEC-RAS model terminated at Station 118+89, approximately 100-feet downstream of Charleston Boulevard. Please refer to the HEC-RAS Cross-Section Map included in this Appendix.

The HEC-RAS model prepared for the Sloan Channel CLOMR was extended upstream by adding a portion of the HEC-2 sections from the Range Wash FIS. The Range Wash FIS was the technical basis of FEMA Case No. 98-09-1054P and constitutes the effective data for this area. The model was extended approximately 510-feet upstream of the Charleston Bridge to FIS station 101+49 (plan station 112+09). As previously discussed, the HEC-2 sections were converted to elevations based on NAVD 88. The bridge at Charleston Boulevard was modeled as a special bridge in the FIS HEC-2 model. It should be noted that some, but not all, of the HEC-2 bridge cross-section data can be inputted directly into HEC-RAS, such as pier and ineffective flow data. Differences in WSEL's can be expected due to the known computational differences between HEC-2 and HEC-RAS. The HEC-2 special bridge routines use a trapezoidal approximation for low flow calculations (Yarnell equation and class B flow check with the momentum equation). The HEC-RAS program uses the actual bridge opening geometry for all flow methodologies. Also, the HEC-2 program uses a single pier (of equivalent width to the sum total width of all piers) placed in the middle of the trapezoid. In the HEC-RAS software, all of the piers are defined separately, and the hydraulic computations are performed by evaluating the water surface and impact on each pier individually.

The model was prepared with two flow profiles to simulate the design flow of 2,870 cfs and the FIS flow of 3,300 cfs through the Charleston Bridge. The slope-area method was used as the upstream boundary condition (0.42%) at FIS station 101+49 (plan station 112+09). Please refer to the Tables below that compare the WSEL's between the FIS and the model prepared for this LOMR. Table 1 is a comparison between the FIS HEC-2 model run with 3,300 cfs and the current HEC-RAS LOMR model run with 2,870 cfs. Table 2 is a comparison between the FIS HEC-2 model run with 3,300 cfs and the current HEC-RAS LOMR model run with 3,300 cfs.

Table 1
FIS HEC-2 3,300 cfs/LOMR HEC-RAS 2,870 cfs

FIS Station	Plan Station	HEC-2 CWSEL (FIS)	Datum Adjusted HEC-2 CWSEL	HEC-RAS CWSEL	Difference in WSEL
101+49	112+09	1725.58	1728.04	1727.63	-0.41*
104+23	114+87	1724.22	1726.68	1726.35	-0.33
105+74	116+40	1723.59	1726.05	1727.45	1.40
106+23	116+90	1722.95	1725.41	1727.59	2.18
106+24	116+91	1725.00	1727.46	1727.60	0.14
107+24	117+91	1722.63	1725.09	1725.15	0.06
107+25	117+92	1720.95	1723.41	1723.17	-0.24

*WSEL within 0.5 feet at terminus of model

Table 2
FIS HEC-2 3,300 cfs/LOMR HEC-RAS 3,300 cfs

FIS Station	Plan Station	HEC-2 CWSEL (FIS)	Datum Adjusted HEC-2 CWSEL	HEC-RAS CWSEL	Difference in WSEL
101+49	112+09	1725.58	1728.04	1727.91	-0.13*
104+23	114+87	1724.22	1726.68	1726.65	-0.03
105+74	116+40	1723.59	1726.05	1727.92	1.87
106+23	116+90	1722.95	1725.41	1728.08	2.67
106+24	116+91	1725.00	1727.46	1728.08	0.62
107+24	117+91	1722.63	1725.09	1725.49	0.40
107+25	117+92	1720.95	1723.41	1723.46	0.05

*WSEL within 0.5 feet at terminus of model

Results

The results show that both models (FIS flow & design flow) tie-in to the effective WSEL to within 0.5'. A digital copy of the HEC-RAS model has been provided on a data CD located in this Appendix.

Datum Conversion

Datum Conversion

Clark County Benchmark 6C02 33SWW6
Benchmark used for vertical control for the Sloan Channel Improvements

NAVD88 = 1744.954 feet
NGVD29 = 1742.497 feet


NGVD29 to NAVD88 conversion = add 2.46 feet

NAVD88 elevation listed as 531.863 meters.

Conversion to U.S. Survey Feet = (Meters x 3.2808)

531.863 x 3.2808 = 1744.954


F:\500-857\dwg\improv\sc_g04.dwg 04-05-04 07:00:58 RBlanchard



LINE TABLE		
No.	Bearing	Distance
L2	N 89°57'02" E	41.00'

CHANNEL ℄ LINE TABLE		
No.	Bearing	Distance
L1	N 00°00'06" W	150.00'
L3	N 00°22'58" E	20.22'
L4	N 66°00'50" E	75.33'
L5	N 00°22'58" W	109.59'
L6	N 00°02'58" W	50.00'

CHANNEL ℄ CURVE TABLE				
No.	Radius	Delta	Length	Tangent
C1	807.70'	27°20'22"	385.40'	196.44'
C2	800.00'	31°55'40"	445.80'	228.85'
C3	462.47'	42°11'02"	340.49'	178.38'
C4	50.00'	66°23'48"	57.94'	32.72'



BASIS OF BEARINGS

SOUTH 00°18'40" EAST, BEING THE WEST LINE OF THE SOUTHWEST QUARTER (SW 1/4) OF SECTION 3, TOWNSHIP 21 SOUTH, RANGE 62 EAST, M.D.M., CLARK COUNTY, NEVADA. AS SHOWN BY FILE 36, PAGE 6 OF SURVEYS IN THE CLARK COUNTY RECORDER'S OFFICE CLARK COUNTY, NEVADA.

BENCHMARK

CLARK COUNTY BM - 6C02 33SWW6

RIVET AND SQUARE ALUMINUM PLATE IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND BELPORT DR. NEAR THE PC OF NELLIS BLVD.

ELEVATION: 531.863 METERS (NAVD 88)
1744.954 FEET (NAVD 88)

LEGEND

- ◉ FOUND MONUMENTATION AS SHOWN AND DESCRIBED
- × CALCULATED POINT
- —— —— SECTION LINE
- — — — QUARTER LINE
- — — — — 1/16 LINE

REFERENCES

FILE 36, PAGE 6 OF SURVEYS
FILE 122, PAGE 76 OF SURVEYS

REV. NO.	DATE	DESCRIPTION	APPROVED

SLOAN CHANNEL
HORIZONTAL CONTROL PLAN

CLARK COUNTY, NEVADA, DEPARTMENT OF PUBLIC WORKS

DANNY E. HILL EXP.6/30/05 LICENSED LAND SURVEYOR NO. 9389 STATE OF NEVADA
5 APRIL 2004


PROJECT No: 500.857 DRAWN BY:
DESIGNED BY: CHECKED BY:
APPROVED BY

G.C. WALLACE, INC.
Engineers/Planners/Surveyors
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89146
TELEPHONE: (702) 804-2000 • FAX: (702) 804-2299

SCALE
HORIZ: 1" = 500'
VERT: NONE
FIELD BOOK

L-1759
DRAWING NO.
G-4
SHT. 4 OF 30

TOWNSHIP 20 SOUTH, RANGE 62 EAST
SOUTHWEST QUARTER



Nº	STATION	ELEVATION	DESCRIPTION
1	6C02 33SWS	1739.619	Set drive rivet in a 2"X2" Aluminum plate, in drilled hole, with epoxy glue in top of curb, Northeast corner of Nellis Blvd. & Charleston Blvd. near the PC of Nellis Bl.
2	6C02 33SWW6	1742.497	Set drive rivet in a 2"X2" Aluminum plate, in drilled hole, with epoxy glue in top of curb, Northeast corner of Nellis Blvd. & Belport Drive.
3	6C02 33W4	1748.529	Found 2" dome head brass cap reference monument in TC, Northeast corner of Nellis Blvd. & Stewart Ave. near the PC of Nellis Blvd.
4	6C02 33NWW6	1752.893	Set drive rivet in a 2"X2" Aluminum plate, in drilled hole, with epoxy glue in top of curb, Northeast corner of Nellis Blvd. & Cedar Ave. near the PC of Nellis Blvd.
5	6C02 28SWS	1759.623	Found 2" dome head brass cap reference monument in TC, Northeast corner of Nellis Blvd. & Bonanza Road, near the PC of Nellis Blvd.
6	6C02 28SWW6	1761.465	Found 2" dome head brass cap reference monument in TC, Northeast corner of Nellis Blvd. & Harris Ave. near the PC of Nellis Blvd.
7	6C02 28W4	1765.754	Set drive rivet in a 2"X2" Aluminum plate, in drilled hole, with epoxy glue in top of curb, Northeast corner of Nellis Blvd. & Washington Ave. near the PC of Nellis Bl.
8	6C02 28NWW6	1770.508	Set drive rivet in a 2"X2" Aluminum plate, in drilled hole, with epoxy glue in top of curb, Northeast corner of Nellis Blvd. & Monroe Ave. near the PC of Nellis Bl.
9	6C02 21SWS	1775.857	Found 2" dome head brass cap reference monument in TC, Northeast corner of Nellis Blvd. & Owens Ave. near the PC of Nellis Blvd.
10	6C02 21SWW6	1781.158	Set drive rivet in a 2"X2" Aluminum plate, in drilled hole, with epoxy glue in top of curb, Northeast corner of Nellis Blvd. & Kell Lane, near the PC of Nellis Bl.
11	6C02 21W4	1786.151	Found 2" dome head brass cap reference monument in TC, Northeast corner of Nellis Blvd. & Lake Mead Blvd. near the PC of Nellis Blvd.
12	6C02 21NWW6	1791.669	Found 2" dome head brass cap reference monument in TC, Northeast corner of Nellis Blvd. & Judson Ave. near the PC of Nellis Blvd.

CLARK COUNTY VERTICAL CONTROL

CLARK COUNTY, NEVADA


LOCAL DATUM

REVISION DATE 1987

NATIONAL GEODETIC VERTICAL DATUM OF 1929

DRAWING Nº 20-62-SW A

TOWNSHIP 20 SOUTH, RANGE 62 EAST
SOUTHWEST QUARTER



NORTH AMERICAN VERTICAL DATUM OF 1988

ALL ELEVATIONS IN METERS

No.	STATION	ELEVATION (METERS)	DESCRIPTION
1	7C02 28SSW6	535.491	2" BRASS CAP REFERENCE MONUMENT IN TOP OF CURB, IN THE NORTHEAST CORNER OF BONANZA RD. AND BETTY LN. NEAR THE PC OF BONANZA RD.
2	6C02 33SWW6	531.863	RIVET AND SQUARE ALUMINUM PLATE IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND BELPORT DR.
3	6C02 33W4	533.689	2" BRASS CAP REFERENCE MONUMENT IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND STEWART AVE. NEAR THE PC OF NELLIS BLVD.
4	6C02 33NWW6	535.023	RIVET AND SQUARE ALUMINUM PLATE IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND CEDAR AVE. NEAR THE PC OF NELLIS BLVD.
5	6C02 28SWS	537.077	2" BRASS CAP REFERENCE MONUMENT IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND BONANZA ROAD, NEAR THE PC OF NELLIS BLVD.
6	6C02 28SWW6	537.638	2" BRASS CAP REFERENCE MONUMENT IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND HARRIS AVE. NEAR THE PC OF NELLIS BLVD.
7	6C02 28W4	538.945	RIVET AND SQUARE ALUMINUM PLATE IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND WASHINGTON AVE. NEAR THE PC OF NELLIS BLVD.
8	6C02 28NWW6	540.398	RIVET AND SQUARE ALUMINUM PLATE IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND MONROE AVE. NEAR THE PC OF NELLIS BLVD.
9	6C02 21SWS	542.032	BRASS CAP REFERENCE MONUMENT IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND OWENS AVE. NEAR THE PC OF NELLIS BLVD.
10	6C02 21SWW6	543.647	RIVET AND SQUARE ALUMINUM PLATE IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND KELL LANE, NEAR THE PC OF NELLIS BLVD.
11	6C02 21W4	545.167	BRASS CAP REFERENCE MONUMENT IN TOP OF CURB, IN THE NORTHEAST CORNER OF NELLIS BLVD. AND LAKE MEAD BLVD. NEAR THE PC OF NELLIS BLVD.

CLARK COUNTY VERTICAL CONTROL

CLARK COUNTY SURVEYOR'S OFFICE
6655 W. SAHARA AVE.–BLDG B–ROOM 102
LAS VEGAS, NEVADA 89102
(702) 455–7726

CONVERSION FACTOR

METERS x $\left(\frac{3937}{1200}\right)$ = U.S. SURVEY FEET

REVISION DATE 1992

20–62
SW A

Cross-Section Map

HEC-RAS Model
Sloanr.prj

HEC-RAS Version 3.1.3 May 2005
U.S. Army Corp of Engineers
Hydrologic Engineering Center
609 Second Street
Davis, California

```
X     X  XXXXXX    XXXX        XXXX       XX      XXXX
X     X  X        X    X       X   X     X  X    X
X     X  X        X            X   X    X    X   X
XXXXXXX  XXXX     X       XXX  XXXX     XXXXXX    XXXX
X     X  X        X            X  X     X    X        X
X     X  X        X    X       X   X    X    X        X
X     X  XXXXXX    XXXX        X    X   X    X   XXXXX
```

****

PROJECT DATA
Project Title: sloanr
Project File : sloanr.prj
Run Date and Time: 11/19/2006 1:39:31 PM

Project in English units

Project Description:

FLOODPLAIN DETERMINATION
FILES: BASE2.DWG, BASE2.DAT

STARTING WSE = NORMAL DEPTH
SUBCRITICAL RUN

****

PLAN DATA

Plan Title: Plan 03
Plan File : l:\PROJECTS\511606-CLOMR's\Sloan Channel\LOMR for CCRFCD\HEC-RAS\sloanr.p03

Geometry Title: sloanr
Geometry File : l:\PROJECTS\511606-CLOMR's\Sloan Channel\LOMR for CCRFCD\HEC-RAS\sloanr.g02

Flow Title : sloanr
Flow File : l:\PROJECTS\511606-CLOMR's\Sloan Channel\LOMR for CCRFCD\HEC-RAS\sloanr.f02

Plan Summary Information:
Number of: Cross Sections = 69 Multiple Openings = 0
Culverts = 0 Inline Structures = 0
Bridges = 2 Lateral Structures = 0

Computational Information
Water surface calculation tolerance = 0.01
Critical depth calculation tolerance = 0.01
Maximum number of iterations = 20
Maximum difference tolerance = 0.3
Flow tolerance factor = 0.001

Computation Options
Critical depth computed only where necessary
Conveyance Calculation Method: At breaks in n values only
Friction Slope Method: Average Conveyance
Computational Flow Regime: Mixed Flow

****

FLOW DATA

Flow Title: sloanr
Flow File : l:\PROJECTS\511606-CLOMR's\Sloan Channel\LOMR for CCRFCD\HEC-RAS\sloanr.f02

Flow Data (cfs)

River	Reach	RS	Post-Project	PF 2
Range Wash	Sloan Channel	225	2870	3300
Range Wash	Sloan Channel	220	2870	3300
Range Wash	Sloan Channel	210	2870	3300
Range Wash	Sloan Channel	100	3891	3300
Range Wash	Sloan Channel	40	3990	3300

Boundary Conditions

River	Reach	Profile	Upstream	Downstream
Range Wash	Sloan Channel	Post-Project	Normal S = 0.0042	Known WS = 1693.4

Changes in WS and EG

River	Reach	RS	Profile	Type	Value
Range Wash	Sloan Channel	10	Post-Project	Known WS	1693

****

GEOMETRY DATA

Geometry Title: sloanr
Geometry File : l:\PROJECTS\511606-CLOMR's\Sloan Channel\LOMR for CCRFCD\HEC-RAS\sloanr.g02

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 225

INPUT
Description: plan station 112+09 (FIS station 101+49)
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	1730.46	10	1724.46	40	1724.16	70	1724.46	80	1730.86

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.015	0	.015	80	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
0 80 274 274 274 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1730.39	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.76	Wt. n-Val.		0.015	
W.S. Elev (ft)	1727.63	Reach Len. (ft)	274.00	274.00	274.00
Crit W.S. (ft)	1728.30	Flow Area (sq ft)		215.29	
E.G. Slope (ft/ft)	*0.004207	Area (sq ft)		215.29	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	70.23	Top Width (ft)		70.23	
Vel Total (ft/s)	13.33	Avg. Vel. (ft/s)		13.33	
Max Chl Dpth (ft)	3.47	Hydr. Depth (ft)		3.07	
Conv. Total (cfs)	44248.5	Conv. (cfs)		44248.5	
Length Wtd. (ft)	274.00	Wetted Per. (ft)		72.04	
Min Ch El (ft)	1724.16	Shear (lb/sq ft)		0.78	
Alpha	1.00	Stream Power (lb/ft s)		10.46	
Frctn Loss (ft)		Cum Volume (acre-ft)		44.17	
C & E Loss (ft)		Cum SA (acres)		12.80	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1730.96	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.05	Wt. n-Val.		0.015	
W.S. Elev (ft)	1727.91	Reach Len. (ft)	274.00	274.00	274.00
Crit W.S. (ft)	1728.68	Flow Area (sq ft)		235.50	
E.G. Slope (ft/ft)	*0.004207	Area (sq ft)		235.50	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	71.15	Top Width (ft)		71.15	
Vel Total (ft/s)	14.01	Avg. Vel. (ft/s)		14.01	
Max Chl Dpth (ft)	3.75	Hydr. Depth (ft)		3.31	
Conv. Total (cfs)	50875.8	Conv. (cfs)		50875.8	
Length Wtd. (ft)	274.00	Wetted Per. (ft)		73.12	
Min Ch El (ft)	1724.16	Shear (lb/sq ft)		0.85	
Alpha	1.00	Stream Power (lb/ft s)		11.85	
Frctn Loss (ft)		Cum Volume (acre-ft)		42.91	
C & E Loss (ft)		Cum SA (acres)		12.79	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 220

INPUT
Description: plan station 114+87 u/s of Charleston Bridge (FIS 104+23)
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	1731.34	10	1723.19	40	1722.89	70	1723.19	80	1730.59

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.015	0	.015	80	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
0 80 151 151 151 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1729.21	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.86	Wt. n-Val.		0.015	
W.S. Elev (ft)	1726.35	Reach Len. (ft)	151.00	151.00	151.00
Crit W.S. (ft)	1727.06	Flow Area (sq ft)		211.55	
E.G. Slope (ft/ft)	*0.004319	Area (sq ft)		211.55	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	68.15	Top Width (ft)		68.15	
Vel Total (ft/s)	13.57	Avg. Vel. (ft/s)		13.57	
Max Chl Dpth (ft)	3.46	Hydr. Depth (ft)		3.10	
Conv. Total (cfs)	43671.3	Conv. (cfs)		43671.3	
Length Wtd. (ft)	151.00	Wetted Per. (ft)		70.32	
Min Ch El (ft)	1722.89	Shear (lb/sq ft)		0.81	
Alpha	1.00	Stream Power (lb/ft s)		11.00	
Frctn Loss (ft)	1.17	Cum Volume (acre-ft)		42.82	
C & E Loss (ft)	0.01	Cum SA (acres)		12.37	

Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1729.79	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.15	Wt. n-Val.		0.015	
W.S. Elev (ft)	1726.65	Reach Len. (ft)	151.00	151.00	151.00
Crit W.S. (ft)	1727.44	Flow Area (sq ft)		231.88	

* E.G. Slope (ft/ft)	*0.004283	* Area (sq ft)	*	* 231.88	*	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*	*
* Top Width (ft)	* 68.92	* Top Width (ft)	*	* 68.92	*	*
* Vel Total (ft/s)	* 14.23	* Avg. Vel. (ft/s)	*	* 14.23	*	*
* Max Chl Dpth (ft)	* 3.76	* Hydr. Depth (ft)	*	* 3.36	*	*
* Conv. Total (cfs)	* 50425.7	* Conv. (cfs)	*	* 50425.7	*	*
* Length Wtd. (ft)	* 151.00	* Wetted Per. (ft)	*	* 71.29	*	*
* Min Ch El (ft)	* 1722.89	* Shear (lb/sq ft)	*	* 0.87	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 12.38	*	*
* Frctn Loss (ft)	* 1.16	* Cum Volume (acre-ft)	*	* 41.44	*	*
* C & E Loss (ft)	* 0.01	* Cum SA (acres)	*	* 12.35	*	*

Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 215

INPUT
Description: Plan Station 116+40 u/s of Charleston Bridge (FIS 105+74)
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	1731	10	1722.56	40	1722.26	70	1722.56	80	1730.3

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.015	0	.015	80	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
0	80	50	50	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1728.61	* Element	* Left OB	* Channel	* Right OB	*
* Vel Head (ft)	* 1.16	* Wt. n-Val.	*	* 0.015	*	*
* W.S. Elev (ft)	* 1727.45	* Reach Len. (ft)	* 50.00	* 50.00	* 50.00	*
* Crit W.S. (ft)	* 1726.44	* Flow Area (sq ft)	*	* 331.87	*	*
* E.G. Slope (ft/ft)	*0.001060	* Area (sq ft)	*	* 331.87	*	*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	*	*
* Top Width (ft)	* 72.11	* Top Width (ft)	*	* 72.11	*	*
* Vel Total (ft/s)	* 8.65	* Avg. Vel. (ft/s)	*	* 8.65	*	*
* Max Chl Dpth (ft)	* 5.19	* Hydr. Depth (ft)	*	* 4.60	*	*
* Conv. Total (cfs)	* 88166.5	* Conv. (cfs)	*	* 88166.5	*	*
* Length Wtd. (ft)	* 50.00	* Wetted Per. (ft)	*	* 75.57	*	*
* Min Ch El (ft)	* 1722.26	* Shear (lb/sq ft)	*	* 0.29	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 2.51	*	*
* Frctn Loss (ft)	* 0.04	* Cum Volume (acre-ft)	*	* 41.88	*	*
* C & E Loss (ft)	* 0.08	* Cum SA (acres)	*	* 12.12	*	*

Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1729.18	* Element	* Left OB	* Channel	* Right OB	*
* Vel Head (ft)	* 1.26	* Wt. n-Val.	*	* 0.015	*	*
* W.S. Elev (ft)	* 1727.92	* Reach Len. (ft)	* 50.00	* 50.00	* 50.00	*
* Crit W.S. (ft)	* 1726.82	* Flow Area (sq ft)	*	* 366.08	*	*
* E.G. Slope (ft/ft)	*0.001037	* Area (sq ft)	*	* 366.08	*	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*	*
* Top Width (ft)	* 73.27	* Top Width (ft)	*	* 73.27	*	*
* Vel Total (ft/s)	* 9.01	* Avg. Vel. (ft/s)	*	* 9.01	*	*
* Max Chl Dpth (ft)	* 5.66	* Hydr. Depth (ft)	*	* 5.00	*	*
* Conv. Total (cfs)	*102476.5	* Conv. (cfs)	*	*102476.5	*	*
* Length Wtd. (ft)	* 50.00	* Wetted Per. (ft)	*	* 77.07	*	*
* Min Ch El (ft)	* 1722.26	* Shear (lb/sq ft)	*	* 0.31	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 2.77	*	*
* Frctn Loss (ft)	* 0.04	* Cum Volume (acre-ft)	*	* 40.40	*	*
* C & E Loss (ft)	* 0.09	* Cum SA (acres)	*	* 12.10	*	*

Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 213

INPUT
Description: plan station 116+90 u/s of Charleston Bridge (FIS 106+23)
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	1730.16	13	1722.26	45	1722.01	75	1722.26	85	1730.16

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.015	0	.015	85	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
0	85	1	1	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1728.48	* Element	* Left OB	* Channel	* Right OB	*
* Vel Head (ft)	* 0.89	* Wt. n-Val.	*	* 0.015	*	*
* W.S. Elev (ft)	* 1727.59	* Reach Len. (ft)	* 1.00	* 1.00	* 1.00	*
* Crit W.S. (ft)	*	* Flow Area (sq ft)	*	* 379.91	*	*

* E.G. Slope (ft/ft)	*0.000739	* Area (sq ft)	*	* 379.91	*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	*
* Top Width (ft)	* 77.53	* Top Width (ft)	*	* 77.53	*
* Vel Total (ft/s)	* 7.55	* Avg. Vel. (ft/s)	*	* 7.55	*
* Max Chl Dpth (ft)	* 5.58	* Hydr. Depth (ft)	*	* 4.90	*
* Conv. Total (cfs)	*105555.9	* Conv. (cfs)	*	*105555.9	*
* Length Wtd. (ft)	* 1.00	* Wetted Per. (ft)	*	* 80.88	*
* Min Ch El (ft)	* 1722.01	* Shear (lb/sq ft)	*	* 0.22	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 1.64	*
* Frctn Loss (ft)	* 0.00	* Cum Volume (acre-ft)	*	* 41.47	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 12.04	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1729.05	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 0.97	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1728.08	* Reach Len. (ft)	* 1.00	* 1.00	* 1.00 *
* Crit W.S. (ft)	*	* Flow Area (sq ft)	*	* 417.75	*
* E.G. Slope (ft/ft)	*0.000732	* Area (sq ft)	*	* 417.75	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*
* Top Width (ft)	* 78.94	* Top Width (ft)	*	* 78.94	*
* Vel Total (ft/s)	* 7.90	* Avg. Vel. (ft/s)	*	* 7.90	*
* Max Chl Dpth (ft)	* 6.07	* Hydr. Depth (ft)	*	* 5.29	*
* Conv. Total (cfs)	*121938.7	* Conv. (cfs)	*	*121938.7	*
* Length Wtd. (ft)	* 1.00	* Wetted Per. (ft)	*	* 82.59	*
* Min Ch El (ft)	* 1722.01	* Shear (lb/sq ft)	*	* 0.23	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 1.83	*
* Frctn Loss (ft)	* 0.00	* Cum Volume (acre-ft)	*	* 39.95	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 12.01	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 212

INPUT
Description: plan station 116+91 u/s of Charleston Bridge (FIS 106+24)
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	1730.15	13	1722.25	45	1722	75	1722.25	85	1730.15

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.015	0	.015	85	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
0	85	100	100	.2	.4

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1728.48	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 0.88	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1727.60	* Reach Len. (ft)	* 0.10	* 0.10	* 0.10 *
* Crit W.S. (ft)	* 1726.05	* Flow Area (sq ft)	*	* 380.85	*
* E.G. Slope (ft/ft)	*0.000734	* Area (sq ft)	*	* 380.85	*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	*
* Top Width (ft)	* 77.57	* Top Width (ft)	*	* 77.57	*
* Vel Total (ft/s)	* 7.54	* Avg. Vel. (ft/s)	*	* 7.54	*
* Max Chl Dpth (ft)	* 5.60	* Hydr. Depth (ft)	*	* 4.91	*
* Conv. Total (cfs)	*105952.9	* Conv. (cfs)	*	*105952.9	*
* Length Wtd. (ft)	* 0.10	* Wetted Per. (ft)	*	* 80.92	*
* Min Ch El (ft)	* 1722.00	* Shear (lb/sq ft)	*	* 0.22	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 1.62	*
* Frctn Loss (ft)	*	* Cum Volume (acre-ft)	*	* 41.46	*
* C & E Loss (ft)	*	* Cum SA (acres)	*	* 12.04	*

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1729.05	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 0.96	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1728.08	* Reach Len. (ft)	* 0.10	* 0.10	* 0.10 *
* Crit W.S. (ft)	* 1726.42	* Flow Area (sq ft)	*	* 418.70	*
* E.G. Slope (ft/ft)	*0.000727	* Area (sq ft)	*	* 418.70	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*
* Top Width (ft)	* 78.97	* Top Width (ft)	*	* 78.97	*
* Vel Total (ft/s)	* 7.88	* Avg. Vel. (ft/s)	*	* 7.88	*
* Max Chl Dpth (ft)	* 6.08	* Hydr. Depth (ft)	*	* 5.30	*
* Conv. Total (cfs)	*122361.0	* Conv. (cfs)	*	*122361.0	*
* Length Wtd. (ft)	* 0.10	* Wetted Per. (ft)	*	* 82.63	*
* Min Ch El (ft)	* 1722.00	* Shear (lb/sq ft)	*	* 0.23	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 1.81	*
* Frctn Loss (ft)	*	* Cum Volume (acre-ft)	*	* 39.94	*
* C & E Loss (ft)	*	* Cum SA (acres)	*	* 12.01	*

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

BRIDGE

RIVER: Range Wash
REACH: Sloan Channel RS: 211.5

```
INPUT
Description: Charleston Bridge
Distance from Upstream XS =       .1
Deck/Roadway Width        =    99.8
Weir Coefficient          =       3
Upstream  Deck/Roadway Coordinates
    num=       2
     Sta Hi Cord Lo Cord     Sta Hi Cord Lo Cord
**********************************************
       0 1729.77 1728.52      85 1729.52 1728.52

Upstream Bridge Cross Section Data
Station Elevation Data    num=       5
     Sta     Elev     Sta     Elev     Sta     Elev     Sta     Elev     Sta     Elev
*********************************************************************************
       0 1730.15      13 1722.25      45    1722      75 1722.25      85 1730.15

Manning's n Values        num=       3
     Sta   n Val     Sta   n Val     Sta   n Val
***********************************************
       0    .015       0    .015      85    .015

Bank Sta: Left   Right    Coeff Contr.   Expan.
             0      85             .2       .4

Downstream  Deck/Roadway Coordinates
    num=       2
     Sta Hi Cord Lo Cord     Sta Hi Cord Lo Cord
**********************************************
       0 1729.77 1728.52      80 1729.77 1728.52

Downstream Bridge Cross Section Data
Station Elevation Data    num=       5
     Sta     Elev     Sta     Elev     Sta     Elev     Sta     Elev     Sta     Elev
*********************************************************************************
       0 1730.16      10 1721.76      40  1721.5      70 1721.76      80 1730.16

Manning's n Values        num=       3
     Sta   n Val     Sta   n Val     Sta   n Val
***********************************************
       0    .015       0    .015      80    .015

Bank Sta: Left   Right    Coeff Contr.   Expan.
             0      80             .2       .4

Upstream Embankment side slope              =       0 horiz. to 1.0 vertical
Downstream Embankment side slope            =       0 horiz. to 1.0 vertical
Maximum allowable submergence for weir flow =     .95
Elevation at which weir flow begins         = 1729.52
Energy head used in spillway design         =
Spillway height used in design              =
Weir crest shape                            = Broad Crested

Number of Piers =  2

Pier Data
Pier Station     Upstream=      30    Downstream=      25
Upstream     num=       2
    Width   Elev    Width   Elev
*********************************
       2    1722       2 1728.52
Downstream     num=       2
    Width   Elev    Width   Elev
*********************************
       2    1722       2 1729.77

Pier Data
Pier Station     Upstream=      60    Downstream=      55
Upstream     num=       2
    Width   Elev    Width   Elev
*********************************
       2    1722       2 1728.52
Downstream     num=       2
    Width   Elev    Width   Elev
*********************************
       2    1722       2 1729.77

Number of Bridge Coefficient Sets =  1

Low Flow Methods and Data
       Yarnell                KVal =      .9
Selected Low Flow Methods = Yarnell

High Flow Method
       Energy Only

Additional Bridge Parameters
       Add Friction component to Momentum
       Do not add Weight component to Momentum
       Class B flow critical depth computations use critical depth
           inside the bridge at the upstream end
       Criteria to check for pressure flow = Upstream energy grade line

BRIDGE OUTPUT  Profile #Post-Project
*************************************************************************************************
* E.G. US. (ft)          *    1728.48  * Element               *Inside BR US *Inside BR DS *
* W.S. US. (ft)          *    1727.60  * E.G. Elev (ft)        *    1728.38  *    1727.80  *
* Q Total (cfs)          *    2870.00  * W.S. Elev (ft)        *    1727.21  *    1725.86  *
* Q Bridge (cfs)         *    2870.00  * Crit W.S. (ft)        *    1726.24  *    1725.86  *
* Q Weir (cfs)           *             * Max Chl Dpth (ft)     *       5.21  *       4.36  *
* Weir Sta Lft (ft)      *             * Vel Total (ft/s)      *       8.67  *      11.17  *
* Weir Sta Rgt (ft)      *             * Flow Area (sq ft)     *     331.05  *     257.03  *
* Weir Submerg           *             * Froude # Chl          *       0.71  *       1.00  *
* Weir Max Depth (ft)    *             * Specif Force (cu ft)  *    1583.34  *    1524.29  *
* Min El Weir Flow (ft)  *    1729.78  * Hydr Depth (ft)       *       4.57  *       3.91  *
```

* Min El Prs (ft)	* 1728.52	* W.P. Total (ft)	* 95.94	* 85.69 *
* Delta EG (ft)	* 0.64	* Conv. Total (cfs)	* 74884.1	* 52957.8 *
* Delta WS (ft)	* 2.44	* Top Width (ft)	* 72.45	* 65.77 *
* BR Open Area (sq ft)	* 428.13	* Frctn Loss (ft)	*	* *
* BR Open Vel (ft/s)	* 11.17	* C & E Loss (ft)	*	* *
* Coef of Q	*	* Shear Total (lb/sq ft)	* 0.32	* 0.55 *
* Br Sel Method	* Momentum	* Power Total (lb/ft s)	* 2.74	* 6.14 *

Warning: Pier drag coefficient of 2.0 assumed for Class B flow.
Warning: The momentum, Class B, supercritical, water surface downstream of the bridge had a higher energy than the upstream cross section. This is not physically possible. The downstream water surface has been computed by taking the momentum result inside of the bridge and performing an energy balance.
Note: The momentum method has computed a class B profile.
Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water surface that had the least amount of error between computed and assumed values.
Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

BRIDGE OUTPUT Profile #PF 2

* E.G. US. (ft)	* 1729.05	* Element	*Inside BR US	*Inside BR DS *
* W.S. US. (ft)	* 1728.08	* E.G. Elev (ft)	* 1728.94	* 1728.37 *
* Q Total (cfs)	* 3300.00	* W.S. Elev (ft)	* 1727.66	* 1726.25 *
* Q Bridge (cfs)	* 3300.00	* Crit W.S. (ft)	* 1726.60	* 1726.25 *
* Q Weir (cfs)	*	* Max Chl Dpth (ft)	* 5.66	* 4.74 *
* Weir Sta Lft (ft)	*	* Vel Total (ft/s)	* 9.07	* 11.69 *
* Weir Sta Rgt (ft)	*	* Flow Area (sq ft)	* 363.80	* 282.36 *
* Weir Submerg	*	* Froude # Chl	* 0.72	* 1.00 *
* Weir Max Depth (ft)	*	* Specif Force (cu ft)	* 1895.87	* 1829.97 *
* Min El Weir Flow (ft)	* 1729.78	* Hydr Depth (ft)	* 4.93	* 4.23 *
* Min El Prs (ft)	* 1728.52	* W.P. Total (ft)	* 99.32	* 88.41 *
* Delta EG (ft)	* 0.63	* Conv. Total (cfs)	* 85633.1	* 60663.5 *
* Delta WS (ft)	* 2.59	* Top Width (ft)	* 73.76	* 66.68 *
* BR Open Area (sq ft)	* 428.13	* Frctn Loss (ft)	*	* *
* BR Open Vel (ft/s)	* 11.69	* C & E Loss (ft)	*	* *
* Coef of Q	*	* Shear Total (lb/sq ft)	* 0.34	* 0.59 *
* Br Sel Method	* Momentum	* Power Total (lb/ft s)	* 3.08	* 6.90 *

Warning: Pier drag coefficient of 2.0 assumed for Class B flow.
Warning: The momentum, Class B, supercritical, water surface downstream of the bridge had a higher energy than the upstream cross section. This is not physically possible. The downstream water surface has been computed by taking the momentum result inside of the bridge and performing an energy balance.
Note: Yarnell answer is not valid if the water surface is above the low chord or if there is weir flow. The Yarnell answer has been disregarded.
Note: The momentum method has computed a class B profile.
Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water surface that had the least amount of error between computed and assumed values.
Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 211

INPUT
Description: plan station 117+90 d/s of Charleston Bridge (FIS 107+24)
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	1730.16	10	1721.76	40	1721.5	70	1721.76	80	1730.16

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.015	0	.015	80	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
0	80	1	1	.2	.4

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1727.68	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.52	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1725.15	* Reach Len. (ft)	* 1.00	* 1.00	* 1.00 *
* Crit W.S. (ft)	* 1725.67	* Flow Area (sq ft)	*	* 225.10	* *
* E.G. Slope (ft/ft)	*0.003527	* Area (sq ft)	*	* 225.10	* *
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	* *
* Top Width (ft)	* 68.08	* Top Width (ft)	*	* 68.08	* *
* Vel Total (ft/s)	* 12.75	* Avg. Vel. (ft/s)	*	* 12.75	* *
* Max Chl Dpth (ft)	* 3.65	* Hydr. Depth (ft)	*	* 3.31	* *
* Conv. Total (cfs)	* 48325.9	* Conv. (cfs)	*	* 48325.9	* *
* Length Wtd. (ft)	* 1.00	* Wetted Per. (ft)	*	* 70.55	* *
* Min Ch El (ft)	* 1721.50	* Shear (lb/sq ft)	*	* 0.70	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 8.96	* *
* Frctn Loss (ft)	*	* Cum Volume (acre-ft)	*	* 40.79	* *
* C & E Loss (ft)	*	* Cum SA (acres)	*	* 11.88	* *

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Note: The energy method has computed a class B profile.

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1728.24	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.75	* Wt. n-Val.	*	* 0.015	* *

* W.S. Elev (ft)	* 1725.49	* Reach Len. (ft)	* 1.00	* 1.00	* 1.00 *
* Crit W.S. (ft)	* 1726.04	* Flow Area (sq ft)	*	* 247.97	* *
* E.G. Slope (ft/ft)	*0.003444	* Area (sq ft)	*	* 247.97	* *
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	* *
* Top Width (ft)	* 68.87	* Top Width (ft)	*	* 68.87	* *
* Vel Total (ft/s)	* 13.31	* Avg. Vel. (ft/s)	*	* 13.31	* *
* Max Chl Dpth (ft)	* 3.99	* Hydr. Depth (ft)	*	* 3.60	* *
* Conv. Total (cfs)	* 56232.7	* Conv. (cfs)	*	* 56232.7	* *
* Length Wtd. (ft)	* 1.00	* Wetted Per. (ft)	*	* 71.59	* *
* Min Ch El (ft)	* 1721.50	* Shear (lb/sq ft)	*	* 0.74	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 9.91	* *
* Frctn Loss (ft)	*	* Cum Volume (acre-ft)	*	* 39.20	* *
* C & E Loss (ft)	*	* Cum SA (acres)	*	* 11.85	* *

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Note: The energy method has computed a class B profile.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 210.5

INPUT
Description: plan station 117+92 d/s of Charleston Bridge (FIS 107+25)
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
0	1729.02	13	1720.62	45	1720.36	75	1720.62	85	1729.02

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
0	.015	0	.015	85	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
0	85	97	97	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1727.34	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 4.17	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1723.17	* Reach Len. (ft)	* 97.00	* 97.00	* 97.00 *
* Crit W.S. (ft)	* 1724.42	* Flow Area (sq ft)	*	* 175.14	* *
* E.G. Slope (ft/ft)	*0.008159	* Area (sq ft)	*	* 175.14	* *
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	* *
* Top Width (ft)	* 68.99	* Top Width (ft)	*	* 68.99	* *
* Vel Total (ft/s)	* 16.39	* Avg. Vel. (ft/s)	*	* 16.39	* *
* Max Chl Dpth (ft)	* 2.81	* Hydr. Depth (ft)	*	* 2.54	* *
* Conv. Total (cfs)	* 31773.6	* Conv. (cfs)	*	* 31773.6	* *
* Length Wtd. (ft)	* 97.00	* Wetted Per. (ft)	*	* 70.67	* *
* Min Ch El (ft)	* 1720.36	* Shear (lb/sq ft)	*	* 1.26	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 20.69	* *
* Frctn Loss (ft)	* 0.01	* Cum Volume (acre-ft)	*	* 40.79	* *
* C & E Loss (ft)	* 0.33	* Cum SA (acres)	*	* 11.88	* *

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1727.89	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 4.43	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1723.46	* Reach Len. (ft)	* 97.00	* 97.00	* 97.00 *
* Crit W.S. (ft)	* 1724.80	* Flow Area (sq ft)	*	* 195.34	* *
* E.G. Slope (ft/ft)	*0.007637	* Area (sq ft)	*	* 195.34	* *
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	* *
* Top Width (ft)	* 69.78	* Top Width (ft)	*	* 69.78	* *
* Vel Total (ft/s)	* 16.89	* Avg. Vel. (ft/s)	*	* 16.89	* *
* Max Chl Dpth (ft)	* 3.10	* Hydr. Depth (ft)	*	* 2.80	* *
* Conv. Total (cfs)	* 37761.7	* Conv. (cfs)	*	* 37761.7	* *
* Length Wtd. (ft)	* 97.00	* Wetted Per. (ft)	*	* 71.66	* *
* Min Ch El (ft)	* 1720.36	* Shear (lb/sq ft)	*	* 1.30	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 21.96	* *
* Frctn Loss (ft)	* 0.00	* Cum Volume (acre-ft)	*	* 39.19	* *
* C & E Loss (ft)	* 0.34	* Cum SA (acres)	*	* 11.85	* *

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 210

INPUT
Description: PLAN STA 118+89
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1727.2	1011.86	1721.27	1046.86	1720.22	1081.86	1721.27	1093.72	1727.2

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

```
Bank Sta: Left   Right    Lengths: Left Channel   Right     Coeff Contr.   Expan.
          1000 1093.72             35.96   35.96   35.96          .1       .3

CROSS SECTION OUTPUT  Profile #Post-Project
**********************************************************************************************
* E.G. Elev (ft)        * 1726.29  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)         *    2.50  * Wt. n-Val.           *          *    0.015  *          *
* W.S. Elev (ft)        * 1723.79  * Reach Len. (ft)      *   35.96  *   35.96  *   35.96  *
* Crit W.S. (ft)        * 1724.40  * Flow Area (sq ft)    *          *  226.17  *          *
* E.G. Slope (ft/ft)    *0.004195  * Area (sq ft)         *          *  226.17  *          *
* Q Total (cfs)         * 2870.00  * Flow (cfs)           *          * 2870.00  *          *
* Top Width (ft)        *   80.10  * Top Width (ft)       *          *   80.10  *          *
* Vel Total (ft/s)      *   12.69  * Avg. Vel. (ft/s)     *          *   12.69  *          *
* Max Chl Dpth (ft)     *    3.57  * Hydr. Depth (ft)     *          *    2.82  *          *
* Conv. Total (cfs)     * 44309.0  * Conv. (cfs)          *          * 44309.0  *          *
* Length Wtd. (ft)      *   35.96  * Wetted Per. (ft)     *          *   81.32  *          *
* Min Ch El (ft)        * 1720.22  * Shear (lb/sq ft)     *          *    0.73  *          *
* Alpha                 *    1.00  * Stream Power (lb/ft s) *          *    9.24  *          *
* Frctn Loss (ft)       *    0.55  * Cum Volume (acre-ft)  *          *   40.34  *          *
* C & E Loss (ft)       *    0.50  * Cum SA (acres)        *          *   11.71  *          *
**********************************************************************************************

Warning: The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for
         additional cross sections.
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross
         section.  This may indicate the need for additional cross sections.

CROSS SECTION OUTPUT  Profile #PF 2
**********************************************************************************************
* E.G. Elev (ft)        * 1726.87  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)         *    2.87  * Wt. n-Val.           *          *    0.015  *          *
* W.S. Elev (ft)        * 1724.00  * Reach Len. (ft)      *   35.96  *   35.96  *   35.96  *
* Crit W.S. (ft)        * 1724.74  * Flow Area (sq ft)    *          *  242.60  *          *
* E.G. Slope (ft/ft)    *0.004456  * Area (sq ft)         *          *  242.60  *          *
* Q Total (cfs)         * 3300.00  * Flow (cfs)           *          * 3300.00  *          *
* Top Width (ft)        *   80.91  * Top Width (ft)       *          *   80.91  *          *
* Vel Total (ft/s)      *   13.60  * Avg. Vel. (ft/s)     *          *   13.60  *          *
* Max Chl Dpth (ft)     *    3.78  * Hydr. Depth (ft)     *          *    3.00  *          *
* Conv. Total (cfs)     * 49433.7  * Conv. (cfs)          *          * 49433.7  *          *
* Length Wtd. (ft)      *   35.96  * Wetted Per. (ft)     *          *   82.23  *          *
* Min Ch El (ft)        * 1720.22  * Shear (lb/sq ft)     *          *    0.82  *          *
* Alpha                 *    1.00  * Stream Power (lb/ft s) *          *   11.16  *          *
* Frctn Loss (ft)       *    0.56  * Cum Volume (acre-ft)  *          *   38.71  *          *
* C & E Loss (ft)       *    0.47  * Cum SA (acres)        *          *   11.68  *          *
**********************************************************************************************

Warning: The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for
         additional cross sections.
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross
         section.  This may indicate the need for additional cross sections.

CROSS SECTION


RIVER: Range Wash
REACH: Sloan Channel      RS: 200

INPUT
Description: PLAN STA 119+25
Station Elevation Data    num=       5
     Sta    Elev     Sta    Elev     Sta    Elev     Sta    Elev     Sta    Elev
*********************************************************************************
    1000 1726.22 1011.86 1720.29 1046.86 1719.24 1081.86 1720.29 1093.72 1726.22

Manning's n Values        num=       3
     Sta   n Val     Sta   n Val     Sta   n Val
***********************************************
    1000    .015    1000    .015 1093.72    .015

Bank Sta: Left   Right    Lengths: Left Channel   Right     Coeff Contr.   Expan.
          1000 1093.72             44.45   49.9   53.55          .1       .3

CROSS SECTION OUTPUT  Profile #Post-Project
**********************************************************************************************
* E.G. Elev (ft)        * 1725.98  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)         *    3.66  * Wt. n-Val.           *          *    0.015  *          *
* W.S. Elev (ft)        * 1722.32  * Reach Len. (ft)      *   44.45  *   49.90  *   53.55  *
* Crit W.S. (ft)        * 1723.42  * Flow Area (sq ft)    *          *  186.96  *          *
* E.G. Slope (ft/ft)    *0.007627  * Area (sq ft)         *          *  186.96  *          *
* Q Total (cfs)         * 2870.00  * Flow (cfs)           *          * 2870.00  *          *
* Top Width (ft)        *   78.11  * Top Width (ft)       *          *   78.11  *          *
* Vel Total (ft/s)      *   15.35  * Avg. Vel. (ft/s)     *          *   15.35  *          *
* Max Chl Dpth (ft)     *    3.08  * Hydr. Depth (ft)     *          *    2.39  *          *
* Conv. Total (cfs)     * 32862.5  * Conv. (cfs)          *          * 32862.5  *          *
* Length Wtd. (ft)      *   49.90  * Wetted Per. (ft)     *          *   79.10  *          *
* Min Ch El (ft)        * 1719.24  * Shear (lb/sq ft)     *          *    1.13  *          *
* Alpha                 *    1.00  * Stream Power (lb/ft s) *          *   17.28  *          *
* Frctn Loss (ft)       *    0.20  * Cum Volume (acre-ft)  *          *   40.17  *          *
* C & E Loss (ft)       *    0.12  * Cum SA (acres)        *          *   11.64  *          *
**********************************************************************************************

Warning: The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for
         additional cross sections.

CROSS SECTION OUTPUT  Profile #PF 2
**********************************************************************************************
* E.G. Elev (ft)        * 1726.55  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)         *    4.00  * Wt. n-Val.           *          *    0.015  *          *
* W.S. Elev (ft)        * 1722.56  * Reach Len. (ft)      *   44.45  *   49.90  *   53.55  *
* Crit W.S. (ft)        * 1723.76  * Flow Area (sq ft)    *          *  205.66  *          *
* E.G. Slope (ft/ft)    *0.007471  * Area (sq ft)         *          *  205.66  *          *
* Q Total (cfs)         * 3300.00  * Flow (cfs)           *          * 3300.00  *          *
* Top Width (ft)        *   79.07  * Top Width (ft)       *          *   79.07  *          *
* Vel Total (ft/s)      *   16.05  * Avg. Vel. (ft/s)     *          *   16.05  *          *
* Max Chl Dpth (ft)     *    3.32  * Hydr. Depth (ft)     *          *    2.60  *          *
* Conv. Total (cfs)     * 38179.0  * Conv. (cfs)          *          * 38179.0  *          *
```

* Length Wtd. (ft)	* 49.90	* Wetted Per. (ft)	*	* 80.17	*
* Min Ch El (ft)	* 1719.24	* Shear (lb/sq ft)	*	* 1.20	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 19.20	*
* Frctn Loss (ft)	* 0.20	* Cum Volume (acre-ft)	*	* 38.52	*
* C & E Loss (ft)	* 0.11	* Cum SA (acres)	*	* 11.61	*

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 198.571*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1726.02	1011.86	1720.09	1046.86	1719.04	1081.86	1720.09	1093.72	1726.02

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	44.45	49.9	53.55	.1 .3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1725.51	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 3.25	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1722.27	* Reach Len. (ft)	* 44.45	* 49.90	* 53.55 *
* Crit W.S. (ft)	* 1723.22	* Flow Area (sq ft)	*	* 198.44	* *
* E.G. Slope (ft/ft)	*0.006322	* Area (sq ft)	*	* 198.44	* *
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	* *
* Top Width (ft)	* 78.70	* Top Width (ft)	*	* 78.70	* *
* Vel Total (ft/s)	* 14.46	* Avg. Vel. (ft/s)	*	* 14.46	* *
* Max Chl Dpth (ft)	* 3.22	* Hydr. Depth (ft)	*	* 2.52	* *
* Conv. Total (cfs)	* 36095.3	* Conv. (cfs)	*	* 36095.3	* *
* Length Wtd. (ft)	* 49.90	* Wetted Per. (ft)	*	* 79.76	* *
* Min Ch El (ft)	* 1719.04	* Shear (lb/sq ft)	*	* 0.98	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 14.20	* *
* Frctn Loss (ft)	* 0.35	* Cum Volume (acre-ft)	*	* 39.95	* *
* C & E Loss (ft)	* 0.12	* Cum SA (acres)	*	* 11.55	* *

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1726.10	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 3.60	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1722.50	* Reach Len. (ft)	* 44.45	* 49.90	* 53.55 *
* Crit W.S. (ft)	* 1723.56	* Flow Area (sq ft)	*	* 216.76	* *
* E.G. Slope (ft/ft)	*0.006336	* Area (sq ft)	*	* 216.76	* *
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	* *
* Top Width (ft)	* 79.62	* Top Width (ft)	*	* 79.62	* *
* Vel Total (ft/s)	* 15.22	* Avg. Vel. (ft/s)	*	* 15.22	* *
* Max Chl Dpth (ft)	* 3.46	* Hydr. Depth (ft)	*	* 2.72	* *
* Conv. Total (cfs)	* 41457.9	* Conv. (cfs)	*	* 41457.9	* *
* Length Wtd. (ft)	* 49.90	* Wetted Per. (ft)	*	* 80.79	* *
* Min Ch El (ft)	* 1719.04	* Shear (lb/sq ft)	*	* 1.06	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 16.16	* *
* Frctn Loss (ft)	* 0.34	* Cum Volume (acre-ft)	*	* 38.28	* *
* C & E Loss (ft)	* 0.12	* Cum SA (acres)	*	* 11.52	* *

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 197.142*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1725.82	1011.86	1719.89	1046.86	1718.84	1081.86	1719.89	1093.72	1725.82

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	44.45	49.9	53.55	.1 .3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1725.13	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.94	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1722.20	* Reach Len. (ft)	* 44.45	* 49.90	* 53.55 *
* Crit W.S. (ft)	* 1723.02	* Flow Area (sq ft)	*	* 208.71	* *
* E.G. Slope (ft/ft)	*0.005395	* Area (sq ft)	*	* 208.71	* *
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	* *
* Top Width (ft)	* 79.22	* Top Width (ft)	*	* 79.22	* *
* Vel Total (ft/s)	* 13.75	* Avg. Vel. (ft/s)	*	* 13.75	* *
* Max Chl Dpth (ft)	* 3.35	* Hydr. Depth (ft)	*	* 2.63	* *
* Conv. Total (cfs)	* 39072.2	* Conv. (cfs)	*	* 39072.2	* *
* Length Wtd. (ft)	* 49.90	* Wetted Per. (ft)	*	* 80.34	* *
* Min Ch El (ft)	* 1718.84	* Shear (lb/sq ft)	*	* 0.88	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 12.03	* *
* Frctn Loss (ft)	* 0.29	* Cum Volume (acre-ft)	*	* 39.71	* *

* C & E Loss (ft)	* 0.09	* Cum SA (acres)	*	* 11.46	*

CROSS SECTION OUTPUT Profile #PF 2

			Left OB	Channel	Right OB
* E.G. Elev (ft)	* 1725.71	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 3.29	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1722.42	* Reach Len. (ft)	* 44.45	* 49.90	* 53.55
* Crit W.S. (ft)	* 1723.36	* Flow Area (sq ft)	*	* 226.73	*
* E.G. Slope (ft/ft)	*0.005504	* Area (sq ft)	*	* 226.73	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*
* Top Width (ft)	* 80.12	* Top Width (ft)	*	* 80.12	*
* Vel Total (ft/s)	* 14.55	* Avg. Vel. (ft/s)	*	* 14.55	*
* Max Chl Dpth (ft)	* 3.58	* Hydr. Depth (ft)	*	* 2.83	*
* Conv. Total (cfs)	* 44482.8	* Conv. (cfs)	*	* 44482.8	*
* Length Wtd. (ft)	* 49.90	* Wetted Per. (ft)	*	* 81.35	*
* Min Ch El (ft)	* 1718.84	* Shear (lb/sq ft)	*	* 0.96	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 13.94	*
* Frctn Loss (ft)	* 0.29	* Cum Volume (acre-ft)	*	* 38.03	*
* C & E Loss (ft)	* 0.09	* Cum SA (acres)	*	* 11.43	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 195.714*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1725.62	1011.86	1719.69	1046.86	1718.64	1081.86	1719.69	1093.72	1725.62

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	44.45	49.9	53.55 .1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
* E.G. Elev (ft)	* 1724.81	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 2.71	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1722.10	* Reach Len. (ft)	* 44.45	* 49.90	* 53.55
* Crit W.S. (ft)	* 1722.82	* Flow Area (sq ft)	*	* 217.26	*
* E.G. Slope (ft/ft)	*0.004758	* Area (sq ft)	*	* 217.26	*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	*
* Top Width (ft)	* 79.65	* Top Width (ft)	*	* 79.65	*
* Vel Total (ft/s)	* 13.21	* Avg. Vel. (ft/s)	*	* 13.21	*
* Max Chl Dpth (ft)	* 3.46	* Hydr. Depth (ft)	*	* 2.73	*
* Conv. Total (cfs)	* 41609.5	* Conv. (cfs)	*	* 41609.5	*
* Length Wtd. (ft)	* 49.90	* Wetted Per. (ft)	*	* 80.82	*
* Min Ch El (ft)	* 1718.64	* Shear (lb/sq ft)	*	* 0.80	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.55	*
* Frctn Loss (ft)	* 0.25	* Cum Volume (acre-ft)	*	* 39.47	*
* C & E Loss (ft)	* 0.07	* Cum SA (acres)	*	* 11.37	*

CROSS SECTION OUTPUT Profile #PF 2

			Left OB	Channel	Right OB
* E.G. Elev (ft)	* 1725.38	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 3.06	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1722.33	* Reach Len. (ft)	* 44.45	* 49.90	* 53.55
* Crit W.S. (ft)	* 1723.16	* Flow Area (sq ft)	*	* 235.23	*
* E.G. Slope (ft/ft)	*0.004906	* Area (sq ft)	*	* 235.23	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*
* Top Width (ft)	* 80.55	* Top Width (ft)	*	* 80.55	*
* Vel Total (ft/s)	* 14.03	* Avg. Vel. (ft/s)	*	* 14.03	*
* Max Chl Dpth (ft)	* 3.69	* Hydr. Depth (ft)	*	* 2.92	*
* Conv. Total (cfs)	* 47113.5	* Conv. (cfs)	*	* 47113.5	*
* Length Wtd. (ft)	* 49.90	* Wetted Per. (ft)	*	* 81.82	*
* Min Ch El (ft)	* 1718.64	* Shear (lb/sq ft)	*	* 0.88	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 12.35	*
* Frctn Loss (ft)	* 0.26	* Cum Volume (acre-ft)	*	* 37.76	*
* C & E Loss (ft)	* 0.07	* Cum SA (acres)	*	* 11.34	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 194.285*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1725.42	1011.86	1719.49	1046.86	1718.44	1081.86	1719.49	1093.72	1725.42

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	44.45	49.9	53.55 .1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1724.54	* Element	* Left OB	* Channel	* Right OB
* Vel Head (ft)	* 2.56	* Wt. n-Val.	*	* 0.015	*

* W.S. Elev (ft)	* 1721.98	* Reach Len. (ft)	* 44.45	* 49.90	* 53.55 *
* Crit W.S. (ft)	* 1722.62	* Flow Area (sq ft)	*	* 223.45	* *
* E.G. Slope (ft/ft)	*0.004357	* Area (sq ft)	*	* 223.45	* *
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	* *
* Top Width (ft)	* 79.96	* Top Width (ft)	*	* 79.96	* *
* Vel Total (ft/s)	* 12.84	* Avg. Vel. (ft/s)	*	* 12.84	* *
* Max Chl Dpth (ft)	* 3.54	* Hydr. Depth (ft)	*	* 2.79	* *
* Conv. Total (cfs)	* 43479.9	* Conv. (cfs)	*	* 43479.9	* *
* Length Wtd. (ft)	* 49.90	* Wetted Per. (ft)	*	* 81.17	* *
* Min Ch El (ft)	* 1718.44	* Shear (lb/sq ft)	*	* 0.75	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 9.62	* *
* Frctn Loss (ft)	* 0.23	* Cum Volume (acre-ft)	*	* 39.22	* *
* C & E Loss (ft)	* 0.04	* Cum SA (acres)	*	* 11.28	* *

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1725.10	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.89	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1722.21	* Reach Len. (ft)	* 44.45	* 49.90	* 53.55 *
* Crit W.S. (ft)	* 1722.96	* Flow Area (sq ft)	*	* 241.85	* *
* E.G. Slope (ft/ft)	*0.004500	* Area (sq ft)	*	* 241.85	* *
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	* *
* Top Width (ft)	* 80.87	* Top Width (ft)	*	* 80.87	* *
* Vel Total (ft/s)	* 13.64	* Avg. Vel. (ft/s)	*	* 13.64	* *
* Max Chl Dpth (ft)	* 3.77	* Hydr. Depth (ft)	*	* 2.99	* *
* Conv. Total (cfs)	* 49195.6	* Conv. (cfs)	*	* 49195.6	* *
* Length Wtd. (ft)	* 49.90	* Wetted Per. (ft)	*	* 82.19	* *
* Min Ch El (ft)	* 1718.44	* Shear (lb/sq ft)	*	* 0.83	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 11.28	* *
* Frctn Loss (ft)	* 0.23	* Cum Volume (acre-ft)	*	* 37.49	* *
* C & E Loss (ft)	* 0.05	* Cum SA (acres)	*	* 11.25	* *

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 192.857*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1725.22	1011.86	1719.29	1046.86	1718.24	1081.86	1719.29	1093.72	1725.22

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	44.45	49.9	53.55 .1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1724.32	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.51	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1721.81	* Reach Len. (ft)	* 44.45	* 49.90	* 53.55 *
* Crit W.S. (ft)	* 1722.42	* Flow Area (sq ft)	*	* 225.91	* *
* E.G. Slope (ft/ft)	*0.004210	* Area (sq ft)	*	* 225.91	* *
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	* *
* Top Width (ft)	* 80.08	* Top Width (ft)	*	* 80.08	* *
* Vel Total (ft/s)	* 12.70	* Avg. Vel. (ft/s)	*	* 12.70	* *
* Max Chl Dpth (ft)	* 3.57	* Hydr. Depth (ft)	*	* 2.82	* *
* Conv. Total (cfs)	* 44231.1	* Conv. (cfs)	*	* 44231.1	* *
* Length Wtd. (ft)	* 49.90	* Wetted Per. (ft)	*	* 81.30	* *
* Min Ch El (ft)	* 1718.24	* Shear (lb/sq ft)	*	* 0.73	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 9.28	* *
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	*	* 38.96	* *
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	*	* 11.19	* *

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1724.87	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.82	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1722.05	* Reach Len. (ft)	* 44.45	* 49.90	* 53.55 *
* Crit W.S. (ft)	* 1722.76	* Flow Area (sq ft)	*	* 244.95	* *
* E.G. Slope (ft/ft)	*0.004324	* Area (sq ft)	*	* 244.95	* *
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	* *
* Top Width (ft)	* 81.03	* Top Width (ft)	*	* 81.03	* *
* Vel Total (ft/s)	* 13.47	* Avg. Vel. (ft/s)	*	* 13.47	* *
* Max Chl Dpth (ft)	* 3.81	* Hydr. Depth (ft)	*	* 3.02	* *
* Conv. Total (cfs)	* 50182.3	* Conv. (cfs)	*	* 50182.3	* *
* Length Wtd. (ft)	* 49.90	* Wetted Per. (ft)	*	* 82.36	* *
* Min Ch El (ft)	* 1718.24	* Shear (lb/sq ft)	*	* 0.80	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.82	* *
* Frctn Loss (ft)	* 0.22	* Cum Volume (acre-ft)	*	* 37.21	* *
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	*	* 11.15	* *

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 191.428*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1725.02	1011.86	1719.09	1046.86	1718.04	1081.86	1719.09	1093.72	1725.02

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1093.72 44.45 49.9 53.55 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1724.11	Element		0.015	
Vel Head (ft)	2.49	Wt. n-Val.		0.015	
W.S. Elev (ft)	1721.62	Reach Len. (ft)	44.45	49.90	53.55
Crit W.S. (ft)	1722.22	Flow Area (sq ft)		226.63	
E.G. Slope (ft/ft)	*0.004169	Area (sq ft)		226.63	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	80.12	Top Width (ft)		80.12	
Vel Total (ft/s)	12.66	Avg. Vel. (ft/s)		12.66	
Max Chl Dpth (ft)	3.58	Hydr. Depth (ft)		2.83	
Conv. Total (cfs)	44451.4	Conv. (cfs)		44451.4	
Length Wtd. (ft)	49.90	Wetted Per. (ft)		81.34	
Min Ch El (ft)	1718.04	Shear (lb/sq ft)		0.73	
Alpha	1.00	Stream Power (lb/ft s)		9.18	
Frctn Loss (ft)	0.21	Cum Volume (acre-ft)		38.70	
C & E Loss (ft)	0.00	Cum SA (acres)		11.10	

CROSS SECTION OUTPUT Profile #PF 2

			Left OB	Channel	Right OB
E.G. Elev (ft)	1724.64	Element		0.015	
Vel Head (ft)	2.77	Wt. n-Val.		0.015	
W.S. Elev (ft)	1721.88	Reach Len. (ft)	44.45	49.90	53.55
Crit W.S. (ft)	1722.56	Flow Area (sq ft)		247.17	
E.G. Slope (ft/ft)	*0.004204	Area (sq ft)		247.17	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	81.14	Top Width (ft)		81.14	
Vel Total (ft/s)	13.35	Avg. Vel. (ft/s)		13.35	
Max Chl Dpth (ft)	3.83	Hydr. Depth (ft)		3.05	
Conv. Total (cfs)	50893.0	Conv. (cfs)		50893.0	
Length Wtd. (ft)	49.90	Wetted Per. (ft)		82.48	
Min Ch El (ft)	1718.04	Shear (lb/sq ft)		0.79	
Alpha	1.00	Stream Power (lb/ft s)		10.50	
Frctn Loss (ft)	0.21	Cum Volume (acre-ft)		36.93	
C & E Loss (ft)	0.02	Cum SA (acres)		11.06	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 190

INPUT
Description: PLAN STA 122+74
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1724.82	1011.86	1718.89	1046.86	1717.84	1081.86	1718.89	1093.72	1724.82

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1093.72 45.13 45.13 45.13 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1723.91	Element		0.015	
Vel Head (ft)	2.49	Wt. n-Val.		0.015	
W.S. Elev (ft)	1721.42	Reach Len. (ft)	45.13	45.13	45.13
Crit W.S. (ft)	1722.02	Flow Area (sq ft)		226.63	
E.G. Slope (ft/ft)	*0.004169	Area (sq ft)		226.63	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	80.12	Top Width (ft)		80.12	
Vel Total (ft/s)	12.66	Avg. Vel. (ft/s)		12.66	
Max Chl Dpth (ft)	3.58	Hydr. Depth (ft)		2.83	
Conv. Total (cfs)	44449.8	Conv. (cfs)		44449.8	
Length Wtd. (ft)	45.13	Wetted Per. (ft)		81.34	
Min Ch El (ft)	1717.84	Shear (lb/sq ft)		0.73	
Alpha	1.00	Stream Power (lb/ft s)		9.18	
Frctn Loss (ft)	0.21	Cum Volume (acre-ft)		38.44	
C & E Loss (ft)	0.00	Cum SA (acres)		11.01	

CROSS SECTION OUTPUT Profile #PF 2

			Left OB	Channel	Right OB
E.G. Elev (ft)	1724.44	Element		0.015	
Vel Head (ft)	2.77	Wt. n-Val.		0.015	
W.S. Elev (ft)	1721.67	Reach Len. (ft)	45.13	45.13	45.13
Crit W.S. (ft)	1722.36	Flow Area (sq ft)		247.17	
E.G. Slope (ft/ft)	*0.004205	Area (sq ft)		247.17	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	81.14	Top Width (ft)		81.14	
Vel Total (ft/s)	13.35	Avg. Vel. (ft/s)		13.35	
Max Chl Dpth (ft)	3.83	Hydr. Depth (ft)		3.05	
Conv. Total (cfs)	50891.3	Conv. (cfs)		50891.3	
Length Wtd. (ft)	45.13	Wetted Per. (ft)		82.48	
Min Ch El (ft)	1717.84	Shear (lb/sq ft)		0.79	
Alpha	1.00	Stream Power (lb/ft s)		10.50	
Frctn Loss (ft)	0.21	Cum Volume (acre-ft)		36.64	
C & E Loss (ft)	0.00	Cum SA (acres)		10.97	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 188.*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1724.64	1011.86	1718.71	1046.86	1717.66	1081.86	1718.71	1093.72	1724.64

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	45.13	45.13	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1723.73	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.49	Wt. n-Val.		0.015	
W.S. Elev (ft)	1721.24	Reach Len. (ft)	45.13	45.13	45.13
Crit W.S. (ft)	1721.84	Flow Area (sq ft)		226.63	
E.G. Slope (ft/ft)	*0.004169	Area (sq ft)		226.63	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	80.12	Top Width (ft)		80.12	
Vel Total (ft/s)	12.66	Avg. Vel. (ft/s)		12.66	
Max Chl Dpth (ft)	3.58	Hydr. Depth (ft)		2.83	
Conv. Total (cfs)	44451.4	Conv. (cfs)		44451.4	
Length Wtd. (ft)	45.13	Wetted Per. (ft)		81.34	
Min Ch El (ft)	1717.66	Shear (lb/sq ft)		0.73	
Alpha	1.00	Stream Power (lb/ft s)		9.18	
Frctn Loss (ft)	0.19	Cum Volume (acre-ft)		38.21	
C & E Loss (ft)	0.00	Cum SA (acres)		10.92	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1724.26	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.77	Wt. n-Val.		0.015	
W.S. Elev (ft)	1721.50	Reach Len. (ft)	45.13	45.13	45.13
Crit W.S. (ft)	1722.20	Flow Area (sq ft)		247.17	
E.G. Slope (ft/ft)	*0.004204	Area (sq ft)		247.17	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	81.14	Top Width (ft)		81.14	
Vel Total (ft/s)	13.35	Avg. Vel. (ft/s)		13.35	
Max Chl Dpth (ft)	3.83	Hydr. Depth (ft)		3.05	
Conv. Total (cfs)	50893.0	Conv. (cfs)		50893.0	
Length Wtd. (ft)	45.13	Wetted Per. (ft)		82.48	
Min Ch El (ft)	1717.66	Shear (lb/sq ft)		0.79	
Alpha	1.00	Stream Power (lb/ft s)		10.50	
Frctn Loss (ft)	0.19	Cum Volume (acre-ft)		36.39	
C & E Loss (ft)	0.00	Cum SA (acres)		10.88	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 186.*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1724.46	1011.86	1718.53	1046.86	1717.48	1081.86	1718.53	1093.72	1724.46

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	45.13	45.13	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1723.55	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.49	Wt. n-Val.		0.015	
W.S. Elev (ft)	1721.06	Reach Len. (ft)	45.13	45.13	45.13
Crit W.S. (ft)	1721.67	Flow Area (sq ft)		226.63	
E.G. Slope (ft/ft)	*0.004169	Area (sq ft)		226.63	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	80.12	Top Width (ft)		80.12	
Vel Total (ft/s)	12.66	Avg. Vel. (ft/s)		12.66	
Max Chl Dpth (ft)	3.58	Hydr. Depth (ft)		2.83	
Conv. Total (cfs)	44449.8	Conv. (cfs)		44449.8	
Length Wtd. (ft)	45.13	Wetted Per. (ft)		81.34	
Min Ch El (ft)	1717.48	Shear (lb/sq ft)		0.73	
Alpha	1.00	Stream Power (lb/ft s)		9.18	
Frctn Loss (ft)	0.19	Cum Volume (acre-ft)		37.97	
C & E Loss (ft)	0.00	Cum SA (acres)		10.84	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1724.08	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.77	Wt. n-Val.		0.015	
W.S. Elev (ft)	1721.31	Reach Len. (ft)	45.13	45.13	45.13
Crit W.S. (ft)	1722.02	Flow Area (sq ft)		247.17	
E.G. Slope (ft/ft)	*0.004205	Area (sq ft)		247.17	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	

* Top Width (ft)	* 81.14	* Top Width (ft)	*	* 81.14 * *
* Vel Total (ft/s)	* 13.35	* Avg. Vel. (ft/s)	*	* 13.35 * *
* Max Chl Dpth (ft)	* 3.83	* Hydr. Depth (ft)	*	* 3.05 * *
* Conv. Total (cfs)	* 50891.3	* Conv. (cfs)	*	* 50891.3 * *
* Length Wtd. (ft)	* 45.13	* Wetted Per. (ft)	*	* 82.48 * *
* Min Ch El (ft)	* 1717.48	* Shear (lb/sq ft)	*	* 0.79 * *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.50 * *
* Frctn Loss (ft)	* 0.19	* Cum Volume (acre-ft)	*	* 36.13 * *
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 10.80 * *

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 184.*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1724.28	1011.86	1718.35	1046.86	1717.3	1081.86	1718.35	1093.72	1724.28

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	45.13	45.13	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1723.37	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.49	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1720.88	* Reach Len. (ft)	* 45.13	* 45.13	* 45.13 *
* Crit W.S. (ft)	* 1721.49	* Flow Area (sq ft)	*	* 226.63	* *
* E.G. Slope (ft/ft)	*0.004169	* Area (sq ft)	*	* 226.63	* *
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	* *
* Top Width (ft)	* 80.12	* Top Width (ft)	*	* 80.12	* *
* Vel Total (ft/s)	* 12.66	* Avg. Vel. (ft/s)	*	* 12.66	* *
* Max Chl Dpth (ft)	* 3.58	* Hydr. Depth (ft)	*	* 2.83	* *
* Conv. Total (cfs)	* 44451.4	* Conv. (cfs)	*	* 44451.4	* *
* Length Wtd. (ft)	* 45.13	* Wetted Per. (ft)	*	* 81.34	* *
* Min Ch El (ft)	* 1717.30	* Shear (lb/sq ft)	*	* 0.73	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 9.18	* *
* Frctn Loss (ft)	* 0.19	* Cum Volume (acre-ft)	*	* 37.74	* *
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 10.76	* *

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1723.90	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.77	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1721.14	* Reach Len. (ft)	* 45.13	* 45.13	* 45.13 *
* Crit W.S. (ft)	* 1721.84	* Flow Area (sq ft)	*	* 247.17	* *
* E.G. Slope (ft/ft)	*0.004204	* Area (sq ft)	*	* 247.17	* *
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	* *
* Top Width (ft)	* 81.14	* Top Width (ft)	*	* 81.14	* *
* Vel Total (ft/s)	* 13.35	* Avg. Vel. (ft/s)	*	* 13.35	* *
* Max Chl Dpth (ft)	* 3.83	* Hydr. Depth (ft)	*	* 3.05	* *
* Conv. Total (cfs)	* 50893.0	* Conv. (cfs)	*	* 50893.0	* *
* Length Wtd. (ft)	* 45.13	* Wetted Per. (ft)	*	* 82.48	* *
* Min Ch El (ft)	* 1717.30	* Shear (lb/sq ft)	*	* 0.79	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.50	* *
* Frctn Loss (ft)	* 0.19	* Cum Volume (acre-ft)	*	* 35.88	* *
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 10.72	* *

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 182.*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1724.1	1011.86	1718.17	1046.86	1717.12	1081.86	1718.17	1093.72	1724.1

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	45.13	45.13	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1723.19	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.49	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1720.70	* Reach Len. (ft)	* 45.13	* 45.13	* 45.13 *
* Crit W.S. (ft)	* 1721.31	* Flow Area (sq ft)	*	* 226.63	* *
* E.G. Slope (ft/ft)	*0.004169	* Area (sq ft)	*	* 226.63	* *
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	* *
* Top Width (ft)	* 80.12	* Top Width (ft)	*	* 80.12	* *
* Vel Total (ft/s)	* 12.66	* Avg. Vel. (ft/s)	*	* 12.66	* *
* Max Chl Dpth (ft)	* 3.58	* Hydr. Depth (ft)	*	* 2.83	* *
* Conv. Total (cfs)	* 44449.8	* Conv. (cfs)	*	* 44449.8	* *
* Length Wtd. (ft)	* 45.13	* Wetted Per. (ft)	*	* 81.34	* *
* Min Ch El (ft)	* 1717.12	* Shear (lb/sq ft)	*	* 0.73	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 9.18	* *

* Frctn Loss (ft)	* 0.19	* Cum Volume (acre-ft)	*	* 37.50	*	*	*	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 10.67	*	*	*	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1723.72	* Element	*	Left OB *	Channel	* Right OB *		
* Vel Head (ft)	* 2.77	* Wt. n-Val.	*	*	0.015	*	*	*
* W.S. Elev (ft)	* 1720.95	* Reach Len. (ft)	*	45.13 *	45.13	* 45.13 *	*	*
* Crit W.S. (ft)	* 1721.66	* Flow Area (sq ft)	*	*	247.17	*	*	*
* E.G. Slope (ft/ft)	*0.004205	* Area (sq ft)	*	*	247.17	*	*	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	*	3300.00	*	*	*
* Top Width (ft)	* 81.14	* Top Width (ft)	*	*	81.14	*	*	*
* Vel Total (ft/s)	* 13.35	* Avg. Vel. (ft/s)	*	*	13.35	*	*	*
* Max Chl Dpth (ft)	* 3.83	* Hydr. Depth (ft)	*	*	3.05	*	*	*
* Conv. Total (cfs)	* 50891.3	* Conv. (cfs)	*	*	50891.3	*	*	*
* Length Wtd. (ft)	* 45.13	* Wetted Per. (ft)	*	*	82.48	*	*	*
* Min Ch El (ft)	* 1717.12	* Shear (lb/sq ft)	*	*	0.79	*	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	*	10.50	*	*	*
* Frctn Loss (ft)	* 0.19	* Cum Volume (acre-ft)	*	*	35.62	*	*	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	*	10.63	*	*	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 180

INPUT
Description: PLAN STA 125+00
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1723.92	1011.86	1717.99	1046.86	1716.94	1081.86	1717.99	1093.72	1723.92

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1093.72	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1093.72	100	100	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1723.01	* Element	*	Left OB *	Channel	* Right OB *		
* Vel Head (ft)	* 2.49	* Wt. n-Val.	*	*	0.015	*	*	*
* W.S. Elev (ft)	* 1720.52	* Reach Len. (ft)	*	100.00 *	100.00	* 100.00 *	*	*
* Crit W.S. (ft)	* 1721.13	* Flow Area (sq ft)	*	*	226.63	*	*	*
* E.G. Slope (ft/ft)	*0.004169	* Area (sq ft)	*	*	226.63	*	*	*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	*	2870.00	*	*	*
* Top Width (ft)	* 80.12	* Top Width (ft)	*	*	80.12	*	*	*
* Vel Total (ft/s)	* 12.66	* Avg. Vel. (ft/s)	*	*	12.66	*	*	*
* Max Chl Dpth (ft)	* 3.58	* Hydr. Depth (ft)	*	*	2.83	*	*	*
* Conv. Total (cfs)	* 44449.8	* Conv. (cfs)	*	*	44449.8	*	*	*
* Length Wtd. (ft)	* 100.00	* Wetted Per. (ft)	*	*	81.34	*	*	*
* Min Ch El (ft)	* 1716.94	* Shear (lb/sq ft)	*	*	0.73	*	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	*	9.18	*	*	*
* Frctn Loss (ft)	* 0.19	* Cum Volume (acre-ft)	*	*	37.27	*	*	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	*	10.59	*	*	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1723.54	* Element	*	Left OB *	Channel	* Right OB *		
* Vel Head (ft)	* 2.77	* Wt. n-Val.	*	*	0.015	*	*	*
* W.S. Elev (ft)	* 1720.77	* Reach Len. (ft)	*	100.00 *	100.00	* 100.00 *	*	*
* Crit W.S. (ft)	* 1721.47	* Flow Area (sq ft)	*	*	247.17	*	*	*
* E.G. Slope (ft/ft)	*0.004205	* Area (sq ft)	*	*	247.17	*	*	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	*	3300.00	*	*	*
* Top Width (ft)	* 81.14	* Top Width (ft)	*	*	81.14	*	*	*
* Vel Total (ft/s)	* 13.35	* Avg. Vel. (ft/s)	*	*	13.35	*	*	*
* Max Chl Dpth (ft)	* 3.83	* Hydr. Depth (ft)	*	*	3.05	*	*	*
* Conv. Total (cfs)	* 50891.3	* Conv. (cfs)	*	*	50891.3	*	*	*
* Length Wtd. (ft)	* 100.00	* Wetted Per. (ft)	*	*	82.48	*	*	*
* Min Ch El (ft)	* 1716.94	* Shear (lb/sq ft)	*	*	0.79	*	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	*	10.50	*	*	*
* Frctn Loss (ft)	* 0.19	* Cum Volume (acre-ft)	*	*	35.36	*	*	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	*	10.55	*	*	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 170

INPUT
Description: PLAN STA 126+00
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1722.67	1011.46	1716.94	1041.46	1716.04	1071.46	1716.94	1082.92	1722.67

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	51.96	51.96	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1722.56	* Element	*	Left OB *	Channel	* Right OB *

* Vel Head (ft)	* 2.76	* Wt. n-Val.	*		* 0.015	*		*
* W.S. Elev (ft)	* 1719.81	* Reach Len. (ft)	*	51.96	* 51.96	*	51.96	*
* Crit W.S. (ft)	* 1720.50	* Flow Area (sq ft)	*		* 215.41	*		*
* E.G. Slope (ft/ft)	*0.004262	* Area (sq ft)	*		* 215.41	*		*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*		* 2870.00	*		*
* Top Width (ft)	* 71.47	* Top Width (ft)	*		* 71.47	*		*
* Vel Total (ft/s)	* 13.32	* Avg. Vel. (ft/s)	*		* 13.32	*		*
* Max Chl Dpth (ft)	* 3.77	* Hydr. Depth (ft)	*		* 3.01	*		*
* Conv. Total (cfs)	* 43961.6	* Conv. (cfs)	*		* 43961.6	*		*
* Length Wtd. (ft)	* 51.96	* Wetted Per. (ft)	*		* 72.85	*		*
* Min Ch El (ft)	* 1716.04	* Shear (lb/sq ft)	*		* 0.79	*		*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*		* 10.48	*		*
* Frctn Loss (ft)	* 0.42	* Cum Volume (acre-ft)	*		* 36.76	*		*
* C & E Loss (ft)	* 0.03	* Cum SA (acres)	*		* 10.42	*		*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1723.10	* Element	*	Left OB	* Channel	*	Right OB	*
* Vel Head (ft)	* 2.98	* Wt. n-Val.	*		* 0.015	*		*
* W.S. Elev (ft)	* 1720.12	* Reach Len. (ft)	*	51.96	* 51.96	*	51.96	*
* Crit W.S. (ft)	* 1720.87	* Flow Area (sq ft)	*		* 238.08	*		*
* E.G. Slope (ft/ft)	*0.004141	* Area (sq ft)	*		* 238.08	*		*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*		* 3300.00	*		*
* Top Width (ft)	* 72.72	* Top Width (ft)	*		* 72.72	*		*
* Vel Total (ft/s)	* 13.86	* Avg. Vel. (ft/s)	*		* 13.86	*		*
* Max Chl Dpth (ft)	* 4.08	* Hydr. Depth (ft)	*		* 3.27	*		*
* Conv. Total (cfs)	* 51282.2	* Conv. (cfs)	*		* 51282.2	*		*
* Length Wtd. (ft)	* 51.96	* Wetted Per. (ft)	*		* 74.25	*		*
* Min Ch El (ft)	* 1716.04	* Shear (lb/sq ft)	*		* 0.83	*		*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*		* 11.49	*		*
* Frctn Loss (ft)	* 0.42	* Cum Volume (acre-ft)	*		* 34.81	*		*
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	*		* 10.37	*		*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 160

INPUT
Description: PLAN STA 126+52
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1722.47	1011.46	1716.74	1041.46	1715.84	1071.46	1716.74	1082.92	1722.47

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	74.33	74.33	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1722.33	* Element	*	Left OB	* Channel	*	Right OB	*
* Vel Head (ft)	* 2.69	* Wt. n-Val.	*		* 0.015	*		*
* W.S. Elev (ft)	* 1719.65	* Reach Len. (ft)	*	74.33	* 74.33	*	74.33	*
* Crit W.S. (ft)	* 1720.30	* Flow Area (sq ft)	*		* 218.16	*		*
* E.G. Slope (ft/ft)	*0.004098	* Area (sq ft)	*		* 218.16	*		*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*		* 2870.00	*		*
* Top Width (ft)	* 71.62	* Top Width (ft)	*		* 71.62	*		*
* Vel Total (ft/s)	* 13.16	* Avg. Vel. (ft/s)	*		* 13.16	*		*
* Max Chl Dpth (ft)	* 3.80	* Hydr. Depth (ft)	*		* 3.05	*		*
* Conv. Total (cfs)	* 44832.0	* Conv. (cfs)	*		* 44832.0	*		*
* Length Wtd. (ft)	* 74.33	* Wetted Per. (ft)	*		* 73.02	*		*
* Min Ch El (ft)	* 1715.84	* Shear (lb/sq ft)	*		* 0.76	*		*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*		* 10.06	*		*
* Frctn Loss (ft)	* 0.22	* Cum Volume (acre-ft)	*		* 36.50	*		*
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	*		* 10.33	*		*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1722.88	* Element	*	Left OB	* Channel	*	Right OB	*
* Vel Head (ft)	* 2.93	* Wt. n-Val.	*		* 0.015	*		*
* W.S. Elev (ft)	* 1719.95	* Reach Len. (ft)	*	74.33	* 74.33	*	74.33	*
* Crit W.S. (ft)	* 1720.67	* Flow Area (sq ft)	*		* 240.13	*		*
* E.G. Slope (ft/ft)	*0.004033	* Area (sq ft)	*		* 240.13	*		*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*		* 3300.00	*		*
* Top Width (ft)	* 72.84	* Top Width (ft)	*		* 72.84	*		*
* Vel Total (ft/s)	* 13.74	* Avg. Vel. (ft/s)	*		* 13.74	*		*
* Max Chl Dpth (ft)	* 4.11	* Hydr. Depth (ft)	*		* 3.30	*		*
* Conv. Total (cfs)	* 51960.7	* Conv. (cfs)	*		* 51960.7	*		*
* Length Wtd. (ft)	* 74.33	* Wetted Per. (ft)	*		* 74.38	*		*
* Min Ch El (ft)	*-1715.84	* Shear (lb/sq ft)	*		* 0.81	*		*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*		* 11.17	*		*
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	*		* 34.52	*		*
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	*		* 10.28	*		*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 158.333*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1722.19	1010.43	1716.97	1011.69	1716.45	1042.29	1715.56	1070.15	1716.42

1071.69 1716.58 1082.92 1722.19

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.

Left	Right	Left	Channel	Right	Coeff Contr.	Expan.
1000	1082.92	74.33	74.33	74.33	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1722.02	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.61	Wt. n-Val.		0.015	
W.S. Elev (ft)	1719.41	Reach Len. (ft)	74.33	74.33	74.33
Crit W.S. (ft)	1720.02	Flow Area (sq ft)		221.52	
E.G. Slope (ft/ft)	*0.003907	Area (sq ft)		221.52	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	71.81	Top Width (ft)		71.81	
Vel Total (ft/s)	12.96	Avg. Vel. (ft/s)		12.96	
Max Chl Dpth (ft)	3.85	Hydr. Depth (ft)		3.08	
Conv. Total (cfs)	45914.8	Conv. (cfs)		45914.8	
Length Wtd. (ft)	74.33	Wetted Per. (ft)		73.19	
Min Ch El (ft)	1715.56	Shear (lb/sq ft)		0.74	
Alpha	1.00	Stream Power (lb/ft s)		9.56	
Frctn Loss (ft)	0.30	Cum Volume (acre-ft)		36.13	
C & E Loss (ft)	0.02	Cum SA (acres)		10.21	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1722.57	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.87	Wt. n-Val.		0.015	
W.S. Elev (ft)	1719.71	Reach Len. (ft)	74.33	74.33	74.33
Crit W.S. (ft)	1720.39	Flow Area (sq ft)		242.91	
E.G. Slope (ft/ft)	*0.003891	Area (sq ft)		242.91	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	72.99	Top Width (ft)		72.99	
Vel Total (ft/s)	13.59	Avg. Vel. (ft/s)		13.59	
Max Chl Dpth (ft)	4.15	Hydr. Depth (ft)		3.33	
Conv. Total (cfs)	52904.0	Conv. (cfs)		52904.0	
Length Wtd. (ft)	74.33	Wetted Per. (ft)		74.52	
Min Ch El (ft)	1715.56	Shear (lb/sq ft)		0.79	
Alpha	1.00	Stream Power (lb/ft s)		10.76	
Frctn Loss (ft)	0.29	Cum Volume (acre-ft)		34.11	
C & E Loss (ft)	0.02	Cum SA (acres)		10.16	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 156.666*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1721.91	1010.64	1716.59	1011.92	1716.17	1043.13	1715.28	1070.41	1716.15
1071.92	1716.41	1082.92	1721.91						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.

Left	Right	Left	Channel	Right	Coeff Contr.	Expan.
1000	1082.92	74.33	74.33	74.33	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1721.73	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.58	Wt. n-Val.		0.015	
W.S. Elev (ft)	1719.15	Reach Len. (ft)	74.33	74.33	74.33
Crit W.S. (ft)	1719.74	Flow Area (sq ft)		222.46	
E.G. Slope (ft/ft)	*0.003856	Area (sq ft)		222.46	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	71.88	Top Width (ft)		71.88	
Vel Total (ft/s)	12.90	Avg. Vel. (ft/s)		12.90	
Max Chl Dpth (ft)	3.87	Hydr. Depth (ft)		3.10	
Conv. Total (cfs)	46219.4	Conv. (cfs)		46219.4	
Length Wtd. (ft)	74.33	Wetted Per. (ft)		73.24	
Min Ch El (ft)	1715.28	Shear (lb/sq ft)		0.73	
Alpha	1.00	Stream Power (lb/ft s)		9.43	
Frctn Loss (ft)	0.29	Cum Volume (acre-ft)		35.75	
C & E Loss (ft)	0.01	Cum SA (acres)		10.09	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1722.29	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.85	Wt. n-Val.		0.015	
W.S. Elev (ft)	1719.44	Reach Len. (ft)	74.33	74.33	74.33
Crit W.S. (ft)	1720.11	Flow Area (sq ft)		243.76	
E.G. Slope (ft/ft)	*0.003849	Area (sq ft)		243.76	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	73.05	Top Width (ft)		73.05	
Vel Total (ft/s)	13.54	Avg. Vel. (ft/s)		13.54	
Max Chl Dpth (ft)	4.16	Hydr. Depth (ft)		3.34	
Conv. Total (cfs)	53193.4	Conv. (cfs)		53193.4	
Length Wtd. (ft)	74.33	Wetted Per. (ft)		74.56	
Min Ch El (ft)	1715.28	Shear (lb/sq ft)		0.79	
Alpha	1.00	Stream Power (lb/ft s)		10.63	
Frctn Loss (ft)	0.29	Cum Volume (acre-ft)		33.69	
C & E Loss (ft)	0.01	Cum SA (acres)		10.04	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 155.*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1721.63	1010.84	1716.21	1012.15	1715.88	1043.96		1715	1070.67
1715.88	1072.15	1716.25	1082.92	1721.63					

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1082.92 74.33 74.33 74.33 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1721.45	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.58	Wt. n-Val.		0.015	
W.S. Elev (ft)	1718.87	Reach Len. (ft)	74.33	74.33	74.33
Crit W.S. (ft)	1719.46	Flow Area (sq ft)		222.44	
E.G. Slope (ft/ft)	*0.003856	Area (sq ft)		222.44	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	71.87	Top Width (ft)		71.87	
Vel Total (ft/s)	12.90	Avg. Vel. (ft/s)		12.90	
Max Chl Dpth (ft)	3.87	Hydr. Depth (ft)		3.10	
Conv. Total (cfs)	46218.1	Conv. (cfs)		46218.1	
Length Wtd. (ft)	74.33	Wetted Per. (ft)		73.23	
Min Ch El (ft)	1715.00	Shear (lb/sq ft)		0.73	
Alpha	1.00	Stream Power (lb/ft s)		9.43	
Frctn Loss (ft)	0.29	Cum Volume (acre-ft)		35.37	
C & E Loss (ft)	0.00	Cum SA (acres)		9.96	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1722.01	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.85	Wt. n-Val.		0.015	
W.S. Elev (ft)	1719.16	Reach Len. (ft)	74.33	74.33	74.33
Crit W.S. (ft)	1719.83	Flow Area (sq ft)		243.74	
E.G. Slope (ft/ft)	*0.003849	Area (sq ft)		243.74	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	73.05	Top Width (ft)		73.05	
Vel Total (ft/s)	13.54	Avg. Vel. (ft/s)		13.54	
Max Chl Dpth (ft)	4.16	Hydr. Depth (ft)		3.34	
Conv. Total (cfs)	53191.8	Conv. (cfs)		53191.8	
Length Wtd. (ft)	74.33	Wetted Per. (ft)		74.54	
Min Ch El (ft)	1715.00	Shear (lb/sq ft)		0.79	
Alpha	1.00	Stream Power (lb/ft s)		10.64	
Frctn Loss (ft)	0.29	Cum Volume (acre-ft)		33.28	
C & E Loss (ft)	0.00	Cum SA (acres)		9.91	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 153.333*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1721.35	1011.05	1715.83	1012.38	1715.6	1044.79	1714.72	1070.94	1715.6
1072.38	1716.08	1082.92	1721.35						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1082.92 74.33 74.33 74.33 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1721.17	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.58	Wt. n-Val.		0.015	
W.S. Elev (ft)	1718.59	Reach Len. (ft)	74.33	74.33	74.33
Crit W.S. (ft)	1719.18	Flow Area (sq ft)		222.49	
E.G. Slope (ft/ft)	*0.003854	Area (sq ft)		222.49	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	71.87	Top Width (ft)		71.87	
Vel Total (ft/s)	12.90	Avg. Vel. (ft/s)		12.90	
Max Chl Dpth (ft)	3.87	Hydr. Depth (ft)		3.10	
Conv. Total (cfs)	46230.6	Conv. (cfs)		46230.6	
Length Wtd. (ft)	74.33	Wetted Per. (ft)		73.24	
Min Ch El (ft)	1714.72	Shear (lb/sq ft)		0.73	
Alpha	1.00	Stream Power (lb/ft s)		9.43	
Frctn Loss (ft)	0.29	Cum Volume (acre-ft)		34.99	
C & E Loss (ft)	0.00	Cum SA (acres)		9.84	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1721.73	Element	Left OB	Channel	Right OB

* Vel Head (ft)	* 2.85	* Wt. n-Val.	*	* 0.015	*			
* W.S. Elev (ft)	* 1718.88	* Reach Len. (ft)	* 74.33	* 74.33	*	74.33	*	
* Crit W.S. (ft)	* 1719.55	* Flow Area (sq ft)	*	* 243.79	*			
* E.G. Slope (ft/ft)	*0.003847	* Area (sq ft)	*	* 243.79	*			
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*			
* Top Width (ft)	* 73.05	* Top Width (ft)	*	* 73.05	*			
* Vel Total (ft/s)	* 13.54	* Avg. Vel. (ft/s)	*	* 13.54	*			
* Max Chl Dpth (ft)	* 4.16	* Hydr. Depth (ft)	*	* 3.34	*			
* Conv. Total (cfs)	* 53204.7	* Conv. (cfs)	*	* 53204.7	*			
* Length Wtd. (ft)	* 74.33	* Wetted Per. (ft)	*	* 74.55	*			
* Min Ch El (ft)	* 1714.72	* Shear (lb/sq ft)	*	* 0.79	*			
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.63	*			
* Frctn Loss (ft)	* 0.29	* Cum Volume (acre-ft)	*	* 32.86	*			
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 9.79	*			

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 151.666*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1721.07	1011.25	1715.44	1012.61	1715.31	1045.63	1714.44	1071.2	1715.33
1072.61	1715.92	1082.92	1721.07						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	74.33	74.33	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1720.89	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.58	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1718.31	* Reach Len. (ft)	* 74.33	* 74.33	* 74.33 *
* Crit W.S. (ft)	* 1718.90	* Flow Area (sq ft)	*	* 222.64	*
* E.G. Slope (ft/ft)	*0.003847	* Area (sq ft)	*	* 222.64	*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	*
* Top Width (ft)	* 71.88	* Top Width (ft)	*	* 71.88	*
* Vel Total (ft/s)	* 12.89	* Avg. Vel. (ft/s)	*	* 12.89	*
* Max Chl Dpth (ft)	* 3.87	* Hydr. Depth (ft)	*	* 3.10	*
* Conv. Total (cfs)	* 46271.3	* Conv. (cfs)	*	* 46271.3	*
* Length Wtd. (ft)	* 74.33	* Wetted Per. (ft)	*	* 73.27	*
* Min Ch El (ft)	* 1714.44	* Shear (lb/sq ft)	*	* 0.73	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 9.41	*
* Frctn Loss (ft)	* 0.29	* Cum Volume (acre-ft)	*	* 34.61	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 9.72	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1721.44	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.84	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1718.60	* Reach Len. (ft)	* 74.33	* 74.33	* 74.33 *
* Crit W.S. (ft)	* 1719.27	* Flow Area (sq ft)	*	* 243.94	*
* E.G. Slope (ft/ft)	*0.003841	* Area (sq ft)	*	* 243.94	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*
* Top Width (ft)	* 73.05	* Top Width (ft)	*	* 73.05	*
* Vel Total (ft/s)	* 13.53	* Avg. Vel. (ft/s)	*	* 13.53	*
* Max Chl Dpth (ft)	* 4.16	* Hydr. Depth (ft)	*	* 3.34	*
* Conv. Total (cfs)	* 53247.1	* Conv. (cfs)	*	* 53247.1	*
* Length Wtd. (ft)	* 74.33	* Wetted Per. (ft)	*	* 74.58	*
* Min Ch El (ft)	* 1714.44	* Shear (lb/sq ft)	*	* 0.78	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.61	*
* Frctn Loss (ft)	* 0.29	* Cum Volume (acre-ft)	*	* 32.45	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 9.66	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 150

INPUT
Description: PLAN STA 130+97
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1720.79	1011.46	1715.06	1046.46	1714.16	1071.46	1715.06	1082.92	1720.79

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	196.55	196.55	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1720.61	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.58	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1718.03	* Reach Len. (ft)	* 196.55	* 196.55	* 196.55 *
* Crit W.S. (ft)	* 1718.62	* Flow Area (sq ft)	*	* 222.76	*
* E.G. Slope (ft/ft)	*0.003843	* Area (sq ft)	*	* 222.76	*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	*
* Top Width (ft)	* 71.88	* Top Width (ft)	*	* 71.88	*

* Vel Total (ft/s)	* 12.88	* Avg. Vel. (ft/s)	*	*	12.88	*	*
* Max Chl Dpth (ft)	* 3.87	* Hydr. Depth (ft)	*	*	3.10	*	*
* Conv. Total (cfs)	* 46296.5	* Conv. (cfs)	*	*	46296.5	*	*
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	*	73.31	*	*
* Min Ch El (ft)	* 1714.16	* Shear (lb/sq ft)	*	*	0.73	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	*	9.39	*	*
* Frctn Loss (ft)	* 0.29	* Cum Volume (acre-ft)	*	*	34.23	*	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	*	9.60	*	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1721.16	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.84	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1718.32	* Reach Len. (ft)	* 196.55	* 196.55	* 196.55 *
* Crit W.S. (ft)	* 1718.99	* Flow Area (sq ft)	*	* 244.06	* *
* E.G. Slope (ft/ft)	*0.003837	* Area (sq ft)	*	* 244.06	* *
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	* *
* Top Width (ft)	* 73.05	* Top Width (ft)	*	* 73.05	* *
* Vel Total (ft/s)	* 13.52	* Avg. Vel. (ft/s)	*	* 13.52	* *
* Max Chl Dpth (ft)	* 4.16	* Hydr. Depth (ft)	*	* 3.34	* *
* Conv. Total (cfs)	* 53272.3	* Conv. (cfs)	*	* 53272.3	* *
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	* 74.62	* *
* Min Ch El (ft)	* 1714.16	* Shear (lb/sq ft)	*	* 0.78	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.59	* *
* Frctn Loss (ft)	* 0.29	* Cum Volume (acre-ft)	*	* 32.03	* *
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 9.54	* *

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 149.285*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1720.05	1011.37	1714.36	1012.74	1714.28	1046.1	1713.42	1071.35	1714.31
1072.74	1714.96	1082.92	1720.05						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	196.55	196.55	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1719.86	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.56	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1717.30	* Reach Len. (ft)	* 196.55	* 196.55	* 196.55 *
* Crit W.S. (ft)	* 1717.87	* Flow Area (sq ft)	*	* 223.51	* *
* E.G. Slope (ft/ft)	*0.003802	* Area (sq ft)	*	* 223.51	* *
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	* *
* Top Width (ft)	* 71.91	* Top Width (ft)	*	* 71.91	* *
* Vel Total (ft/s)	* 12.84	* Avg. Vel. (ft/s)	*	* 12.84	* *
* Max Chl Dpth (ft)	* 3.88	* Hydr. Depth (ft)	*	* 3.11	* *
* Conv. Total (cfs)	* 46546.1	* Conv. (cfs)	*	* 46546.1	* *
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	* 73.33	* *
* Min Ch El (ft)	* 1713.42	* Shear (lb/sq ft)	*	* 0.72	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 9.29	* *
* Frctn Loss (ft)	* 0.75	* Cum Volume (acre-ft)	*	* 33.22	* *
* C & E Loss (ft)	* 0.01	* Cum SA (acres)	*	* 9.27	* *

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1720.41	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.82	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1717.59	* Reach Len. (ft)	* 196.55	* 196.55	* 196.55 *
* Crit W.S. (ft)	* 1718.25	* Flow Area (sq ft)	*	* 244.75	* *
* E.G. Slope (ft/ft)	*0.003803	* Area (sq ft)	*	* 244.75	* *
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	* *
* Top Width (ft)	* 73.08	* Top Width (ft)	*	* 73.08	* *
* Vel Total (ft/s)	* 13.48	* Avg. Vel. (ft/s)	*	* 13.48	* *
* Max Chl Dpth (ft)	* 4.17	* Hydr. Depth (ft)	*	* 3.35	* *
* Conv. Total (cfs)	* 53510.8	* Conv. (cfs)	*	* 53510.8	* *
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	* 74.64	* *
* Min Ch El (ft)	* 1713.42	* Shear (lb/sq ft)	*	* 0.78	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.50	* *
* Frctn Loss (ft)	* 0.75	* Cum Volume (acre-ft)	*	* 30.93	* *
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 9.21	* *

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 148.571*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1719.3	1011.28	1713.66	1012.64	1713.54	1045.75	1712.67	1071.24	1713.57
1072.64	1714.17	1082.92	1719.3						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val

```
    1000    .015    1000    .015 1082.92    .015

Bank Sta: Left   Right    Lengths: Left Channel   Right     Coeff Contr.    Expan.
          1000 1082.92           196.55  196.55  196.55            .1        .3

CROSS SECTION OUTPUT  Profile #Post-Project
**********************************************************************************************
* E.G. Elev (ft)         * 1719.11  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)          *    2.56  * Wt. n-Val.           *          *    0.015  *          *
* W.S. Elev (ft)         * 1716.56  * Reach Len. (ft)      *  196.55  *  196.55  *  196.55  *
* Crit W.S. (ft)         * 1717.13  * Flow Area (sq ft)    *          *  223.68  *          *
* E.G. Slope (ft/ft)     *0.003792  * Area (sq ft)         *          *  223.68  *          *
* Q Total (cfs)          * 2870.00  * Flow (cfs)           *          * 2870.00  *          *
* Top Width (ft)         *   71.93  * Top Width (ft)       *          *   71.93  *          *
* Vel Total (ft/s)       *   12.83  * Avg. Vel. (ft/s)     *          *   12.83  *          *
* Max Chl Dpth (ft)      *    3.89  * Hydr. Depth (ft)     *          *    3.11  *          *
* Conv. Total (cfs)      * 46604.4  * Conv. (cfs)          *          * 46604.4  *          *
* Length Wtd. (ft)       *  196.55  * Wetted Per. (ft)     *          *   73.33  *          *
* Min Ch El (ft)         * 1712.67  * Shear (lb/sq ft)     *          *    0.72  *          *
* Alpha                  *    1.00  * Stream Power (lb/ft s) *        *    9.27  *          *
* Frctn Loss (ft)        *    0.75  * Cum Volume (acre-ft)  *          *   32.21  *          *
* C & E Loss (ft)        *    0.00  * Cum SA (acres)        *          *    8.95  *          *
**********************************************************************************************

CROSS SECTION OUTPUT  Profile #PF 2
**********************************************************************************************
* E.G. Elev (ft)         * 1719.67  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)          *    2.82  * Wt. n-Val.           *          *    0.015  *          *
* W.S. Elev (ft)         * 1716.85  * Reach Len. (ft)      *  196.55  *  196.55  *  196.55  *
* Crit W.S. (ft)         * 1717.52  * Flow Area (sq ft)    *          *  244.93  *          *
* E.G. Slope (ft/ft)     *0.003794  * Area (sq ft)         *          *  244.93  *          *
* Q Total (cfs)          * 3300.00  * Flow (cfs)           *          * 3300.00  *          *
* Top Width (ft)         *   73.10  * Top Width (ft)       *          *   73.10  *          *
* Vel Total (ft/s)       *   13.47  * Avg. Vel. (ft/s)     *          *   13.47  *          *
* Max Chl Dpth (ft)      *    4.18  * Hydr. Depth (ft)     *          *    3.35  *          *
* Conv. Total (cfs)      * 53576.3  * Conv. (cfs)          *          * 53576.3  *          *
* Length Wtd. (ft)       *  196.55  * Wetted Per. (ft)     *          *   74.64  *          *
* Min Ch El (ft)         * 1712.67  * Shear (lb/sq ft)     *          *    0.78  *          *
* Alpha                  *    1.00  * Stream Power (lb/ft s) *        *   10.47  *          *
* Frctn Loss (ft)        *    0.75  * Cum Volume (acre-ft)  *          *   29.82  *          *
* C & E Loss (ft)        *    0.00  * Cum SA (acres)        *          *    8.88  *          *
**********************************************************************************************

CROSS SECTION


RIVER: Range Wash
REACH: Sloan Channel      RS: 147.857*

INPUT
Description:
Station Elevation Data    num=       7
     Sta    Elev     Sta    Elev     Sta    Elev     Sta    Elev     Sta    Elev
**********************************************************************************
    1000 1718.56  1011.2 1712.96 1012.55  1712.8 1045.39 1711.93 1071.12 1712.82
 1072.55 1713.37 1082.92 1718.56

Manning's n Values        num=       3
     Sta   n Val     Sta   n Val     Sta   n Val
***********************************************
    1000    .015    1000    .015 1082.92    .015

Bank Sta: Left   Right    Lengths: Left Channel   Right     Coeff Contr.    Expan.
          1000 1082.92           196.55  196.55  196.55            .1        .3

CROSS SECTION OUTPUT  Profile #Post-Project
**********************************************************************************************
* E.G. Elev (ft)         * 1718.37  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)          *    2.55  * Wt. n-Val.           *          *    0.015  *          *
* W.S. Elev (ft)         * 1715.82  * Reach Len. (ft)      *  196.55  *  196.55  *  196.55  *
* Crit W.S. (ft)         * 1716.39  * Flow Area (sq ft)    *          *  223.82  *          *
* E.G. Slope (ft/ft)     *0.003785  * Area (sq ft)         *          *  223.82  *          *
* Q Total (cfs)          * 2870.00  * Flow (cfs)           *          * 2870.00  *          *
* Top Width (ft)         *   71.95  * Top Width (ft)       *          *   71.95  *          *
* Vel Total (ft/s)       *   12.82  * Avg. Vel. (ft/s)     *          *   12.82  *          *
* Max Chl Dpth (ft)      *    3.89  * Hydr. Depth (ft)     *          *    3.11  *          *
* Conv. Total (cfs)      * 46650.7  * Conv. (cfs)          *          * 46650.7  *          *
* Length Wtd. (ft)       *  196.55  * Wetted Per. (ft)     *          *   73.34  *          *
* Min Ch El (ft)         * 1711.93  * Shear (lb/sq ft)     *          *    0.72  *          *
* Alpha                  *    1.00  * Stream Power (lb/ft s) *        *    9.25  *          *
* Frctn Loss (ft)        *    0.74  * Cum Volume (acre-ft)  *          *   31.20  *          *
* C & E Loss (ft)        *    0.00  * Cum SA (acres)        *          *    8.62  *          *
**********************************************************************************************

CROSS SECTION OUTPUT  Profile #PF 2
**********************************************************************************************
* E.G. Elev (ft)         * 1718.92  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)          *    2.82  * Wt. n-Val.           *          *    0.015  *          *
* W.S. Elev (ft)         * 1716.11  * Reach Len. (ft)      *  196.55  *  196.55  *  196.55  *
* Crit W.S. (ft)         * 1716.78  * Flow Area (sq ft)    *          *  245.07  *          *
* E.G. Slope (ft/ft)     *0.003787  * Area (sq ft)         *          *  245.07  *          *
* Q Total (cfs)          * 3300.00  * Flow (cfs)           *          * 3300.00  *          *
* Top Width (ft)         *   73.12  * Top Width (ft)       *          *   73.12  *          *
* Vel Total (ft/s)       *   13.47  * Avg. Vel. (ft/s)     *          *   13.47  *          *
* Max Chl Dpth (ft)      *    4.18  * Hydr. Depth (ft)     *          *    3.35  *          *
* Conv. Total (cfs)      * 53627.1  * Conv. (cfs)          *          * 53627.1  *          *
* Length Wtd. (ft)       *  196.55  * Wetted Per. (ft)     *          *   74.65  *          *
* Min Ch El (ft)         * 1711.93  * Shear (lb/sq ft)     *          *    0.78  *          *
* Alpha                  *    1.00  * Stream Power (lb/ft s) *        *   10.45  *          *
* Frctn Loss (ft)        *    0.74  * Cum Volume (acre-ft)  *          *   28.72  *          *
* C & E Loss (ft)        *    0.00  * Cum SA (acres)        *          *    8.55  *          *
**********************************************************************************************

CROSS SECTION
```

RIVER: Range Wash
REACH: Sloan Channel RS: 147.142*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1717.82	1011.11	1712.26	1012.45	1712.06	1045.03	1711.19	1071.01	1712.08
1072.45	1712.58	1082.92	1717.82						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	196.55	196.55 196.55	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1717.63	Element			
Vel Head (ft)	2.55	Wt. n-Val.		0.015	
W.S. Elev (ft)	1715.08	Reach Len. (ft)	196.55	196.55	196.55
Crit W.S. (ft)	1715.65	Flow Area (sq ft)		223.80	
E.G. Slope (ft/ft)	*0.003786	Area (sq ft)		223.80	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	71.95	Top Width (ft)		71.95	
Vel Total (ft/s)	12.82	Avg. Vel. (ft/s)		12.82	
Max Chl Dpth (ft)	3.89	Hydr. Depth (ft)		3.11	
Conv. Total (cfs)	46645.1	Conv. (cfs)		46645.1	
Length Wtd. (ft)	196.55	Wetted Per. (ft)		73.33	
Min Ch El (ft)	1711.19	Shear (lb/sq ft)		0.72	
Alpha	1.00	Stream Power (lb/ft s)		9.25	
Frctn Loss (ft)	0.74	Cum Volume (acre-ft)		30.19	
C & E Loss (ft)	0.00	Cum SA (acres)		8.30	

CROSS SECTION OUTPUT Profile #PF 2

			Left OB	Channel	Right OB
E.G. Elev (ft)	1718.18	Element			
Vel Head (ft)	2.82	Wt. n-Val.		0.015	
W.S. Elev (ft)	1715.37	Reach Len. (ft)	196.55	196.55	196.55
Crit W.S. (ft)	1716.04	Flow Area (sq ft)		245.05	
E.G. Slope (ft/ft)	*0.003787	Area (sq ft)		245.05	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	73.12	Top Width (ft)		73.12	
Vel Total (ft/s)	13.47	Avg. Vel. (ft/s)		13.47	
Max Chl Dpth (ft)	4.18	Hydr. Depth (ft)		3.35	
Conv. Total (cfs)	53622.1	Conv. (cfs)		53622.1	
Length Wtd. (ft)	196.55	Wetted Per. (ft)		74.64	
Min Ch El (ft)	1711.19	Shear (lb/sq ft)		0.78	
Alpha	1.00	Stream Power (lb/ft s)		10.45	
Frctn Loss (ft)	0.74	Cum Volume (acre-ft)		27.61	
C & E Loss (ft)	0.00	Cum SA (acres)		8.22	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 146.428*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1717.08	1011.02	1711.57	1012.35	1711.32	1044.67	1710.45	1070.9	1711.33
1072.35	1711.79	1082.92	1717.08						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	196.55	196.55 196.55	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1716.89	Element			
Vel Head (ft)	2.55	Wt. n-Val.		0.015	
W.S. Elev (ft)	1714.34	Reach Len. (ft)	196.55	196.55	196.55
Crit W.S. (ft)	1714.91	Flow Area (sq ft)		223.89	
E.G. Slope (ft/ft)	*0.003780	Area (sq ft)		223.89	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	71.95	Top Width (ft)		71.95	
Vel Total (ft/s)	12.82	Avg. Vel. (ft/s)		12.82	
Max Chl Dpth (ft)	3.89	Hydr. Depth (ft)		3.11	
Conv. Total (cfs)	46679.1	Conv. (cfs)		46679.1	
Length Wtd. (ft)	196.55	Wetted Per. (ft)		73.32	
Min Ch El (ft)	1710.45	Shear (lb/sq ft)		0.72	
Alpha	1.00	Stream Power (lb/ft s)		9.24	
Frctn Loss (ft)	0.74	Cum Volume (acre-ft)		29.18	
C & E Loss (ft)	0.00	Cum SA (acres)		7.97	

CROSS SECTION OUTPUT Profile #PF 2

			Left OB	Channel	Right OB
E.G. Elev (ft)	1717.44	Element			
Vel Head (ft)	2.81	Wt. n-Val.		0.015	
W.S. Elev (ft)	1714.63	Reach Len. (ft)	196.55	196.55	196.55
Crit W.S. (ft)	1715.30	Flow Area (sq ft)		245.14	
E.G. Slope (ft/ft)	*0.003782	Area (sq ft)		245.14	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	

* Top Width (ft)	* 73.12	* Top Width (ft)	*	*	73.12	*	*
* Vel Total (ft/s)	* 13.46	* Avg. Vel. (ft/s)	*	*	13.46	*	*
* Max Chl Dpth (ft)	* 4.18	* Hydr. Depth (ft)	*	*	3.35	*	*
* Conv. Total (cfs)	* 53657.4	* Conv. (cfs)	*	*	53657.4	*	*
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	*	74.63	*	*
* Min Ch El (ft)	* 1710.45	* Shear (lb/sq ft)	*	*	0.78	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	*	10.44	*	*
* Frctn Loss (ft)	* 0.74	* Cum Volume (acre-ft)	*	*	26.50	*	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	*	7.89	*	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 145.714*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1716.33	1010.93	1710.87	1012.25	1710.58	1044.32	1709.7	1070.79	1710.58
1072.25	1711	1082.92	1716.33						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	196.55	196.55	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1716.14	* Element	* Left OB *	Channel *	Right OB *
* Vel Head (ft)	* 2.55	* Wt. n-Val.	*	* 0.015 *	*
* W.S. Elev (ft)	* 1713.59	* Reach Len. (ft)	* 196.55 *	196.55 *	196.55 *
* Crit W.S. (ft)	* 1714.16	* Flow Area (sq ft)	*	* 224.09 *	*
* E.G. Slope (ft/ft)	*0.003769	* Area (sq ft)	*	* 224.09 *	*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00 *	*
* Top Width (ft)	* 71.96	* Top Width (ft)	*	* 71.96 *	*
* Vel Total (ft/s)	* 12.81	* Avg. Vel. (ft/s)	*	* 12.81 *	*
* Max Chl Dpth (ft)	* 3.89	* Hydr. Depth (ft)	*	* 3.11 *	*
* Conv. Total (cfs)	* 46748.8	* Conv. (cfs)	*	* 46748.8 *	*
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	* 73.33 *	*
* Min Ch El (ft)	* 1709.70	* Shear (lb/sq ft)	*	* 0.72 *	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 9.21 *	*
* Frctn Loss (ft)	* 0.74	* Cum Volume (acre-ft)	*	* 28.17 *	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 7.65 *	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1716.69	* Element	* Left OB *	Channel *	Right OB *
* Vel Head (ft)	* 2.81	* Wt. n-Val.	*	* 0.015 *	*
* W.S. Elev (ft)	* 1713.89	* Reach Len. (ft)	* 196.55 *	196.55 *	196.55 *
* Crit W.S. (ft)	* 1714.55	* Flow Area (sq ft)	*	* 245.32 *	*
* E.G. Slope (ft/ft)	*0.003773	* Area (sq ft)	*	* 245.32 *	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00 *	*
* Top Width (ft)	* 73.13	* Top Width (ft)	*	* 73.13 *	*
* Vel Total (ft/s)	* 13.45	* Avg. Vel. (ft/s)	*	* 13.45 *	*
* Max Chl Dpth (ft)	* 4.18	* Hydr. Depth (ft)	*	* 3.35 *	*
* Conv. Total (cfs)	* 53722.0	* Conv. (cfs)	*	* 53722.0 *	*
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	* 74.64 *	*
* Min Ch El (ft)	* 1709.70	* Shear (lb/sq ft)	*	* 0.77 *	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.42 *	*
* Frctn Loss (ft)	* 0.74	* Cum Volume (acre-ft)	*	* 25.40 *	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 7.56 *	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 145.*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1715.59	1010.84	1710.17	1012.15	1709.84	1043.96	1708.96	1070.67	1709.84
1072.15	1710.21	1082.92	1715.59						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	196.55	196.55	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1715.40	* Element	* Left OB *	Channel *	Right OB *
* Vel Head (ft)	* 2.55	* Wt. n-Val.	*	* 0.015 *	*
* W.S. Elev (ft)	* 1712.85	* Reach Len. (ft)	* 196.55 *	196.55 *	196.55 *
* Crit W.S. (ft)	* 1713.42	* Flow Area (sq ft)	*	* 224.10 *	*
* E.G. Slope (ft/ft)	*0.003769	* Area (sq ft)	*	* 224.10 *	*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00 *	*
* Top Width (ft)	* 71.96	* Top Width (ft)	*	* 71.96 *	*
* Vel Total (ft/s)	* 12.81	* Avg. Vel. (ft/s)	*	* 12.81 *	*
* Max Chl Dpth (ft)	* 3.89	* Hydr. Depth (ft)	*	* 3.11 *	*
* Conv. Total (cfs)	* 46750.1	* Conv. (cfs)	*	* 46750.1 *	*
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	* 73.33 *	*

* Min Ch El (ft)	* 1708.96	* Shear (lb/sq ft)	*	* 0.72	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 9.21	*
* Frctn Loss (ft)	* 0.74	* Cum Volume (acre-ft)	*	* 27.16	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 7.32	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1715.95	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.81	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1713.15	* Reach Len. (ft)	* 196.55	* 196.55	* 196.55 *
* Crit W.S. (ft)	* 1713.81	* Flow Area (sq ft)	*	* 245.33	*
* E.G. Slope (ft/ft)	*0.003773	* Area (sq ft)	*	* 245.33	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*
* Top Width (ft)	* 73.13	* Top Width (ft)	*	* 73.13	*
* Vel Total (ft/s)	* 13.45	* Avg. Vel. (ft/s)	*	* 13.45	*
* Max Chl Dpth (ft)	* 4.18	* Hydr. Depth (ft)	*	* 3.35	*
* Conv. Total (cfs)	* 53723.9	* Conv. (cfs)	*	* 53723.9	*
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	* 74.64	*
* Min Ch El (ft)	* 1708.96	* Shear (lb/sq ft)	*	* 0.77	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.41	*
* Frctn Loss (ft)	* 0.74	* Cum Volume (acre-ft)	*	* 24.29	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 7.23	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 144.285*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1714.85	1010.76	1709.47	1012.05	1709.1	1043.6	1708.22	1070.56	1709.09
1072.05	1709.41	1082.92	1714.85						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	196.55	196.55	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1714.65	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.54	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1712.11	* Reach Len. (ft)	* 196.55	* 196.55	* 196.55 *
* Crit W.S. (ft)	* 1712.68	* Flow Area (sq ft)	*	* 224.29	*
* E.G. Slope (ft/ft)	*0.003759	* Area (sq ft)	*	* 224.29	*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	*
* Top Width (ft)	* 71.97	* Top Width (ft)	*	* 71.97	*
* Vel Total (ft/s)	* 12.80	* Avg. Vel. (ft/s)	*	* 12.80	*
* Max Chl Dpth (ft)	* 3.89	* Hydr. Depth (ft)	*	* 3.12	*
* Conv. Total (cfs)	* 46810.7	* Conv. (cfs)	*	* 46810.7	*
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	* 73.35	*
* Min Ch El (ft)	* 1708.22	* Shear (lb/sq ft)	*	* 0.72	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 9.18	*
* Frctn Loss (ft)	* 0.74	* Cum Volume (acre-ft)	*	* 26.15	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 7.00	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1715.21	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.81	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1712.41	* Reach Len. (ft)	* 196.55	* 196.55	* 196.55 *
* Crit W.S. (ft)	* 1713.07	* Flow Area (sq ft)	*	* 245.52	*
* E.G. Slope (ft/ft)	*0.003764	* Area (sq ft)	*	* 245.52	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*
* Top Width (ft)	* 73.14	* Top Width (ft)	*	* 73.14	*
* Vel Total (ft/s)	* 13.44	* Avg. Vel. (ft/s)	*	* 13.44	*
* Max Chl Dpth (ft)	* 4.18	* Hydr. Depth (ft)	*	* 3.36	*
* Conv. Total (cfs)	* 53788.5	* Conv. (cfs)	*	* 53788.5	*
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	* 74.66	*
* Min Ch El (ft)	* 1708.22	* Shear (lb/sq ft)	*	* 0.77	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.39	*
* Frctn Loss (ft)	* 0.74	* Cum Volume (acre-ft)	*	* 23.18	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 6.90	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 143.571*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1714.1	1010.67	1708.77	1011.95	1708.36	1043.25	1707.47	1070.45	1708.34
1071.95	1708.62	1082.92	1714.1						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	196.55	196.55	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1713.91	Element		0.015	
Vel Head (ft)	2.56	Wt. n-Val.		0.015	
W.S. Elev (ft)	1711.36	Reach Len. (ft)	196.55	196.55	196.55
Crit W.S. (ft)	1711.93	Flow Area (sq ft)		223.66	
E.G. Slope (ft/ft)	*0.003792	Area (sq ft)		223.66	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	71.93	Top Width (ft)		71.93	
Vel Total (ft/s)	12.83	Avg. Vel. (ft/s)		12.83	
Max Chl Dpth (ft)	3.89	Hydr. Depth (ft)		3.11	
Conv. Total (cfs)	46607.2	Conv. (cfs)		46607.2	
Length Wtd. (ft)	196.55	Wetted Per. (ft)		73.31	
Min Ch El (ft)	1707.47	Shear (lb/sq ft)		0.72	
Alpha	1.00	Stream Power (lb/ft s)		9.27	
Frctn Loss (ft)	0.74	Cum Volume (acre-ft)		25.14	
C & E Loss (ft)	0.00	Cum SA (acres)		6.67	

CROSS SECTION OUTPUT Profile #PF 2

			Left OB	Channel	Right OB
E.G. Elev (ft)	1714.47	Element		0.015	
Vel Head (ft)	2.82	Wt. n-Val.		0.015	
W.S. Elev (ft)	1711.65	Reach Len. (ft)	196.55	196.55	196.55
Crit W.S. (ft)	1712.32	Flow Area (sq ft)		244.99	
E.G. Slope (ft/ft)	*0.003789	Area (sq ft)		244.99	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	73.11	Top Width (ft)		73.11	
Vel Total (ft/s)	13.47	Avg. Vel. (ft/s)		13.47	
Max Chl Dpth (ft)	4.18	Hydr. Depth (ft)		3.35	
Conv. Total (cfs)	53607.4	Conv. (cfs)		53607.4	
Length Wtd. (ft)	196.55	Wetted Per. (ft)		74.62	
Min Ch El (ft)	1707.47	Shear (lb/sq ft)		0.78	
Alpha	1.00	Stream Power (lb/ft s)		10.46	
Frctn Loss (ft)	0.74	Cum Volume (acre-ft)		22.08	
C & E Loss (ft)	0.00	Cum SA (acres)		6.57	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 142.857*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1713.36	1010.58	1708.07	1011.85	1707.62	1042.89	1706.73	1070.34	1707.6
1071.85	1707.83	1082.92	1713.36						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	196.55	196.55	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1713.17	Element		0.015	
Vel Head (ft)	2.56	Wt. n-Val.		0.015	
W.S. Elev (ft)	1710.62	Reach Len. (ft)	196.55	196.55	196.55
Crit W.S. (ft)	1711.19	Flow Area (sq ft)		223.71	
E.G. Slope (ft/ft)	*0.003790	Area (sq ft)		223.71	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	71.94	Top Width (ft)		71.94	
Vel Total (ft/s)	12.83	Avg. Vel. (ft/s)		12.83	
Max Chl Dpth (ft)	3.89	Hydr. Depth (ft)		3.11	
Conv. Total (cfs)	46617.9	Conv. (cfs)		46617.9	
Length Wtd. (ft)	196.55	Wetted Per. (ft)		73.32	
Min Ch El (ft)	1706.73	Shear (lb/sq ft)		0.72	
Alpha	1.00	Stream Power (lb/ft s)		9.26	
Frctn Loss (ft)	0.75	Cum Volume (acre-ft)		24.13	
C & E Loss (ft)	0.00	Cum SA (acres)		6.35	

CROSS SECTION OUTPUT Profile #PF 2

			Left OB	Channel	Right OB
E.G. Elev (ft)	1713.73	Element		0.015	
Vel Head (ft)	2.82	Wt. n-Val.		0.015	
W.S. Elev (ft)	1710.91	Reach Len. (ft)	196.55	196.55	196.55
Crit W.S. (ft)	1711.58	Flow Area (sq ft)		245.03	
E.G. Slope (ft/ft)	*0.003788	Area (sq ft)		245.03	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	73.12	Top Width (ft)		73.12	
Vel Total (ft/s)	13.47	Avg. Vel. (ft/s)		13.47	
Max Chl Dpth (ft)	4.18	Hydr. Depth (ft)		3.35	
Conv. Total (cfs)	53619.0	Conv. (cfs)		53619.0	
Length Wtd. (ft)	196.55	Wetted Per. (ft)		74.64	
Min Ch El (ft)	1706.73	Shear (lb/sq ft)		0.78	
Alpha	1.00	Stream Power (lb/ft s)		10.46	
Frctn Loss (ft)	0.74	Cum Volume (acre-ft)		20.97	
C & E Loss (ft)	0.00	Cum SA (acres)		6.24	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 142.142*

INPUT

Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1712.62	1010.49	1707.37	1011.76	1706.88	1042.53	1705.99	1070.23	1706.85
1071.76	1707.04	1082.92	1712.62						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1082.92 196.55 196.55 196.55 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1712.43	Element			
Vel Head (ft)	2.55	Wt. n-Val.		0.015	
W.S. Elev (ft)	1709.88	Reach Len. (ft)	196.55	196.55	196.55
Crit W.S. (ft)	1710.45	Flow Area (sq ft)		223.92	
E.G. Slope (ft/ft)	*0.003779	Area (sq ft)		223.92	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	71.95	Top Width (ft)		71.95	
Vel Total (ft/s)	12.82	Avg. Vel. (ft/s)		12.82	
Max Chl Dpth (ft)	3.89	Hydr. Depth (ft)		3.11	
Conv. Total (cfs)	46684.0	Conv. (cfs)		46684.0	
Length Wtd. (ft)	196.55	Wetted Per. (ft)		73.34	
Min Ch El (ft)	1705.99	Shear (lb/sq ft)		0.72	
Alpha	1.00	Stream Power (lb/ft s)		9.23	
Frctn Loss (ft)	0.74	Cum Volume (acre-ft)		23.12	
C & E Loss (ft)	0.00	Cum SA (acres)		6.03	

CROSS SECTION OUTPUT Profile #PF 2

			Left OB	Channel	Right OB
E.G. Elev (ft)	1712.98	Element			
Vel Head (ft)	2.81	Wt. n-Val.		0.015	
W.S. Elev (ft)	1710.17	Reach Len. (ft)	196.55	196.55	196.55
Crit W.S. (ft)	1710.84	Flow Area (sq ft)		245.25	
E.G. Slope (ft/ft)	*0.003778	Area (sq ft)		245.25	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	73.13	Top Width (ft)		73.13	
Vel Total (ft/s)	13.46	Avg. Vel. (ft/s)		13.46	
Max Chl Dpth (ft)	4.18	Hydr. Depth (ft)		3.35	
Conv. Total (cfs)	53689.2	Conv. (cfs)		53689.2	
Length Wtd. (ft)	196.55	Wetted Per. (ft)		74.66	
Min Ch El (ft)	1705.99	Shear (lb/sq ft)		0.77	
Alpha	1.00	Stream Power (lb/ft s)		10.43	
Frctn Loss (ft)	0.74	Cum Volume (acre-ft)		19.87	
C & E Loss (ft)	0.00	Cum SA (acres)		5.91	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 141.428*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1711.88	1010.4	1706.67	1011.66	1706.14	1042.17	1705.25	1070.11	1706.11
1071.66	1706.24	1082.92	1711.88						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1082.92 196.55 196.55 196.55 .1 .3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1711.69	Element			
Vel Head (ft)	2.55	Wt. n-Val.		0.015	
W.S. Elev (ft)	1709.14	Reach Len. (ft)	196.55	196.55	196.55
Crit W.S. (ft)	1709.71	Flow Area (sq ft)		224.03	
E.G. Slope (ft/ft)	*0.003775	Area (sq ft)		224.03	
Q Total (cfs)	2870.00	Flow (cfs)		2870.00	
Top Width (ft)	71.97	Top Width (ft)		71.97	
Vel Total (ft/s)	12.81	Avg. Vel. (ft/s)		12.81	
Max Chl Dpth (ft)	3.89	Hydr. Depth (ft)		3.11	
Conv. Total (cfs)	46709.8	Conv. (cfs)		46709.8	
Length Wtd. (ft)	196.55	Wetted Per. (ft)		73.37	
Min Ch El (ft)	1705.25	Shear (lb/sq ft)		0.72	
Alpha	1.00	Stream Power (lb/ft s)		9.22	
Frctn Loss (ft)	0.74	Cum Volume (acre-ft)		22.11	
C & E Loss (ft)	0.00	Cum SA (acres)		5.70	

CROSS SECTION OUTPUT Profile #PF 2

			Left OB	Channel	Right OB
E.G. Elev (ft)	1712.24	Element			
Vel Head (ft)	2.81	Wt. n-Val.		0.015	
W.S. Elev (ft)	1709.43	Reach Len. (ft)	196.55	196.55	196.55
Crit W.S. (ft)	1710.10	Flow Area (sq ft)		245.37	
E.G. Slope (ft/ft)	*0.003774	Area (sq ft)		245.37	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	73.14	Top Width (ft)		73.14	
Vel Total (ft/s)	13.45	Avg. Vel. (ft/s)		13.45	
Max Chl Dpth (ft)	4.18	Hydr. Depth (ft)		3.35	
Conv. Total (cfs)	53717.5	Conv. (cfs)		53717.5	

* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	*	74.68	*	*
* Min Ch El (ft)	* 1705.25	* Shear (lb/sq ft)	*	*	0.77	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	*	10.41	*	*
* Frctn Loss (ft)	* 0.74	* Cum Volume (acre-ft)	*	*	18.76	*	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	*	5.58	*	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 140.714*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1711.13	1010.31	1705.98	1011.56	1705.4	1041.82	1704.5	1070	1705.36
1071.56	1705.45	1082.92	1711.13						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	196.55	196.55	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1710.94	* Element	* Left OB	* Channel	* Right OB	*
* Vel Head (ft)	* 2.54	* Wt. n-Val.	*	* 0.015	*	*
* W.S. Elev (ft)	* 1708.39	* Reach Len. (ft)	* 196.55	* 196.55	* 196.55	*
* Crit W.S. (ft)	* 1708.97	* Flow Area (sq ft)	*	* 224.36	*	*
* E.G. Slope (ft/ft)	*0.003758	* Area (sq ft)	*	* 224.36	*	*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	*	*
* Top Width (ft)	* 71.97	* Top Width (ft)	*	* 71.97	*	*
* Vel Total (ft/s)	* 12.79	* Avg. Vel. (ft/s)	*	* 12.79	*	*
* Max Chl Dpth (ft)	* 3.89	* Hydr. Depth (ft)	*	* 3.12	*	*
* Conv. Total (cfs)	* 46814.7	* Conv. (cfs)	*	* 46814.7	*	*
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	* 73.39	*	*
* Min Ch El (ft)	* 1704.50	* Shear (lb/sq ft)	*	* 0.72	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 9.18	*	*
* Frctn Loss (ft)	* 0.74	* Cum Volume (acre-ft)	*	* 21.10	*	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 5.38	*	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1711.49	* Element	* Left OB	* Channel	* Right OB	*
* Vel Head (ft)	* 2.80	* Wt. n-Val.	*	* 0.015	*	*
* W.S. Elev (ft)	* 1708.69	* Reach Len. (ft)	* 196.55	* 196.55	* 196.55	*
* Crit W.S. (ft)	* 1709.35	* Flow Area (sq ft)	*	* 245.71	*	*
* E.G. Slope (ft/ft)	*0.003758	* Area (sq ft)	*	* 245.71	*	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*	*
* Top Width (ft)	* 73.15	* Top Width (ft)	*	* 73.15	*	*
* Vel Total (ft/s)	* 13.43	* Avg. Vel. (ft/s)	*	* 13.43	*	*
* Max Chl Dpth (ft)	* 4.19	* Hydr. Depth (ft)	*	* 3.36	*	*
* Conv. Total (cfs)	* 53832.5	* Conv. (cfs)	*	* 53832.5	*	*
* Length Wtd. (ft)	* 196.55	* Wetted Per. (ft)	*	* 74.71	*	*
* Min Ch El (ft)	* 1704.50	* Shear (lb/sq ft)	*	* 0.77	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.36	*	*
* Frctn Loss (ft)	* 0.74	* Cum Volume (acre-ft)	*	* 17.65	*	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 5.25	*	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 140

INPUT
Description: PLAN STA 158+50
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1710.39	1011.46	1704.66	1041.46	1703.76	1071.46	1704.66	1082.92	1710.39

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	50	50	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1710.37	* Element	* Left OB	* Channel	* Right OB	*
* Vel Head (ft)	* 1.04	* Wt. n-Val.	*	* 0.015	*	*
* W.S. Elev (ft)	* 1709.34	* Reach Len. (ft)	* 50.00	* 50.00	* 50.00	*
* Crit W.S. (ft)	* 1708.23	* Flow Area (sq ft)	*	* 351.20	*	*
* E.G. Slope (ft/ft)	*0.000962	* Area (sq ft)	*	* 351.20	*	*
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	*	*
* Top Width (ft)	* 78.70	* Top Width (ft)	*	* 78.70	*	*
* Vel Total (ft/s)	* 8.17	* Avg. Vel. (ft/s)	*	* 8.17	*	*
* Max Chl Dpth (ft)	* 5.57	* Hydr. Depth (ft)	*	* 4.46	*	*
* Conv. Total (cfs)	* 92555.6	* Conv. (cfs)	*	* 92555.6	*	*
* Length Wtd. (ft)	* 50.00	* Wetted Per. (ft)	*	* 80.93	*	*
* Min Ch El (ft)	* 1703.76	* Shear (lb/sq ft)	*	* 0.26	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 2.13	*	*
* Frctn Loss (ft)	* 0.04	* Cum Volume (acre-ft)	*	* 19.80	*	*
* C & E Loss (ft)	* 0.03	* Cum SA (acres)	*	* 5.04	*	*

Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1710.75	Element	Left OB	Channel	Right OB	
Vel Head (ft)	2.80	Wt. n-Val.		0.015		
W.S. Elev (ft)	1707.95	Reach Len. (ft)	50.00	50.00	50.00	
Crit W.S. (ft)	1708.61	Flow Area (sq ft)		245.91		
E.G. Slope (ft/ft)	*0.003750	Area (sq ft)		245.91		
Q Total (cfs)	3300.00	Flow (cfs)		3300.00		
Top Width (ft)	73.15	Top Width (ft)		73.15		
Vel Total (ft/s)	13.42	Avg. Vel. (ft/s)		13.42		
Max Chl Dpth (ft)	4.19	Hydr. Depth (ft)		3.36		
Conv. Total (cfs)	53892.0	Conv. (cfs)		53892.0		
Length Wtd. (ft)	50.00	Wetted Per. (ft)		74.73		
Min Ch El (ft)	1703.76	Shear (lb/sq ft)		0.77		
Alpha	1.00	Stream Power (lb/ft s)		10.34		
Frctn Loss (ft)	0.74	Cum Volume (acre-ft)		16.54		
C & E Loss (ft)	0.00	Cum SA (acres)		4.92		

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 130

INPUT
Description: PLAN STA 159+00
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1710.2	1011.46	1704.47	1041.46	1703.57	1071.46	1704.47	1082.92	1710.2

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	129.35	129.35	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1710.30	Element	Left OB	Channel	Right OB	
Vel Head (ft)	0.95	Wt. n-Val.		0.015		
W.S. Elev (ft)	1709.35	Reach Len. (ft)	129.35	129.35	129.35	
Crit W.S. (ft)		Flow Area (sq ft)		367.67		
E.G. Slope (ft/ft)	*0.000838	Area (sq ft)		367.67		
Q Total (cfs)	2870.00	Flow (cfs)		2870.00		
Top Width (ft)	79.53	Top Width (ft)		79.53		
Vel Total (ft/s)	7.81	Avg. Vel. (ft/s)		7.81		
Max Chl Dpth (ft)	5.78	Hydr. Depth (ft)		4.62		
Conv. Total (cfs)	99145.9	Conv. (cfs)		99145.9		
Length Wtd. (ft)	129.35	Wetted Per. (ft)		81.86		
Min Ch El (ft)	1703.57	Shear (lb/sq ft)		0.23		
Alpha	1.00	Stream Power (lb/ft s)		1.83		
Frctn Loss (ft)	0.09	Cum Volume (acre-ft)		19.39		
C & E Loss (ft)	0.05	Cum SA (acres)		4.95		

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1710.55	Element	Left OB	Channel	Right OB	
Vel Head (ft)	2.79	Wt. n-Val.		0.015		
W.S. Elev (ft)	1707.76	Reach Len. (ft)	129.35	129.35	129.35	
Crit W.S. (ft)	1708.42	Flow Area (sq ft)		246.08		
E.G. Slope (ft/ft)	*0.003742	Area (sq ft)		246.08		
Q Total (cfs)	3300.00	Flow (cfs)		3300.00		
Top Width (ft)	73.16	Top Width (ft)		73.16		
Vel Total (ft/s)	13.41	Avg. Vel. (ft/s)		13.41		
Max Chl Dpth (ft)	4.19	Hydr. Depth (ft)		3.36		
Conv. Total (cfs)	53949.0	Conv. (cfs)		53949.0		
Length Wtd. (ft)	129.35	Wetted Per. (ft)		74.74		
Min Ch El (ft)	1703.57	Shear (lb/sq ft)		0.77		
Alpha	1.00	Stream Power (lb/ft s)		10.31		
Frctn Loss (ft)	0.19	Cum Volume (acre-ft)		16.26		
C & E Loss (ft)	0.00	Cum SA (acres)		4.83		

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 120

INPUT
Description: PLAN STA 160+29
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1711.59	1015.2	1703.99	1045.2	1703.09	1075.2	1703.99	1090.4	1711.59

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1090.4	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1090.4	50	50	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1710.15	Element	Left OB	Channel	Right OB	
Vel Head (ft)	0.76	Wt. n-Val.		0.015		

* W.S. Elev (ft)	* 1709.39	* Reach Len. (ft)	* 50.00	* 50.00	* 50.00 *
* Crit W.S. (ft)	*	* Flow Area (sq ft)	*	* 409.02	* *
* E.G. Slope (ft/ft)	*0.000609	* Area (sq ft)	*	* 409.02	* *
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	* *
* Top Width (ft)	* 81.59	* Top Width (ft)	*	* 81.59	* *
* Vel Total (ft/s)	* 7.02	* Avg. Vel. (ft/s)	*	* 7.02	* *
* Max Chl Dpth (ft)	* 6.30	* Hydr. Depth (ft)	*	* 5.01	* *
* Conv. Total (cfs)	*116255.5	* Conv. (cfs)	*	*116255.5	* *
* Length Wtd. (ft)	* 50.00	* Wetted Per. (ft)	*	* 84.16	* *
* Min Ch El (ft)	* 1703.09	* Shear (lb/sq ft)	*	* 0.18	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 1.30	* *
* Frctn Loss (ft)	* 0.03	* Cum Volume (acre-ft)	*	* 18.23	* *
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	*	* 4.71	* *

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1710.07	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.79	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1707.28	* Reach Len. (ft)	* 50.00	* 50.00	* 50.00 *
* Crit W.S. (ft)	* 1707.93	* Flow Area (sq ft)	*	* 246.08	* *
* E.G. Slope (ft/ft)	*0.003742	* Area (sq ft)	*	* 246.08	* *
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	* *
* Top Width (ft)	* 73.16	* Top Width (ft)	*	* 73.16	* *
* Vel Total (ft/s)	* 13.41	* Avg. Vel. (ft/s)	*	* 13.41	* *
* Max Chl Dpth (ft)	* 4.19	* Hydr. Depth (ft)	*	* 3.36	* *
* Conv. Total (cfs)	* 53948.9	* Conv. (cfs)	*	* 53948.9	* *
* Length Wtd. (ft)	* 50.00	* Wetted Per. (ft)	*	* 74.74	* *
* Min Ch El (ft)	* 1703.09	* Shear (lb/sq ft)	*	* 0.77	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 10.31	* *
* Frctn Loss (ft)	* 0.48	* Cum Volume (acre-ft)	*	* 15.53	* *
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 4.62	* *

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 110

INPUT
Description: PLAN STA 160+79
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1712.33	1000	1703.83	1031	1702.9	1072.5	1704.15	1072.5	1712.65

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1072.5	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1072.5	100	100	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1710.10	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 0.69	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1709.41	* Reach Len. (ft)	* 100.00	* 100.00	* 100.00 *
* Crit W.S. (ft)	*	* Flow Area (sq ft)	*	* 431.89	* *
* E.G. Slope (ft/ft)	*0.000502	* Area (sq ft)	*	* 431.89	* *
* Q Total (cfs)	* 2870.00	* Flow (cfs)	*	* 2870.00	* *
* Top Width (ft)	* 72.50	* Top Width (ft)	*	* 72.50	* *
* Vel Total (ft/s)	* 6.65	* Avg. Vel. (ft/s)	*	* 6.65	* *
* Max Chl Dpth (ft)	* 6.51	* Hydr. Depth (ft)	*	* 5.96	* *
* Conv. Total (cfs)	*128080.7	* Conv. (cfs)	*	*128080.7	* *
* Length Wtd. (ft)	* 100.00	* Wetted Per. (ft)	*	* 83.38	* *
* Min Ch El (ft)	* 1702.90	* Shear (lb/sq ft)	*	* 0.16	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 1.08	* *
* Frctn Loss (ft)	* 0.08	* Cum Volume (acre-ft)	*	* 17.75	* *
* C & E Loss (ft)	* 0.09	* Cum SA (acres)	*	* 4.62	* *

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1709.81	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 3.17	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1706.64	* Reach Len. (ft)	* 100.00	* 100.00	* 100.00 *
* Crit W.S. (ft)	* 1707.46	* Flow Area (sq ft)	*	* 230.83	* *
* E.G. Slope (ft/ft)	*0.004888	* Area (sq ft)	*	* 230.83	* *
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	* *
* Top Width (ft)	* 72.50	* Top Width (ft)	*	* 72.50	* *
* Vel Total (ft/s)	* 14.30	* Avg. Vel. (ft/s)	*	* 14.30	* *
* Max Chl Dpth (ft)	* 3.74	* Hydr. Depth (ft)	*	* 3.18	* *
* Conv. Total (cfs)	* 47201.5	* Conv. (cfs)	*	* 47201.5	* *
* Length Wtd. (ft)	* 100.00	* Wetted Per. (ft)	*	* 77.83	* *
* Min Ch El (ft)	* 1702.90	* Shear (lb/sq ft)	*	* 0.90	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 12.94	* *
* Frctn Loss (ft)	* 0.21	* Cum Volume (acre-ft)	*	* 15.25	* *
* C & E Loss (ft)	* 0.04	* Cum SA (acres)	*	* 4.53	* *

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 100

INPUT
Description: PLAN STA 161+79
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev

```
*****************************************************************************
    1000 1711.95    1000 1703.45    1031 1702.52  1072.5 1703.57  1072.5 1712.27

Manning's n Values         num=       3
     Sta   n Val     Sta   n Val     Sta   n Val
*********************************************
    1000    .015    1000    .015  1072.5    .015

Bank Sta: Left   Right    Lengths: Left Channel   Right     Coeff Contr.   Expan.
          1000  1072.5               100     100     100           .1       .3

CROSS SECTION OUTPUT  Profile #Post-Project
*************************************************************************************************
* E.G. Elev (ft)         * 1709.93  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)          *    1.57  * Wt. n-Val.            *          *    0.015  *          *
* W.S. Elev (ft)         * 1708.36  * Reach Len. (ft)      *  100.00  *  100.00  *  100.00  *
* Crit W.S. (ft)         *          * Flow Area (sq ft)     *          *  387.42  *          *
* E.G. Slope (ft/ft)     *0.001301  * Area (sq ft)          *          *  387.42  *          *
* Q Total (cfs)          * 3891.00  * Flow (cfs)            *          * 3891.00  *          *
* Top Width (ft)         *   72.50  * Top Width (ft)        *          *   72.50  *          *
* Vel Total (ft/s)       *   10.04  * Avg. Vel. (ft/s)      *          *   10.04  *          *
* Max Chl Dpth (ft)      *    5.84  * Hydr. Depth (ft)      *          *    5.34  *          *
* Conv. Total (cfs)      *107854.8  * Conv. (cfs)          *          *107854.8  *          *
* Length Wtd. (ft)       *  100.00  * Wetted Per. (ft)      *          *   82.23  *          *
* Min Ch El (ft)         * 1702.52  * Shear (lb/sq ft)     *          *    0.38  *          *
* Alpha                  *    1.00  * Stream Power (lb/ft s) *          *    3.84  *          *
* Frctn Loss (ft)        *    0.08  * Cum Volume (acre-ft)  *          *   16.81  *          *
* C & E Loss (ft)        *    0.23  * Cum SA (acres)        *          *    4.45  *          *
*************************************************************************************************

Warning: The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for
         additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than
         0.7 or greater than 1.4.  This may indicate the need for additional cross sections.

CROSS SECTION OUTPUT  Profile #PF 2
*************************************************************************************************
* E.G. Elev (ft)         * 1709.30  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)          *    3.01  * Wt. n-Val.            *          *    0.015  *          *
* W.S. Elev (ft)         * 1706.29  * Reach Len. (ft)      *  100.00  *  100.00  *  100.00  *
* Crit W.S. (ft)         * 1707.01  * Flow Area (sq ft)     *          *  237.09  *          *
* E.G. Slope (ft/ft)     *0.004490  * Area (sq ft)          *          *  237.09  *          *
* Q Total (cfs)          * 3300.00  * Flow (cfs)            *          * 3300.00  *          *
* Top Width (ft)         *   72.50  * Top Width (ft)        *          *   72.50  *          *
* Vel Total (ft/s)       *   13.92  * Avg. Vel. (ft/s)      *          *   13.92  *          *
* Max Chl Dpth (ft)      *    3.77  * Hydr. Depth (ft)      *          *    3.27  *          *
* Conv. Total (cfs)      * 49246.9  * Conv. (cfs)          *          * 49246.9  *          *
* Length Wtd. (ft)       *  100.00  * Wetted Per. (ft)      *          *   78.09  *          *
* Min Ch El (ft)         * 1702.52  * Shear (lb/sq ft)     *          *    0.85  *          *
* Alpha                  *    1.00  * Stream Power (lb/ft s) *          *   11.85  *          *
* Frctn Loss (ft)        *    0.47  * Cum Volume (acre-ft)  *          *   14.72  *          *
* C & E Loss (ft)        *    0.05  * Cum SA (acres)        *          *    4.37  *          *
*************************************************************************************************

CROSS SECTION


RIVER: Range Wash
REACH: Sloan Channel      RS: 90

INPUT
Description: PLAN STA 162+79
Station Elevation Data    num=       5
     Sta     Elev      Sta     Elev      Sta     Elev      Sta     Elev      Sta     Elev
*****************************************************************************
    1000 1712.14    1000 1703.61    1049 1702.14  1090.5 1703.39  1090.5 1710.16

Manning's n Values         num=       3
     Sta   n Val     Sta   n Val     Sta   n Val
*********************************************
    1000    .015    1000    .015  1090.5    .015

Bank Sta: Left   Right    Lengths: Left Channel   Right     Coeff Contr.   Expan.
          1000  1090.5               50      50      50           .1       .3

CROSS SECTION OUTPUT  Profile #Post-Project
*************************************************************************************************
* E.G. Elev (ft)         * 1709.62  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)          *    0.80  * Wt. n-Val.            *          *    0.015  *          *
* W.S. Elev (ft)         * 1708.82  * Reach Len. (ft)      *   50.00  *   50.00  *   50.00  *
* Crit W.S. (ft)         *          * Flow Area (sq ft)     *          *  542.38  *          *
* E.G. Slope (ft/ft)     *0.000559  * Area (sq ft)          *          *  542.38  *          *
* Q Total (cfs)          * 3891.00  * Flow (cfs)            *          * 3891.00  *          *
* Top Width (ft)         *   90.50  * Top Width (ft)        *          *   90.50  *          *
* Vel Total (ft/s)       *    7.17  * Avg. Vel. (ft/s)      *          *    7.17  *          *
* Max Chl Dpth (ft)      *    6.68  * Hydr. Depth (ft)      *          *    5.99  *          *
* Conv. Total (cfs)      *164574.1  * Conv. (cfs)          *          *164574.1  *          *
* Length Wtd. (ft)       *   50.00  * Wetted Per. (ft)      *          *  101.18  *          *
* Min Ch El (ft)         * 1702.14  * Shear (lb/sq ft)     *          *    0.19  *          *
* Alpha                  *    1.00  * Stream Power (lb/ft s) *          *    1.34  *          *
* Frctn Loss (ft)        *    0.05  * Cum Volume (acre-ft)  *          *   15.74  *          *
* C & E Loss (ft)        *    0.14  * Cum SA (acres)        *          *    4.26  *          *
*************************************************************************************************

Warning: The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for
         additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than
         0.7 or greater than 1.4.  This may indicate the need for additional cross sections.

CROSS SECTION OUTPUT  Profile #PF 2
*************************************************************************************************
* E.G. Elev (ft)         * 1708.93  * Element               *  Left OB *  Channel * Right OB *
* Vel Head (ft)          *    0.71  * Wt. n-Val.            *          *    0.015  *          *
* W.S. Elev (ft)         * 1708.22  * Reach Len. (ft)      *   50.00  *   50.00  *   50.00  *
* Crit W.S. (ft)         * 1706.28  * Flow Area (sq ft)     *          *  488.54  *          *
* E.G. Slope (ft/ft)     *0.000561  * Area (sq ft)          *          *  488.54  *          *
```

* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*
* Top Width (ft)	* 90.50	* Top Width (ft)	*	* 90.50	*
* Vel Total (ft/s)	* 6.75	* Avg. Vel. (ft/s)	*	* 6.75	*
* Max Chl Dpth (ft)	* 6.08	* Hydr. Depth (ft)	*	* 5.40	*
* Conv. Total (cfs)	*139350.2	* Conv. (cfs)	*	*139350.2	*
* Length Wtd. (ft)	* 50.00	* Wetted Per. (ft)	*	* 99.99	*
* Min Ch El (ft)	* 1702.14	* Shear (lb/sq ft)	*	* 0.17	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 1.16	*
* Frctn Loss (ft)	* 0.05	* Cum Volume (acre-ft)	*	* 13.88	*
* C & E Loss (ft)	* 0.12	* Cum SA (acres)	*	* 4.18	*

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.
Note: Hydraulic jump has occurred between this cross section and the previous upstream section.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 80

INPUT
Description: PLAN STA 163+29
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1708.85	1011.5	1702.85	1041.5	1701.95	1071.5	1702.85	1083	1708.85

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1083	.015

Bank Sta: Left 1000 Right 1083 Lengths: Left Channel 91.21 Right 91.21 Coeff Contr. .1 Expan. .3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1709.43	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 2.15	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1707.28	* Reach Len. (ft)	* 91.21	* 91.21	* 91.21 *
* Crit W.S. (ft)	* 1707.28	* Flow Area (sq ft)	*	* 330.74	* *
* E.G. Slope (ft/ft)	*0.002097	* Area (sq ft)	*	* 330.74	* *
* Q Total (cfs)	* 3891.00	* Flow (cfs)	*	* 3891.00	* *
* Top Width (ft)	* 77.00	* Top Width (ft)	*	* 77.00	* *
* Vel Total (ft/s)	* 11.76	* Avg. Vel. (ft/s)	*	* 11.76	* *
* Max Chl Dpth (ft)	* 5.33	* Hydr. Depth (ft)	*	* 4.30	* *
* Conv. Total (cfs)	* 84963.4	* Conv. (cfs)	*	* 84963.4	* *
* Length Wtd. (ft)	* 91.21	* Wetted Per. (ft)	*	* 79.20	* *
* Min Ch El (ft)	* 1701.95	* Shear (lb/sq ft)	*	* 0.55	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 6.43	* *
* Frctn Loss (ft)	* 0.19	* Cum Volume (acre-ft)	*	* 15.24	* *
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 4.17	* *

Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water surface that had the least amount of error between computed and assumed values.
Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1708.76	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 1.96	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1706.80	* Reach Len. (ft)	* 91.21	* 91.21	* 91.21 *
* Crit W.S. (ft)	* 1706.80	* Flow Area (sq ft)	*	* 294.08	* *
* E.G. Slope (ft/ft)	*0.002154	* Area (sq ft)	*	* 294.08	* *
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	* *
* Top Width (ft)	* 75.15	* Top Width (ft)	*	* 75.15	* *
* Vel Total (ft/s)	* 11.22	* Avg. Vel. (ft/s)	*	* 11.22	* *
* Max Chl Dpth (ft)	* 4.85	* Hydr. Depth (ft)	*	* 3.91	* *
* Conv. Total (cfs)	* 71106.5	* Conv. (cfs)	*	* 71106.5	* *
* Length Wtd. (ft)	* 91.21	* Wetted Per. (ft)	*	* 77.12	* *
* Min Ch El (ft)	* 1701.95	* Shear (lb/sq ft)	*	* 0.51	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 5.75	* *
* Frctn Loss (ft)	* 0.20	* Cum Volume (acre-ft)	*	* 13.44	* *
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 4.08	* *

Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water surface that had the least amount of error between computed and assumed values.
Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 78.8888*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1708.34	1011.47	1702.38	1011.5	1702.37	1041.5	1701.47	1071.49	1702.37
1071.52	1702.38	1082.99	1708.34						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.99	.015

Bank Sta: Left 1000 Right 1082.99 Lengths: Left Channel Right 91.21 91.21 91.21 Coeff Contr. .1 Expan. .3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1709.11	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.95	Wt. n-Val.		0.015	
W.S. Elev (ft)	1706.17	Reach Len. (ft)	91.21	91.21	91.21
Crit W.S. (ft)	1706.80	Flow Area (sq ft)		282.42	
E.G. Slope (ft/ft)	*0.003390	Area (sq ft)		282.42	
Q Total (cfs)	3891.00	Flow (cfs)		3891.00	
Top Width (ft)	74.62	Top Width (ft)		74.62	
Vel Total (ft/s)	13.78	Avg. Vel. (ft/s)		13.78	
Max Chl Dpth (ft)	4.69	Hydr. Depth (ft)		3.78	
Conv. Total (cfs)	66831.1	Conv. (cfs)		66831.1	
Length Wtd. (ft)	91.21	Wetted Per. (ft)		76.50	
Min Ch El (ft)	1701.47	Shear (lb/sq ft)		0.78	
Alpha	1.00	Stream Power (lb/ft s)		10.76	
Frctn Loss (ft)	0.24	Cum Volume (acre-ft)		14.60	
C & E Loss (ft)	0.08	Cum SA (acres)		4.01	

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1708.43	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.71	Wt. n-Val.		0.015	
W.S. Elev (ft)	1705.72	Reach Len. (ft)	91.21	91.21	91.21
Crit W.S. (ft)	1706.32	Flow Area (sq ft)		249.92	
E.G. Slope (ft/ft)	*0.003543	Area (sq ft)		249.92	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	72.92	Top Width (ft)		72.92	
Vel Total (ft/s)	13.20	Avg. Vel. (ft/s)		13.20	
Max Chl Dpth (ft)	4.25	Hydr. Depth (ft)		3.43	
Conv. Total (cfs)	55439.1	Conv. (cfs)		55439.1	
Length Wtd. (ft)	91.21	Wetted Per. (ft)		74.59	
Min Ch El (ft)	1701.47	Shear (lb/sq ft)		0.74	
Alpha	1.00	Stream Power (lb/ft s)		9.79	
Frctn Loss (ft)	0.25	Cum Volume (acre-ft)		12.87	
C & E Loss (ft)	0.08	Cum SA (acres)		3.93	

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 77.7777*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1707.83	1011.47	1701.9	1011.5	1701.89	1041.49	1700.99	1071.48	1701.89
1071.51	1701.9	1082.98	1707.83						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.98	.015

Bank Sta: Left 1000 Right 1082.98 Lengths: Left Channel 91.21 Right 91.21 91.21 Coeff Contr. .1 Expan. .3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1708.75	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.24	Wt. n-Val.		0.015	
W.S. Elev (ft)	1705.51	Reach Len. (ft)	91.21	91.21	91.21
Crit W.S. (ft)	1706.32	Flow Area (sq ft)		269.37	
E.G. Slope (ft/ft)	*0.003919	Area (sq ft)		269.37	
Q Total (cfs)	3891.00	Flow (cfs)		3891.00	
Top Width (ft)	74.00	Top Width (ft)		74.00	
Vel Total (ft/s)	14.44	Avg. Vel. (ft/s)		14.44	
Max Chl Dpth (ft)	4.52	Hydr. Depth (ft)		3.64	
Conv. Total (cfs)	62151.1	Conv. (cfs)		62151.1	
Length Wtd. (ft)	91.21	Wetted Per. (ft)		75.78	
Min Ch El (ft)	1700.99	Shear (lb/sq ft)		0.87	
Alpha	1.00	Stream Power (lb/ft s)		12.56	
Frctn Loss (ft)	0.33	Cum Volume (acre-ft)		14.02	
C & E Loss (ft)	0.03	Cum SA (acres)		3.85	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1708.05	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.96	Wt. n-Val.		0.015	
W.S. Elev (ft)	1705.09	Reach Len. (ft)	91.21	91.21	91.21
Crit W.S. (ft)	1705.84	Flow Area (sq ft)		238.94	
E.G. Slope (ft/ft)	*0.004071	Area (sq ft)		238.94	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	72.39	Top Width (ft)		72.39	
Vel Total (ft/s)	13.81	Avg. Vel. (ft/s)		13.81	
Max Chl Dpth (ft)	4.10	Hydr. Depth (ft)		3.30	
Conv. Total (cfs)	51722.6	Conv. (cfs)		51722.6	
Length Wtd. (ft)	91.21	Wetted Per. (ft)		73.97	
Min Ch El (ft)	1700.99	Shear (lb/sq ft)		0.82	

* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 11.34	*	*
* Frctn Loss (ft)	* 0.35	* Cum Volume (acre-ft)	*	* 12.35	*	*
* C & E Loss (ft)	* 0.03	* Cum SA (acres)	*	* 3.78	*	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 76.6666*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1707.32	1011.47	1701.42	1011.5	1701.41	1041.49	1700.51	1071.48	1701.41
1071.51	1701.42	1082.97	1707.32						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.97	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.97	91.21	91.21	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1708.35	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 3.42	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1704.93	* Reach Len. (ft)	* 91.21	* 91.21	* 91.21 *
* Crit W.S. (ft)	* 1705.84	* Flow Area (sq ft)	*	* 262.14	* *
* E.G. Slope (ft/ft)	*0.004263	* Area (sq ft)	*	* 262.14	* *
* Q Total (cfs)	* 3891.00	* Flow (cfs)	*	* 3891.00	* *
* Top Width (ft)	* 73.67	* Top Width (ft)	*	* 73.67	* *
* Vel Total (ft/s)	* 14.84	* Avg. Vel. (ft/s)	*	* 14.84	* *
* Max Chl Dpth (ft)	* 4.42	* Hydr. Depth (ft)	*	* 3.56	* *
* Conv. Total (cfs)	* 59593.0	* Conv. (cfs)	*	* 59593.0	* *
* Length Wtd. (ft)	* 91.21	* Wetted Per. (ft)	*	* 75.40	* *
* Min Ch El (ft)	* 1700.51	* Shear (lb/sq ft)	*	* 0.93	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 13.73	* *
* Frctn Loss (ft)	* 0.37	* Cum Volume (acre-ft)	*	* 13.47	* *
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	*	* 3.70	* *

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1707.65	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 3.12	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1704.52	* Reach Len. (ft)	* 91.21	* 91.21	* 91.21 *
* Crit W.S. (ft)	* 1705.36	* Flow Area (sq ft)	*	* 232.68	* *
* E.G. Slope (ft/ft)	*0.004421	* Area (sq ft)	*	* 232.68	* *
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	* *
* Top Width (ft)	* 72.10	* Top Width (ft)	*	* 72.10	* *
* Vel Total (ft/s)	* 14.18	* Avg. Vel. (ft/s)	*	* 14.18	* *
* Max Chl Dpth (ft)	* 4.01	* Hydr. Depth (ft)	*	* 3.23	* *
* Conv. Total (cfs)	* 49632.8	* Conv. (cfs)	*	* 49632.8	* *
* Length Wtd. (ft)	* 91.21	* Wetted Per. (ft)	*	* 73.64	* *
* Min Ch El (ft)	* 1700.51	* Shear (lb/sq ft)	*	* 0.87	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 12.37	* *
* Frctn Loss (ft)	* 0.39	* Cum Volume (acre-ft)	*	* 11.86	* *
* C & E Loss (ft)	* 0.02	* Cum SA (acres)	*	* 3.63	* *

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 75.5555*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1706.81	1011.47	1700.94	1011.5	1700.93	1041.48	1700.03	1071.47	1700.93
1071.5	1700.94	1082.96	1706.81						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.96	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.96	91.21	91.21	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1707.94	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 3.56	* Wt. n-Val.	*	* 0.015	* *
* W.S. Elev (ft)	* 1704.38	* Reach Len. (ft)	* 91.21	* 91.21	* 91.21 *
* Crit W.S. (ft)	* 1705.36	* Flow Area (sq ft)	*	* 257.14	* *
* E.G. Slope (ft/ft)	*0.004526	* Area (sq ft)	*	* 257.14	* *
* Q Total (cfs)	* 3891.00	* Flow (cfs)	*	* 3891.00	* *
* Top Width (ft)	* 73.46	* Top Width (ft)	*	* 73.46	* *
* Vel Total (ft/s)	* 15.13	* Avg. Vel. (ft/s)	*	* 15.13	* *
* Max Chl Dpth (ft)	* 4.35	* Hydr. Depth (ft)	*	* 3.50	* *
* Conv. Total (cfs)	* 57838.5	* Conv. (cfs)	*	* 57838.5	* *
* Length Wtd. (ft)	* 91.21	* Wetted Per. (ft)	*	* 75.15	* *
* Min Ch El (ft)	* 1700.03	* Shear (lb/sq ft)	*	* 0.97	* *
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 14.63	* *
* Frctn Loss (ft)	* 0.40	* Cum Volume (acre-ft)	*	* 12.92	* *
* C & E Loss (ft)	* 0.01	* Cum SA (acres)	*	* 3.55	* *

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1707.22	Element	Left OB	Channel	Right OB	
Vel Head (ft)	3.23	Wt. n-Val.		0.015		
W.S. Elev (ft)	1703.99	Reach Len. (ft)	91.21	91.21	91.21	
Crit W.S. (ft)	1704.88	Flow Area (sq ft)		228.65		
E.G. Slope (ft/ft)	*0.004668	Area (sq ft)		228.65		
Q Total (cfs)	3300.00	Flow (cfs)		3300.00		
Top Width (ft)	71.93	Top Width (ft)		71.93		
Vel Total (ft/s)	14.43	Avg. Vel. (ft/s)		14.43		
Max Chl Dpth (ft)	3.96	Hydr. Depth (ft)		3.18		
Conv. Total (cfs)	48298.1	Conv. (cfs)		48298.1		
Length Wtd. (ft)	91.21	Wetted Per. (ft)		73.43		
Min Ch El (ft)	1700.03	Shear (lb/sq ft)		0.91		
Alpha	1.00	Stream Power (lb/ft s)		13.10		
Frctn Loss (ft)	0.41	Cum Volume (acre-ft)		11.38		
C & E Loss (ft)	0.01	Cum SA (acres)		3.47		

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 74.4444*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1706.31	1011.46	1700.46	1011.49	1700.46	1041.48	1699.56	1071.46	1700.46
1071.49	1700.46	1082.96	1706.31						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.96	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.96	91.21	91.21	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1707.51	Element	Left OB	Channel	Right OB	
Vel Head (ft)	3.64	Wt. n-Val.		0.015		
W.S. Elev (ft)	1703.86	Reach Len. (ft)	91.21	91.21	91.21	
Crit W.S. (ft)	1704.89	Flow Area (sq ft)		253.99		
E.G. Slope (ft/ft)	*0.004705	Area (sq ft)		253.99		
Q Total (cfs)	3891.00	Flow (cfs)		3891.00		
Top Width (ft)	73.37	Top Width (ft)		73.37		
Vel Total (ft/s)	15.32	Avg. Vel. (ft/s)		15.32		
Max Chl Dpth (ft)	4.30	Hydr. Depth (ft)		3.46		
Conv. Total (cfs)	56724.6	Conv. (cfs)		56724.6		
Length Wtd. (ft)	91.21	Wetted Per. (ft)		75.03		
Min Ch El (ft)	1699.56	Shear (lb/sq ft)		0.99		
Alpha	1.00	Stream Power (lb/ft s)		15.23		
Frctn Loss (ft)	0.42	Cum Volume (acre-ft)		12.39		
C & E Loss (ft)	0.01	Cum SA (acres)		3.39		

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1706.78	Element	Left OB	Channel	Right OB	
Vel Head (ft)	3.29	Wt. n-Val.		0.015		
W.S. Elev (ft)	1703.49	Reach Len. (ft)	91.21	91.21	91.21	
Crit W.S. (ft)	1704.41	Flow Area (sq ft)		226.68		
E.G. Slope (ft/ft)	*0.004800	Area (sq ft)		226.68		
Q Total (cfs)	3300.00	Flow (cfs)		3300.00		
Top Width (ft)	71.90	Top Width (ft)		71.90		
Vel Total (ft/s)	14.56	Avg. Vel. (ft/s)		14.56		
Max Chl Dpth (ft)	3.93	Hydr. Depth (ft)		3.15		
Conv. Total (cfs)	47631.5	Conv. (cfs)		47631.5		
Length Wtd. (ft)	91.21	Wetted Per. (ft)		73.38		
Min Ch El (ft)	1699.56	Shear (lb/sq ft)		0.93		
Alpha	1.00	Stream Power (lb/ft s)		13.48		
Frctn Loss (ft)	0.43	Cum Volume (acre-ft)		10.90		
C & E Loss (ft)	0.01	Cum SA (acres)		3.32		

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 73.3333*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1705.8	1011.46	1699.98	1011.49	1699.98	1041.47	1699.08	1071.45	1699.98
1071.48	1699.98	1082.95	1705.8						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.95	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.95	91.21	91.21	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1707.06	Element	Left OB	Channel	Right OB	
Vel Head (ft)	3.71	Wt. n-Val.		0.015		
W.S. Elev (ft)	1703.35	Reach Len. (ft)	91.21	91.21	91.21	

* Crit W.S. (ft)	* 1704.41	* Flow Area (sq ft)	*	*	251.78	*	*
* E.G. Slope (ft/ft)	*0.004837	* Area (sq ft)	*	*	251.78	*	*
* Q Total (cfs)	* 3891.00	* Flow (cfs)	*	*	3891.00	*	*
* Top Width (ft)	* 73.31	* Top Width (ft)	*	*	73.31	*	*
* Vel Total (ft/s)	* 15.45	* Avg. Vel. (ft/s)	*	*	15.45	*	*
* Max Chl Dpth (ft)	* 4.27	* Hydr. Depth (ft)	*	*	3.43	*	*
* Conv. Total (cfs)	* 55947.3	* Conv. (cfs)	*	*	55947.3	*	*
* Length Wtd. (ft)	* 91.21	* Wetted Per. (ft)	*	*	74.95	*	*
* Min Ch El (ft)	* 1699.08	* Shear (lb/sq ft)	*	*	1.01	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	*	15.68	*	*
* Frctn Loss (ft)	* 0.44	* Cum Volume (acre-ft)	*	*	11.86	*	*
* C & E Loss (ft)	* 0.01	* Cum SA (acres)	*	*	3.24	*	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1706.33	* Element	* Left OB	*	Channel	* Right OB	*
* Vel Head (ft)	* 3.35	* Wt. n-Val.	*	*	0.015	*	*
* W.S. Elev (ft)	* 1702.98	* Reach Len. (ft)	* 91.21	*	91.21	* 91.21	*
* Crit W.S. (ft)	* 1703.93	* Flow Area (sq ft)	*	*	224.80	*	*
* E.G. Slope (ft/ft)	*0.004929	* Area (sq ft)	*	*	224.80	*	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	*	3300.00	*	*
* Top Width (ft)	* 71.84	* Top Width (ft)	*	*	71.84	*	*
* Vel Total (ft/s)	* 14.68	* Avg. Vel. (ft/s)	*	*	14.68	*	*
* Max Chl Dpth (ft)	* 3.90	* Hydr. Depth (ft)	*	*	3.13	*	*
* Conv. Total (cfs)	* 47004.6	* Conv. (cfs)	*	*	47004.6	*	*
* Length Wtd. (ft)	* 91.21	* Wetted Per. (ft)	*	*	73.30	*	*
* Min Ch El (ft)	* 1699.08	* Shear (lb/sq ft)	*	*	0.94	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	*	13.85	*	*
* Frctn Loss (ft)	* 0.44	* Cum Volume (acre-ft)	*	*	10.43	*	*
* C & E Loss (ft)	* 0.01	* Cum SA (acres)	*	*	3.17	*	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 72.2222*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1705.29	1011.46	1699.5	1011.49	1699.5	1041.47	1698.6	1071.45	1699.5
1071.48	1699.5	1082.94	1705.29						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.94	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.94	91.21	91.21	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1706.61	* Element	* Left OB	*	Channel	* Right OB	*
* Vel Head (ft)	* 3.76	* Wt. n-Val.	*	*	0.015	*	*
* W.S. Elev (ft)	* 1702.85	* Reach Len. (ft)	* 91.21	*	91.21	* 91.21	*
* Crit W.S. (ft)	* 1703.93	* Flow Area (sq ft)	*	*	250.00	*	*
* E.G. Slope (ft/ft)	*0.004948	* Area (sq ft)	*	*	250.00	*	*
* Q Total (cfs)	* 3891.00	* Flow (cfs)	*	*	3891.00	*	*
* Top Width (ft)	* 73.27	* Top Width (ft)	*	*	73.27	*	*
* Vel Total (ft/s)	* 15.56	* Avg. Vel. (ft/s)	*	*	15.56	*	*
* Max Chl Dpth (ft)	* 4.25	* Hydr. Depth (ft)	*	*	3.41	*	*
* Conv. Total (cfs)	* 55317.4	* Conv. (cfs)	*	*	55317.4	*	*
* Length Wtd. (ft)	* 91.21	* Wetted Per. (ft)	*	*	74.89	*	*
* Min Ch El (ft)	* 1698.60	* Shear (lb/sq ft)	*	*	1.03	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	*	16.05	*	*
* Frctn Loss (ft)	* 0.45	* Cum Volume (acre-ft)	*	*	11.33	*	*
* C & E Loss (ft)	* 0.01	* Cum SA (acres)	*	*	3.08	*	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1705.87	* Element	* Left OB	*	Channel	* Right OB	*
* Vel Head (ft)	* 3.39	* Wt. n-Val.	*	*	0.015	*	*
* W.S. Elev (ft)	* 1702.48	* Reach Len. (ft)	* 91.21	*	91.21	* 91.21	*
* Crit W.S. (ft)	* 1703.45	* Flow Area (sq ft)	*	*	223.42	*	*
* E.G. Slope (ft/ft)	*0.005027	* Area (sq ft)	*	*	223.42	*	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	*	3300.00	*	*
* Top Width (ft)	* 71.82	* Top Width (ft)	*	*	71.82	*	*
* Vel Total (ft/s)	* 14.77	* Avg. Vel. (ft/s)	*	*	14.77	*	*
* Max Chl Dpth (ft)	* 3.88	* Hydr. Depth (ft)	*	*	3.11	*	*
* Conv. Total (cfs)	* 46541.6	* Conv. (cfs)	*	*	46541.6	*	*
* Length Wtd. (ft)	* 91.21	* Wetted Per. (ft)	*	*	73.26	*	*
* Min Ch El (ft)	* 1698.60	* Shear (lb/sq ft)	*	*	0.96	*	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	*	14.14	*	*
* Frctn Loss (ft)	* 0.45	* Cum Volume (acre-ft)	*	*	9.96	*	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	*	3.02	*	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 71.1111*

INPUT
Description:
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1704.78	1011.46	1699.02	1011.49	1699.02	1041.46	1698.12	1071.44	1699.02
1071.47	1699.02	1082.93	1704.78						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.93	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.93	91.21	91.21	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1706.15	Element			
Vel Head (ft)	3.80	Wt. n-Val.		0.015	
W.S. Elev (ft)	1702.35	Reach Len. (ft)	91.21	91.21	91.21
Crit W.S. (ft)	1703.45	Flow Area (sq ft)		248.71	
E.G. Slope (ft/ft)	*0.005031	Area (sq ft)		248.71	
Q Total (cfs)	3891.00	Flow (cfs)		3891.00	
Top Width (ft)	73.25	Top Width (ft)		73.25	
Vel Total (ft/s)	15.64	Avg. Vel. (ft/s)		15.64	
Max Chl Dpth (ft)	4.23	Hydr. Depth (ft)		3.40	
Conv. Total (cfs)	54857.4	Conv. (cfs)		54857.4	
Length Wtd. (ft)	91.21	Wetted Per. (ft)		74.86	
Min Ch El (ft)	1698.12	Shear (lb/sq ft)		1.04	
Alpha	1.00	Stream Power (lb/ft s)		16.33	
Frctn Loss (ft)	0.46	Cum Volume (acre-ft)		10.81	
C & E Loss (ft)	0.00	Cum SA (acres)		2.93	

CROSS SECTION OUTPUT Profile #PF 2

			Left OB	Channel	Right OB
E.G. Elev (ft)	1705.40	Element			
Vel Head (ft)	3.42	Wt. n-Val.		0.015	
W.S. Elev (ft)	1701.99	Reach Len. (ft)	91.21	91.21	91.21
Crit W.S. (ft)	1702.96	Flow Area (sq ft)		222.47	
E.G. Slope (ft/ft)	*0.005098	Area (sq ft)		222.47	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	71.81	Top Width (ft)		71.81	
Vel Total (ft/s)	14.83	Avg. Vel. (ft/s)		14.83	
Max Chl Dpth (ft)	3.87	Hydr. Depth (ft)		3.10	
Conv. Total (cfs)	46219.2	Conv. (cfs)		46219.2	
Length Wtd. (ft)	91.21	Wetted Per. (ft)		73.25	
Min Ch El (ft)	1698.12	Shear (lb/sq ft)		0.97	
Alpha	1.00	Stream Power (lb/ft s)		14.34	
Frctn Loss (ft)	0.46	Cum Volume (acre-ft)		9.49	
C & E Loss (ft)	0.00	Cum SA (acres)		2.87	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 70

INPUT
Description: PLAN STA 171+50
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1704.27	1011.46	1698.54	1041.46	1697.64	1071.46	1698.54	1082.92	1704.27

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1082.92	46.25	46.25	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

			Left OB	Channel	Right OB
E.G. Elev (ft)	1705.68	Element			
Vel Head (ft)	3.83	Wt. n-Val.		0.015	
W.S. Elev (ft)	1701.85	Reach Len. (ft)	46.25	46.25	46.25
Crit W.S. (ft)	1702.97	Flow Area (sq ft)		247.75	
E.G. Slope (ft/ft)	*0.005095	Area (sq ft)		247.75	
Q Total (cfs)	3891.00	Flow (cfs)		3891.00	
Top Width (ft)	73.25	Top Width (ft)		73.25	
Vel Total (ft/s)	15.71	Avg. Vel. (ft/s)		15.71	
Max Chl Dpth (ft)	4.21	Hydr. Depth (ft)		3.38	
Conv. Total (cfs)	54511.3	Conv. (cfs)		54511.3	
Length Wtd. (ft)	46.25	Wetted Per. (ft)		74.84	
Min Ch El (ft)	1697.64	Shear (lb/sq ft)		1.05	
Alpha	1.00	Stream Power (lb/ft s)		16.54	
Frctn Loss (ft)	0.46	Cum Volume (acre-ft)		10.29	
C & E Loss (ft)	0.00	Cum SA (acres)		2.78	

CROSS SECTION OUTPUT Profile #PF 2

			Left OB	Channel	Right OB
E.G. Elev (ft)	1704.93	Element			
Vel Head (ft)	3.44	Wt. n-Val.		0.015	
W.S. Elev (ft)	1701.50	Reach Len. (ft)	46.25	46.25	46.25
Crit W.S. (ft)	1702.47	Flow Area (sq ft)		221.78	
E.G. Slope (ft/ft)	*0.005150	Area (sq ft)		221.78	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	71.82	Top Width (ft)		71.82	
Vel Total (ft/s)	14.88	Avg. Vel. (ft/s)		14.88	
Max Chl Dpth (ft)	3.86	Hydr. Depth (ft)		3.09	
Conv. Total (cfs)	45982.6	Conv. (cfs)		45982.6	
Length Wtd. (ft)	46.25	Wetted Per. (ft)		73.24	
Min Ch El (ft)	1697.64	Shear (lb/sq ft)		0.97	
Alpha	1.00	Stream Power (lb/ft s)		14.49	
Frctn Loss (ft)	0.47	Cum Volume (acre-ft)		9.03	
C & E Loss (ft)	0.00	Cum SA (acres)		2.72	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 60

INPUT
Description: PLAN STA 171+96
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1710.12	1000	1704	1011.46	1698.28	1041.46	1697.38	1071.46	1698.28
1082.92	1704	1082.92	1710.12						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1082.92 90 90 90 .3 .5

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1705.44	Element	Left OB	Channel	Right OB	
Vel Head (ft)	3.86	Wt. n-Val.		0.015		
W.S. Elev (ft)	1701.58	Reach Len. (ft)	2.00	2.00	2.00	
Crit W.S. (ft)	1702.71	Flow Area (sq ft)		246.64		
E.G. Slope (ft/ft)	*0.005167	Area (sq ft)		246.64		
Q Total (cfs)	3891.00	Flow (cfs)		3891.00		
Top Width (ft)	73.21	Top Width (ft)		73.21		
Vel Total (ft/s)	15.78	Avg. Vel. (ft/s)		15.78		
Max Chl Dpth (ft)	4.20	Hydr. Depth (ft)		3.37		
Conv. Total (cfs)	54130.1	Conv. (cfs)		54130.1		
Length Wtd. (ft)		Wetted Per. (ft)		74.80		
Min Ch El (ft)	1697.38	Shear (lb/sq ft)		1.06		
Alpha	1.00	Stream Power (lb/ft s)		16.78		
Frctn Loss (ft)	0.24	Cum Volume (acre-ft)		10.03		
C & E Loss (ft)	0.00	Cum SA (acres)		2.70		

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1704.69	Element	Left OB	Channel	Right OB	
Vel Head (ft)	3.47	Wt. n-Val.		0.015		
W.S. Elev (ft)	1701.22	Reach Len. (ft)	2.00	2.00	2.00	
Crit W.S. (ft)	1702.21	Flow Area (sq ft)		220.79		
E.G. Slope (ft/ft)	*0.005223	Area (sq ft)		220.79		
Q Total (cfs)	3300.00	Flow (cfs)		3300.00		
Top Width (ft)	71.78	Top Width (ft)		71.78		
Vel Total (ft/s)	14.95	Avg. Vel. (ft/s)		14.95		
Max Chl Dpth (ft)	3.84	Hydr. Depth (ft)		3.08		
Conv. Total (cfs)	45661.0	Conv. (cfs)		45661.0		
Length Wtd. (ft)		Wetted Per. (ft)		73.20		
Min Ch El (ft)	1697.38	Shear (lb/sq ft)		0.98		
Alpha	1.00	Stream Power (lb/ft s)		14.70		
Frctn Loss (ft)	0.24	Cum Volume (acre-ft)		8.79		
C & E Loss (ft)	0.00	Cum SA (acres)		2.65		

BRIDGE

RIVER: Range Wash
REACH: Sloan Channel RS: 50

INPUT
Description: PLAN STA 171+99
Distance from Upstream XS = 2
Deck/Roadway Width = 87
Weir Coefficient = 2.6
Upstream Deck/Roadway Coordinates
num= 2

Sta Hi Cord	Lo Cord	Sta Hi Cord	Lo Cord
1000 1710.12	1704.33	1082.92	1710.12	1704.33

Upstream Bridge Cross Section Data
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1710.12	1000	1704	1011.46	1698.28	1041.46	1697.38	1071.46	1698.28
1082.92	1704	1082.92	1710.12						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left Right Coeff Contr. Expan.
1000 1082.92 .3 .5

Downstream Deck/Roadway Coordinates
num= 2

Sta Hi Cord	Lo Cord	Sta Hi Cord	Lo Cord
1000 1710.12	1704.33	1082.92	1710.12	1704.33

Downstream Bridge Cross Section Data
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1710.12	1000	1703.72	1011.46	1697.99	1041.46	1697.09	1071.46	1697.99
1082.92	1703.72	1082.92	1710.12						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left Right Coeff Contr. Expan.
1000 1082.92 .3 .5

Upstream Embankment side slope = 0 horiz. to 1.0 vertical
Downstream Embankment side slope = 0 horiz. to 1.0 vertical
Maximum allowable submergence for weir flow = .95
Elevation at which weir flow begins = 1710.12
Energy head used in spillway design =
Spillway height used in design =
Weir crest shape = Broad Crested

Number of Piers = 4

Pier Data
Pier Station Upstream=1017.708 Downstream=1017.708

Upstream num= 2			
Width	Elev	Width	Elev
.67	1694	.67	1705
Downstream num= 2			
Width	Elev	Width	Elev
.67	1694	.67	1705

Pier Data
Pier Station Upstream=1033.458 Downstream=1033.458

Upstream num= 2			
Width	Elev	Width	Elev
.67	1694	.67	1705
Downstream num= 2			
Width	Elev	Width	Elev
.67	1694	.67	1705

Pier Data
Pier Station Upstream=1049.291 Downstream=1049.291

Upstream num= 2			
Width	Elev	Width	Elev
.67	1694	.67	1705
Downstream num= 2			
Width	Elev	Width	Elev
.67	1694	.67	1705

Pier Data
Pier Station Upstream=1065.041 Downstream=1065.041

Upstream num= 2			
Width	Elev	Width	Elev
.67	1694	.67	1705
Downstream num= 2			
Width	Elev	Width	Elev
.67	1694	.67	1705

Number of Bridge Coefficient Sets = 1

Low Flow Methods and Data
Energy
Selected Low Flow Methods = Highest Energy Answer

High Flow Method
Energy Only

Additional Bridge Parameters
Add Friction component to Momentum
Do not add Weight component to Momentum
Class B flow critical depth computations use critical depth
inside the bridge at the upstream end
Criteria to check for pressure flow = Upstream energy grade line

BRIDGE OUTPUT Profile #Post-Project

E.G. US. (ft)	1705.44	Element	Inside BR US	Inside BR DS	
W.S. US. (ft)	1701.58	E.G. Elev (ft)	1705.01	1704.72	
Q Total (cfs)	3891.00	W.S. Elev (ft)	1702.83	1702.55	
Q Bridge (cfs)	3891.00	Crit W.S. (ft)	1702.83	1702.55	
Q Weir (cfs)		Max Chl Dpth (ft)	5.45	5.46	
Weir Sta Lft (ft)		Vel Total (ft/s)	11.86	11.84	
Weir Sta Rgt (ft)		Flow Area (sq ft)	328.17	328.65	
Weir Submerg		Froude # Chl	1.00	1.00	
Weir Max Depth (ft)		Specif Force (cu ft)	2214.54	2214.74	
Min El Weir Flow (ft)	1710.13	Hydr Depth (ft)	4.34	4.35	
Min El Prs (ft)	1704.33	W.P. Total (ft)	117.54	117.60	
Delta EG (ft)	-22.11	Conv. Total (cfs)	64459.7	64594.4	
Delta WS (ft)	-0.46	Top Width (ft)	75.55	75.55	
BR Open Area (sq ft)	445.75	Frctn Loss (ft)		0.32	
BR Open Vel (ft/s)	11.86	C & E Loss (ft)		0.00	
Coef of Q		Shear Total (lb/sq ft)	0.64	0.63	
Br Sel Method	Energy only	Power Total (lb/ft s)	7.53	7.50	

Note: Momentum answer is not valid if the water surface is above the low chord or if there is weir flow. The momentum answer has been disregarded.
Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water surface that had the least amount of error between computed and

assumed values.

BRIDGE OUTPUT Profile #PF 2

E.G. US. (ft)	1704.69	Element	Inside BR US	Inside BR DS
W.S. US. (ft)	1701.22	E.G. Elev (ft)	1704.33	1704.04
Q Total (cfs)	3300.00	W.S. Elev (ft)	1702.36	1702.06
Q Bridge (cfs)	3300.00	Crit W.S. (ft)	1702.36	1702.06
Q Weir (cfs)		Max Chl Dpth (ft)	4.98	4.97
Weir Sta Lft (ft)		Vel Total (ft/s)	11.26	11.30
Weir Sta Rgt (ft)		Flow Area (sq ft)	293.01	292.09
Weir Submerg		Froude # Chl	1.00	1.00
Weir Max Depth (ft)		Specif Force (cu ft)	1789.69	1789.83
Min El Weir Flow (ft)	1710.13	Hydr Depth (ft)	3.98	3.97
Min El Prs (ft)	1704.33	W.P. Total (ft)	111.66	111.48
Delta EG (ft)	-23.41	Conv. Total (cfs)	55222.1	54989.8
Delta WS (ft)	-0.36	Top Width (ft)	73.67	73.59
BR Open Area (sq ft)	445.75	Frctn Loss (ft)		0.31
BR Open Vel (ft/s)	11.30	C & E Loss (ft)		0.00
Coef of Q		Shear Total (lb/sq ft)	0.59	0.59
Br Sel Method	Energy only	Power Total (lb/ft s)	6.59	6.66

Note: Momentum answer is not valid if the water surface is above the low chord or if there is weir flow. The momentum answer has been disregarded.
Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water surface that had the least amount of error between computed and assumed values.

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 40

INPUT
Description: PLAN STA 172+86
Station Elevation Data num= 7

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1710.12	1000	1703.72	1011.46	1697.99	1041.46	1697.09	1071.46	1697.99
1082.92	1703.72	1082.92	1710.12						

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1082.92	.015

Bank Sta: Left Right Lengths: Left Channel Right Coeff Contr. Expan.
1000 1082.92 113.64 113.64 113.64 .3 .5

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1704.61	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.57	Wt. n-Val.		0.015	
W.S. Elev (ft)	1702.03	Reach Len. (ft)	113.64	113.64	113.64
Crit W.S. (ft)	1702.41	Flow Area (sq ft)		302.33	
E.G. Slope (ft/ft)	0.002778	Area (sq ft)		302.33	
Q Total (cfs)	3891.00	Flow (cfs)		3891.00	
Top Width (ft)	76.17	Top Width (ft)		76.17	
Vel Total (ft/s)	12.87	Avg. Vel. (ft/s)		12.87	
Max Chl Dpth (ft)	4.94	Hydr. Depth (ft)		3.97	
Conv. Total (cfs)	73828.0	Conv. (cfs)		73828.0	
Length Wtd. (ft)	113.64	Wetted Per. (ft)		78.11	
Min Ch El (ft)	1697.09	Shear (lb/sq ft)		0.67	
Alpha	1.00	Stream Power (lb/ft s)		8.64	
Frctn Loss (ft)	0.00	Cum Volume (acre-ft)		10.01	
C & E Loss (ft)	0.11	Cum SA (acres)		2.70	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1703.93	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.35	Wt. n-Val.		0.015	
W.S. Elev (ft)	1701.58	Reach Len. (ft)	113.64	113.64	113.64
Crit W.S. (ft)	1701.93	Flow Area (sq ft)		268.49	
E.G. Slope (ft/ft)	0.002866	Area (sq ft)		268.49	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	74.38	Top Width (ft)		74.38	
Vel Total (ft/s)	12.29	Avg. Vel. (ft/s)		12.29	
Max Chl Dpth (ft)	4.49	Hydr. Depth (ft)		3.61	
Conv. Total (cfs)	61640.1	Conv. (cfs)		61640.1	
Length Wtd. (ft)	113.64	Wetted Per. (ft)		76.10	
Min Ch El (ft)	1697.09	Shear (lb/sq ft)		0.63	
Alpha	1.00	Stream Power (lb/ft s)		7.76	
Frctn Loss (ft)	0.00	Cum Volume (acre-ft)		8.78	
C & E Loss (ft)	0.11	Cum SA (acres)		2.64	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 30

INPUT
Description: PLAN STA 174+00
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1704.06	1011.46	1697.46	1041.46	1696.56	1071.46	1697.46	1081.36	1704.06

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	179.28	179.28	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1704.30	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.59	Wt. n-Val.		0.015	
W.S. Elev (ft)	1701.71	Reach Len. (ft)	179.28	179.28	179.28
Crit W.S. (ft)	1702.01	Flow Area (sq ft)		308.96	
E.G. Slope (ft/ft)	*0.002590	Area (sq ft)		308.96	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	72.76	Top Width (ft)		72.76	
Vel Total (ft/s)	12.91	Avg. Vel. (ft/s)		12.91	
Max Chl Dpth (ft)	5.15	Hydr. Depth (ft)		4.25	
Conv. Total (cfs)	78402.0	Conv. (cfs)		78402.0	
Length Wtd. (ft)	179.28	Wetted Per. (ft)		75.36	
Min Ch El (ft)	1696.56	Shear (lb/sq ft)		0.66	
Alpha	1.00	Stream Power (lb/ft s)		8.56	
Frctn Loss (ft)	0.30	Cum Volume (acre-ft)		9.22	
C & E Loss (ft)	0.01	Cum SA (acres)		2.50	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1703.53	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.53	Wt. n-Val.		0.015	
W.S. Elev (ft)	1701.00	Reach Len. (ft)	179.28	179.28	179.28
Crit W.S. (ft)	1701.43	Flow Area (sq ft)		258.53	
E.G. Slope (ft/ft)	*0.003066	Area (sq ft)		258.53	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	70.65	Top Width (ft)		70.65	
Vel Total (ft/s)	12.76	Avg. Vel. (ft/s)		12.76	
Max Chl Dpth (ft)	4.44	Hydr. Depth (ft)		3.66	
Conv. Total (cfs)	59600.4	Conv. (cfs)		59600.4	
Length Wtd. (ft)	179.28	Wetted Per. (ft)		72.82	
Min Ch El (ft)	1696.56	Shear (lb/sq ft)		0.68	
Alpha	1.00	Stream Power (lb/ft s)		8.67	
Frctn Loss (ft)	0.34	Cum Volume (acre-ft)		8.09	
C & E Loss (ft)	0.06	Cum SA (acres)		2.45	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 28.5714*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1703.23	1011.46	1696.63	1041.46	1695.73	1071.46	1696.63	1081.36	1703.23

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	179.28	179.28	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1703.68	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.27	Wt. n-Val.		0.015	
W.S. Elev (ft)	1700.40	Reach Len. (ft)	179.28	179.28	179.28
Crit W.S. (ft)	1701.17	Flow Area (sq ft)		274.83	
E.G. Slope (ft/ft)	*0.003711	Area (sq ft)		274.83	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	71.34	Top Width (ft)		71.34	
Vel Total (ft/s)	14.52	Avg. Vel. (ft/s)		14.52	
Max Chl Dpth (ft)	4.67	Hydr. Depth (ft)		3.85	
Conv. Total (cfs)	65500.0	Conv. (cfs)		65500.0	
Length Wtd. (ft)	179.28	Wetted Per. (ft)		73.65	
Min Ch El (ft)	1695.73	Shear (lb/sq ft)		0.86	
Alpha	1.00	Stream Power (lb/ft s)		12.55	
Frctn Loss (ft)	0.55	Cum Volume (acre-ft)		8.02	
C & E Loss (ft)	0.07	Cum SA (acres)		2.21	

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1702.87	Element	Left OB	Channel	Right OB
Vel Head (ft)	2.99	Wt. n-Val.		0.015	
W.S. Elev (ft)	1699.88	Reach Len. (ft)	179.28	179.28	179.28
Crit W.S. (ft)	1700.60	Flow Area (sq ft)		238.00	
E.G. Slope (ft/ft)	*0.003961	Area (sq ft)		238.00	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	69.77	Top Width (ft)		69.77	
Vel Total (ft/s)	13.87	Avg. Vel. (ft/s)		13.87	
Max Chl Dpth (ft)	4.15	Hydr. Depth (ft)		3.41	
Conv. Total (cfs)	52433.3	Conv. (cfs)		52433.3	
Length Wtd. (ft)	179.28	Wetted Per. (ft)		71.76	
Min Ch El (ft)	1695.73	Shear (lb/sq ft)		0.82	
Alpha	1.00	Stream Power (lb/ft s)		11.37	
Frctn Loss (ft)	0.62	Cum Volume (acre-ft)		7.07	
C & E Loss (ft)	0.05	Cum SA (acres)		2.16	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 27.1428*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1702.4	1011.46	1695.8	1041.46	1694.9	1071.46	1695.8	1081.36	1702.4

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	179.28	179.28	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1702.95	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.50	Wt. n-Val.		0.015	
W.S. Elev (ft)	1699.45	Reach Len. (ft)	179.28	179.28	179.28
Crit W.S. (ft)	1700.34	Flow Area (sq ft)		265.71	
E.G. Slope (ft/ft)	*0.004118	Area (sq ft)		265.71	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	70.95	Top Width (ft)		70.95	
Vel Total (ft/s)	15.02	Avg. Vel. (ft/s)		15.02	
Max Chl Dpth (ft)	4.55	Hydr. Depth (ft)		3.74	
Conv. Total (cfs)	62178.7	Conv. (cfs)		62178.7	
Length Wtd. (ft)	179.28	Wetted Per. (ft)		73.19	
Min Ch El (ft)	1694.90	Shear (lb/sq ft)		0.93	
Alpha	1.00	Stream Power (lb/ft s)		14.02	
Frctn Loss (ft)	0.70	Cum Volume (acre-ft)		6.90	
C & E Loss (ft)	0.02	Cum SA (acres)		1.91	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1702.11	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.14	Wt. n-Val.		0.015	
W.S. Elev (ft)	1698.97	Reach Len. (ft)	179.28	179.28	179.28
Crit W.S. (ft)	1699.77	Flow Area (sq ft)		232.05	
E.G. Slope (ft/ft)	*0.004286	Area (sq ft)		232.05	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	69.51	Top Width (ft)		69.51	
Vel Total (ft/s)	14.22	Avg. Vel. (ft/s)		14.22	
Max Chl Dpth (ft)	4.07	Hydr. Depth (ft)		3.34	
Conv. Total (cfs)	50408.2	Conv. (cfs)		50408.2	
Length Wtd. (ft)	179.28	Wetted Per. (ft)		71.46	
Min Ch El (ft)	1694.90	Shear (lb/sq ft)		0.87	
Alpha	1.00	Stream Power (lb/ft s)		12.36	
Frctn Loss (ft)	0.74	Cum Volume (acre-ft)		6.10	
C & E Loss (ft)	0.02	Cum SA (acres)		1.88	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 25.7142*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1701.57	1011.46	1694.97	1041.46	1694.07	1071.46	1694.97	1081.36	1701.57

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	179.28	179.28	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1702.18	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.63	Wt. n-Val.		0.015	
W.S. Elev (ft)	1698.55	Reach Len. (ft)	179.28	179.28	179.28
Crit W.S. (ft)	1699.51	Flow Area (sq ft)		261.14	
E.G. Slope (ft/ft)	*0.004345	Area (sq ft)		261.14	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	70.76	Top Width (ft)		70.76	
Vel Total (ft/s)	15.28	Avg. Vel. (ft/s)		15.28	
Max Chl Dpth (ft)	4.48	Hydr. Depth (ft)		3.69	
Conv. Total (cfs)	60533.0	Conv. (cfs)		60533.0	
Length Wtd. (ft)	179.28	Wetted Per. (ft)		72.95	
Min Ch El (ft)	1694.07	Shear (lb/sq ft)		0.97	
Alpha	1.00	Stream Power (lb/ft s)		14.83	
Frctn Loss (ft)	0.76	Cum Volume (acre-ft)		5.82	
C & E Loss (ft)	0.01	Cum SA (acres)		1.62	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1701.32	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.23	Wt. n-Val.		0.015	
W.S. Elev (ft)	1698.09	Reach Len. (ft)	179.28	179.28	179.28

* Crit W.S. (ft)	* 1698.94	* Flow Area (sq ft)	*	* 228.97	*
* E.G. Slope (ft/ft)	*0.004467	* Area (sq ft)	*	* 228.97	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*
* Top Width (ft)	* 69.38	* Top Width (ft)	*	* 69.38	*
* Vel Total (ft/s)	* 14.41	* Avg. Vel. (ft/s)	*	* 14.41	*
* Max Chl Dpth (ft)	* 4.02	* Hydr. Depth (ft)	*	* 3.30	*
* Conv. Total (cfs)	* 49372.7	* Conv. (cfs)	*	* 49372.7	*
* Length Wtd. (ft)	* 179.28	* Wetted Per. (ft)	*	* 71.30	*
* Min Ch El (ft)	* 1694.07	* Shear (lb/sq ft)	*	* 0.90	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 12.91	*
* Frctn Loss (ft)	* 0.78	* Cum Volume (acre-ft)	*	* 5.16	*
* C & E Loss (ft)	* 0.01	* Cum SA (acres)	*	* 1.59	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 24.2857*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1700.75	1011.46	1694.15	1041.46	1693.25	1071.46	1694.15	1081.36	1700.75

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	179.28	179.28	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1701.38	* Element	* Left OB *	Channel *	Right OB *
* Vel Head (ft)	* 3.68	* Wt. n-Val.	*	* 0.015 *	*
* W.S. Elev (ft)	* 1697.71	* Reach Len. (ft)	* 179.28 *	179.28 *	179.28 *
* Crit W.S. (ft)	* 1698.69	* Flow Area (sq ft)	*	* 259.32 *	*
* E.G. Slope (ft/ft)	*0.004440	* Area (sq ft)	*	* 259.32 *	*
* Q Total (cfs)	* 3990.00	* Flow (cfs)	*	* 3990.00 *	*
* Top Width (ft)	* 70.68	* Top Width (ft)	*	* 70.68 *	*
* Vel Total (ft/s)	* 15.39	* Avg. Vel. (ft/s)	*	* 15.39 *	*
* Max Chl Dpth (ft)	* 4.46	* Hydr. Depth (ft)	*	* 3.67 *	*
* Conv. Total (cfs)	* 59881.8	* Conv. (cfs)	*	* 59881.8 *	*
* Length Wtd. (ft)	* 179.28	* Wetted Per. (ft)	*	* 72.86 *	*
* Min Ch El (ft)	* 1693.25	* Shear (lb/sq ft)	*	* 0.99 *	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 15.18 *	*
* Frctn Loss (ft)	* 0.79	* Cum Volume (acre-ft)	*	* 4.75 *	*
* C & E Loss (ft)	* 0.01	* Cum SA (acres)	*	* 1.33 *	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1700.51	* Element	* Left OB *	Channel *	Right OB *
* Vel Head (ft)	* 3.25	* Wt. n-Val.	*	* 0.015 *	*
* W.S. Elev (ft)	* 1697.26	* Reach Len. (ft)	* 179.28 *	179.28 *	179.28 *
* Crit W.S. (ft)	* 1698.12	* Flow Area (sq ft)	*	* 228.12 *	*
* E.G. Slope (ft/ft)	*0.004519	* Area (sq ft)	*	* 228.12 *	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00 *	*
* Top Width (ft)	* 69.34	* Top Width (ft)	*	* 69.34 *	*
* Vel Total (ft/s)	* 14.47	* Avg. Vel. (ft/s)	*	* 14.47 *	*
* Max Chl Dpth (ft)	* 4.01	* Hydr. Depth (ft)	*	* 3.29 *	*
* Conv. Total (cfs)	* 49089.0	* Conv. (cfs)	*	* 49089.0 *	*
* Length Wtd. (ft)	* 179.28	* Wetted Per. (ft)	*	* 71.25 *	*
* Min Ch El (ft)	* 1693.25	* Shear (lb/sq ft)	*	* 0.90 *	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 13.07 *	*
* Frctn Loss (ft)	* 0.81	* Cum Volume (acre-ft)	*	* 4.21 *	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 1.31 *	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 22.8571*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1699.92	1011.46	1693.32	1041.46	1692.42	1071.46	1693.32	1081.36	1699.92

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	179.28	179.28	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1700.57	* Element	* Left OB *	Channel *	Right OB *
* Vel Head (ft)	* 3.72	* Wt. n-Val.	*	* 0.015 *	*
* W.S. Elev (ft)	* 1696.85	* Reach Len. (ft)	* 179.28 *	179.28 *	179.28 *
* Crit W.S. (ft)	* 1697.86	* Flow Area (sq ft)	*	* 257.80 *	*
* E.G. Slope (ft/ft)	*0.004521	* Area (sq ft)	*	* 257.80 *	*
* Q Total (cfs)	* 3990.00	* Flow (cfs)	*	* 3990.00 *	*
* Top Width (ft)	* 70.62	* Top Width (ft)	*	* 70.62 *	*
* Vel Total (ft/s)	* 15.48	* Avg. Vel. (ft/s)	*	* 15.48 *	*
* Max Chl Dpth (ft)	* 4.43	* Hydr. Depth (ft)	*	* 3.65 *	*
* Conv. Total (cfs)	* 59342.5	* Conv. (cfs)	*	* 59342.5 *	*

* Length Wtd. (ft)	* 179.28	* Wetted Per. (ft)	*	* 72.78	*
* Min Ch El (ft)	* 1692.42	* Shear (lb/sq ft)	*	* 1.00	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 15.47	*
* Frctn Loss (ft)	* 0.80	* Cum Volume (acre-ft)	*	* 3.68	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 1.04	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1699.69	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 3.27	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1696.42	* Reach Len. (ft)	* 179.28	* 179.28	* 179.28 *
* Crit W.S. (ft)	* 1697.29	* Flow Area (sq ft)	*	* 227.25	*
* E.G. Slope (ft/ft)	*0.004573	* Area (sq ft)	*	* 227.25	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*
* Top Width (ft)	* 69.31	* Top Width (ft)	*	* 69.31	*
* Vel Total (ft/s)	* 14.52	* Avg. Vel. (ft/s)	*	* 14.52	*
* Max Chl Dpth (ft)	* 4.00	* Hydr. Depth (ft)	*	* 3.28	*
* Conv. Total (cfs)	* 48799.0	* Conv. (cfs)	*	* 48799.0	*
* Length Wtd. (ft)	* 179.28	* Wetted Per. (ft)	*	* 71.21	*
* Min Ch El (ft)	* 1692.42	* Shear (lb/sq ft)	*	* 0.91	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 13.23	*
* Frctn Loss (ft)	* 0.82	* Cum Volume (acre-ft)	*	* 3.28	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 1.02	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 21.4285*

INPUT
Description:
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1699.09	1011.46	1692.49	1041.46	1691.59	1071.46	1692.49	1081.36	1699.09

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	179.28	179.28	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

* E.G. Elev (ft)	* 1699.76	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 3.74	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1696.01	* Reach Len. (ft)	* 179.28	* 179.28	* 179.28 *
* Crit W.S. (ft)	* 1697.03	* Flow Area (sq ft)	*	* 256.95	*
* E.G. Slope (ft/ft)	*0.004568	* Area (sq ft)	*	* 256.95	*
* Q Total (cfs)	* 3990.00	* Flow (cfs)	*	* 3990.00	*
* Top Width (ft)	* 70.58	* Top Width (ft)	*	* 70.58	*
* Vel Total (ft/s)	* 15.53	* Avg. Vel. (ft/s)	*	* 15.53	*
* Max Chl Dpth (ft)	* 4.42	* Hydr. Depth (ft)	*	* 3.64	*
* Conv. Total (cfs)	* 59037.5	* Conv. (cfs)	*	* 59037.5	*
* Length Wtd. (ft)	* 179.28	* Wetted Per. (ft)	*	* 72.74	*
* Min Ch El (ft)	* 1691.59	* Shear (lb/sq ft)	*	* 1.01	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 15.64	*
* Frctn Loss (ft)	* 0.81	* Cum Volume (acre-ft)	*	* 2.62	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 0.75	*

CROSS SECTION OUTPUT Profile #PF 2

* E.G. Elev (ft)	* 1698.86	* Element	* Left OB	* Channel	* Right OB *
* Vel Head (ft)	* 3.28	* Wt. n-Val.	*	* 0.015	*
* W.S. Elev (ft)	* 1695.59	* Reach Len. (ft)	* 179.28	* 179.28	* 179.28 *
* Crit W.S. (ft)	* 1696.46	* Flow Area (sq ft)	*	* 227.10	*
* E.G. Slope (ft/ft)	*0.004583	* Area (sq ft)	*	* 227.10	*
* Q Total (cfs)	* 3300.00	* Flow (cfs)	*	* 3300.00	*
* Top Width (ft)	* 69.30	* Top Width (ft)	*	* 69.30	*
* Vel Total (ft/s)	* 14.53	* Avg. Vel. (ft/s)	*	* 14.53	*
* Max Chl Dpth (ft)	* 4.00	* Hydr. Depth (ft)	*	* 3.28	*
* Conv. Total (cfs)	* 48746.6	* Conv. (cfs)	*	* 48746.6	*
* Length Wtd. (ft)	* 179.28	* Wetted Per. (ft)	*	* 71.20	*
* Min Ch El (ft)	* 1691.59	* Shear (lb/sq ft)	*	* 0.91	*
* Alpha	* 1.00	* Stream Power (lb/ft s)	*	* 13.26	*
* Frctn Loss (ft)	* 0.82	* Cum Volume (acre-ft)	*	* 2.34	*
* C & E Loss (ft)	* 0.00	* Cum SA (acres)	*	* 0.74	*

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 20

INPUT
Description: PLAN STA 186+54
Station Elevation Data num= 5

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1001.53	1698.26	1011.46	1691.66	1041.46	1690.76	1071.46	1691.66	1081.36	1698.26

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1001.53	.015	1001.53	.015	1081.36	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1001.53	1081.36	260.12	280 299.88	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1698.93	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.75	Wt. n-Val.		0.015	
W.S. Elev (ft)	1695.18	Reach Len. (ft)	260.12	280.00	299.88
Crit W.S. (ft)	1696.20	Flow Area (sq ft)		256.78	
E.G. Slope (ft/ft)	*0.004577	Area (sq ft)		256.78	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	70.57	Top Width (ft)		70.57	
Vel Total (ft/s)	15.54	Avg. Vel. (ft/s)		15.54	
Max Chl Dpth (ft)	4.42	Hydr. Depth (ft)		3.64	
Conv. Total (cfs)	58979.3	Conv. (cfs)		58979.3	
Length Wtd. (ft)		Wetted Per. (ft)		72.73	
Min Ch El (ft)	1690.76	Shear (lb/sq ft)		1.01	
Alpha	1.00	Stream Power (lb/ft s)		15.67	
Frctn Loss (ft)	0.82	Cum Volume (acre-ft)		1.57	
C & E Loss (ft)	0.00	Cum SA (acres)		0.46	

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1698.04	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.28	Wt. n-Val.		0.015	
W.S. Elev (ft)	1694.75	Reach Len. (ft)	260.12	280.00	299.88
Crit W.S. (ft)	1695.63	Flow Area (sq ft)		227.03	
E.G. Slope (ft/ft)	*0.004587	Area (sq ft)		227.03	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	69.30	Top Width (ft)		69.30	
Vel Total (ft/s)	14.54	Avg. Vel. (ft/s)		14.54	
Max Chl Dpth (ft)	3.99	Hydr. Depth (ft)		3.28	
Conv. Total (cfs)	48724.0	Conv. (cfs)		48724.0	
Length Wtd. (ft)	280.00	Wetted Per. (ft)		71.19	
Min Ch El (ft)	1690.76	Shear (lb/sq ft)		0.91	
Alpha	1.00	Stream Power (lb/ft s)		13.27	
Frctn Loss (ft)	0.82	Cum Volume (acre-ft)		1.41	
C & E Loss (ft)	0.00	Cum SA (acres)		0.45	

CROSS SECTION

RIVER: Range Wash
REACH: Sloan Channel RS: 10

INPUT
Description: PLAN STA 189+14
Station Elevation Data num= 4

Sta	Elev	Sta	Elev	Sta	Elev	Sta	Elev
1000	1700	1021	1689.5	1081	1689.5	1096	1700

Manning's n Values num= 3

Sta	n Val	Sta	n Val	Sta	n Val
1000	.015	1000	.015	1096	.015

Bank Sta: Left	Right	Lengths: Left Channel	Right	Coeff Contr.	Expan.
1000	1096	0	0	.1	.3

CROSS SECTION OUTPUT Profile #Post-Project

E.G. Elev (ft)	1697.63	Element	Left OB	Channel	Right OB
Vel Head (ft)	4.63	Wt. n-Val.		0.015	
W.S. Elev (ft)	1693.00	Reach Len. (ft)			
Crit W.S. (ft)		Flow Area (sq ft)		231.00	
E.G. Slope (ft/ft)	*0.006656	Area (sq ft)		231.00	
Q Total (cfs)	3990.00	Flow (cfs)		3990.00	
Top Width (ft)	72.00	Top Width (ft)		72.00	
Vel Total (ft/s)	17.27	Avg. Vel. (ft/s)		17.27	
Max Chl Dpth (ft)	3.50	Hydr. Depth (ft)		3.21	
Conv. Total (cfs)	48907.9	Conv. (cfs)		48907.9	
Length Wtd. (ft)		Wetted Per. (ft)		73.93	
Min Ch El (ft)	1689.50	Shear (lb/sq ft)		1.30	
Alpha	1.00	Stream Power (lb/ft s)		22.43	
Frctn Loss (ft)		Cum Volume (acre-ft)			
C & E Loss (ft)		Cum SA (acres)			

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.
Note: The user has entered a known water surface elevation at this cross section.

CROSS SECTION OUTPUT Profile #PF 2

E.G. Elev (ft)	1696.52	Element	Left OB	Channel	Right OB
Vel Head (ft)	3.80	Wt. n-Val.		0.015	
W.S. Elev (ft)	1692.72	Reach Len. (ft)			
Crit W.S. (ft)	1693.85	Flow Area (sq ft)		210.99	
E.G. Slope (ft/ft)	*0.006035	Area (sq ft)		210.99	
Q Total (cfs)	3300.00	Flow (cfs)		3300.00	
Top Width (ft)	71.04	Top Width (ft)		71.04	
Vel Total (ft/s)	15.64	Avg. Vel. (ft/s)		15.64	
Max Chl Dpth (ft)	3.22	Hydr. Depth (ft)		2.97	
Conv. Total (cfs)	42480.3	Conv. (cfs)		42480.3	
Length Wtd. (ft)		Wetted Per. (ft)		72.82	
Min Ch El (ft)	1689.50	Shear (lb/sq ft)		1.09	
Alpha	1.00	Stream Power (lb/ft s)		17.07	
Frctn Loss (ft)	1.47	Cum Volume (acre-ft)			
C & E Loss (ft)	0.05	Cum SA (acres)			

Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross

section. This may indicate the need for additional cross sections.

****

SUMMARY OF MANNING'S N VALUES

River:Range Wash

Reach	River Sta.	n1	n2	n3
Sloan Channel	225	.015	.015	.015
Sloan Channel	220	.015	.015	.015
Sloan Channel	215	.015	.015	.015
Sloan Channel	213	.015	.015	.015
Sloan Channel	212	.015	.015	.015
Sloan Channel	211.5	Bridge		
Sloan Channel	211	.015	.015	.015
Sloan Channel	210.5	.015	.015	.015
Sloan Channel	210	.015	.015	.015
Sloan Channel	200	.015	.015	.015
Sloan Channel	198.571*	.015	.015	.015
Sloan Channel	197.142*	.015	.015	.015
Sloan Channel	195.714*	.015	.015	.015
Sloan Channel	194.285*	.015	.015	.015
Sloan Channel	192.857*	.015	.015	.015
Sloan Channel	191.428*	.015	.015	.015
Sloan Channel	190	.015	.015	.015
Sloan Channel	188.*	.015	.015	.015
Sloan Channel	186.*	.015	.015	.015
Sloan Channel	184.*	.015	.015	.015
Sloan Channel	182.*	.015	.015	.015
Sloan Channel	180	.015	.015	.015
Sloan Channel	170	.015	.015	.015
Sloan Channel	160	.015	.015	.015
Sloan Channel	158.333*	.015	.015	.015
Sloan Channel	156.666*	.015	.015	.015
Sloan Channel	155.*	.015	.015	.015
Sloan Channel	153.333*	.015	.015	.015
Sloan Channel	151.666*	.015	.015	.015
Sloan Channel	150	.015	.015	.015
Sloan Channel	149.285*	.015	.015	.015
Sloan Channel	148.571*	.015	.015	.015
Sloan Channel	147.857*	.015	.015	.015
Sloan Channel	147.142*	.015	.015	.015
Sloan Channel	146.428*	.015	.015	.015
Sloan Channel	145.714*	.015	.015	.015
Sloan Channel	145.*	.015	.015	.015
Sloan Channel	144.285*	.015	.015	.015
Sloan Channel	143.571*	.015	.015	.015
Sloan Channel	142.857*	.015	.015	.015
Sloan Channel	142.142*	.015	.015	.015
Sloan Channel	141.428*	.015	.015	.015
Sloan Channel	140.714*	.015	.015	.015
Sloan Channel	140	.015	.015	.015
Sloan Channel	130	.015	.015	.015
Sloan Channel	120	.015	.015	.015
Sloan Channel	110	.015	.015	.015
Sloan Channel	100	.015	.015	.015
Sloan Channel	90	.015	.015	.015
Sloan Channel	80	.015	.015	.015
Sloan Channel	78.8888*	.015	.015	.015
Sloan Channel	77.7777*	.015	.015	.015
Sloan Channel	76.6666*	.015	.015	.015
Sloan Channel	75.5555*	.015	.015	.015
Sloan Channel	74.4444*	.015	.015	.015
Sloan Channel	73.3333*	.015	.015	.015
Sloan Channel	72.2222*	.015	.015	.015
Sloan Channel	71.1111*	.015	.015	.015
Sloan Channel	70	.015	.015	.015
Sloan Channel	60	.015	.015	.015
Sloan Channel	50	Bridge		
Sloan Channel	40	.015	.015	.015
Sloan Channel	30	.015	.015	.015
Sloan Channel	28.5714*	.015	.015	.015
Sloan Channel	27.1428*	.015	.015	.015
Sloan Channel	25.7142*	.015	.015	.015
Sloan Channel	24.2857*	.015	.015	.015
Sloan Channel	22.8571*	.015	.015	.015
Sloan Channel	21.4285*	.015	.015	.015
Sloan Channel	20	.015	.015	.015
Sloan Channel	10	.015	.015	.015

****

SUMMARY OF REACH LENGTHS

River: Range Wash

Reach	River Sta.	Left	Channel	Right
Sloan Channel	225	274	274	274
Sloan Channel	220	151	151	151
Sloan Channel	215	50	50	50
Sloan Channel	213	1	1	1
Sloan Channel	212	100	100	100
Sloan Channel	211.5	Bridge		
Sloan Channel	211	1	1	1
Sloan Channel	210.5	97	97	97
Sloan Channel	210	35.96	35.96	35.96
Sloan Channel	200	44.45	49.9	53.55
Sloan Channel	198.571*	44.45	49.9	53.55
Sloan Channel	197.142*	44.45	49.9	53.55
Sloan Channel	195.714*	44.45	49.9	53.55
Sloan Channel	194.285*	44.45	49.9	53.55
Sloan Channel	192.857*	44.45	49.9	53.55

*Sloan Channel	*	191.428*	*	44.45*	49.9*	53.55*
*Sloan Channel	*	190	*	45.13*	45.13*	45.13*
*Sloan Channel	*	188.*	*	45.13*	45.13*	45.13*
*Sloan Channel	*	186.*	*	45.13*	45.13*	45.13*
*Sloan Channel	*	184.*	*	45.13*	45.13*	45.13*
*Sloan Channel	*	182.*	*	45.13*	45.13*	45.13*
*Sloan Channel	*	180	*	100*	100*	100*
*Sloan Channel	*	170	*	51.96*	51.96*	51.96*
*Sloan Channel	*	160	*	74.33*	74.33*	74.33*
*Sloan Channel	*	158.333*	*	74.33*	74.33*	74.33*
*Sloan Channel	*	156.666*	*	74.33*	74.33*	74.33*
*Sloan Channel	*	155.*	*	74.33*	74.33*	74.33*
*Sloan Channel	*	153.333*	*	74.33*	74.33*	74.33*
*Sloan Channel	*	151.666*	*	74.33*	74.33*	74.33*
*Sloan Channel	*	150	*	196.55*	196.55*	196.55*
*Sloan Channel	*	149.285*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	148.571*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	147.857*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	147.142*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	146.428*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	145.714*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	145.*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	144.285*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	143.571*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	142.857*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	142.142*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	141.428*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	140.714*	*	196.55*	196.55*	196.55*
*Sloan Channel	*	140	*	50*	50*	50*
*Sloan Channel	*	130	*	129.35*	129.35*	129.35*
*Sloan Channel	*	120	*	50*	50*	50*
*Sloan Channel	*	110	*	100*	100*	100*
*Sloan Channel	*	100	*	100*	100*	100*
*Sloan Channel	*	90	*	50*	50*	50*
*Sloan Channel	*	80	*	91.21*	91.21*	91.21*
*Sloan Channel	*	78.8888*	*	91.21*	91.21*	91.21*
*Sloan Channel	*	77.7777*	*	91.21*	91.21*	91.21*
*Sloan Channel	*	76.6666*	*	91.21*	91.21*	91.21*
*Sloan Channel	*	75.5555*	*	91.21*	91.21*	91.21*
*Sloan Channel	*	74.4444*	*	91.21*	91.21*	91.21*
*Sloan Channel	*	73.3333*	*	91.21*	91.21*	91.21*
*Sloan Channel	*	72.2222*	*	91.21*	91.21*	91.21*
*Sloan Channel	*	71.1111*	*	91.21*	91.21*	91.21*
*Sloan Channel	*	70	*	46.25*	46.25*	46.25*
*Sloan Channel	*	60	*	90*	90*	90*
*Sloan Channel	*	50	*Bridge	*	*	*
*Sloan Channel	*	40	*	113.64*	113.64*	113.64*
*Sloan Channel	*	30	*	179.28*	179.28*	179.28*
*Sloan Channel	*	28.5714*	*	179.28*	179.28*	179.28*
*Sloan Channel	*	27.1428*	*	179.28*	179.28*	179.28*
*Sloan Channel	*	25.7142*	*	179.28*	179.28*	179.28*
*Sloan Channel	*	24.2857*	*	179.28*	179.28*	179.28*
*Sloan Channel	*	22.8571*	*	179.28*	179.28*	179.28*
*Sloan Channel	*	21.4285*	*	179.28*	179.28*	179.28*
*Sloan Channel	*	20	*	260.12*	280*	299.88*
*Sloan Channel	*	10	*	0*	0*	0*

SUMMARY OF CONTRACTION AND EXPANSION COEFFICIENTS
River: Range Wash

Reach	River Sta.	Contr.	Expan.
*Sloan Channel	225	.1	.3
*Sloan Channel	220	.1	.3
*Sloan Channel	215	.1	.3
*Sloan Channel	213	.1	.3
*Sloan Channel	212	.2	.4
*Sloan Channel	211.5	*Bridge	*
*Sloan Channel	211	.2	.4
*Sloan Channel	210.5	.1	.3
*Sloan Channel	210	.1	.3
*Sloan Channel	200	.1	.3
*Sloan Channel	198.571**	.1	.3
*Sloan Channel	197.142**	.1	.3
*Sloan Channel	195.714**	.1	.3
*Sloan Channel	194.285**	.1	.3
*Sloan Channel	192.857**	.1	.3
*Sloan Channel	191.428**	.1	.3
*Sloan Channel	190	.1	.3
*Sloan Channel	188.*	.1	.3
*Sloan Channel	186.*	.1	.3
*Sloan Channel	184.*	.1	.3
*Sloan Channel	182.*	.1	.3
*Sloan Channel	180	.1	.3
*Sloan Channel	170	.1	.3
*Sloan Channel	160	.1	.3
*Sloan Channel	158.333**	.1	.3
*Sloan Channel	156.666**	.1	.3
*Sloan Channel	155.*	.1	.3
*Sloan Channel	153.333**	.1	.3
*Sloan Channel	151.666**	.1	.3
*Sloan Channel	150	.1	.3
*Sloan Channel	149.285**	.1	.3
*Sloan Channel	148.571**	.1	.3
*Sloan Channel	147.857**	.1	.3
*Sloan Channel	147.142**	.1	.3
*Sloan Channel	146.428**	.1	.3
*Sloan Channel	145.714**	.1	.3
*Sloan Channel	145.*	.1	.3
*Sloan Channel	144.285**	.1	.3
*Sloan Channel	143.571**	.1	.3
*Sloan Channel	142.857**	.1	.3

```
*Sloan Channel   *    142.142**       .1*       .3*
*Sloan Channel   *    141.428**       .1*       .3*
*Sloan Channel   *    140.714**       .1*       .3*
*Sloan Channel   *    140     *       .1*       .3*
*Sloan Channel   *    130     *       .1*       .3*
*Sloan Channel   *    120     *       .1*       .3*
*Sloan Channel   *    110     *       .1*       .3*
*Sloan Channel   *    100     *       .1*       .3*
*Sloan Channel   *    90      *       .1*       .3*
*Sloan Channel   *    80      *       .1*       .3*
*Sloan Channel   *    78.8888**       .1*       .3*
*Sloan Channel   *    77.7777**       .1*       .3*
*Sloan Channel   *    76.6666**       .1*       .3*
*Sloan Channel   *    75.5555**       .1*       .3*
*Sloan Channel   *    74.4444**       .1*       .3*
*Sloan Channel   *    73.3333**       .1*       .3*
*Sloan Channel   *    72.2222**       .1*       .3*
*Sloan Channel   *    71.1111**       .1*       .3*
*Sloan Channel   *    70      *       .1*       .3*
*Sloan Channel   *    60      *       .3*       .5*
*Sloan Channel   *    50      *Bridge   *         *
*Sloan Channel   *    40      *       .3*       .5*
*Sloan Channel   *    30      *       .1*       .3*
*Sloan Channel   *    28.5714**       .1*       .3*
*Sloan Channel   *    27.1428**       .1*       .3*
*Sloan Channel   *    25.7142**       .1*       .3*
*Sloan Channel   *    24.2857**       .1*       .3*
*Sloan Channel   *    22.8571**       .1*       .3*
*Sloan Channel   *    21.4285**       .1*       .3*
*Sloan Channel   *    20      *       .1*       .3*
*Sloan Channel   *    10      *       .1*       .3*
**************************************************

*******************************************************************************

ERRORS WARNINGS AND NOTES
Errors Warnings and Notes for Plan : Plan 03

River: Range Wash  Reach: Sloan Channel     RS: 220     Profile: Post-Project
     Warning:The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section.  This may indicate
             the need for additional cross sections.
River: Range Wash  Reach: Sloan Channel     RS: 220     Profile: PF 2
     Warning:The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section.  This may indicate
             the need for additional cross sections.
River: Range Wash  Reach: Sloan Channel     RS: 215     Profile: Post-Project
     Note:   Hydraulic jump has occurred between this cross section and the previous upstream section.
River: Range Wash  Reach: Sloan Channel     RS: 215     Profile: PF 2
     Note:   Hydraulic jump has occurred between this cross section and the previous upstream section.
River: Range Wash  Reach: Sloan Channel     RS: 212     Profile: Post-Project
     Warning:The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for additional cross sections.
     Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.
             This may indicate the need for additional cross sections.
River: Range Wash  Reach: Sloan Channel     RS: 212     Profile: PF 2
     Warning:The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for additional cross sections.
     Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.
             This may indicate the need for additional cross sections.
River: Range Wash  Reach: Sloan Channel     RS: 211.5     Profile: Post-Project
     Warning:Pier drag coefficient of 2.0 assumed for Class B flow.
     Warning:The momentum, Class B, supercritical, water surface downstream of the bridge had a higher energy than the upstream
             cross section.  This is not physically possible.  The downstream water surface has been computed by taking the
             momentum result inside of the bridge and performing an energy balance.
     Note:   The momentum method has computed a class B profile.
River: Range Wash  Reach: Sloan Channel     RS: 211.5     Profile: Post-Project Downstream
     Warning:The energy equation could not be balanced within the specified number of iterations.  The program selected the water
             surface that had the least amount of error between computed and assumed values.
     Warning:During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated
             water surface came back below critical depth.  This indicates that there is not a valid subcritical answer.  The
             program defaulted to critical depth.
River: Range Wash  Reach: Sloan Channel     RS: 211.5     Profile: PF 2
     Warning:Pier drag coefficient of 2.0 assumed for Class B flow.
     Warning:The momentum, Class B, supercritical, water surface downstream of the bridge had a higher energy than the upstream
             cross section.  This is not physically possible.  The downstream water surface has been computed by taking the
             momentum result inside of the bridge and performing an energy balance.
     Note:   Yarnell answer is not valid if the water surface is above the low chord or if there is weir flow.  The Yarnell answer
             has been disregarded.
     Note:   The momentum method has computed a class B profile.
River: Range Wash  Reach: Sloan Channel     RS: 211.5     Profile: PF 2 Downstream
     Warning:The energy equation could not be balanced within the specified number of iterations.  The program selected the water
             surface that had the least amount of error between computed and assumed values.
     Warning:During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated
             water surface came back below critical depth.  This indicates that there is not a valid subcritical answer.  The
             program defaulted to critical depth.
River: Range Wash  Reach: Sloan Channel     RS: 211     Profile: Post-Project
     Warning:The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for additional cross sections.
     Note:   The energy method has computed a class B profile.
River: Range Wash  Reach: Sloan Channel     RS: 211     Profile: PF 2
     Warning:The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for additional cross sections.
     Note:   The energy method has computed a class B profile.
River: Range Wash  Reach: Sloan Channel     RS: 210.5     Profile: Post-Project
     Warning:The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for additional cross sections.
     Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.
             This may indicate the need for additional cross sections.
River: Range Wash  Reach: Sloan Channel     RS: 210.5     Profile: PF 2
     Warning:The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for additional cross sections.
     Warning:The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4.
             This may indicate the need for additional cross sections.
River: Range Wash  Reach: Sloan Channel     RS: 210     Profile: Post-Project
     Warning:The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for additional cross sections.
     Warning:The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section.  This may indicate
             the need for additional cross sections.
River: Range Wash  Reach: Sloan Channel     RS: 210     Profile: PF 2
     Warning:The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for additional cross sections.
     Warning:The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section.  This may indicate
             the need for additional cross sections.
River: Range Wash  Reach: Sloan Channel     RS: 200     Profile: Post-Project
     Warning:The velocity head has changed by more than 0.5 ft (0.15 m).  This may indicate the need for additional cross sections.
```

River: Range Wash Reach: Sloan Channel RS: 200 Profile: PF 2
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
River: Range Wash Reach: Sloan Channel RS: 140 Profile: Post-Project
Note: Hydraulic jump has occurred between this cross section and the previous upstream section.
River: Range Wash Reach: Sloan Channel RS: 110 Profile: Post-Project
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
River: Range Wash Reach: Sloan Channel RS: 100 Profile: Post-Project
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.
River: Range Wash Reach: Sloan Channel RS: 90 Profile: Post-Project
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.
River: Range Wash Reach: Sloan Channel RS: 90 Profile: PF 2
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The conveyance ratio (upstream conveyance divided by downstream conveyance) is less than 0.7 or greater than 1.4. This may indicate the need for additional cross sections.
Note: Hydraulic jump has occurred between this cross section and the previous upstream section.
River: Range Wash Reach: Sloan Channel RS: 80 Profile: Post-Project
Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water surface that had the least amount of error between computed and assumed values.
Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.
River: Range Wash Reach: Sloan Channel RS: 80 Profile: PF 2
Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water surface that had the least amount of error between computed and assumed values.
Warning: During the standard step iterations, when the assumed water surface was set equal to critical depth, the calculated water surface came back below critical depth. This indicates that there is not a valid subcritical answer. The program defaulted to critical depth.
River: Range Wash Reach: Sloan Channel RS: 78.8888* Profile: Post-Project
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
River: Range Wash Reach: Sloan Channel RS: 78.8888* Profile: PF 2
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
River: Range Wash Reach: Sloan Channel RS: 50 Profile: Post-Project
Note: Momentum answer is not valid if the water surface is above the low chord or if there is weir flow. The momentum answer has been disregarded.
River: Range Wash Reach: Sloan Channel RS: 50 Profile: Post-Project Upstream
Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
River: Range Wash Reach: Sloan Channel RS: 50 Profile: Post-Project Downstream
Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water surface that had the least amount of error between computed and assumed values.
River: Range Wash Reach: Sloan Channel RS: 50 Profile: PF 2
Note: Momentum answer is not valid if the water surface is above the low chord or if there is weir flow. The momentum answer has been disregarded.
River: Range Wash Reach: Sloan Channel RS: 50 Profile: PF 2 Upstream
Warning: The energy equation could not be balanced within the specified number of iterations. The program used critical depth for the water surface and continued on with the calculations.
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
River: Range Wash Reach: Sloan Channel RS: 50 Profile: PF 2 Downstream
Warning: The energy equation could not be balanced within the specified number of iterations. The program selected the water surface that had the least amount of error between computed and assumed values.
River: Range Wash Reach: Sloan Channel RS: 28.5714* Profile: Post-Project
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
River: Range Wash Reach: Sloan Channel RS: 10 Profile: Post-Project
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.
Note: The user has entered a known water surface elevation at this cross section.
River: Range Wash Reach: Sloan Channel RS: 10 Profile: PF 2
Warning: The velocity head has changed by more than 0.5 ft (0.15 m). This may indicate the need for additional cross sections.
Warning: The energy loss was greater than 1.0 ft (0.3 m). between the current and previous cross section. This may indicate the need for additional cross sections.

HEC-RAS Plan: Plan 03 River: Range Wash Reach: Sloan Channel


Reach	River Sta	Profile	Q Total	Min Ch El	W.S. Elev	Crit W.S.	E.G. Elev	E.G. Slope	Vel Chnl	Flow Area	Top Width	Froude # Chl
			(cfs)	(ft)	(ft)	(ft)	(ft)	(ft/ft)	(ft/s)	(sq ft)	(ft)	
Sloan Channel	225	Post-Project	2870.00	1724.16	1727.63	1728.30	1730.39	0.004207	13.33	215.29	70.23	1.34
Sloan Channel	225	PF 2	3300.00	1724.16	1727.91	1728.68	1730.96	0.004207	14.01	235.50	71.15	1.36
Sloan Channel	220	Post-Project	2870.00	1722.89	1726.35	1727.06	1729.21	0.004319	13.57	211.55	68.15	1.36
Sloan Channel	220	PF 2	3300.00	1722.89	1726.65	1727.44	1729.79	0.004283	14.23	231.88	68.92	1.37
Sloan Channel	215	Post-Project	2870.00	1722.26	1727.45	1726.44	1728.61	0.001060	8.65	331.87	72.11	0.71
Sloan Channel	215	PF 2	3300.00	1722.26	1727.92	1726.82	1729.18	0.001037	9.01	366.08	73.27	0.71
Sloan Channel	213	Post-Project	2870.00	1722.01	1727.59		1728.48	0.000739	7.55	379.91	77.53	0.60
Sloan Channel	213	PF 2	3300.00	1722.01	1728.08		1729.05	0.000732	7.90	417.75	78.94	0.61
Sloan Channel	212	Post-Project	2870.00	1722.00	1727.60	1726.05	1728.48	0.000734	7.54	380.85	77.57	0.60
Sloan Channel	212	PF 2	3300.00	1722.00	1728.08	1726.42	1729.05	0.000727	7.88	418.70	78.97	0.60
Sloan Channel	211.5		Bridge									
Sloan Channel	211	Post-Project	2870.00	1721.50	1725.15	1725.67	1727.68	0.003527	12.75	225.10	68.08	1.24
Sloan Channel	211	PF 2	3300.00	1721.50	1725.49	1726.04	1728.24	0.003444	13.31	247.97	68.87	1.24
Sloan Channel	210.5	Post-Project	2870.00	1720.36	1723.17	1724.42	1727.34	0.008159	16.39	175.14	68.99	1.81
Sloan Channel	210.5	PF 2	3300.00	1720.36	1723.46	1724.80	1727.89	0.007637	16.89	195.34	69.78	1.78
Sloan Channel	210	Post-Project	2870.00	1720.22	1723.79	1724.40	1726.29	0.004195	12.69	226.17	80.10	1.33
Sloan Channel	210	PF 2	3300.00	1720.22	1724.00	1724.74	1726.87	0.004456	13.60	242.60	80.91	1.38
Sloan Channel	200	Post-Project	2870.00	1719.24	1722.32	1723.42	1725.98	0.007627	15.35	186.96	78.11	1.75
Sloan Channel	200	PF 2	3300.00	1719.24	1722.56	1723.76	1726.55	0.007471	16.05	205.66	79.07	1.75
Sloan Channel	198.571*	Post-Project	2870.00	1719.04	1722.27	1723.22	1725.51	0.006322	14.46	198.44	78.70	1.61
Sloan Channel	198.571*	PF 2	3300.00	1719.04	1722.50	1723.56	1726.10	0.006336	15.22	216.76	79.62	1.63
Sloan Channel	197.142*	Post-Project	2870.00	1718.84	1722.20	1723.02	1725.13	0.005395	13.75	208.71	79.22	1.49
Sloan Channel	197.142*	PF 2	3300.00	1718.84	1722.42	1723.36	1725.71	0.005504	14.55	226.73	80.12	1.52
Sloan Channel	195.714*	Post-Project	2870.00	1718.64	1722.10	1722.82	1724.81	0.004758	13.21	217.26	79.65	1.41
Sloan Channel	195.714*	PF 2	3300.00	1718.64	1722.33	1723.16	1725.38	0.004906	14.03	235.23	80.55	1.45
Sloan Channel	194.285*	Post-Project	2870.00	1718.44	1721.98	1722.62	1724.54	0.004357	12.84	223.45	79.96	1.35
Sloan Channel	194.285*	PF 2	3300.00	1718.44	1722.21	1722.96	1725.10	0.004500	13.64	241.85	80.87	1.39
Sloan Channel	192.857*	Post-Project	2870.00	1718.24	1721.81	1722.42	1724.32	0.004210	12.70	225.91	80.08	1.33
Sloan Channel	192.857*	PF 2	3300.00	1718.24	1722.05	1722.76	1724.87	0.004324	13.47	244.95	81.03	1.37
Sloan Channel	191.428*	Post-Project	2870.00	1718.04	1721.62	1722.22	1724.11	0.004169	12.66	226.63	80.12	1.33
Sloan Channel	191.428*	PF 2	3300.00	1718.04	1721.88	1722.56	1724.64	0.004204	13.35	247.17	81.14	1.35
Sloan Channel	190	Post-Project	2870.00	1717.84	1721.42	1722.02	1723.91	0.004169	12.66	226.63	80.12	1.33
Sloan Channel	190	PF 2	3300.00	1717.84	1721.67	1722.36	1724.44	0.004205	13.35	247.17	81.14	1.35
Sloan Channel	188.*	Post-Project	2870.00	1717.66	1721.24	1721.84	1723.73	0.004169	12.66	226.63	80.12	1.33
Sloan Channel	188.*	PF 2	3300.00	1717.66	1721.50	1722.20	1724.26	0.004204	13.35	247.17	81.14	1.35
Sloan Channel	186.*	Post-Project	2870.00	1717.48	1721.06	1721.67	1723.55	0.004169	12.66	226.63	80.12	1.33
Sloan Channel	186.*	PF 2	3300.00	1717.48	1721.31	1722.02	1724.08	0.004205	13.35	247.17	81.14	1.35
Sloan Channel	184.*	Post-Project	2870.00	1717.30	1720.88	1721.49	1723.37	0.004169	12.66	226.63	80.12	1.33
Sloan Channel	184.*	PF 2	3300.00	1717.30	1721.14	1721.84	1723.90	0.004204	13.35	247.17	81.14	1.35
Sloan Channel	182.*	Post-Project	2870.00	1717.12	1720.70	1721.31	1723.19	0.004169	12.66	226.63	80.12	1.33
Sloan Channel	182.*	PF 2	3300.00	1717.12	1720.95	1721.66	1723.72	0.004205	13.35	247.17	81.14	1.35
Sloan Channel	180	Post-Project	2870.00	1716.94	1720.52	1721.13	1723.01	0.004169	12.66	226.63	80.12	1.33
Sloan Channel	180	PF 2	3300.00	1716.94	1720.77	1721.47	1723.54	0.004205	13.35	247.17	81.14	1.35
Sloan Channel	170	Post-Project	2870.00	1716.04	1719.81	1720.50	1722.56	0.004262	13.32	215.41	71.47	1.35
Sloan Channel	170	PF 2	3300.00	1716.04	1720.12	1720.87	1723.10	0.004141	13.86	238.08	72.72	1.35
Sloan Channel	160	Post-Project	2870.00	1715.84	1719.65	1720.30	1722.33	0.004098	13.16	218.16	71.62	1.33
Sloan Channel	160	PF 2	3300.00	1715.84	1719.95	1720.67	1722.88	0.004033	13.74	240.13	72.84	1.33
Sloan Channel	158.333*	Post-Project	2870.00	1715.56	1719.41	1720.02	1722.02	0.003507	12.96	221.52	71.81	1.30
Sloan Channel	158.333*	PF 2	3300.00	1715.56	1719.71	1720.39	1722.57	0.003891	13.59	242.91	72.99	1.31
Sloan Channel	156.666*	Post-Project	2870.00	1715.28	1719.15	1719.74	1721.73	0.003856	12.90	222.46	71.88	1.29
Sloan Channel	156.666*	PF 2	3300.00	1715.28	1719.44	1720.11	1722.29	0.003849	13.54	243.76	73.05	1.31
Sloan Channel	155.*	Post-Project	2870.00	1715.00	1718.87	1719.46	1721.45	0.003856	12.90	222.44	71.87	1.29
Sloan Channel	155.*	PF 2	3300.00	1715.00	1719.16	1719.83	1722.01	0.003849	13.54	243.74	73.05	1.31


HEC-RAS Plan: Plan 03 River: Range Wash Reach: Sloan Channel (Continued)


Reach	River Sta	Profile	Q Total	Min Ch El	W.S. Elev	Crit W.S.	E.G. Elev	E.G. Slope	Vel Chnl	Flow Area	Top Width	Froude # Chl
			(cfs)	(ft)	(ft)	(ft)	(ft)	(ft/ft)	(ft/s)	(sq ft)	(ft)	
Sloan Channel	153.333*	Post-Project	2870.00	1714.72	1718.59	1719.18	1721.17	0.003854	12.90	222.49	71.87	1.29
Sloan Channel	153.333*	PF 2	3300.00	1714.72	1718.88	1719.55	1721.73	0.003847	13.54	243.79	73.05	1.31
Sloan Channel	151.666*	Post-Project	2870.00	1714.44	1718.31	1718.90	1720.89	0.003847	12.89	222.64	71.88	1.29
Sloan Channel	151.666*	PF 2	3300.00	1714.44	1718.60	1719.27	1721.44	0.003841	13.53	243.94	73.05	1.30
Sloan Channel	150	Post-Project	2870.00	1714.16	1718.03	1718.62	1720.61	0.003843	12.88	222.76	71.88	1.29
Sloan Channel	150	PF 2	3300.00	1714.16	1718.32	1718.99	1721.16	0.003837	13.52	244.06	73.05	1.30
Sloan Channel	149.285*	Post-Project	2870.00	1713.42	1717.30	1717.87	1719.86	0.003802	12.84	223.51	71.91	1.28
Sloan Channel	149.285*	PF 2	3300.00	1713.42	1717.59	1718.25	1720.41	0.003803	13.48	244.75	73.08	1.30
Sloan Channel	148.571*	Post-Project	2870.00	1712.67	1716.56	1717.13	1719.11	0.003792	12.83	223.68	71.93	1.28
Sloan Channel	148.571*	PF 2	3300.00	1712.67	1716.85	1717.52	1719.67	0.003794	13.47	244.93	73.10	1.30
Sloan Channel	147.857*	Post-Project	2870.00	1711.93	1715.82	1716.39	1718.37	0.003785	12.82	223.82	71.95	1.28
Sloan Channel	147.857*	PF 2	3300.00	1711.93	1716.11	1716.78	1718.92	0.003787	13.47	245.07	73.12	1.30
Sloan Channel	147.142*	Post-Project	2870.00	1711.19	1715.08	1715.65	1717.63	0.003786	12.82	223.80	71.95	1.28
Sloan Channel	147.142*	PF 2	3300.00	1711.19	1715.37	1716.04	1718.18	0.003787	13.47	245.05	73.12	1.30
Sloan Channel	146.428*	Post-Project	2870.00	1710.45	1714.34	1714.91	1716.89	0.003780	12.82	223.89	71.95	1.28
Sloan Channel	146.428*	PF 2	3300.00	1710.45	1714.63	1715.30	1717.44	0.003782	13.46	245.14	73.12	1.30
Sloan Channel	145.714*	Post-Project	2870.00	1709.70	1713.59	1714.16	1716.14	0.003769	12.81	224.09	71.96	1.28
Sloan Channel	145.714*	PF 2	3300.00	1709.70	1713.89	1714.55	1716.69	0.003773	13.45	245.32	73.13	1.29
Sloan Channel	145.*	Post-Project	2870.00	1708.96	1712.85	1713.42	1715.40	0.003769	12.81	224.10	71.96	1.28
Sloan Channel	145.*	PF 2	3300.00	1708.96	1713.15	1713.81	1715.95	0.003773	13.45	245.33	73.13	1.29
Sloan Channel	144.285*	Post-Project	2870.00	1708.22	1712.11	1712.68	1714.65	0.003759	12.80	224.29	71.97	1.28
Sloan Channel	144.285*	PF 2	3300.00	1708.22	1712.41	1713.07	1715.21	0.003764	13.44	245.52	73.14	1.29
Sloan Channel	143.571*	Post-Project	2870.00	1707.47	1711.36	1711.93	1713.91	0.003792	12.83	223.66	71.93	1.28
Sloan Channel	143.571*	PF 2	3300.00	1707.47	1711.65	1712.32	1714.47	0.003789	13.47	244.99	73.11	1.30
Sloan Channel	142.857*	Post-Project	2870.00	1706.73	1710.62	1711.19	1713.17	0.003790	12.83	223.71	71.94	1.28
Sloan Channel	142.857*	PF 2	3300.00	1706.73	1710.91	1711.58	1713.73	0.003788	13.47	245.03	73.12	1.30
Sloan Channel	142.142*	Post-Project	2870.00	1705.99	1709.88	1710.45	1712.43	0.003779	12.82	223.92	71.95	1.28
Sloan Channel	142.142*	PF 2	3300.00	1705.99	1710.17	1710.84	1712.98	0.003778	13.46	245.25	73.13	1.29
Sloan Channel	141.428*	Post-Project	2870.00	1705.25	1709.14	1709.71	1711.69	0.003775	12.81	224.03	71.97	1.28
Sloan Channel	141.428*	PF 2	3300.00	1705.25	1709.43	1710.10	1712.24	0.003774	13.45	245.37	73.14	1.29
Sloan Channel	140.714*	Post-Project	2870.00	1704.50	1708.39	1708.97	1710.94	0.003758	12.79	224.36	71.97	1.28
Sloan Channel	140.714*	PF 2	3300.00	1704.50	1708.69	1709.35	1711.49	0.003758	13.43	245.71	73.15	1.29
Sloan Channel	140	Post-Project	2870.00	1703.76	1709.34	1708.23	1710.37	0.000962	8.17	351.20	78.70	0.68
Sloan Channel	140	PF 2	3300.00	1703.76	1707.95	1708.61	1710.75	0.003750	13.42	245.91	73.15	1.29
Sloan Channel	130	Post-Project	2870.00	1703.57	1709.35		1710.30	0.000838	7.81	367.67	79.53	0.64
Sloan Channel	130	PF 2	3300.00	1703.57	1707.76	1708.42	1710.55	0.003742	13.41	246.08	73.16	1.29
Sloan Channel	120	Post-Project	2870.00	1703.09	1709.39		1710.15	0.000609	7.02	409.02	81.59	0.55
Sloan Channel	120	PF 2	3300.00	1703.09	1707.28	1707.93	1710.07	0.003742	13.41	246.08	73.16	1.29
Sloan Channel	110	Post-Project	2870.00	1702.90	1709.41		1710.10	0.000502	6.65	431.89	72.50	0.48
Sloan Channel	110	PF 2	3300.00	1702.90	1706.64	1707.46	1709.81	0.004888	14.30	230.83	72.50	1.41
Sloan Channel	100	Post-Project	3891.00	1702.52	1708.36		1709.93	0.001301	10.04	387.42	72.50	0.77
Sloan Channel	100	PF 2	3300.00	1702.52	1706.29	1707.01	1709.30	0.004490	13.92	237.09	72.50	1.36
Sloan Channel	90	Post-Project	3891.00	1702.14	1708.82		1709.62	0.000559	7.17	542.38	90.50	0.52
Sloan Channel	90	PF 2	3300.00	1702.14	1708.22	1706.28	1708.93	0.000561	6.75	488.54	90.50	0.51
Sloan Channel	80	Post-Project	3891.00	1701.95	1707.28	1707.28	1709.43	0.002097	11.76	330.74	77.00	1.00
Sloan Channel	80	PF 2	3300.00	1701.95	1706.80	1706.80	1708.76	0.002154	11.22	294.08	75.15	1.00
Sloan Channel	78.8888*	Post-Project	3891.00	1701.47	1706.17	1706.80	1709.11	0.003390	13.78	282.42	74.62	1.25
Sloan Channel	78.8888*	PF 2	3300.00	1701.47	1705.72	1706.32	1708.43	0.003543	13.20	249.92	72.92	1.26
Sloan Channel	77.7777*	Post-Project	3891.00	1700.99	1705.51	1706.32	1708.75	0.003919	14.44	269.37	74.00	1.33
Sloan Channel	77.7777*	PF 2	3300.00	1700.99	1705.09	1705.84	1708.05	0.004071	13.81	238.94	72.39	1.34
Sloan Channel	76.6666*	Post-Project	3891.00	1700.51	1704.93	1705.84	1708.35	0.004263	14.84	262.14	73.67	1.39
Sloan Channel	76.6666*	PF 2	3300.00	1700.51	1704.52	1705.36	1707.65	0.004421	14.18	232.68	72.10	1.39


HEC-RAS Plan: Plan 03 River: Range Wash Reach: Sloan Channel (Continued)


Reach	River Sta	Profile	Q Total	Min Ch El	W.S. Elev	Crit W.S.	E.G. Elev	E.G. Slope	Vel Chnl	Flow Area	Top Width	Froude # Chl
			(cfs)	(ft)	(ft)	(ft)	(ft)	(ft/ft)	(ft/s)	(sq ft)	(ft)	
Sloan Channel	75.5555*	Post-Project	3891.00	1700.03	1704.38	1705.36	1707.94	0.004526	15.13	257.14	73.46	1.43
Sloan Channel	75.5555*	PF 2	3300.00	1700.03	1703.99	1704.88	1707.22	0.004668	14.43	228.65	71.93	1.43
Sloan Channel	74.4444*	Post-Project	3891.00	1699.56	1703.86	1704.89	1707.51	0.004705	15.32	253.99	73.37	1.45
Sloan Channel	74.4444*	PF 2	3300.00	1699.56	1703.49	1704.41	1706.78	0.004800	14.56	226.68	71.90	1.44
Sloan Channel	73.3333*	Post-Project	3891.00	1699.08	1703.35	1704.41	1707.06	0.004837	15.45	251.78	73.31	1.47
Sloan Channel	73.3333*	PF 2	3300.00	1699.08	1702.98	1703.93	1706.33	0.004929	14.68	224.80	71.84	1.46
Sloan Channel	72.2222*	Post-Project	3891.00	1698.60	1702.85	1703.93	1706.61	0.004948	15.56	250.00	73.27	1.48
Sloan Channel	72.2222*	PF 2	3300.00	1698.60	1702.48	1703.45	1705.87	0.005027	14.77	223.42	71.82	1.48
Sloan Channel	71.1111*	Post-Project	3891.00	1698.12	1702.35	1703.45	1706.15	0.005031	15.64	248.71	73.25	1.50
Sloan Channel	71.1111*	PF 2	3300.00	1698.12	1701.99	1702.96	1705.40	0.005098	14.83	222.47	71.81	1.49
Sloan Channel	70	Post-Project	3891.00	1697.64	1701.85	1702.97	1705.68	0.005095	15.71	247.75	73.25	1.50
Sloan Channel	70	PF 2	3300.00	1697.64	1701.50	1702.47	1704.93	0.005150	14.88	221.78	71.82	1.49
Sloan Channel	60	Post-Project	3891.00	1697.38	1701.58	1702.71	1705.44	0.005167	15.78	246.64	73.21	1.51
Sloan Channel	60	PF 2	3300.00	1697.38	1701.22	1702.21	1704.69	0.005223	14.95	220.79	71.78	1.50
Sloan Channel	50		Bridge									
Sloan Channel	40	Post-Project	3891.00	1697.09	1702.03	1702.41	1704.61	0.002778	12.87	302.33	76.17	1.14
Sloan Channel	40	PF 2	3300.00	1697.09	1701.58	1701.93	1703.93	0.002866	12.29	268.49	74.38	1.14
Sloan Channel	30	Post-Project	3990.00	1696.56	1701.71	1702.01	1704.30	0.002590	12.91	308.96	72.76	1.10
Sloan Channel	30	PF 2	3300.00	1696.56	1701.00	1701.43	1703.53	0.003066	12.76	258.53	70.65	1.18
Sloan Channel	28.5714*	Post-Project	3990.00	1695.73	1700.40	1701.17	1703.68	0.003711	14.52	274.83	71.34	1.30
Sloan Channel	28.5714*	PF 2	3300.00	1695.73	1699.88	1700.60	1702.87	0.003961	13.87	238.00	69.77	1.32
Sloan Channel	27.1428*	Post-Project	3990.00	1694.90	1699.45	1700.34	1702.95	0.004118	15.02	265.71	70.95	1.37
Sloan Channel	27.1428*	PF 2	3300.00	1694.90	1698.97	1699.77	1702.11	0.004286	14.22	232.05	69.51	1.37
Sloan Channel	25.7142*	Post-Project	3990.00	1694.07	1698.55	1699.51	1702.18	0.004345	15.28	261.14	70.76	1.40
Sloan Channel	25.7142*	PF 2	3300.00	1694.07	1698.09	1698.94	1701.32	0.004467	14.41	228.97	69.38	1.40
Sloan Channel	24.2857*	Post-Project	3990.00	1693.25	1697.71	1698.69	1701.38	0.004440	15.39	259.32	70.68	1.42
Sloan Channel	24.2857*	PF 2	3300.00	1693.25	1697.26	1698.12	1700.51	0.004519	14.47	228.12	69.34	1.41
Sloan Channel	22.8571*	Post-Project	3990.00	1692.42	1696.85	1697.86	1700.57	0.004521	15.48	257.80	70.62	1.43
Sloan Channel	22.8571*	PF 2	3300.00	1692.42	1696.42	1697.29	1699.69	0.004573	14.52	227.25	69.31	1.41
Sloan Channel	21.4285*	Post-Project	3990.00	1691.59	1696.01	1697.03	1699.76	0.004568	15.53	256.95	70.58	1.43
Sloan Channel	21.4285*	PF 2	3300.00	1691.59	1695.59	1696.46	1698.86	0.004583	14.53	227.10	69.30	1.41
Sloan Channel	20	Post-Project	3990.00	1690.76	1695.18	1696.20	1698.93	0.004577	15.54	256.78	70.57	1.44
Sloan Channel	20	PF 2	3300.00	1690.76	1694.75	1695.63	1698.04	0.004587	14.54	227.03	69.30	1.42
Sloan Channel	10	Post-Project	3990.00	1689.50	1693.00		1697.63	0.006656	17.27	231.00	72.00	1.70
Sloan Channel	10	PF 2	3300.00	1689.50	1692.72	1693.85	1696.52	0.006035	15.64	210.99	71.04	1.60



sloanr Plan: Plan 03 11/19/2006
plan station 112+09 (FIS station 101+49)
.015
Elevation (ft)
1731
1730
1729
1728
1727
1726
1725
1724
0
20
40
60
80
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
plan station 114+87 u/s of Charleston Bridge (FIS 104+23)
.015
Elevation (ft)
1732
1730
1728
1726
1724
1722
0
20
40
60
80
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta



sloanr Plan: Plan 03 11/19/2006
Plan Station 116+40 u/s of Charleston Bridge (FIS 105+74)
.015
Elevation (ft)
1732
1730
1728
1726
1724
1722
0
20
40
60
80
Station (ft)
Legend
EG PF 2
EG Post-Project
WS PF 2
WS Post-Project
Crit PF 2
Crit Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
plan station 116+90 u/s of Charleston Bridge (FIS 106+23)
.015
Elevation (ft)
1732
1730
1728
1726
1724
1722
0
20
40
60
80
100
Station (ft)
Legend
EG PF 2
EG Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006
plan station 116+91 u/s of Charleston Bridge (FIS 106+24)
.015
1732
1730
1728
1726
1724
1722
Elevation (ft)
0
20
40
60
80
100
Station (ft)
Legend
EG PF 2
EG Post-Project
WS PF 2
WS Post-Project
Crit PF 2
Crit Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
Charleston Bridge
.015
1732
1730
1728
1726
1724
1722
Elevation (ft)
0
20
40
60
80
100
Station (ft)
Legend
EG PF 2
EG Post-Project
WS PF 2
WS Post-Project
Crit PF 2
Crit Post-Project
Ground
Bank Sta



sloanr Plan: Plan 03 11/19/2006
Charleston Bridge
.015
1732
1730
1728
1726
1724
1722
1720
Elevation (ft)
0
20
40
60
80
Station (ft)
Legend
EG PF 2
EG Post-Project
WS PF 2
Crit PF 2
WS Post-Project
Crit Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
plan station 117+90 d/s of Charleston Bridge (FIS 107+24)
.015
1732
1730
1728
1726
1724
1722
1720
Elevation (ft)
0
20
40
60
80
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006
plan station 117+92 d/s of Charleston Bridge (FIS 107+25)
.015
Elevation (ft)
1730
1728
1726
1724
1722
1720
0
20
40
60
80
100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
PLAN STA 118+89
.015
Elevation (ft)
1728
1727
1726
1725
1724
1723
1722
1721
1720
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta



sloanr Plan: Plan 03 11/19/2006
PLAN STA 119+25
.015
Elevation (ft)
1727
1726
1725
1724
1723
1722
1721
1720
1719
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
.015
Elevation (ft)
1727
1726
1725
1724
1723
1722
1721
1720
1719
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006
.015
1726
1725
1724
1723
1722
1721
1720
1719
1718
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
.015
1726
1725
1724
1723
1722
1721
1720
1719
1718
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006



sloanr Plan: Plan 03 11/19/2006





sloanr Plan: Plan 03 11/19/2006




sloanr Plan: Plan 03 11/19/2006

PLAN STA 122+74






sloanr Plan: Plan 03 11/19/2006
.015
Elevation (ft)
1725
1724
1723
1722
1721
1720
1719
1718
1717
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
.015
Elevation (ft)
1725
1724
1723
1722
1721
1720
1719
1718
1717
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006




sloanr Plan: Plan 03 11/19/2006





sloanr Plan: Plan 03 11/19/2006
PLAN STA 125+00
.015
Elevation (ft)
1724
1723
1722
1721
1720
1719
1718
1717
1716
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
PLAN STA 126+00
.015
Elevation (ft)
1724
1723
1722
1721
1720
1719
1718
1717
1716
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006
PLAN STA 126+52
.015
Elevation (ft)
1723
1722
1721
1720
1719
1718
1717
1716
1715
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
.015
Elevation (ft)
1723
1722
1721
1720
1719
1718
1717
1716
1715
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006




sloanr Plan: Plan 03 11/19/2006





sloanr Plan: Plan 03 11/19/2006




sloanr Plan: Plan 03 11/19/2006





sloanr Plan: Plan 03 11/19/2006
PLAN STA 130+97
.015
Elevation (ft)
Station (ft)
1722
1721
1720
1719
1718
1717
1716
1715
1714
1000
1020
1040
1060
1080
1100
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
.015
Elevation (ft)
Station (ft)
1721
1720
1719
1718
1717
1716
1715
1714
1713
1000
1020
1040
1060
1080
1100
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta



sloanr Plan: Plan 03 11/19/2006
.015
Elevation (ft)
1720
1719
1718
1717
1716
1715
1714
1713
1712
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
.015
Elevation (ft)
1719
1718
1717
1716
1715
1714
1713
1712
1711
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta

sloanr Plan: Plan 03 11/19/2006




sloanr Plan: Plan 03 11/19/2006






sloanr Plan: Plan 03 11/19/2006
.015
1717
1716
1715
1714
1713
1712
1711
1710
1709
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
.015
1716
1715
1714
1713
1712
1711
1710
1709
1708
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta

sloanr Plan: Plan 03 11/19/2006




sloanr Plan: Plan 03 11/19/2006






sloanr Plan: Plan 03 11/19/2006
.015
1714
1713
1712
1711
1710
1709
1708
1707
1706
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
.015
1713
1712
1711
1710
1709
1708
1707
1706
1705
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
WS Post-Project
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006





sloanr Plan: Plan 03 11/19/2006





sloanr Plan: Plan 03 11/19/2006
PLAN STA 158+50
.015
Elevation (ft)
1711
1710
1709
1708
1707
1706
1705
1704
1703
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
WS Post-Project
Crit PF 2
Crit Post-Project
WS PF 2
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
PLAN STA 159+00
.015
Elevation (ft)
1711
1710
1709
1708
1707
1706
1705
1704
1703
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG PF 2
EG Post-Project
WS Post-Project
Crit PF 2
WS PF 2
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006
PLAN STA 160+29
.015
Elevation (ft)
1712
1710
1708
1706
1704
1702
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
WS Post-Project
Crit PF 2
WS PF 2
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
PLAN STA 160+79
.015
Elevation (ft)
1714
1712
1710
1708
1706
1704
1702
1000
1010
1020
1030
1040
1050
1060
1070
1080
Station (ft)
Legend
EG Post-Project
EG PF 2
WS Post-Project
Crit PF 2
WS PF 2
Ground
Bank Sta



sloanr Plan: Plan 03 11/19/2006
PLAN STA 161+79
.015
Elevation (ft)
1714
1712
1710
1708
1706
1704
1702
1000
1010
1020
1030
1040
1050
1060
1070
1080
Station (ft)
Legend
EG Post-Project
EG PF 2
WS Post-Project
Crit PF 2
WS PF 2
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
PLAN STA 162+79
.015
Elevation (ft)
1714
1712
1710
1708
1706
1704
1702
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
WS Post-Project
WS PF 2
Crit PF 2
Ground
Bank Sta



sloanr Plan: Plan 03 11/19/2006
PLAN STA 163+29
.015
Elevation (ft)
Station (ft)
1710
1709
1708
1707
1706
1705
1704
1703
1702
1701
1000
1020
1040
1060
1080
1100
Legend
EG Post-Project
EG PF 2
Crit Post-Project
WS Post-Project
WS PF 2
Crit PF 2
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
.015
Elevation (ft)
Station (ft)
1710
1708
1706
1704
1702
1700
1000
1020
1040
1060
1080
1100
Legend
EG Post-Project
EG PF 2
Crit Post-Project
Crit PF 2
WS Post-Project
WS PF 2
Ground
Bank Sta

sloanr Plan: Plan 03 11/19/2006




sloanr Plan: Plan 03 11/19/2006






sloanr Plan: Plan 03 11/19/2006
.015
1708
1706
1704
1702
1700
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit Post-Project
Crit PF 2
WS Post-Project
WS PF 2
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
.015
1708
1706
1704
1702
1700
1698
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit Post-Project
Crit PF 2
WS Post-Project
WS PF 2
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006





sloanr Plan: Plan 03 11/19/2006





sloanr Plan: Plan 03 11/19/2006
.015
1708
1706
1704
1702
1700
1698
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit Post-Project
Crit PF 2
WS Post-Project
WS PF 2
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
PLAN STA 171+50
.015
1706
1704
1702
1700
1698
1696
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit Post-Project
Crit PF 2
WS Post-Project
WS PF 2
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006
PLAN STA 171+96
.015
Elevation (ft)
1712
1710
1708
1706
1704
1702
1700
1698
1696
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit Post-Project
Crit PF 2
WS Post-Project
WS PF 2
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
PLAN STA 171+99
.015
Elevation (ft)
1712
1710
1708
1706
1704
1702
1700
1698
1696
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit Post-Project
WS Post-Project
WS PF 2
Crit PF 2
Ground
Bank Sta



sloanr Plan: Plan 03 11/19/2006
PLAN STA 171+99
.015
1712
1710
1708
1706
1704
1702
1700
1698
1696
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit Post-Project
WS Post-Project
WS PF 2
Crit PF 2
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
PLAN STA 172+86
.015
1712
1710
1708
1706
1704
1702
1700
1698
1696
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit Post-Project
WS Post-Project
Crit PF 2
WS PF 2
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006
PLAN STA 174+00
.015
1706
1704
1702
1700
1698
1696
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit Post-Project
WS Post-Project
Crit PF 2
WS PF 2
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
.015
1704
1702
1700
1698
1696
1694
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit Post-Project
Crit PF 2
WS Post-Project
WS PF 2
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006




sloanr Plan: Plan 03 11/19/2006





sloanr Plan: Plan 03 11/19/2006



sloanr Plan: Plan 03 11/19/2006




sloanr Plan: Plan 03 11/19/2006
.015
1700
1698
1696
1694
1692
1690
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit Post-Project
Crit PF 2
WS Post-Project
WS PF 2
Ground
Bank Sta
sloanr Plan: Plan 03 11/19/2006
PLAN STA 186+54
.015
1700
1698
1696
1694
1692
1690
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit Post-Project
Crit PF 2
WS Post-Project
WS PF 2
Ground
Bank Sta


sloanr Plan: Plan 03 11/19/2006
PLAN STA 189+14
.015
1700
1698
1696
1694
1692
1690
1688
Elevation (ft)
1000
1020
1040
1060
1080
1100
Station (ft)
Legend
EG Post-Project
EG PF 2
Crit PF 2
WS Post-Project
WS PF 2
Ground
Bank Sta

Range Wash FIS Reference Material

HEC-2 Data

TECHNICAL SUPPORT DATA NOTEBOOK

for

CLARK COUNTY, NEVADA AND INCORPORATED AREAS
INCLUDING:
CITY OF NORTH LAS VEGAS
AND
UNINCORPORATED AREAS OF CLARK COUNTY

RANGE WASH
FLOOD INSURANCE STUDY RESTUDY

VOLUME 5

SECTION 5 REFERENCE MATERIALS
Sloan Channel & Developer Improvements
Documentation

Submitted by:	Clark County Regional Flood Control District
Study Contractor:	Post, Buckley, Schuh & Jernigan, Inc.
Date Submitted:	February 27, 1996

TABLE OF CONTENTS

VOLUME 5

SECTION 5 MISCELLANEOUS REFERENCE MATERIALS

5.5	Sloan Channel & Developer Improvements Documentation
5.5.1	Predesign Report Sloan Channel Owens Anvenue to Las Vegas Wash
5.5.2	Cibola Drainage Study
5.5.3	Cibola (Magnolia Estates) Grading Plans
5.5.4	Collins Business Park Hydrology Study

5.5 Sloan Channel & Developer Improvements Documentation

5.5.1 Predesign Report Sloan Channel Owens Avenue to Las Vegas Wash

DRAFT
PREDESIGN MEMORANDUM
SLOAN CHANNEL - OWENS AVENUE TO THE LAS VEGAS WASH

May 1993

Prepared for:

Clark County Public Works
6655 West Sahara Avenue
Las Vegas, Nevada 89102

Prepared by:

G. C. Wallace, Inc.
1555 South Rainbow Boulevard
Las Vegas, Nevada 89102

I. INTRODUCTION

The Sloan Channel improvements from Owens Avenue to the Las Vegas Wash confluence is part of the current Clark County Regional Flood Control District (CCRFCD) Master Plan Update of the Las Vegas Valley. This facility is intended to convey storm flows from the Range Wash drainage basin to the Las Vegas Wash. Other CCRFCD Master Plan facilities will eventually limit the 100-year return period flow in the Sloan Channel to 3,300 cfs. The location of the project is shown on Figure 1.


The Sloan Channel from Owens Avenue south to the Las Vegas Wash is currently an excavated, earthlined channel with an approximate bottom width of 60 feet and side slopes of roughly 2:1 (H:V). The Sloan Channel is crossed by five existing roadways in the project area. Bridges are present over the Sloan Channel at Washington Avenue and Charleston Boulevard. Reinforced Concrete Box (RCB) culvert crossings are present at Owens Avenue, Bonanza Road, and Stewart Avenue (see Figure 2). The length of this project is approximately 17,590 feet (3.3 miles).


Improvement drawings for this reach of Sloan Channel were previously prepared by Boyle Engineering Corporation (Boyle) in 1986. However, the project was not constructed. Boyle's design for the Sloan Channel proposed a trapezoidal, concrete-lined channel with side slopes varying from 1.5:1 (H:V) to 2:1 (H:V), and a bottom width varying from 60 feet to 70 feet.


II. SCOPE

The purpose and scope of this Predesign Memorandum is to :

- Present the results of an update to a previous geotechnical investigation and field reconnaissance to document surficial soils and subsurface conditions along the channel alignment.


PROJECT LIMITS
NORTH
SCALE: 1" = 2000'
SLOAN CHANNEL
- OWENS AVENUE TO
THE LAS VEGAS WASH
FIGURE 1
VICINITY MAP
G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89102


Charleston Boulevard
3-Span Bridge
Bonanza Road
5-10'x 5' RCB
Owens Avenue
3-9'x 5' RCB
3-7'x 5' RCB
Stewart Avenue
8-10'x 3.5' RCB
Washington Avenue
3-Span Bridge
NORTH
SLOAN CHANNEL
- OWENS AVENUE TO
THE LAS VEGAS WASH
FIGURE 2
EXISTING STRUCTURES
G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89102


PROJECT LIMIT
NORTH
SCALE: 1" = 2000'
1 DESIGN POINT
SLOAN CHANNEL
- OWENS AVENUE TO
THE LAS VEGAS WASH
FIGURE 3
LOCAL INFLOWS
G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89102

- Present the results of a hydraulic analysis of the Boyle design using design flows of 3,300 cfs with freeboard as required in the CCRFCD Hydrologic Criteria and Drainage Design Manual (Manual), and 6,000 cfs without freeboard.

  The design flow of 3,300 cfs is the ultimate flow that will be conveyed in the Sloan Channel when the Confluence Detention Basin has been constructed. The Confluence Detention Basin is a CCRFCD Master Plan facility that is to be located just south of Nellis Air Force Base. This detention facility will detain flows from the eastern and western tributaries of the Range Wash watershed. This facility is presently under design.

  The design flow of 6,000 cfs is an interim flow for the Sloan Channel prior to the construction of the Confluence Detention Basin. This design flow is based on existing diversion facilities within the upper portions of the western tributary of the Range Wash being place.

- Provide a review and evaluation of the 1986 Boyle design for the Sloan Channel from Owens Avenue to the Las Vegas Wash using current design as criteria as set forth in the CCRFCD Manual.

- Present a hydrologic analysis of the watershed which contributes storm runoff directly to this reach of the Sloan Channel. The hydrologic analysis will identify points of local inflow into the Sloan Channel within the project limits and quantify the flows at these points.

- Provide recommendations for the following:

  - the adequacy of the previous design to convey the design flows of 3,300 cfs with freeboard and 6,000 cfs without freeboard;

- mitigation measures to protect the channel improvements from local inflows;
- the adequacy of the previous design to meet current design standards;
- the need for additional Special Services as described in Section 2.03 of the Professional Engineering Services Contract for this project.

III. SUMMARY OF UPDATED GEOTECHNICAL INVESTIGATION

As part of this predesign memorandum, the geotechnical investigation for this reach of the Sloan Channel was updated. Converse Consultants Southwest, Inc. (Converse) was employed to update their geotechnical investigation which had been prepared for the 1986 Boyle design of this project. The updated geotechnical report is included in this predesign memorandum as Appendix A.

Converse performed three (3) additional exploratory borings as part of the updated soils report. The subsoils encountered in this update and the previous investigation generally consisted of soft to firm silts and clays overlying very stiff clays and silts, and medium dense sands. The laboratory test results yield soils that are compressible, have low to moderate dry densities, low to high degree of solubility, a low to high clay swell potential, low to moderate chemical heave potential, and contain sulfate salts.

Groundwater was encountered in the three borings performed with the update and several locations in the original investigation. It should be noted that the three borings performed with the update were located south of Charleston Boulevard. These boring locations were selected to identify the extents of groundwater in the reach of this project south of Charleston Boulevard in light of the higher than normal precipitation in the year proceeding the preparation of this report.

No additional geotechnical services for design are anticipated at this time.

IV. REVIEW OF PREVIOUS DESIGN

The 1986 Boyle design of the Sloan Channel from Owens Avenue to the Las Vegas Wash was prepared prior to the publication of the CCRFCD Hydrologic Criteria and Drainage Design Manual (Manual). The Manual has established design parameters for concrete lined channels constructed within the Clark County area. The 1986 design for the Sloan Channel was reviewed using the currently accepted CCRFCD criteria and the updated geotechnical report. The following is a summary of the evaluation of the 1986 Boyle design using current criteria.

- Most of the channel lining (approximately 15,990 feet) is shown to have a side slope of greater than 2:1 (H:V). Section 705.7.1.1 b) of the Manual lists a maximum side os slope of 2:1 (H:V) for non-structurally reinforced walls.

- The longitudinal and transverse reinforcement of the channel lining shown on the Boyle design does not meet current criteria as set forth in Section 705.7.1.5 b) of the Manual. The Boyle design calls for #5 bars at 12-inch spacing for longitudinal reinforcement, and #5 bars at 18-inch spacing for transverse reinforcement. This equates to a steel area to concrete cross sectional area ratio of 0.0043 for the longitudinal reinforcement of 0.0028 for the transverse reinforcement. The Manual requires a ratio of longitudinal steel area to concrete cross sectional area greater than 0.005 (but not less than #4 rebar at 12-inch spacing). The transverse steel area to concrete cross section is to be greater than 0.0025 (but not less than #4 rebar at 12-inch spacing). To meet current CCRFCD Design Standards, the minimum longitudinal steel required for the 6-inch lining shown on the Boyle drawings needs to be #6 rebar at 12-inch spacing, and the transverse steel needs to be #4 rebar at 12-inch spacing.

- The 1986 design does not require the top 12-inches of earth surface within 10-feet of the concrete channel lip to be compacted to at least 90 percent of the

maximum density per ASTM 1557 as required in Section 705.7.1.6 d) of the Manual.

- The Boyle design does not include longitudinal or transverse cutoff walls. The Manual requires that transverse cutoff walls shall be constructed at a maximum spacing of 90 feet and shall extend a minimum of 3-feet below the bottom of the concrete lining. Longitudinal cutoff walls along the top of the bank at a minimum depth of 3-feet are also required by the Manual. However; due to the fact that much of the west side of the channel is protected from the surface inflows by existing masonry walls, the longitudinal cutoff wall could be omitted for portions of the west side of the channel.

- Maintenance access per Section 707.2 of the Manual appears to be met. Since the channel top width is greater than 30-feet, the maintenance road can be located in the bottom of the channel. The 1986 design, apparently, utilized this concept.

- Ladder-type steps per Section 707.3 b) of the Manual need to be incorporated into the channel design.

- The updated geotechnical investigation recommends "Concrete panels on the channel sides and bottom be supported by a blanket of granular filter material that is a least 6-inches and 12-inches thick, respectively." The 1986 design shows a 6-inch blanket of Type 2 drain backfill throughout.

Considerations for development which has occurred or is presently ongoing along the Sloan Channel alignment need to be made. Numerous residential developments have been, or are being constructed along the channel alignment. A number of these developments discharge storm flows directly into the Sloan Channel via storm drains and/or surface outlets. Design consideration should be made to incorporate the features constructed after 1986 into overall design of the channel.

The majority of the development which has taken place since the 1986 design was prepared is located south of Charleston Boulevard. Peachtree, a master planned development on the east side of the Sloan Channel, will discharge approximately 1,200 cfs into the Sloan Channel via a concrete lined channel to be located 1,200 feet north of the Sahara Avenue alignment.

Developments on the west side of the Sloan Channel south of Charleston Boulevard, including Sunrise Valley Garden Homes, Sunrise Valley Unit 8, and Stonebridge D2A, also discharge local storm flows into the Sloan Channel via surface inlets.

The access ramp/surface inlet shown at Station 41+21 should be moved. An apartment development adjacent to this location has intercepted and diverted the surface flows which formerly entered the channel at this location. This access ramp/surface inlet could be relocated approximately 250-feet north at the northern boundary of the aforementioned apartment development and provide surface flow access the channel.

An existing wash intersects the Sloan Channel from the west just south of Stewart Avenue. The 1986 design shows this wash being blocked by the construction of the channel improvements. This wash bisects an undeveloped parcel of land. As will be presented in the section of this Predesign Memorandum entitled Hydrology, a considerable amount of storm runoff (580 cfs in a 100-year storm) presently is conveyed to the Sloan Channel across the undeveloped parcel in this wash. The undeveloped parcel does not have improvements on Stewart Avenue to contain local storm flows within the Stewart Avenue right-of-way. Considerations must be given to either containing storm flow along Stewart Avenue, or providing means to safely introduce flows from this wash into the Sloan Channel.

Since the 1986 design for the Sloan Channel was prepared, the CCRFCD Master Plan (October 1986) and the Master Plan Update (August 1991) have been published. The 1991 Master Plan Update identifies existing and proposed drainage

facilities of regional significance for the Las Vegas Valley area. A review of the Master Plan Update shows existing and proposed collector systems from the east tying into the Sloan Channel. The collector system intersect the Sloan Channel at the major roadway crossings within the project area. The 1991 Master Plan Update lists the following collector facilities (see Figures F-11 and F-15 of the Master Plan Update):

Owens Avenue	60-inch RCP
Washington Avenue	90-inch RCP
Bonanza Road	72-inch RCP (existing)
Stewart Avenue	66-inch RCP
Charleston Boulevard	20 ft. W, 6.5 ft. D, rip-rap channel

The existing facilities and the proposed facilities shown on the Boyle Drawings at these locations are as follows:

Owens Avenue	54-inch RCP (proposed)
Washington Avenue	60-inch RCP stub (existing)
Bonanza Road	72-inch RCP (existing)
Stewart Avenue	43" x 68" HE RCP (54" equiv. stub) (existing)
Charleston Boulevard	48" x 91" in HE RCP (72" equiv.) (existing)

All of the existing facilities and proposed facilities shown on the Boyle drawings are located in the downstream transition structures of the RCB culverts or bridges at these locations. Accommodations could be made to update existing facilities that differ from the Master Plan facilities as part of this project. However, the Master Plan is only a guide, and the facilities at these locations may change when detailed drainage studies and designs are prepared.

Utilities

No utility conflicts are anticipated with the construction of this project. GCW preliminary utility research indicates that, with the exception of the future bridge crossing of Sahara Avenue at the Sloan Channel, all existing utilities are located beneath the existing bridge and RCB culvert structures at major roadway crossings. However, we have not received written responses from all of the utility companies at this time.

An inverted sewer siphon is present under the Sloan Channel in the Sahara Avenue alignment. This inverted siphon was designed to accommodate the future improvements to the Sloan Channel and the future RCB culvert at Sahara Avenue. The top of pipe for the siphon is approximately 6-feet below the proposed invert of the channel.

The Clark County Sanitation District (CCSD) has indicated that the Betty Lane Relief Sewer is currently being designed. The Relief Sewer will be located in the general vicinity of Owens Avenue and the Sloan Channel. The Betty Lane Relief Sewer will approach the Sloan Channel from the east in Owens Avenue. The relief sewer will need to cross the Sloan Channel in the vicinity of Owens Avenue. The sewer line crossing could most easily be accomplished just downstream of the existing concrete transition structure associated with the Owens Avenue RCB culvert. Provided that the sewer line is constructed prior to or in conjunction with the Sloan Channel improvements, the existing RCB and transition structure at Owens Avenue can remain in place. The CCSD has indicated that the construction of this relief sewer is scheduled for late 1993. The design and/or construction of the Sloan Channel will need to be coordinated with the CCSD and their contractor.

Right-of-Way

Preliminary right-of-way research indicates that continuous right-of-way and easements of sufficient width exists to construct the proposed basic channel improvements throughout the project area with the exception of an 873 foot long portion located immediately north of Sahara Avenue. This needed right-of-way is a portion of an undeveloped 25 acre parcel identified by APN 320-160-005.

Additional minor right-of-ways and/or construction easements requirements may be identified during the design phase of the project.

The Record-of-Survey, and right-of-way research are currently ongoing and will be submitted with the final Predesign Memorandum as per Section 2.02 I of the Professional Engineering Services Contract.

V. HYDROLOGY

The purpose and scope of the Hydrology section of this report was to establish the localized inflows to the Sloan Channel between Owens Avenue and the Las Vegas Wash. A detailed explanation of the model and the modeling techniques and calculations are contained in Appendix "B" of this report.

Methodology

The hydrologic methods used to establish the localized inflows to the Sloan Channel between Owens Avenue and Las Vegas Wash are based on methods established in the "Clark County Regional Flood Control District Hydrologic Criteria and Drainage Manual" (Manual). The hydrologic model utilized in this study is an HEC-1 flood hydrograph package developed by the U.S. Army Corps of Engineers, Hydrologic Engineering Center.

The rainfall relationships were generated using adjusted rainfall and a 6 hour SDN-3 distribution curve. A detailed explanation of the methodology and modeling is contained in Appendix "B."

Analysis

Two conditions were analyzed. Alternative 1 assumes existing conditions with ultimate buildout within the drainage area. Alternative 2 is the ultimate development condition and assumes future CCRFCD Master Plan facilities in place. Two detention basins have significant impact to the local runoff generated between Owens Avenue and the Las Vegas Wash. These are identified as facilities SLW/0154 and SLST/0169 on Figures F-12 and F-16 of 1991 Flood Control Master Plan Update. The facilities dampen peak flows generated on the Sunrise Mountain and route flows down Washington Avenue and Stewart Avenue into the Sloan Channel.

Figure No. 3 shows locations where inflow are calculated into the channel. Peak flow values for Alternative 1 and Alternative 2 are contained in Tables 1 and 2, respectively.

TABLE 1
LOCAL INFLOW INTO SLOAN CHANNEL
EXISTING CONDITION

Point Location*	Cross Street	INFLOW (cfs) East 10-Year	East 100-Year	West 10-Year	West 100-Year
1	Monroe Ave.	31	99		
2	Washington Ave.	505	1339		
3	Harris Ave.	5	39		
4	Bonanza Road	449	1232		
5	Stewart Ave.	178	665	169	579
6	Sunrise Ave.	44	133		
7	Charleston Blvd.	161	470	57	146
8	–	11	59	33	64
9	–	532	1206	10	22
10	Sahara Ave.	57	164	20	45
11	–	101	208	28	63

*See Figure 3

TABLE 2
LOCAL INFLOW INTO SLOAN CHANNEL
ULTIMATE DEVELOPMENT CONDITION

		INFLOW (cfs)			
		East		West	
Point Location*	Cross Street	10-Year	100-Year	10-Year	100-Year
1	Monroe Ave.	31	99		
2	Washington Ave.	177	449		
3	Harris Ave.	5	39		
4	Bonanza Road	77	356		
5	Stewart Ave.	196	581	169	579
6	Sunrise Ave	44	133		
7	Charleston Blvd.	46	233	57	146
8	--	11	59	33	64
9	--	532	1206	10	22
10	Sahara Ave.	57	164	20	45
11	--	101	208	28	63

*See Figure 3

The detailed HEC-1 model used for this analysis only identified those storm flow that enter the Sloan Channel south of Owens Avenue. The accumulative impact of the inflows generated by the model suggest that, at least under existing conditions in the local watershed, the local inflows may control the 100-year peak storm flow in the Sloan Channel south of Washington Avenue. Therefore, a preliminary hydrologic analysis of the Sloan Channel watershed from Carey Avenue to the Las Vegas Wash was prepared. The model indicates that the local inflows will exceed the design flow of 3,300 cfs as far north as Bonanza Road. The peak flows in the channel generated by the local inflows for existing and ultimate conditions are listed in Table 3 below:

TABLE 3
SLOAN CHANNEL
LOCAL 100-YEAR PEAK FLOWS

Location	Existing Condition (Carey to LV Wash)	Ultimate Local Inflows with Regional Facilities (Carey to LV Wash)
Washington Ave.	3100	1340
Bonanza Road	3400	1640
Stewart Avenue	3660	2010
Charleston Blvd.	4225	2250
Sahara Avenue	4900	3230
Las Vegas Wash	4975	3300

The proposed channel sections will convey the calculated flows within current design standards. Preliminary calculations indicate that the Charleston Bridge has capacity to pass a flow of 4,225, but the culvert at Stewart Avenue may experience some minor overtopping (approximately 50 cfs) for a flow of 3,660 cfs. The County may want to prepare a detailed study of the inflows to the Sloan Channel south of Carey Avenue (the outfall of the Confluence Detention Basin) to determine if the future bridge structure at Sahara Avenue needs to be sized for a flow greater than 3,300 cfs. As Table 3 indicates, ultimately, Regional facilities in the local watershed will reduce the local inflows to less than the design flow of 3,300 cfs.

VI. HYDRAULICS

Methodology

Water surface profiles for the Sloan Channel were calculated using the U.S. Army Corps of Engineers HEC-2 "Water Surface Profiles" computer program. Profiles were calculated assuming both supercritical and subcritical flow regimes. Bridges and culverts were modeled using the special bridge subroutine. Slope and channel

configurations are based on the Boyle drawings provided by the Clark County Public Works Department.

Channel stationings were taken from the above mentioned design drawings. Cross section numbers in the HEC-2 model correspond to the channel stationing. Cross sections were taken approximately every 300 feet with additional sections taken at grade breaks, transitions, bridge crossings and culvert crossings. Per contract requirements, models were prepared for both a 3,300 cfs and a 6,000 cfs flow. The calculated water surface elevation for the two flow models are contained in Tables 4 and 6.

Analysis

In general, it was determined that the typical channel sections proposed by the 1986 Boyle drawings have sufficient capacity to convey the 3,300 cfs, and meet current CCRFCD requirements for depth, velocity and freeboard. However, it was found that the existing culvert crossings at Stewart Avenue and Bonanza Road lack capacity to convey the 3,300 cfs flow with freeboard. The models suggest that the 3,300 cfs will pass through the culvert crossings at these locations in a pressure flow condition. The bridge crossings at Washington Avenue and Charleston Boulevard had sufficient capacity to pass 3,300 cfs with freeboard. A tabulation of the channel and bridge flow depths are contained in Table 5.

With a flow of 6,000 cfs in the channel, both the culvert crossings at Bonanza Road and Stewart Avenue and the bridge crossings at Washington Avenue and Charleston Boulevard are overtopped. The amount of flow overtopping in the case of the culvert crossing is significant (1,700 to 2,100 cfs) and exceeds the depth velocity criteria allowed within the CCRFCD Manual. At Washington Avenue and Charleston Boulevard bridges, the overflow is minimal. The majority of the proposed channel will meet CCRFCD Manual requirement for freeboard and will

convey the 6,000 cfs flow except where the bridge and culvert crossings lack capacity. The data for the 6,000 cfs flow is contained in Table 6.

VII. COST ESTIMATE

A preliminary cost estimate for the construction of this project is presented in Table 8. The cost estimate was prepared for two phases of construction. The limits of Phase I are from Owens Avenue to Stewart Avenue. Phase II extends from Stewart Avenue to the Las Vegas Wash.

The quantities shown for Overexcavation, are based on roughly 2 feet of overexcavation below the invert and benched excavation on the sides as described in the geotechnical report. The quantities for Imported Drain Backfill, and Recompact Native Material are based on 6 inches of drain backfill under the channel lining and the balance of the excavated prism being filled with recompacted native material. Chain-link fence quantities were estimated for portions of the channel with no adjacent, existing development. Channel lining quantities are shown in square feet. The unit price was adjusted to account for incidental items such as cutoff walls and access ramps.

TABLE 4
HYDRAULIC CHARACTERISTICS OF SLOAN CHANNEL/EXISTING DESIGN DRAWINGS
DESIGN FLOW (Q = 3300 cfs)

STATION	FLOW	DEPTH	INV.ELV	CWSEL	RB.ELV	LB.ELV	VCH	FB	FB+DEPT	CH.DEPTH
137.48	3300	4.54	771.47	776.01	778.77	778.77	11.37	1.47	6.0	7.3
437.48	3300	3.86	770.31	774.17	777.61	777.61	13.67	1.54	5.4	7.3
737.48	3300	3.85	769.16	773.01	776.46	776.46	13.67	1.54	5.4	7.3
1037.50	3300	3.85	768.00	771.86	775.30	775.30	13.68	1.54	5.4	7.3
1337.50	3300	3.85	766.85	770.70	774.15	774.15	13.66	1.54	5.4	7.3
1637.50	3300	3.85	765.69	769.55	772.99	772.99	13.67	1.54	5.4	7.3
1937.50	3300	3.85	764.54	768.39	771.84	771.84	13.66	1.54	5.4	7.3
2237.50	3300	3.85	763.38	767.24	770.68	770.68	13.67	1.54	5.4	7.3
2532.20	3300	3.86	762.25	766.11	769.55	769.55	13.66	1.54	5.4	7.3
2572.70	3300	5.54	762.10	767.64	769.40	769.40	12.98	1.57	7.1	7.3
2652.70	3300	3.61	761.80	765.41	768.70	768.70	14.10	1.54	5.2	6.9
2712.20	3300	4.48	761.36	765.84	768.33	768.33	11.53	1.48	6.0	6.97
3012.20	3300	3.60	759.83	763.43	766.80	766.80	14.75	1.57	5.2	6.97
3312.20	3300	3.57	758.30	761.88	765.27	765.27	14.90	1.57	5.1	6.97
3612.20	3300	3.56	756.77	760.33	763.74	763.74	14.94	1.57	5.1	6.97
3912.20	3300	3.56	755.24	758.80	762.21	762.21	14.95	1.57	5.1	6.97
4121.00	3300	3.56	754.17	757.73	761.14	761.14	14.95	1.57	5.1	6.97
4222.00	3300	3.56	753.66	757.22	760.63	760.63	14.95	1.57	5.1	6.97
4512.20	3300	3.54	752.13	755.66	759.10	759.10	15.07	1.57	5.1	6.97
4812.20	3300	3.57	750.60	754.16	757.57	757.57	14.93	1.57	5.1	6.97
5100.00	3300	3.56	749.13	752.69	756.10	756.10	14.96	1.57	5.1	6.97
5147.30	3300	3.81	748.94	752.75	755.90	755.91	13.87	1.54	5.4	6.97
5168.30	3300	6.30	747.50	753.80	754.46	754.47	13.20	1.61	7.9	6.97
5268.30	3300	7.37	746.80	754.17	754.00	754.00	8.62	1.42	8.8	7.2
5290.10	3300	3.02	746.86	749.88	753.79	753.79	17.98	1.65	4.7	6.93
5484.00	3300	3.15	745.40	748.56	752.34	752.34	17.18	1.63	4.8	6.94
5590.10	3300	3.15	744.61	747.78	751.55	751.55	17.09	1.63	4.8	6.94
5890.10	3300	3.20	742.36	745.55	749.30	749.30	16.89	1.62	4.8	6.94
6190.10	3300	3.20	740.11	743.30	747.05	747.05	16.91	1.62	4.8	6.94
6208.70	3300	3.17	739.93	743.11	746.87	746.87	17.01	1.62	4.8	6.94
6508.70	3300	3.59	738.46	742.06	745.40	745.40	14.79	1.57	5.2	6.94
6808.70	3300	3.59	736.99	740.59	743.93	743.93	14.77	1.57	5.2	6.94
7108.70	3300	3.59	735.52	739.12	742.46	742.46	14.76	1.57	5.2	6.94
7480.00	3300	3.60	733.70	737.31	740.64	740.64	14.75	1.57	5.2	6.94
7584.70	3300	3.60	733.19	736.80	740.13	740.13	14.75	1.57	5.2	6.94
7662.60	3300	4.31	732.80	737.11	739.10	739.10	11.94	1.49	5.8	6.3
7747.50	3300	4.79	732.19	736.98	738.49	738.49	11.79	1.50	6.3	6.3
7847.50	3300	6.81	731.30	738.11	737.60	737.60	7.03	1.33	8.1	6.3
8049.30	3300	3.11	730.45	733.56	736.75	736.75	17.34	1.63	4.7	6.3
8156.70	3300	3.39	730.00	733.39	736.30	736.70	15.73	1.59	5.0	6.7

TABLE 4 (Cont.)
HYDRAULIC CHARACTERISTICS OF SLOAN CHANNEL/EXISTING DESIGN DRAWINGS
SUPERCRITICAL FLOW (Q = 3300 cfs)

STATION	FLOW	DEPTH	INV.ELV	CWSEL	RB.ELV	LB.ELV	VCH	FB	FB+DEPT	CH.DEPTH
8349.30	3300	3.70	729.19	732.89	735.49	735.89	14.23	1.55	5.3	6.7
8649.30	3300	3.75	727.92	731.67	734.22	734.62	14.00	1.54	5.3	6.7
8949.30	3300	3.75	726.65	730.40	732.95	733.35	14.02	1.54	5.3	6.7
9249.30	3300	3.75	725.39	729.14	731.69	732.09	14.02	1.54	5.3	6.7
9549.30	3300	3.75	724.12	727.87	730.42	730.82	14.03	1.54	5.3	6.7
9849.30	3300	3.75	722.86	726.60	729.16	729.56	14.03	1.54	5.3	6.7
10149.00	3300	3.89	721.70	725.58	728.00	728.40	13.41	1.53	5.4	6.7
10423.00	3300	3.79	720.43	724.22	728.88	728.13	14.09	1.55	5.3	7.7
10574.00	3300	3.79	719.80	723.59	728.54	727.84	14.09	1.55	5.3	8.04
10623.00	3300	3.40	719.55	722.95	727.70	727.70	14.86	1.56	5.0	8.15
10624.00	3300	5.46	719.54	725.00	727.69	727.69	14.81	1.65	7.1	8.15
10724.00	3300	3.59	719.04	722.63	727.70	727.70	14.35	1.55	5.1	8.66
10725.00	3300	3.05	717.90	720.95	726.56	726.56	17.21	1.62	4.7	8.66
10830.00	3300	4.20	717.80	722.02	723.15	728.10	12.03	1.49	5.7	10.3
10900.00	3300	3.19	717.52	720.71	723.82	723.82	14.57	1.54	4.7	6.3
11191.00	3300	3.65	716.35	720.00	723.85	723.85	12.65	1.49	5.1	7.5
11491.00	3300	3.44	714.99	718.43	722.49	722.49	13.56	1.51	5.0	7.5
11791.00	3300	3.40	713.63	717.04	721.13	721.13	13.70	1.52	4.9	7.5
12091.00	3300	3.40	712.27	715.67	719.77	719.77	13.72	1.52	4.9	7.5
12430.00	3300	3.40	710.74	714.14	718.24	718.24	13.72	1.52	4.9	7.5
12730.00	3300	3.48	709.45	712.93	716.95	716.95	13.38	1.51	5.0	7.5
13030.00	3300	3.45	708.16	711.61	715.66	715.66	13.50	1.51	5.0	7.5
13330.00	3300	3.46	706.87	710.33	714.37	714.37	13.48	1.51	5.0	7.5
13630.00	3300	3.45	705.58	709.03	713.08	713.08	13.51	1.51	5.0	7.5
13930.00	3300	3.46	704.29	707.75	711.79	711.79	13.48	1.51	5.0	7.5
14230.00	3300	3.46	703.00	706.46	710.50	710.50	13.49	1.51	5.0	7.5
14500.00	3300	3.45	701.84	705.28	709.34	709.34	13.52	1.51	5.0	7.5
14900.00	3300	3.45	700.12	703.57	707.62	707.62	13.49	1.51	5.0	7.5
15130.00	3300	3.45	699.13	702.58	706.63	706.63	13.50	1.51	5.0	7.5
15430.00	3300	3.46	697.84	701.30	705.34	705.34	13.48	1.51	5.0	7.5
15730.00	3300	3.45	696.55	700.00	704.05	704.05	13.51	1.51	5.0	7.5
16030.00	3300	3.46	695.26	698.72	702.76	702.76	13.48	1.51	5.0	7.5
16330.00	3300	3.45	693.97	697.42	701.47	701.47	13.51	1.51	5.0	7.5
16630.00	3300	3.46	692.68	696.14	700.18	700.18	13.48	1.51	5.0	7.5
16930.00	3300	3.45	691.39	694.84	698.89	698.89	13.51	1.51	5.0	7.5
17230.00	3300	3.46	690.10	693.56	697.60	697.60	13.49	1.51	5.0	7.5
17410.00	3300	3.45	689.32	692.77	696.82	696.82	13.51	1.51	5.0	7.5

TABLE 5
BRIDGE INFORMATION DESIGN Q=3300 CFS.

CHANNEL STATION	BRIDGE ID.	UPSTREAM INFO.		BRIDGE INFO.				DOWNSTREAM INFO.	
		DEPTH (FT.)	VELOCIT (FPS)	BRIDGE AREA (SQ.FT.)	DEPTH AT UPSTREAM FACE (FT.)	Q PASSING THRU BRIDGE (CFS)	Q OVERTOPPING ROADWAY (CFS)	DEPTH (FT.)	VELOCITY (FPS)
19+37 *		3.9	13.7						
25+32	WASHINGTON	3.9	13.7						
25+72	BRIDGE			437	5.5	3300	0		
26+52								3.6	14.1
33+12 *								3.6	14.9
33+12 *		3.6	14.9						
51+47	BONANZA	3.8	13.9						
51+68	5(10'X5')			250	6.3	3300	0		
52+68	RCB.							7.4	8.6
52+90								3.0	18.0
58+90 *								3.2	19.9
58+08 *		3.6	14.8						
76+62	STEWART	4.3	11.9						
77+47	8(10'X3.5')			280	4.8	3300	0		
78+47	RCB.							6.8	7.0
80+49								3.1	17.3
83+49 *								3.7	14.2
101+49 *		3.9	13.5						
105+74	CHARLESTON	3.8	14.1						
106+23	BRIDGE	3.4	14.9						
106+24				437	5.5	3300	0		
107+24								3.6	14.4
107+25								3.1	17.2
108+30								4.3	12.0
117+91 *								3.4	13.7

* TYPICAL CHANNEL CROSS SECTIONS

TABLE 6
HYDRAULIC CHARACTERISTICS OF SLOAN CHANNEL/EXISTING DESIGN DRAWINGS
DESIGN FLOW (Q = 6000 cfs)

STATION	FLOW	DEPTH	INV.ELV	CWSEL	RB.ELV	LB.ELV	VCH	FB	FB+DEPTH	CH.DEPTH
137.48	6000	6.55	771.47	778.02	778.77	778.77	13.54	1.63	8.2	7.3
437.48	6000	5.64	770.31	775.96	777.61	777.61	16.12	1.72	7.4	7.3
737.48	6000	5.51	769.16	774.67	776.46	776.46	16.54	1.73	7.2	7.3
1037.50	6000	5.47	768.00	773.47	775.30	775.30	16.70	1.74	7.2	7.3
1337.50	6000	5.45	766.85	772.30	774.15	774.15	16.78	1.74	7.2	7.3
1637.50	6000	5.44	765.69	771.13	772.99	772.99	16.81	1.74	7.2	7.3
1937.50	6000	5.43	764.54	769.97	771.84	771.84	16.83	1.74	7.2	7.3
2237.50	6000	5.43	763.38	768.81	770.68	770.68	16.84	1.74	7.2	7.3
2532.20	6000	5.42	762.25	767.67	769.55	769.55	16.85	1.74	7.2	7.3
2572.70	6000	8.01	762.10	770.11	769.40	769.40	13.01	1.65	9.7	7.3
2652.70	6000	8.34	761.80	770.14	768.70	768.70	9.87	1.50	9.8	6.9
2712.20	6000	5.62	761.36	766.98	768.33	768.33	16.19	1.72	7.3	6.97
3012.20	6000	5.25	759.83	765.08	766.80	766.80	17.51	1.76	7.0	6.97
3312.20	6000	5.12	758.30	763.42	765.27	765.27	18.01	1.78	6.9	6.97
3612.20	6000	5.06	756.77	761.85	763.74	763.74	18.24	1.78	6.8	6.97
3912.20	6000	5.04	755.24	760.28	762.21	762.21	18.32	1.79	6.8	6.97
4121.00	6000	5.03	754.17	759.20	761.14	761.14	18.38	1.79	6.8	6.97
4222.00	6000	5.03	753.66	758.69	760.63	760.63	18.39	1.79	6.8	6.97
4512.20	6000	4.99	752.13	757.12	759.10	759.10	18.53	1.79	6.8	6.97
4812.20	6000	4.99	750.60	755.59	757.57	757.57	18.50	1.79	6.8	6.97
5100.00	6000	5.00	749.13	754.13	756.10	756.10	18.48	1.79	6.8	6.97
5147.30	6000	9.32	748.94	758.26	755.90	755.91	9.03	1.48	10.8	6.97
5168.30	6000	9.39	747.50	754.52	756.89	754.47	15.73	1.83	11.2	6.97
5268.30	6000	7.37	746.80	757.65	754.00	754.00	17.30	1.84	9.2	7.2
5290.10	6000	4.26	746.86	751.12	753.79	753.79	20.30	1.82	6.1	6.93
5484.00	6000	4.38	745.40	749.78	752.34	752.34	20.52	1.84	6.2	6.94
5590.10	6000	4.42	744.61	749.02	751.55	751.55	20.60	1.85	6.3	6.94
5890.10	6000	4.47	742.36	746.82	749.30	749.30	20.77	1.86	6.3	6.94
6190.10	6000	4.48	740.11	744.58	747.05	747.05	20.86	1.86	6.3	6.94
6208.70	6000	4.47	739.93	744.40	746.87	746.87	20.93	1.86	6.3	6.94
6508.70	6000	4.88	738.46	743.35	745.40	745.40	18.96	1.80	6.7	6.94
6808.70	6000	5.02	736.99	742.01	743.93	743.93	18.34	1.79	6.8	6.94
7108.70	6000	5.07	735.52	740.60	742.46	742.46	18.24	1.78	6.9	6.94
7480.00	6000	5.06	733.70	738.77	740.64	740.64	18.24	1.78	6.8	6.94
7584.70	6000	5.06	733.19	738.26	740.13	740.13	18.23	1.78	6.8	6.94
7662.60	6000	8.29	732.80	741.09	739.10	739.10	10.21	1.52	9.8	6.3
7747.50	6000	7.14	732.19	739.33	738.49	738.49	15.34	1.74	8.9	6.3
7847.50	6000	10.24	731.30	741.54	737.60	737.60	8.07	1.44	11.7	6.3
8049.30	6000	4.44	730.45	734.89	736.75	736.75	21.01	1.86	6.3	6.3
8156.70	6000	4.69	730.00	734.69	736.30	736.70	19.78	1.83	6.5	6.7

(Cont.)

TABLE 6 (Cont.)
HYDRAULIC CHARACTERISTICS OF SLOAN CHANNEL/EXISTING DESIGN DRAWINGS
DESIGN FLOW (Q = 6000 cfs)

STATION	FLOW	DEPTH	INV.ELV	CWSEL	RB.ELV	LB.ELV	VCH	FB	FB+DEPTH	CH.DEPTH
8349.30	6000	5.00	729.19	734.43	735.49	735.89	17.34	1.74	6.7	6.7
8649.30	6000	5.23	727.92	733.18	734.22	734.62	17.28	1.75	7.0	6.7
8949.30	6000	5.26	726.65	731.93	732.95	733.35	17.26	1.75	7.0	6.7
9249.30	6000	5.27	725.39	730.66	731.69	732.09	17.27	1.75	7.0	6.7
9549.30	6000	5.27	724.12	729.39	730.42	730.82	17.27	1.75	7.0	6.7
9849.30	6000	5.27	722.86	728.13	729.16	729.56	17.28	1.75	7.0	6.7
10149.00	6000	5.41	721.70	727.10	728.00	728.40	16.78	1.74	7.1	6.7
10423.00	6000	5.44	720.43	725.87	728.88	728.13	17.08	1.75	7.2	7.7
10574.00	6000	5.44	719.80	725.24	728.54	727.84	17.13	1.75	7.2	8.04
10623.00	6000	6.31	719.55	725.86	727.70	727.70	13.58	1.63	7.9	8.15
10624.00	6000	7.90	719.54	727.44	727.69	727.69	12.77	1.64	9.5	8.15
10724.00	6000	8.59	719.04	727.63	727.70	727.70	9.68	1.50	10.1	8.66
10725.00	6000	4.78	717.90	722.68	726.56	726.56	18.94	1.80	6.6	8.66
10830.00	6000	5.96	717.80	723.76	723.15	728.10	15.15	1.69	7.6	10.3
10900.00	6000	4.53	717.52	722.05	723.82	723.82	17.74	1.73	6.3	6.3
11191.00	6000	5.01	716.35	721.36	723.85	723.85	16.06	1.69	6.7	7.5
11491.00	6000	4.88	714.99	719.87	722.49	722.49	16.59	1.70	6.6	7.5
11791.00	6000	4.81	713.63	718.44	721.13	721.13	16.85	1.71	6.5	7.5
12091.00	6000	4.78	712.27	717.06	719.77	719.77	16.94	1.71	6.5	7.5
12430.00	6000	4.77	710.74	715.51	718.24	718.24	16.98	1.71	6.5	7.5
12730.00	6000	4.84	709.45	714.29	716.95	716.95	16.72	1.71	6.5	7.5
13030.00	6000	4.85	708.16	713.00	715.66	715.66	16.72	1.71	6.6	7.5
13330.00	6000	4.85	706.87	711.71	714.37	714.37	16.72	1.71	6.6	7.5
13630.00	6000	4.84	705.58	710.42	713.08	713.08	16.73	1.71	6.5	7.5
13930.00	6000	4.83	704.29	709.12	711.79	711.79	16.75	1.71	6.5	7.5
14230.00	6000	4.84	703.00	707.84	710.50	710.50	16.71	1.71	6.5	7.5
14500.00	6000	4.85	701.84	706.68	709.34	709.34	16.71	1.71	6.6	7.5
14900.00	6000	4.83	700.12	704.95	707.62	707.62	16.74	1.71	6.5	7.5
15130.00	6000	4.84	699.13	703.97	706.63	706.63	16.71	1.71	6.5	7.5
15430.00	6000	4.85	697.84	702.69	705.34	705.34	16.71	1.71	6.6	7.5
15730.00	6000	4.85	696.55	701.39	704.05	704.05	16.72	1.71	6.6	7.5
16030.00	6000	4.85	695.26	700.10	702.76	702.76	16.73	1.71	6.6	7.5
16330.00	6000	4.84	693.97	698.81	701.47	701.47	16.73	1.71	6.5	7.5
16630.00	6000	4.84	692.68	697.52	700.18	700.18	16.73	1.71	6.5	7.5
16930.00	6000	4.84	691.39	696.23	698.89	698.89	16.73	1.71	6.5	7.5
17230.00	6000	4.83	690.10	694.93	697.60	697.60	16.75	1.71	6.5	7.5
17410.00	6000	4.84	689.32	694.16	696.82	696.82	16.72	1.71	6.5	7.5

TABLE 7
BRIDGE INFORMATION DESIGN Q = 6000 CFS.

CHANNEL STATION	BRIDGE ID.	UPSTREAM INFO		BRIDGE INFO.				DOWNSTREAM INFO.	
		DEPTH (FT.)	VELOCIT (FPS)	BRIDGE AREA (SQ.FT.)	DEPTH AT UPSTREAM FACE (FT.)	Q PASSING THRU BRIDGE (CFS)	Q OVERTOPPING ROADWAY (CFS)	DEPTH (FT.)	VELOCITY (FPS)
19+37 *		5.4	16.8						
25+32	WASHINGTON	5.4	16.9						
25+72	BRIDGE			437	8.0	5689	319		
26+52								8.3	9.9
27+12								5.6	16.2
33+12 *								5.1	18.2
33+12 *		5.1	18.2						
51+47	BONANZA	9.3	9.0						
51+68	5(10'X5')			250	9.4	3932	2074		
52+68	RCB							10.9	10.6
52+90								4.3	22.2
58+90 *								4.5	21.0
58+08 *		5.0	18.4						
76+62	STEWART	8.3	10.2						
77+47	8(10'X3.5')			280	7.1	4296	1727		
78+47	RCB.							10.2	8.1
80+49								4.4	21.0
83+49 *								5.0	18.4
101+49 *		5.4	16.8						
105+74	CHARLESTON	5.4	17.1						
106+23	BRIDGE	6.3	13.6						
106+24				437	7.9	5580	419		
107+24								8.6	9.7
107+25								4.8	18.9
108+30								4.4	11.9
117+91 *								5.0	16.1

* TYPICAL CHANNEL CROSS SECTIONS

TABLE 8

SLOAN CHANNEL 7320 LINEAR FEET
PHASE I - OWENS TO STEWART
PRELIMINARY COST ESTIMATE

ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	EXTENSION
OVEREXCAVATION	CY	54,900	$4.00	$219,600
IMPORTED DRAIN BACKFILL	CY	12,444	$10.00	$124,440
RECOMPACT NATIVE MATERIAL	CY	42,456	$1.50	$63,684
MAJOR SURFACE INLETS	EA	2	$50,000.00	$100,000
CHAIN LINK FENCE	LF	8,700	$10.00	$87,000
CHANNEL LINING	SF	668,316	$6.00	$4,009,896
		TOTAL		$4,604,620

SLOAN CHANNEL 7682 LINEAR FEET 60' B. WIDTH
PHASE II - STEWART TO LV WASH 1600 LINEAR FEET 70' B. WIDTH
PRELIMINARY COST ESTIMATE

ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	EXTENSION
OVEREXCAVATION	CY	70,735	$4.00	$282,940
IMPORTED DRAIN BACKFILL	CY	16,099	$10.00	$160,994
RECOMPACT NATIVE MATERIAL	CY	54,636	$1.50	$81,953
MAJOR SURFACE INLETS	EA	3	$50,000.00	$150,000
CHAIN LINK FENCE	LF	13,300	$10.00	$133,000
CHANNEL LINING	SF	863,447	$6.00	$5,180,680
		TOTAL		$5,989,567

GRAND TOTAL PHASE I AND PHASE II $10,594,187

VIII. RECOMMENDATIONS AND CONCLUSIONS

The channel section proposed in the 1986 Boyle design has adequate capacity to safely convey the design flows of 3,300 cfs and 6,000 cfs with freeboard except at the bridge and culvert crossings. The existing RCB culverts and bridges within the project limits have adequate capacity to convey the design flow of 3,300 cfs without overtopping. However, all of the culverts and bridges are overtopped for the design flow of 6,000 cfs. The flows that overtop the bridges at Washington Avenue and Charleston Boulevard are relatively minor (319 cfs and 419 cfs, respectively) in respect to the design flow of 6,000 cfs. These flows could be diverted back into the Sloan Channel via a surface inlet constructed within the Sloan Lane right-of-way.

The overtopping flows at the culverts at Bonanza Road and Stewart Avenue for the flow of 6,000 cfs are significant (2,074 cfs and 1,727 cfs, respectively). However, the Confluence Detention Basin is currently under design and is scheduled for a construction start in 1994. The Confluence Detention Basin will reduce the design flow for the Sloan Channel to 3,300 cfs. Based on this information, the detention basin will be in place before the culverts at Bonanza Road and Stewart Avenue could be redesigned and reconstructed. Therefore, the existing facilities are recommended to be left in place.

Provisions to accept local inflows into the Sloan Channel need to be incorporated into the design drawings. Significant inflows will be incurred at the points shown on Table 1 and Table 2. Future Master Plan facilities will eventually reduce the magnitude of the local inflows at some points. The surface inlets shown in the 1986 design were most likely sized for flows determined using hydrologic criteria which is not currently accepted. The surface inlets need to be reanalyzed to account for the updated local inflows and flow patterns presented in this memorandum. Major surface inlets need to be constructed on the east side of the channel at Owens Avenue and Washington Avenue, on the east and west side of the channel at Stewart

Avenue, and on the east side of the channel at Charleston Boulevard. Major surface inlets at existing roadway crossings should be similar in design to the existing surface inlet at Bonanza Road. This inlet consists of a warped pavement section for Sloan Lane adjacent to the Sloan Channel (and a depressed section of curb and gutter and sidewalk to act as the surface inlet. Minor surface inlets or, inlets at inflow points not associated with the major roadway crossing, should be similar to the surface inlets shown on the 1986 design. These inlets will consist of a depressed section of channel lining and upstream erosion protection to prevent undermining of the channel lining. The size and configuration of each inlet will be determined by the amount of inflow, allowable inlet velocities, and local topographic features. Provisions also need to be made to protect the proposed channel improvements from storm flows which are discharged directly into the Sloan Channel from adjacent residential developments.

The 1986 Sloan Channel design does not meet the currently accepted CCRFCD criteria for open channel design for the following items: steel area, transverse and longitudinal cutoff walls, safety ladders, and side slopes.

Based on work performed in the preparation of this Predesign Memorandum, the following recommendations are made:

- Based on the magnitude of the design flows for the Sloan Channel, the portion of Sloan Channel from Owens Avenue to the Las Vegas Wash confluence must be improved as a fully-lined, concrete trapezoidal channel. The existing, earth-lined channel section does not have adequate capacity to safely convey the design flows. The recommended improvements will protect the existing bridge and culvert structures at the major roadway crossings and will protect the surrounding residential developments.

- New design drawing for the Sloan Channel should be prepared that will incorporate current design standards, the updated soils information, and

current development conditions. The updated channel design will include 2:1 (H:V) side slopes, transverse and longitudinal cutoff walls, safety ladders, and steel areas per CCRFCD criteria. Portions of the longitudinal cutoff wall on the west side of the channel could be omitted where the channel will be protected from surface inflows by existing masonry walls. A low flow channel will also be incorporated into the channel design in order to contain nuisance flows in the center of the channel.

- No new bridges or modifications to existing culvert structures are recommended at this time. The existing culverts and bridges have capacity to convey the design flow of 3,300 cfs within the proposed channel sections. Regional facilities will soon be constructed that will limit the upstream inflow into this portion of the Sloan Channel to 3,300 cfs.

- The existing storm drain stubs for future Master Plan storm drains should not be constructed or reconstructed at this time, but rather should be placed at such a time that the future Master Plan facilities are designed.

- Surface runoff approaching the Sloan Channel from the west at Stewart Avenue can be introduced to the Sloan Channel either by perpetuating the existing flow pattern across an undeveloped parcel, or by constructing a channel parallel to Stewart Avenue along the frontage of the vacant parcel to the Sloan Channel. Presently, major storm flows in Stewart Avenue from the west are introduced into the Sloan Channel via an existing wash which bisects an undeveloped parcel located in the southwest quadrant of Sloan Channel and Stewart Avenue. The existing wash could be partially filled and regraded in order to improve the hydraulics of the confluence with Sloan Channel. The invert of the wash should be raised sufficiently so that minor flows conveyed in the Sloan Channel would not inundate this property. The wash should be concrete lined within the right-of-way for Sloan Channel with a concrete cutoff wall at the right-of-way line to prevent undermining the lining. An

easement would be required through this property to construct these improvements.

Runoff in Stewart Avenue could also be conveyed into the Sloan Channel by construction an interceptor channel along the south side of Stewart Avenue adjacent to the vacant parcel. In this option, the channel would act as a side weir to remove flows from Stewart Avenue. This option would require the construction of a warped pavement section in Stewart Avenue to force flows into the interceptor channel. The exact size and configuration of the channel can be determined when more detailed topographic data is available. Preliminary estimates indicated that a 20-foot wide, rectangular, concrete-lined channel at a slope of 0.4% could convey the 100-year flow of 580 cfs at a depth of 2.8 feet. The construction of this channel would require the acquisition of some right-of-way from the vacant parcel.

The construction of the channel along the south side of Stewart Avenue is recommended for construction. This channel will provide a one-time solution to the introduction of surface flows into the Sloan Channel at this location. Whereas, the improvements to the existing wash across the vacant parcel would only be a temporary solution. In the future, if an upsized storm drain is constructed within Stewart Avenue, it could be connected to the proposed channel.

The HEC-1 model prepared to identify local inflows into the Sloan Channel within the project limits for existing conditions suggests that local inflows into the Sloan Channel may exceed the design flow of 3,300 cfs in the middle and lower reaches of the project. A preliminary analysis of the entire watershed that contributes local inflows to the Sloan Channel south of the Confluence Detention Basin (Carey Avenue) indicates that the accumulation of local inflows into the channel will exceed 3,300 cfs as far north as Bonanza Road. A detailed hydrologic analysis of the local watershed for the Sloan Channel

north of Owens Avenue is beyond the scope of this Predesign Memorandum. While it appears that the existing structures will convey these flows, Clark County may want to perform a detailed hydrologic analysis for the Sloan Channel watershed to insure that the future culvert structure at Sahara Avenue is adequately sized.

Hydraulic Analysis

The water surface profile for the Sloan Channel was computed for supercritical and subcritical flow conditions beginning with critical flow depth approximately 137 feet downstream from the Owens Avenue RCB culvert. The channel stationing starts at 1+37.48 per the 1986 channel design drawing Boyle provided by Clark County Public Works.

The cross section locations are taken from the above mentioned design drawing. The cross section numbers in the HEC-2 model correspond to the channel stationing. Cross sections were taken at 300 foot intervals through the length of the channel. Additional sections were taken at grade breaks, transitions and culvert crossings. The channel cross section geometry and channel flow line were matched as closely as possible to the Boyle design mentioned above.

The design flows to be used in the HEC-2 model were established by the contract as 3,300 cfs and 6,000 cfs.

To evaluate the existing culverts and bridges, the special bridge routine was selected.

The computed water surface elevations and hydraulic characteristics of the channel 3,300 cfs and 6,000 cfs are shown in Table C1 and Table C2. A printout of each HEC-2 model run is also contained in this Appendix.

Channel Capacity

Per existing design drawings from Station 0+00 to Station 105+74, and from Station 125+30 to end of channel, the channel bottom width is 60 feet, the side slopes are 1.5:1 (H:V), and the depth varies from 6 feet to 7.5 feet. From Station 108+30 to Station 124+30 the channel bottom width is 70 feet, the side slopes are 1.5:1 (H:V), and the depth varies from 5.3 feet to 7.5 feet. The analysis shows the design flow of 3,300 cfs is contained in the typical channel section and meets the CCRFCD freeboard requirements. The invert slope of the channel is sufficient to maintain supercritical flow for both design

flows. The existing bridges and culverts will cause a backwater effect immediately upstream from these structures. The backwater effect will cause the flow to pass from supercritical to subcritical for a short distance upstream from the structures. The channel flows do not have sufficient energy to sustain a strong hydraulic jump. An undular jump (Fr = $1 < x < 1.7$) can be expected upstream from the bridges and culverts.

The super-elevation of the water surface for both design flows caused by the reverse curve in the channel alignment located south of Charleston Boulevard was calculated per Equation 730 of the Manual. The calculated super-elevations in the reverse curve for 3,300 cfs and 6,000 cfs is on the order of 0.6 feet and 1.0 feet, respectively.

The design flow of 6,000 cfs is contained within a typical section of the Sloan Channel without freeboard.

Bridge and Culvert Capacity

To evaluate the bridge and culvert capacities, the special bridge routine was used in the HEC-2 analysis. The design flow of 3,300 cfs passes through the Washington and Charleston bridges as Class B low flow, and passes through the Bonanza Road and Stewart Avenue culverts as pressure flow.

The design flow of 6,000 cfs passes through and overflows the above mentioned bridges and culverts as pressure and weir flow. The restriction of flow at the bridges and culverts will cause a backwater upstream from these structures, and will cause overflow from the channel onto adjacent properties and streets.

A summary of bridge information and ponding depth is shown in Table C3 and Table C4 for the 3,300 cfs and the 6,000 cfs design flows.

TABLE B2
LOCAL INFLOW INTO SLOAN CHANNEL
EXISTING CONDITION

Point Location*	Cross Street	INFLOW (cfs) East 10-Year	East 100-Year	West 10-Year	West 100-Year
1	Monroe Ave.	31	99		
2	Washington Ave.	505	1339		
3	Harris Ave.	5	39		
4	Bonanza Road	449	1232		
5	Stewart Ave.	178	665	169	579
6	Sunrise Ave.	44	133		
7	Charleston Blvd.	161	470	57	146
8	--	11	59	33	64
9	--	532	1206	10	22
10	Sahara Ave.	57	164	20	45
11	--	101	208	28	63

TABLE B3
LOCAL INFLOW INTO SLOAN CHANNEL
ULTIMATE DEVELOPMENT CONDITION

Point Location*	Cross Street	INFLOW (cfs) East 10-Year	East 100-Year	West 10-Year	West 100-Year
1	Monroe Ave.	31	99		
2	Washington Ave.	177	449		
3	Harris Ave.	5	39		
4	Bonanza Road	77	356		
5	Stewart Ave.	169	579	169	579
6	Sunrise Ave	44	133		
7	Charleston Blvd.	46	233	57	146
8	--	11	59	33	64
9	--	532	1206	10	22
10	Sahara Ave.	57	164	20	45
11	--	101	208	28	63

TABLE C1

HYDRAULIC CHARACTERISTICS OF SLOAN CHANNEL/EXISTING DESIGN DRAWINGS

DESIGN FLOW (Q = 3300 cfs)

STATION	FLOW	DEPTH	INV.ELV	CWSEL	LB.ELV	LB.ELV	VCH	FB	FB+DEPTH	ICH.DEPTH
137.48	3300	4.54	771.47	776.01	778.77	778.77	11.37	1.47	6.0	7.3
437.48	3300	3.86	770.31	774.17	777.61	777.61	13.67	1.54	5.4	7.3
737.48	3300	3.85	769.16	773.01	776.46	776.46	13.67	1.54	5.4	7.3
1037.50	3300	3.85	768.00	771.86	775.30	775.30	13.68	1.54	5.4	7.3
1337.50	3300	3.85	766.85	770.70	774.15	774.15	13.66	1.54	5.4	7.3
1637.50	3300	3.85	765.69	769.55	772.99	772.99	13.67	1.54	5.4	7.3
1937.50	3300	3.85	764.54	768.39	771.84	771.84	13.66	1.54	5.4	7.3
2237.50	3300	3.85	763.38	767.24	770.68	770.68	13.67	1.54	5.4	7.3
2532.20	3300	3.86	762.25	766.11	769.55	769.55	13.66	1.54	5.4	7.3
2572.70	3300	5.54	762.10	767.64	769.40	769.40	12.98	1.57	7.1	7.3
2652.70	3300	3.61	761.80	765.41	768.70	768.70	14.10	1.54	5.2	6.9
2712.20	3300	4.48	761.36	765.84	768.33	768.33	11.53	1.48	6.0	6.97
3012.20	3300	3.60	759.83	763.43	766.80	766.80	14.75	1.57	5.2	6.97
3312.20	3300	3.57	758.30	761.88	765.27	765.27	14.90	1.57	5.1	6.97
3612.20	3300	3.56	756.77	760.33	763.74	763.74	14.94	1.57	5.1	6.97
3912.20	3300	3.56	755.24	758.80	762.21	762.21	14.95	1.57	5.1	6.97
4121.00	3300	3.56	754.17	757.73	761.14	761.14	14.95	1.57	5.1	6.97
4222.00	3300	3.56	753.66	757.22	760.63	760.63	14.95	1.57	5.1	6.97
4512.20	3300	3.54	752.13	755.66	759.10	759.10	15.07	1.57	5.1	6.97
4812.20	3300	3.57	750.60	754.16	757.57	757.57	14.93	1.57	5.1	6.97

TABLE C1 Continue
HYDRAULIC CHARACTERISTICS OF SLOAN CHANNEL/EXISTING DESIGN DRAWINGS
SUPERCRITICAL FLOW (Q = 3300 cfs)

STATION	FLOW	DEPTH	INV.ELV	CWSEL	LB.ELV	LB.ELV	VCH	FB	FB+DEPTH	ICH.DEPTH
5100.00	3300	3.56	749.13	752.69	756.10	756.10	14.96	1.57	5.1	6.97
5147.30	3300	3.81	748.94	752.75	755.90	755.91	13.87	1.54	5.4	6.97
5168.30	3300	6.30	747.50	753.80	754.46	754.47	13.20	1.61	7.9	6.97
5268.30	3300	7.37	746.80	754.17	754.00	754.00	8.62	1.42	8.8	7.2
5290.10	3300	3.02	746.86	749.88	753.79	753.79	17.98	1.65	4.7	6.93
5484.00	3300	3.15	745.40	748.56	752.34	752.34	17.18	1.63	4.8	6.94
5590.10	3300	3.15	744.61	747.78	751.55	751.55	17.09	1.63	4.8	6.94
5890.10	3300	3.20	742.36	745.55	749.30	749.30	16.89	1.62	4.8	6.94
6190.10	3300	3.20	740.11	743.30	747.05	747.05	16.91	1.62	4.8	6.94
6208.70	3300	3.17	739.93	743.11	746.87	746.87	17.01	1.62	4.8	6.94
6508.70	3300	3.59	738.46	742.06	745.40	745.40	14.79	1.57	5.2	6.94
6808.70	3300	3.59	736.99	740.59	743.93	743.93	14.77	1.57	5.2	6.94
7108.70	3300	3.59	735.52	739.12	742.46	742.46	14.76	1.57	5.2	6.94
7480.60	3300	3.60	733.70	737.31	740.64	740.64	14.75	1.57	5.2	6.94
7584.70	3300	3.60	733.19	736.80	740.13	740.13	14.75	1.57	5.2	6.94
7662.60	3300	4.31	732.80	737.11	739.10	739.10	11.94	1.49	5.8	6.3
7747.50	3300	4.79	732.19	736.98	738.49	738.49	11.79	1.50	6.3	6.3
7847.50	3300	6.81	731.30	738.11	737.60	737.60	7.03	1.33	8.1	6.3
8049.30	3300	3.11	730.45	733.56	736.75	736.75	17.34	1.63	4.7	6.3
8156.70	3300	3.39	730.00	733.39	736.30	736.70	15.73	1.59	5.0	6.7

TABLE C1 Continue

HYDRAULIC CHARACTERISTICS OF SLOAN CHANNEL/EXISTING DESIGN DRAWINGS

SUPERCRITICAL FLOW (Q = 3300 cfs)

STATION	FLOW	DEPTH	INV.ELV	CWSEL	LB.ELV	LB.ELV	VCH	FB	FB+DEPTH	
8349.30	3300	3.70	729.19	732.89	735.49	735.89	14.23	1.55	5.3	6.7
8649.30	3300	3.75	727.92	731.67	734.22	734.62	14.00	1.54	5.3	6.7
8949.30	3300	3.75	726.65	730.40	732.95	733.35	14.02	1.54	5.3	6.7
9249.30	3300	3.75	725.39	729.14	731.69	732.09	14.02	1.54	5.3	6.7
9549.30	3300	3.75	724.12	727.87	730.42	730.82	14.03	1.54	5.3	6.7
9849.30	3300	3.75	722.86	726.60	729.16	729.56	14.03	1.54	5.3	6.7
10149.00	3300	3.89	721.70	725.58	728.00	728.40	13.41	1.53	5.4	6.7
10423.00	3300	3.79	720.43	724.22	728.08	728.13	14.09	1.55	5.3	7.7
10574.00	3300	3.79	719.80	723.59	726.54	727.84	14.09	1.55	5.3	8.04
10623.00	3300	3.40	719.55	722.95	727.70	727.70	14.86	1.56	5.0	8.15
10624.00	3300	5.46	719.54	725.00	727.69	727.69	14.81	1.65	7.1	8.15
10724.00	3300	3.59	719.04	722.63	727.70	727.70	14.35	1.55	5.1	8.66
10725.00	3300	3.05	717.90	720.95	726.56	726.56	17.21	1.62	4.7	8.66
10830.00	3300	4.20	717.80	722.02	723.15	728.10	12.03	1.49	5.7	10.3
10900.00	3300	3.19	717.52	720.71	723.82	723.82	14.57	1.54	4.7	6.3
11191.00	3300	3.65	716.35	720.00	723.85	723.85	12.65	1.49	5.1	7.5
11491.00	3300	3.44	714.99	718.43	722.49	722.49	13.56	1.51	5.0	7.5
11791.00	3300	3.40	713.63	717.04	721.13	721.13	13.78	1.52	4.9	7.5
12091.00	3300	3.40	712.27	715.67	719.77	719.77	13.72	1.52	4.9	7.5
12430.00	3300	3.40	710.74	714.14	718.24	718.24	13.72	1.52	4.9	7.5

abutment

TABLE C2
HYDRAULIC CHARACTERISTICS OF SLOAN CHANNEL/EXISTING DESIGN DRAWINGS
DESIGN FLOW (Q = 6000 cfs)

STATION	FLOW	DEPTH	INV.ELV	CWSEL	LB.ELV	LB.ELV	VCH	FB	FB+DEPTH	ICH.DEPTH	
137.48	6000	6.55	771.47	778.02	778.77	778.77	13.54	1.63	8.2	7.3	6.6
437.48	6000	5.64	770.31	775.96	777.61	777.61	16.12	1.72	7.4	7.3	5.6
737.48	6000	5.51	769.16	774.67	776.46	776.46	16.54	1.73	7.2	7.3	
1037.50	6000	5.47	768.00	773.47	775.30	775.30	16.70	1.74	7.2	7.3	
1337.50	6000	5.45	766.85	772.30	774.15	774.15	16.78	1.74	7.2	7.3	
1637.50	6000	5.44	765.69	771.13	772.99	772.99	16.81	1.74	7.2	7.3	
1937.50	6000	5.43	764.54	769.97	771.84	771.84	16.83	1.74	7.2	7.3	
2237.50	6000	5.43	763.38	768.81	770.68	770.68	16.84	1.74	7.2	7.3	
2532.20	6000	5.42	762.25	767.67	769.55	769.55	16.85	1.74	7.2	7.3	
2572.70	6000	8.81	762.10	770.11	769.40	769.40	13.81	1.65	9.7	7.3	8.0
2652.70	6000	8.34	761.80	770.14	768.70	768.70	9.87	1.50	9.8	6.9	8.3
2712.20	6000	5.62	761.36	766.98	768.33	768.33	16.19	1.72	7.3	6.97	5.6
3012.20	6000	5.25	759.83	765.08	766.80	766.80	17.51	1.76	7.0	6.97	
3312.20	6000	5.12	758.30	763.42	765.27	765.27	18.01	1.78	6.9	6.97	
3612.20	6000	5.06	756.77	761.85	763.74	763.74	18.24	1.78	6.8	6.97	
3912.20	6000	5.04	755.24	760.28	762.21	762.21	18.32	1.79	6.8	6.97	
4121.00	6000	5.03	754.17	759.20	761.14	761.14	18.38	1.79	6.8	6.97	
4222.00	6000	5.03	753.66	758.69	760.63	760.63	18.39	1.79	6.8	6.97	
4512.20	6000	4.99	752.13	757.12	759.10	759.10	18.53	1.79	6.8	6.97	
4812.20	6000	4.99	750.60	755.59	757.57	757.57	18.50	1.79	6.8	6.97	

TABLE C2 CONTINUE
HYDRAULIC CHARACTERISTICS OF SLOAN CHANNEL/EXISTING DESIGN DRAWINGS
DESIGN FLOW (Q = 6000 cfs)

STATION	FLOW	DEPTH	INV.ELV	CWSEL	LB.ELV	LB.ELV	VCH	FB	FB+DEPTH	CH.DEPTH	
5100.00	6000	5.00	749.13	754.13	756.10	756.10	18.48	1.79	6.8	6.97	
5147.30	6000	9.32	748.94	758.26	755.90	755.91	9.03	1.48	10.8	6.97	9.3
5168.30	6000	9.39	747.50	754.52	756.89	754.47	15.73	1.83	11.2	6.97	9.4
5268.30	6000	7.37	746.80	757.65	754.00	754.00	17.30	1.84	9.2	7.2	7.4
5290.10	6000	4.26	746.86	751.12	753.79	753.79	20.30	1.82	6.1	6.93	
5484.00	6000	4.38	745.40	749.78	752.34	752.34	20.52	1.84	6.2	6.94	
5590.10	6000	4.42	744.61	749.02	751.55	751.55	20.60	1.85	6.3	6.94	
5890.10	6000	4.47	742.36	746.82	749.30	749.30	20.77	1.86	6.3	6.94	
6190.10	6000	4.48	740.11	744.58	747.05	747.05	20.86	1.86	6.3	6.94	
6208.70	6000	4.47	739.93	744.40	746.87	746.87	20.93	1.86	6.3	6.94	
6508.70	6000	4.88	738.46	743.35	745.40	745.40	18.96	1.80	6.7	6.94	
6808.70	6000	5.02	736.99	742.01	743.93	743.93	18.34	1.79	6.8	6.94	
7108.70	6000	5.07	735.52	740.60	742.46	742.46	18.24	1.78	6.9	6.94	
7480.00	6000	5.06	733.70	738.77	740.64	740.64	18.24	1.78	6.8	6.94	
7584.70	6000	5.06	733.19	738.26	740.13	740.13	18.23	1.78	6.8	6.94	
7662.60	6000	8.29	732.80	741.09	739.10	739.10	10.21	1.52	9.8	6.3	8.3
7747.50	6000	7.14	732.19	739.33	738.49	738.49	15.34	1.74	8.9	6.3	7.1
7847.50	6000	10.24	731.30	741.54	737.60	737.60	8.07	1.44	11.7	6.3	10.2
8049.30	6000	4.44	730.45	734.89	736.75	736.75	21.01	1.86	6.3	6.3	
8156.70	6000	4.69	730.00	734.69	736.30	736.70	19.78	1.83	6.5	6.7	

TABLE C2 CONTINUE

HYDRAULIC CHARACTERISTICS OF SLOAN CHANNEL/EXISTING DESIGN DRAWINGS

DESIGN FLOW (Q = 6000 cfs)

STATION	FLOW	DEPTH	INV.ELV	CWSEL	LB.ELV	LB.ELV	VCH	FB	FB+DEPTH	CH.DEPTH	
8349.30	6000	5.00	729.19	734.43	735.49	735.89	17.34	1.74	6.7	6.7	
8649.30	6000	5.23	727.92	733.18	734.22	734.62	17.28	1.75	7.0	6.7	
8949.30	6000	5.26	726.65	731.93	732.95	733.35	17.26	1.75	7.0	6.7	
9249.30	6000	5.27	725.39	730.66	731.69	732.09	17.27	1.75	7.0	6.7	
9549.30	6000	5.27	724.12	729.39	730.42	730.82	17.27	1.75	7.0	6.7	
9849.30	6000	5.27	722.86	728.13	729.16	729.56	17.28	1.75	7.0	6.7	
10149.00	6000	5.41	721.70	727.10	728.00	728.40	16.78	1.74	7.1	6.7	
10423.00	6000	5.44	720.43	725.87	728.88	728.13	17.08	1.75	7.2	7.7	
10574.00	6000	5.44	719.80	725.24	728.54	727.84	17.13	1.75	7.2	8.04	
10623.00	6000	6.31	719.55	725.86	727.70	727.70	13.58	1.63	7.9	8.15	
10624.00	6000	7.90	719.54	727.44	727.69	727.69	12.77	1.64	9.5	8.15	7.9
10724.00	6000	8.59	719.04	727.63	727.70	727.70	9.68	1.50	10.1	8.66	8.6
10725.00	6000	4.78	717.90	722.68	726.56	726.56	18.94	1.80	6.6	8.66	
10830.00	6000	5.96	717.80	723.76	723.15	728.10	15.15	1.69	7.6	10.3	
10980.00	6000	4.53	717.52	722.05	723.82	723.82	17.74	1.73	6.3	6.3	
11191.00	6000	5.01	716.35	721.36	723.85	723.85	16.06	1.69	6.7	7.5	
11491.00	6000	4.88	714.99	719.87	722.49	722.49	16.59	1.70	6.6	7.5	
11791.00	6000	4.81	713.63	718.44	721.13	721.13	16.85	1.71	6.5	7.5	
12091.00	6000	4.78	712.27	717.06	719.77	719.77	16.94	1.71	6.5	7.5	
12430.00	6000	4.77	710.74	715.51	718.24	718.24	16.98	1.71	6.5	7.5	

TABLE C3

BRIDGE INFORMATION DESIGN Q=3300 CFS.

STATION	BRIDGE ID.	UPSTREAM INFO DEPTH (FT.)	UPSTREAM INFO VELOCITY (FPS)	BRIDGE INFO B.AREA (SQFT)	BRIDGE INFO PONDING DEPTH (FT.)	BRIDGE INFO Q.THRU (CFS)	BRIDGE INFO WIER Q (CFS)
11937 *		3.86	13.66				
12532	WSHINGTON	3.86	13.66				
12572	BRIDGE			437	5.54	3300	0
12652							
13312 *							
13312 *		3.57	14.92				
15147	BANANZA	3.81	13.87				
15168	5(10'X5')			250	6.3	3300	0
	PCB.						
15268							
[illegible]00							
15890 *							
16888 *		3.59	14.77				
17662	STEWART	4.31	11.94				
17747	8(10'X3.5			280	4.79	3300	0
	RCB.						
17847							
18049							
18349 *							
110149 *		3.89	13.47				
110574	CHARESTON	3.8	14.08				
110623	BRIDGE	3.4	14.86				
110624				437	5.46	3300	0
110724							
110725							
110830							
111791 *							

* CHANNEL TYPICAL CROSS SECTIONS

TABLE C4

BRIDGE INFORMATION DESIGN Q=6000 CFS.

STATION		BRIDGE ID.	UPSTREAM INFO DEPTH (FT.)	UPSTREAM INFO VELOCITY (FPS)	BRIDGE INFO B.AREA (SQFT)	BRIDGE INFO PONDING DEPTH (FT.)	BRIDGE INFO Q.THRU (CFS)	BRIDGE INFO WIER Q (CFS)	DOWNSTREAM INFO. DEPTH (FT.)	DOWNSTREAM INFO. VELOCITY (FPS)
11937	*		5.43	16.83						
12532		WSHINGTON	5.42	16.85						
12572		BRIDGE			437	8.81	5683	319		
12652									8.34	9.87
12712									5.62	16.19
13312	*								5.06	18.24
13312	*		5.06	18.24						
15147		BANANZA	9.32	9.03						
15168		5(10'X5')			250	9.39	3932	2074		
		PCB.								
15268									10.85	10.6
15290									4.26	22.19
15890	*								4.47	21.04
16808	*		5.02	18.37						
17662		STEWART	8.29	10.21						
17747		8(10'X3.5			280	7.14	4296	1727		
		RCB.								
17847									10.24	8.07
18049									4.44	21.01
18349	*								5	18.36
110149	*		5.41	16.78						
110574		CHARESTON	5.44	17.13						
110623		BRIDGE	6.31	13.58						
110624					437	7.9	5580	419		
110724									8.59	9.68
110725									4.78	18.94
110830									4.36	11.91
111791	*								5.01	16.86

* CHANNEL TYPICAL CROSS SECTIONS

DATE

CLIENT CCPW JOB NO 500.710 CALC BY NCL

DESCRIPTION SLOAN CHANNEL - SUPERELEVATION CHECKED BY

SUPERELEVATION FOR REVERSE CURVES SOUTH OF CHARLESTON

EQ. 730 FROM THE CCRFCD MANUAL

$S_e = \frac{V^2 T_W}{g r}$ WHERE: S_e = SUPERELEVATION (ft)

T_W = TOP WIDTH OF FLOW (ft)

g = ACCEL. OF GRAVITY (ft/sec^2)

r = RADIUS OF CURVE (ft)

*CURVE 1 (STA 107+75.83 TO STA 111+91.30)

$r = 853.02$ ft

3300 cfs (X-SECT 10900)

$V = 14.57$ fps

$T_W = 80.97$ ft

$S_e = \frac{(14.57)^2 (80.97)}{(32.17)(853.02)} = 0.62$ ft

6000 cfs

$V = 17.74$ fps

$T_W = 86.14$ ft

$S_e = \frac{(17.74)^2 (86.14)}{(32.17)(853.02)} = 0.99$ ft

(CON'T.)

G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89102

DATE

CLIENT CCPW JOB NO. CALC BY NCI

DESCRIPTION SLOAN CHANNEL - SUPERELEVATION CHECKED BY

*CURVE 2 (STA 1116+00.30 TO 120+30.43)

r = 800 ft

3300 cfs (X-SECT 11791.00)

V = 13.70 ft

TW = 79.62 ft

$$S_e = \frac{(13.70)^2(79.62)}{(32.17)(800)} = \boxed{0.58 \text{ ft}}$$

6000 cfs

V = 16.85 fps

TW = 84.05 ft

$$S_e = \frac{(16.85)^2(84.05)}{(32.17)(800)} = \boxed{0.93 \text{ ft}}$$

EN-3-N

SHEET 2 OF 2

G.C. WALLACE, INC.
Engineering/Architecture
1555 SOUTH RAINBOW BLVD./LAS VEGAS, NEVADA 89102

SUBCRITICAL FLOW

```
**********************************************
*  HEC-2 WATER SURFACE PROFILES              *
*                                            *
*  Version   4.6.2;  May 1991                *
*                                            *
*  RUN DATE    05APR93    TIME   10:27:13     *
**********************************************
```


```
**************************************
*  U.S. ARMY CORPS OF ENGINEERS      *
*  HYDROLOGIC ENGINEERING CENTER     *
*  609 SECOND STREET, SUITE D        *
*  DAVIS, CALIFORNIA 95616-4687      *
*          (916) 756-1104            *
**************************************
```


```
X     X  XXXXXXX   XXXXX             XXXXX
X     X  X        X     X           X     X
X     X  X        X                       X
XXXXXXX  XXXX     X         XXXXX    XXXXX
X     X  X        X                  X
X     X  X        X     X            X
X     X  XXXXXXX  XXXXX              XXXXXXX
```

THIS RUN EXECUTED 05APR93 10:27:18

```
**********************************
 HEC-2 WATER SURFACE PROFILES

 Version  4.6.2;  May 1991
**********************************


T1      SLOAN CHANNEL HYDRAULICS
T2      FROM OWNES AVENUE TO LAS VEGAS WASH CONF
T3      SUBCRITICAL RUN              FILE:SLCH.SUB

J1  ICHECK    INQ       NINV      IDIR      STRT      METRIC    HVINS     Q         WSEL      FQ

       0        2         0         0        -1         0         0         0       732         0

J2  NPROF     IPLOT     PRFVS     XSECV     XSECH     FN        ALLDC     IBW       CHNIM     ITRACE

       0        0        -1         0         0         0        -1         0         0         0


J3  VARIABLE CODES FOR SUMMARY PRINTOUT

     38        43         3        42         1        53        54        55        25        36

NC    .015      .015      .015       .1        .3
ET       2      3300      6000
X1   17410         5         0     32.5         0         0         0
GR  696.33         0    688.68     11.5    688.33     41.25    689.66     71.25    686.83     82.5

X1   17230         0         0         0       180       180       180                 .77

X1   16930         0         0         0       300       300       300                1.29

X1   16630         0         0         0       300       300       300                1.29

X1   16330         0         0         0       300       300       300                1.29

X1   16030         0         0         0       300       300       300                1.29

X1   15730         0         0         0       300       300       300                1.29

X1   15430         0         0         0       300       300       300                1.29

X1   15130         0         0         0       300       300       300                1.29

X1   14900         0         0         0       230       230       230                 .99

X1   14500         0         0         0       400       400       400                1.72
```

X1	14230	0	0	0	270	270	270		1.161	
X1	13930	0	0	0	300	300	300		1.29	
X1	13630	0	0	0	300	300	300		1.29	
X1	13330	0	0	0	300	300	300		1.29	
X1	13030	0	0	0	300	300	300		1.29	
X1	12730	0	0	0	300	300	300		1.29	
X1	12430	0	0	0	300	300	300		1.29	
X1	12091	0	0	0	339	339	339		1.5357	
X1	11791	0	0	0	300	300	300		1.359	
X1	11491	0	0	0	300	300	300		1.359	
X1	11191	5	0	92.5	300	300	300			
GR	723.85	0	716.70	11.25	716.35	46.25	716.70	81.25	723.85	92.5
X1	10900	5	0	93	291	291	291			
GR	723.82	0	717.67	10	717.52	45	717.87	80	723.82	93
X1	10830	5		80	0	0	0			
GR	723.15		718.1	10	717.8	40	718.1	70	728.10	80
X1	10725	0	0	85	105	105	105		.1	
X1	10724	5	0	85	1	1	1			
X3	10							727.3	727.3	
GR	727.7		719.3	13	719.04	45	719.3	75	727.7	85
NC	.015	.015	.015	.3	.4					
SB	.90	1.27	3		62	4	437	1.5	719.55	719.04
X1	10624	0		0	100	100	100		.31	
X2			1	726.15	727.4			1.33		
X3	10							727.4	727.4	
BT	7		727.4		6.5	730		8.5	727.6	
BT	40	727.4		71.5	727.4		73.5	730		80
BT	727.4									
X1	10574	5	0	80	49	49	49			
GR	726.54	0	720.1	10	719.80	40	720.1	70	728.54	80
NC	.015	.015	.015	.1	.3					
X1	10423	5		80	151	151	151			
GR	728.88		720.73	10	720.43	40	720.73	70	726.13	80

X1	10149	0	0	0	274	274	274		1.27	
X1	9849.3			80	300	300	300		1.16	
X1	9549.3			80	300	300	300		1.26	
X1	9249.3			80	300	300	300		1.27	
X1	8949.3			80	300	300	300		1.26	
X1	8649.3			80	300	300	300		1.27	
X1	8349.3			80	300	300	300		1.27	
X1	8156.7	5		80	193	193	193			
GR	736.3		730.3	10	730.6	40	730.3	70	736.7	80
X1	8049.3	5		80	107	107	107			
GR	735.75		730.75	10	730.45	40	730.75	70	736.75	80
X1	7847.5	0	0	0	201.8	199	200		.85	
X3	10							739.07	739.07	
NC	.015	.015	.015	.3	.5					
SB	.50	1.27	3		87	6.8	280		732.2	731.31
X1	7747.5	0	0	0	100	100	100		.90	
X2			1	735.5	739.17			1.33		
X3	10							739.17	739.17	
BT	3		735.1		45	739.1		90	739.1	
X1	7662.6	5		80	83.9	95.2	85.5			
GR	739.1		733.1	10	732.80	40	733.1	70	739.1	80
NC	.015	.015	.015	.1	.3					
X1	7584.7	5		80	77.9	77.9	77.9			
GR	740.03		733.39	10	733.19	40	733.39	70	740.03	80
X1	7480.0	0		80	104.7	104.7	104.7		.5	
X1	7108.7			80	371	371	371		1.82	
X1	6808.7			80	300	300	300		1.47	
X1	6508.7			80	300	300	300		1.47	
X1	6208.7			80	300	300	300		1.47	
X1	6190.1			80	18	18	18		.18	

X1	5890.1			80	300	300	300		2.25	
X1	5590.1			80	300	300	300		2.25	
X1	5484	5		80	106	106	106			
GR	752.34		745.7	10	745.4	40	745.7	70	752.34	80
NC	.015	.015	.015	.2	.4					
X1	5290.1	5		80	194	194	194			
GR	753.79		747.16	10	746.86	40	747.16	70	753.79	80
X1	5268.3	5	0	52.7	21.8	21.8	21.8			
X3	10							755.4	755.4	
GR	754.0		747.0	.1	746.8	25	747.0	52.6	754.0	52.7
NC	.015	.015	.015	.2	.4					
SB	.50	1.27	3		53.7	2.7	250		747.3	746.3
X1	5168.3	0		0	100	100	100		.7	
X2			1	752.5	755.5			1.33		
X3	10							755.5	755.5	
BT	5		756.14		20	755.66		46	755.52	
BT	76	755.62		96	755.72					
X1	5147.3	5		80	20	20	20			
GR	755.5		748.24	10	748.94	40	749.24	70	755.91	80
NC	.015	.015	.015	.2	.4					
X1	5100.0	0	0	0	47.3	47.3	47.3		.19	
X1	4812.2			60	288	288	288		1.47	
X1	4512.2			80	300	300	300		1.53	
X1	4222.0			80	290	290	290		1.53	
X1	4121.0			80	101	101	101		.51	
X1	3912.2			80	209	209	209		1.07	
X1	3612.2			80	300	300	300		1.53	
X1	3312.2			60	300	300	300		1.53	
X1	3012.2			80	300	300	300		1.53	
X1	2712.2	5		60	300	300	300			
GR	768.33		761.66	10	761.36	40	761.66	70	768.33	80

X1	2652.7	7		81	60	60	60			
X3	10							770.4	770.4	
GR	768.7		767.8	.1	762.2	8	761.8	40	762.2	72
GR	767.8	80.9	768.7	81						
SB	.90	1.27	3		62	4	437	1.5	762.1	761.82
X1	2572.7	5		81	80	80	80			
X2			1	758.88	770.13			1.33		
X3	10							770.5	770.5	
BT	7		770.13		6.5	772.8		8.5	770.2	
BT	40	769.68		71.5	770.2		73.5	772.8		80
BT	770.13									
GR	769.4		762.4	10.5	762.1	40.5	762.4	70.5	769.4	81
X1	2532.2	5		81	40.5	40.5	40.5			
GR	769.55		762.55	10.5	762.25	40.5	762.55	70.5	769.55	81
X1	2237.5	5		81	295	295	295			
GR	770.68		763.68	10.5	763.38	40.5	763.63	70.5	770.68	81
X1	1937.5			81	300	300	300		1.155	
X1	1637.5	0	0	0	300	300	300		1.155	
X1	1337.5	0	0	0	300	300	300		1.155	
X1	1037.5	0	0	0	300	300	300		1.155	
X1	737.48	0	0	0	300	300	300		1.155	
X1	437.48	0	0	0	300	300	300		1.155	
X1	137.48	5	0	81	300	300	300			
GR	778.77	0	771.77	10.5	771.47	40.5	771.77	70.5	778.77	81

SECND	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*PROF 1

CRITICAL DEPTH TO BE CALCULATED AT ALL CROSS SECTIONS

CCHV= .100 CEHV= .300
*SECND 17410.000
3720 CRITICAL DEPTH ASSUMED

17410.000	4.56	693.89	693.89	732.00	695.89	1.99	.00	.00	696.83
3300.0	.0	3300.0	.0	.0	291.1	.0	.0	.0	696.83
.00	.00	11.33	.00	.000	.015	.000	.000	689.33	4.52
.002173	0.	0.	0.	0	19	0	.00	73.23	77.88

*SECND 17230.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

17230.000	4.55	694.65	694.65	.00	696.66	2.00	.39	.00	697.60
3300.0	.0	3300.0	.0	.0	290.5	.0	1.2	.3	697.60
.00	.00	11.35	.00	.000	.015	.000	.000	690.10	4.64
.002186	180.	180.	180.	0	5	0	.00	73.23	77.86

*SECND 16930.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

16930.000	4.55	695.95	695.95	.00	697.95	2.00	.66	.00	698.89
3300.0	.0	3300.0	.0	.0	290.6	.0	3.2	.6	698.89
.01	.00	11.35	.00	.000	.015	.000	.000	691.39	4.63
.002185	300.	300.	300.	0	5	0	.00	73.23	77.87

*SECND 16630.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

16630.000	4.55	697.23	697.23	.00	699.24	2.00	.66	.00	700.18
3300.0	.0	3300.0	.0	.0	290.5	.0	5.2	1.3	700.18
.02	.00	11.36	.00	.000	.015	.000	.000	692.68	4.64
.002187	300.	300.	300.	0	5	0	.00	73.23	77.86

*SECND 16330.000
7185 MINIMUM SPECIFIC ENERGY

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	OLOB	OCH	OROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST
3720 CRITICAL DEPTH ASSUMED									
16330.000	4.55	698.52	698.52	.00	700.53	2.00	.66	.00	701.47
3300.0	.0	3300.0	.0	.0	290.6	.0	7.2	1.8	701.47
.03	.00	11.36	.00	.000	.015	.000	.000	693.97	4.63
.002185	300.	300.	300.	0	5	0	.00	73.23	77.87
*SECNO 16030.000									
7185 MINIMUM SPECIFIC ENERGY									
3720 CRITICAL DEPTH ASSUMED									
16030.000	4.55	699.81	699.81	.00	701.82	2.00	.65	.00	702.76
3300.0	.0	3300.0	.0	.0	290.5	.0	9.2	2.3	702.76
.03	.00	11.35	.00	.000	.015	.000	.000	695.26	4.64
.002187	300.	300.	300.	0	5	0	.00	73.23	77.86
*SECNO 15730.000									
7185 MINIMUM SPECIFIC ENERGY									
3720 CRITICAL DEPTH ASSUMED									
15730.000	4.55	701.10	701.10	.00	703.11	2.00	.66	.00	704.05
3300.0	.0	3300.0	.0	.0	290.6	.0	11.2	2.8	704.05
.04	.00	11.35	.00	.000	.015	.000	.000	696.53	4.63
.002183	300.	300.	300.	0	5	0	.00	73.23	77.87
*SECNO 15430.000									
7185 MINIMUM SPECIFIC ENERGY									
3720 CRITICAL DEPTH ASSUMED									
15430.000	4.55	702.39	702.39	.00	704.40	2.00	.66	.00	705.34
3300.0	.0	3300.0	.0	.0	290.5	.0	13.2	3.3	705.34
.05	.00	11.35	.00	.000	.015	.000	.000	697.84	4.64
.002187	300.	300.	300.	0	5	0	.00	73.23	77.86
*SECNO 15130.000									
7185 MINIMUM SPECIFIC ENERGY									
3720 CRITICAL DEPTH ASSUMED									
15130.000	4.55	703.68	703.68	.00	705.69	2.00	.66	.00	706.63
3300.0	.0	3300.0	.0	.0	290.6	.0	15.2	3.8	706.63
.06	.00	11.36	.00	.000	.015	.000	.000	699.13	4.63
.002185	300.	300.	300.	0	5	0	.00	73.23	77.87

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 14900.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

14900.000	4.55	704.67	704.67	.00	706.68	2.00	.50	.00	707.62
3300.0	.0	3300.0	.0	.0	290.5	.0	16.7	4.2	707.62
.06	.00	11.36	.00	.000	.015	.000	.000	700.12	4.64
.002167	230.	230.	230.	0	5	0	.00	73.23	77.86

*SECNO 14500.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

14500.000	4.55	706.35	706.35	.00	708.40	2.00	.67	.00	709.34
3300.0	.0	3300.0	.0	.0	290.6	.0	19.4	4.9	709.34
.07	.00	11.35	.00	.000	.015	.000	.000	701.84	4.63
.002185	400.	400.	400.	0	5	0	.00	73.23	77.87

*SECNO 14230.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

14230.000	4.55	707.55	707.55	.00	709.56	2.00	.55	.00	710.50
3300.0	.0	3300.0	.0	.0	290.3	.0	21.2	5.3	710.50
.06	.00	11.36	.00	.000	.015	.000	.000	703.00	4.64
.002187	270.	270.	270.	0	5	0	.00	73.23	77.86

*SECNO 13930.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

13930.000	4.55	708.84	708.84	.00	710.85	2.00	.66	.00	711.79
3300.0	.0	3300.0	.0	.0	290.6	.0	23.2	5.9	711.79
.09	.00	11.36	.00	.000	.015	.000	.000	704.29	4.64
.002186	300.	300.	300.	0	5	0	.00	73.23	77.86

*SECNO 13630.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

13630.000	4.55	710.14	710.14	.00	712.14	2.00	.66	.00	713.08
3300.0	.0	3300.0	.0	.0	290.6	.0	25.2	6.4	713.08
.09	.00	11.36	.00	.000	.015	.000	.000	705.58	4.63
.002185	300.	300.	300.	0	5	0	.00	73.23	77.87

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 13330.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

13330.000	4.55	711.42	711.42	.00	713.43	2.00	.66	.00	714.37
3300.0	.0	3300.0	.0	.0	290.5	.0	27.2	6.9	714.37
.10	.00	11.36	.00	.000	.015	.000	.000	706.87	4.64
.002187	300.	300.	300.	0	5	0	.00	73.23	77.86

*SECNO 13030.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

13030.000	4.55	712.72	712.72	.00	714.72	2.00	.66	.00	715.66
3300.0	.0	3300.0	.0	.0	290.6	.0	29.2	7.4	715.66
.11	.00	11.35	.00	.000	.015	.000	.000	708.15	4.53
.002185	300.	300.	300.	0	5	0	.00	73.23	77.87

*SECNO 12730.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

12730.000	4.55	714.00	714.00	.00	716.01	2.00	.66	.00	716.95
3300.0	.0	3300.0	.0	.0	290.5	.0	31.2	7.9	716.95
.11	.00	11.36	.00	.000	.015	.000	.000	709.45	4.64
.002187	300.	300.	300.	0	5	0	.00	73.23	77.86

*SECNO 12430.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

12430.000	4.55	715.30	715.30	.00	717.30	2.00	.66	.00	718.24
3300.0	.0	3300.0	.0	.0	290.6	.0	33.2	8.4	718.24
.12	.00	11.35	.00	.000	.015	.000	.000	710.74	4.63
.002185	300.	300.	300.	0	5	0	.00	73.23	77.87

*SECNO 12091.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

12091.000	4.55	716.83	716.83	.00	718.83	2.00	.74	.00	719.78
3300.0	.0	3300.0	.0	.0	290.5	.0	35.5	8.9	719.78
.13	.00	11.36	.00	.000	.015	.000	.000	712.29	4.64
.002187	339.	339.	339.	0	5	0	.00	73.23	77.86

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	CLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 11791.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

11791.000	4.55	718.19	718.19	.00	720.19	2.00	.66	.00	721.14
3300.0	.0	3300.0	.0	.0	290.6	.0	37.5	9.4	721.14
.14	.00	11.36	.00	.000	.015	.000	.000	713.64	4.64
.002186	300.	300.	300.	0	5	0	.00	73.23	77.86

*SECNO 11491.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

11491.000	4.55	719.55	719.55	.00	721.55	2.00	.66	.00	722.49
3300.0	.0	3300.0	.0	.0	290.6	.0	35.5	10.0	722.49
.14	.00	11.36	.00	.000	.015	.000	.000	714.99	4.63
.002185	300.	300.	300.	0	5	0	.00	73.23	77.87

*SECNO 11191.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

11191.000	4.18	720.51	720.51	.00	722.37	1.86	.65	.01	723.65
3300.0	.0	3300.0	.0	.0	301.4	.0	41.5	10.5	723.35
.15	.00	10.95	.00	.000	.015	.000	.000	715.35	5.26
.002220	300.	300.	300.	0	11	0	.00	81.97	87.24

*SECNO 10900.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

10900.000	4.13	721.65	721.65	.00	723.47	1.82	.65	.00	723.82
3300.0	.0	3300.0	.0	.0	304.5	.0	43.5	11.0	723.82
.16	.00	10.84	.00	.000	.015	.000	.000	717.52	3.65
.002234	291.	291.	291.	0	3	0	.00	84.61	88.26

*SECNO 10830.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

10830.000	4.53	722.33	722.33	.00	724.35	2.01	.00	.06	723.15
3300.0	.0	3300.0	.0	.0	288.7	.0	43.5	11.0	723.10
.16	.00	11.39	.00	.000	.015	.000	.000	717.80	1.52
.002195	0.	0.	0.	0	8	0	.00	72.62	74.23

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 10725.000

3301 HV CHANGED MORE THAN HVINS

10725.000	5.23	723.13	722.43	.00	724.58	1.45	.16	.06	723.25
3300.0	.0	3300.0	.0	.0	341.1	.0	44.3	11.2	728.20
.16	.00	9.68	.00	.000	.015	.000	.000	717.90	.24
.001332	105.	105.	105.	5	5	0	.00	74.69	74.93

*SECNO 10724.000

3301 HV CHANGED MORE THAN HVINS

7165 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3495 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 727.30 ELREA= 727.30

10724.000	4.44	723.48	723.48	.00	725.47	1.99	.00	.16	727.70
3300.0	.0	3300.0	.0	.0	291.5	.0	44.3	11.2	727.70
.16	.00	11.32	.00	.000	.015	.000	.000	719.04	5.52
.002164	1.	1.	1.	0	11	0	.00	73.45	75.58

CCHV= .200 CEHV= .400

SPECIAL BRIDGE

5227 DOWNSTREAM ELEV IS 722.63 , NOT 723.46 HYDRAULIC JUMP OCCURS DOWNSTREAM (IF LOW FLOW CONTROLS)

SE	XK	XKOR	COFQ	RDLEN	BWC	BWP	FAREA	ES	ELCHU	ELCHD
	.50	1.27	3.00	.00	52.00	4.00	437.00	1.30	719.55	715.04

*SECNO 10624.000

3301 HV CHANGED MORE THAN HVINS

3302 WARNING: CONVEYANCE CHANGE OUTSIDE OF ACCEPTABLE RANGE, KRATIO = 1.46

CLASS 2 LOW FLOW

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

3420 BRIDGE W.S.= 723.76 BRIDGE VELOCITY= 11.42 CALCULATED CHANNEL AREA= 271.

EGPRS	EGLWC	H3	DWEIR	QLOW	BAREA	TRAPEZOID AREA	ELLC	ELTRD	WEIRLN
724.61	726.30	.00	0.	3300.	437.	448.	726.15	727.40	0.

3495 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 727.40 ELREA= 727.40

10624.000	5.54	725.09	.00	.00	726.30	1.21	.33	.00	726.21
3300.0	.0	3300.0	.0	.0	373.4	.0	45.1	11.4	726.21
.17	.00	8.84	.00	.000	.015	.000	.000	719.35	4.83
.001019	100.	100.	100.	0	0	0	.00	76.45	31.25

*SECNO 10574.000

10574.000	5.12	724.92	724.35	.00	726.51	1.59	.06	.15	728.54
3300.0	.0	3300.0	.0	.0	326.0	.0	45.5	11.5	728.54
.17	.00	10.12	.00	.000	.015	.000	.000	715.30	4.26
.001471	49.	49.	49.	2	15	0	.00	71.43	75.72

CCHV= .100 CEHV= .300
*SECNO 10423.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

10423.000	4.55	724.98	724.98	.00	727.03	2.05	.27	.14	728.58
3300.0	.0	3300.0	.0	.0	287.3	.0	46.5	11.7	728.13
.17	.00	11.49	.00	.000	.015	.000	.000	720.43	4.78
.002197	151.	151.	151.	0	11	0	.00	70.96	75.74

*SECNO 10149.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

10149.000	4.56	726.26	726.26	.00	728.30	2.04	.60	.00	730.15
3300.0	.0	3300.0	.0	.0	287.6	.0	48.3	12.2	729.40
.18	.00	11.47	.00	.000	.015	.000	.000	721.70	4.78
.002190	274.	274.	274.	0	5	0	.00	70.97	75.75

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

+SECNO 8349.300
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

8349.300	4.55	733.74	733.74	.00	735.79	2.04	.66	.00	737.64
3300.0	.0	3300.0	.0	.0	287.6	.0	60.2	15.1	736.89
.22	.00	11.46	.00	.000	.015	.000	.000	729.15	4.76
.002192	300.	300.	300.	0	5	0	.00	70.97	75.75

+SECNO 8156.700
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

8156.700	4.51	734.51	734.51	.00	736.52	2.00	.48	.00	736.30
3300.0	.0	3300.0	.0	.0	290.6	.0	61.5	15.4	736.79
.23	.00	11.35	.00	.000	.015	.000	.000	730.01	2.95
.002198	193.	193.	193.	0	5	0	.00	73.61	76.53

+SECNO 8049.300
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

8049.300	4.52	734.97	734.97	.00	736.95	1.99	.43	.00	736.75
3300.0	.0	3300.0	.0	.0	291.7	.0	62.2	15.6	736.75
.23	.00	11.31	.00	.000	.015	.000	.000	730.45	2.97
.002183	107.	107.	107.	0	5	0	.00	74.06	77.03

+SECNO 7847.300
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3455 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 739.07 ELREA= 739.07

7847.300	4.52	735.82	735.82	.00	737.80	1.99	.44	.00	737.60
3300.0	.0	3300.0	.0	.0	291.7	.0	63.5	15.9	737.60
.23	.00	11.31	.00	.000	.015	.000	.000	731.30	2.97
.002186	202.	200.	199.	0	5	0	.00	74.06	77.03

CCHV= .300 CEHV= .500

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	QLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

SPECIAL BRIDGE

5227 DOWNSTREAM ELEV IS 734.17 , NOT 735.82 HYDRAULIC JUMP OCCURS DOWNSTREAM (IF LOW FLOW CONTROLS)

SB	XK	XKOR	COFQ	RDLEN	BWC	BWP	BAREA	SS	ELCHU	ELCHD
	.90	1.27	3.00	.00	87.00	6.50	280.00	.00	732.20	731.31

*SECNO 7747.500
PRESS FLOW BECAUSE EGLWC OF 738.73 EXCEEDS 1.5 DEPTH
PRESSURE FLOW

EGPRS	EGLWC	H3	QWEIR	QPR	BAREA	TRAPEZOID AREA	ELLC	ELTRD	WEIRLN
738.56	738.73	.00	0.	3300.	280.	265.	735.50	739.17	0.

3685 20 TRIALS ATTEMPTED WSEL,CWSEL
3710 WSEL ASSUMED BASED ON MIN DIFF
3693 PROBABLE MINIMUM SPECIFIC ENERGY

3493 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 739.17 ELREA= 739.17

7747.500	4.52	736.72	736.72	.00	738.70	1.98	.22	.03	738.50
3300.0	.0	3300.0	.0	.0	292.1	.0	64.2	16.1	738.50
.24	.00	11.30	.00	.000	.015	.000	.000	732.20	2.96
.002176	100.	100.	100.	20	5	0	.00	74.06	77.04

*SECNO 7662.600
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

7662.500	4.52	737.32	737.32	.00	739.30	1.99	.20	.00	739.10
3300.0	.0	3300.0	.0	.0	291.6	.0	64.8	16.3	739.10
.24	.00	11.32	.00	.000	.015	.000	.000	732.80	2.97
.002188	84.	90.	95.	0	3	0	.00	74.05	77.03

CCHV= .100 CEHV= .300
*SECNO 7584.700
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

7584.700	4.47	737.66	737.66	.00	739.68	2.02	.17	.01	740.03
3300.0	.0	3300.0	.0	.0	289.3	.0	65.3	16.4	740.03
.24	.00	11.40	.00	.000	.015	.000	.000	733.19	3.57
.002204	78.	78.	76.	0	5	0	.00	72.85	76.43

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	OLOB	QCH	OROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 6190.100
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

6190.100	4.46	744.58	744.58	.00	746.59	2.01	.04	.00	746.94
3300.0	.0	3300.0	.0	.0	290.1	.0	74.6	18.7	746.94
.27	.00	11.38	.00	.000	.015	.000	.000	740.10	3.56
.002150	18.	18.	18.	0	5	0	.00	72.88	76.44

*SECNO 5890.100
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

5890.100	4.46	746.83	746.83	.00	748.84	2.01	.55	.00	749.19
3300.0	.0	3300.0	.0	.0	290.2	.0	76.6	19.2	749.19
.28	.00	11.37	.00	.000	.015	.000	.000	742.35	3.56
.002168	300.	300.	300.	0	5	0	.00	72.86	76.44

*SECNO 5590.100
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

5590.100	4.46	749.08	749.08	.00	751.09	2.01	.66	.00	751.44
3300.0	.0	3300.0	.0	.0	290.1	.0	78.6	19.7	751.44
.25	.00	11.38	.00	.000	.015	.000	.000	744.60	3.56
.002190	300.	300.	300.	0	5	0	.00	72.88	76.44

*SECNO 5484.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

5484.000	4.54	749.94	749.94	.00	751.94	2.00	.23	.00	752.34
3300.0	.0	3300.0	.0	.0	290.7	.0	79.3	19.9	752.34
.29	.00	11.35	.00	.000	.015	.000	.000	745.40	3.61
.002170	106.	106.	106.	0	5	0	.00	72.78	76.39

CCHV= .200 CEHV= .400
*SECNO 5290.100
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

5290.100	4.53	751.39	751.39	.00	753.40	2.01	.42	.01	753.79
3300.0	.0	3300.0	.0	.0	289.7	.0	80.6	20.2	753.79
.30	.00	11.39	.00	.000	.015	.000	.000	746.86	3.62
.002192	194.	194.	194.	0	5	0	.00	72.76	76.38

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 5268.300
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3455 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 755.40 ELREA= 755.40

5268.300	3.06	751.86	751.86	.00	754.35	2.49	.05	.19	754.00
3300.0	.0	3300.0	.0	.0	260.5	.0	60.8	20.3	754.00
.30	.00	12.67	.00	.000	.015	.000	.000	746.80	.03
.002422	22.	22.	22.	0	3	0	.00	52.64	52.67

CCHV= .200 CEHV= .400

SPECIAL BRIDGE

5227 DOWNSTREAM ELEV IS 750.95 , NOT 751.86 HYDRAULIC JUMP OCCURS DOWNSTREAM (IF LOW FLOW CONTROLS)

SB	XR	XKOR	CDFG	RDLEN	BWC	BWF	BAREA	SS	ELCHC	ELCHC
	.30	1.27	3.00	.00	52.70	2.70	250.00	.00	747.30	748.30

*SECNO 5168.300
PRESS FLOW BECAUSE EGLWC OF 755.30 EXCEEDS 1.5 DEPTH

3301 HV CHANGED MORE THAN HVINS

PRESSURE FLOW

EGPRS	EGLWC	H3	QWEIR	QPR	BAREA	TRAPEZOID AREA	ELLC	ELTRD	WEIRLN
755.29	755.30	.00	0.	3300.	250.	260.	752.5[illegible]	755.30	0.

3455 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 755.50 ELREA= 755.50

5168.300	6.09	753.59	.00	.00	755.29	1.71	.94	.00	754.70
3300.0	.0	3300.0	.0	.0	314.9	.0	81.4	20.4	754.70
.30	.00	10.46	.00	.000	.013	.000	.000	747.50	.02
.001345	100.	100.	100.	4	0	0	.00	52.57	52.53

*SECNO 5147.300
7185 MINIMUM SPECIFIC ENERGY

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	%OL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST
3720 CRITICAL DEPTH ASSUMED									
5147.300	4.53	753.47	753.47	.00	755.49	2.01	.03	.12	755.90
3300.0	.0	3300.0	.0	.0	289.6	.0	81.6	20.4	755.91
.30	.00	11.39	.00	.000	.015	.000	.000	748.54	3.64
.002188	20.	20.	20.	0	15	0	.00	72.70	76.35
CCHV= .200 CEHV= .400									
*SECNO 5100.000									
7185 MINIMUM SPECIFIC ENERGY									
3720 CRITICAL DEPTH ASSUMED									
5100.000	4.53	753.66	753.66	.00	755.68	2.01	.10	.00	756.09
3300.0	.0	3300.0	.0	.0	289.9	.0	81.9	20.5	756.10
.30	.00	11.38	.00	.000	.015	.000	.000	749.13	3.64
.002187	47.	47.	47.	0	5	0	.00	72.70	76.35
*SECNO 4812.300									
7185 MINIMUM SPECIFIC ENERGY									
3720 CRITICAL DEPTH ASSUMED									
4812.200	4.53	755.13	755.13	.00	757.15	2.01	.63	.00	757.56
3300.0	.0	3300.0	.0	.0	286.3	.0	83.8	21.0	757.57
.31	.00	11.38	.00	.000	.015	.000	.000	750.60	3.64
.002187	288.	288.	288.	0	5	0	.00	72.70	76.35
*SECNO 4512.200									
7185 MINIMUM SPECIFIC ENERGY									
3720 CRITICAL DEPTH ASSUMED									
4512.200	4.53	756.66	756.66	.00	758.68	2.01	.66	.00	759.09
3300.0	.0	3300.0	.0	.0	289.9	.0	85.8	21.5	759.10
.32	.00	11.38	.00	.000	.015	.000	.000	752.13	3.64
.002187	300.	300.	300.	0	5	0	.00	72.70	76.35
*SECNO 4222.000									
7185 MINIMUM SPECIFIC ENERGY									
3720 CRITICAL DEPTH ASSUMED									
4222.000	4.53	758.19	758.19	.00	760.21	2.01	.63	.00	760.62
3300.0	.0	3300.0	.0	.0	289.9	.0	87.7	22.0	760.63
.32	.00	11.38	.00	.000	.015	.000	.000	753.66	3.64
.002187	290.	290.	290.	0	5	0	.00	72.70	76.35

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	OLOB	OCH	OROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 4121.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

4121.000	4.53	758.70	758.70	.00	760.72	2.01	.22	.00	761.13
3300.0	.0	3300.0	.0	.0	289.9	.0	88.4	22.1	761.14
.32	.00	11.38	.00	.000	.015	.000	.000	754.17	3.64
.002187	101.	101.	101.	0	5	0	.00	72.70	76.35

*SECNO 3912.200
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3912.200	4.53	759.77	759.77	.00	761.79	2.01	.46	.00	762.20
3300.0	.0	3300.0	.0	.0	289.9	.0	89.6	22.5	762.21
.33	.00	11.38	.00	.000	.015	.000	.000	755.24	3.64
.002187	209.	209.	209.	0	5	0	.00	72.70	76.35

*SECNO 3612.200
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3612.200	4.53	761.30	761.30	.00	763.32	2.01	.66	.00	763.73
3300.0	.0	3300.0	.0	.0	289.9	.0	91.8	23.0	763.74
.34	.00	11.38	.00	.000	.015	.000	.000	756.77	3.64
.002187	300.	300.	300.	0	5	0	.00	72.70	76.35

*SECNO 3312.200
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3312.200	4.53	762.83	762.83	.00	764.85	2.01	.65	.00	765.26
3300.0	.0	3300.0	.0	.0	289.9	.0	93.8	23.5	765.27
.34	.00	11.38	.00	.000	.015	.000	.000	758.30	3.64
.002187	300.	300.	300.	0	5	0	.00	72.70	76.35

*SECNO 3012.200
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3012.200	4.53	764.36	764.36	.00	766.38	2.01	.65	.00	766.79
3300.0	.0	3300.0	.0	.0	289.9	.0	95.3	24.0	766.80
.33	.00	11.38	.00	.000	.015	.000	.000	759.83	3.64
.002187	300.	300.	300.	0	5	0	.00	72.70	76.35

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 2712.200
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

2712.200	4.53	765.89	765.89	.00	767.91	2.01	.66	.00	766.33
3300.0	.0	3300.0	.0	.0	289.9	.0	97.8	24.5	768.33
.35	.00	11.38	.00	.000	.015	.000	.000	761.36	3.65
.002187	300.	300.	300.	0	5	0	.00	72.69	76.35

*SECNO 2552.700
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3495 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 770.40 ELREA= 770.40

2552.700	4.43	766.23	766.23	.00	768.17	1.95	.13	.01	768.70
3300.0	.0	3300.0	.0	.0	334.7	.0	38.2	24.6	768.70
.35	.00	11.20	.00	.000	.015	.000	.000	761.80	3.32
.002189	60.	60.	60.	0	6	0	.00	76.08	76.40

SPECIAL BRIDGE

5227 DOWNSTREAM ELEV IS 765.41 , NOT 766.23 HYDRAULIC JUMP OCCURS DOWNSTREAM (IF LOW FLOW CONTROLS)

SB XK	XKOR	COFQ	ROLEN	BWC	BWP	BAREA	SS	ELCHU	ELCHD
.50	1.27	3.00	.00	82.00	4.00	437.00	1.50	762.11	761.82

*SECNO 2573.700

3301 HV CHANGED MORE THAN HVINS

CLASS B LOW FLOW

3420 BRIDGE W.S.= 766.43 BRIDGE VELOCITY= 11.42 CALCULATED CHANNEL AREA= 273.

EGPRS	EGLWC	H3	QWEIR	QLOW	BAREA	TRAPEZOID AREA	ELLC	ELTRD	WEIRLN
.00	768.87	.00	0.	3300.	437.	462.	768.88	770.13	0.

3495 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 770.50 ELREA= 770.50

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	QLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST
2572.700	5.45	767.55	.00	.00	768.87	1.32	.70	.00	765.40
3300.0	.0	3300.0	.0	.0	357.8	.0	98.8	24.7	769.40
.36	.00	5.22	.00	.000	.015	.000	.000	762.10	2.77
.001146	80.	80.	80.	0	0	0	.00	75.45	78.23
*SECNO 2532.200									
2532.200	5.29	767.54	766.78	.00	768.96	1.41	.05	.04	759.55
3300.0	.0	3300.0	.0	.0	346.2	.0	99.1	24.8	769.55
.36	.00	5.53	.00	.000	.015	.000	.000	762.25	3.01
.001270	41.	41.	41.	2	15	0	.00	74.55	77.99
*SECNO 2237.500									
3301 HV CHANGED MORE THAN HVINS									
7185 MINIMUM SPECIFIC ENERGY									
3720 CRITICAL DEPTH ASSUMED									
2237.500	4.54	767.92	767.92	.00	769.93	2.01	.48	.34	770.63
3300.0	.0	3300.0	.0	.0	350.4	.0	101.3	25.3	770.68
.37	.00	11.37	.00	.000	.015	.000	.000	753.33	4.14
.002176	235.	235.	235.	0	11	0	.00	72.72	76.86
*SECNO 1937.500									
7185 MINIMUM SPECIFIC ENERGY									
3720 CRITICAL DEPTH ASSUMED									
1937.500	4.53	769.07	769.07	.00	771.08	2.01	.55	.00	771.84
3300.0	.0	3300.0	.0	.0	289.8	.0	103.3	25.8	771.84
.38	.00	11.39	.00	.000	.015	.000	.000	764.54	4.15
.002190	300.	300.	300.	3	5	0	.00	72.70	76.85
*SECNO 1637.500									
7185 MINIMUM SPECIFIC ENERGY									
3720 CRITICAL DEPTH ASSUMED									
1637.500	4.53	770.22	770.22	.00	772.24	2.01	.66	.00	772.99
3300.0	.0	3300.0	.0	.0	289.9	.0	105.2	26.3	772.99
.39	.00	11.38	.00	.000	.015	.000	.000	765.69	4.15
.002187	300.	300.	300.	0	5	0	.00	72.70	76.85

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 1337.500
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

1337.500	4.53	771.38	771.38	.00	773.39	2.01	.66	.00	774.15
3300.0	.0	3300.0	.0	.0	289.9	.0	107.2	26.8	774.13
.39	.00	11.38	.00	.000	.015	.000	.000	765.65	4.15
.002187	300.	300.	300.	0	5	0	.00	72.70	76.85

*SECNO 1037.500
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

1037.500	4.53	772.53	772.53	.00	774.55	2.01	.66	.00	775.30
3300.0	.0	3300.0	.0	.0	289.9	.0	109.2	27.3	775.30
.40	.00	11.38	.00	.000	.015	.000	.000	768.00	4.15
.002188	300.	300.	300.	0	5	0	.00	72.70	76.85

*SECNO 737.480
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

737.480	4.53	773.69	773.69	.00	775.70	2.01	.66	.00	776.46
3300.0	.0	3300.0	.0	.0	289.8	.0	111.2	27.8	776.46
.41	.00	11.39	.00	.000	.015	.000	.000	769.16	4.15
.002188	300.	300.	300.	0	5	0	.00	72.70	76.85

*SECNO 437.480
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

437.480	4.53	774.84	774.84	.00	776.85	2.01	.66	.00	777.61
3300.0	.0	3300.0	.0	.0	289.9	.0	113.2	28.3	777.61
.42	.00	11.38	.00	.000	.015	.000	.000	770.31	4.15
.002187	300.	300.	300.	0	5	0	.00	72.70	76.85

*SECNO 137.480
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

137.480	4.53	775.00	776.00	.00	778.02	2.01	.66	.00	778.77
3300.0	.0	3300.0	.0	.0	289.9	.0	115.2	28.8	775.77
.42	.00	11.38	.00	.000	.015	.000	.000	771.47	4.15
.002187	300.	300.	300.	0	5	0	.00	72.70	76.85

```
T1     SLOAN CHANNEL HYDRAULICS
T2     FROM OWNES AVENUE TO LAS VEGAS WASH CONF
T3     SUBCRITICAL RUN              FILE:SLSUB.HI

J1  ICHECK    INQ       NINV      IDIR      STRT      METRIC    AVINS     Q         WSEL      FQ

                3                   0        -1                            0         3

J2  NPROF     IPLOT     PRFVS     XSECV     XSECH     FN        ALLOC     IBW       CHNIM     ITRACE

     15                  -1                                      -1
```

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*PROF 2

CRITICAL DEPTH TO BE CALCULATED AT ALL CROSS SECTIONS

CCHV= .100 CEHV= .300
*SECNO 17410.000
2096 WSEL NOT GIVEN, AVG OF MAX, MIN USED
3720 CRITICAL DEPTH ASSUMED

17410.000	6.57	695.90	695.90	.00	698.73	2.83	.00	.00	696.83
6000.0	.0	6000.0	.0	.0	444.8	.0	.0	.0	696.83
.00	.00	13.45	.00	.000	.015	.000	.000	689.33	1.46
.001383	0.	0.	0.	0	13	0	.00	79.58	81.04

*SECNO 17230.000
7135 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

17230.000	6.58	696.68	696.68	.00	699.50	2.82	.38	.00	697.80
6000.0	.0	6000.0	.0	.0	445.1	.0	1.8	.3	697.80
.01	.00	13.46	.00	.000	.015	.000	.000	690.10	1.45
.001980	180.	180.	180.	0	5	0	.00	79.39	81.05

*SECNO 16930.000
7135 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

16930.000	6.58	697.97	697.97	.00	700.79	2.82	.39	.00	698.85
6000.0	.0	6000.0	.0	.0	445.0	.0	4.9	.9	698.85
.01	.00	13.46	.00	.000	.015	.000	.000	691.39	1.45
.001980	300.	300.	300.	0	5	0	.00	79.59	81.05

*SECNO 16630.000
7135 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

16630.000	6.58	699.26	699.26	.00	702.08	2.82	.59	.00	700.18
6000.0	.0	6000.0	.0	.0	445.0	.0	8.0	1.4	700.18
.02	.00	13.46	.00	.000	.015	.000	.000	692.68	1.45
.001980	300.	300.	300.	0	5	0	.00	79.39	81.05

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

+SECNO 16330.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

16330.000	6.58	700.55	700.55	.00	703.37	2.82	.59	.00	701.47
6000.0	.0	6000.0	.0	.0	445.0	.0	11.0	2.0	701.47
.02	.00	13.48	.00	.000	.015	.000	.000	593.97	1.45
.001980	300.	300.	300.	0	5	0	.00	79.59	81.05

+SECNO 16030.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

16030.000	6.58	701.84	701.84	.00	704.66	2.82	.59	.00	702.76
6000.0	.0	6000.0	.0	.0	445.0	.0	14.1	2.5	702.76
.03	.00	13.48	.00	.000	.015	.000	.000	595.26	1.45
.001980	300.	300.	300.	0	5	0	.00	79.59	81.05

+SECNO 15730.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

15730.000	6.58	703.13	703.13	.00	705.95	2.82	.59	.00	704.05
6000.0	.0	6000.0	.0	.0	445.0	.0	17.2	3.1	704.05
.03	.00	13.48	.00	.000	.015	.000	.000	596.55	1.45
.001980	300.	300.	300.	0	5	0	.00	79.59	81.05

+SECNO 15430.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

15430.000	6.58	704.42	704.42	.00	707.24	2.82	.59	.00	705.34
6000.0	.0	6000.0	.0	.0	445.0	.0	20.3	3.6	705.34
.04	.00	13.48	.00	.000	.015	.000	.000	597.34	1.45
.001980	300.	300.	300.	0	5	0	.00	79.59	81.05

+SECNO 15130.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

15130.000	6.58	705.71	705.71	.00	708.53	2.82	.59	.00	706.63
6000.0	.0	6000.0	.0	.0	445.0	.0	23.3	4.2	706.63
.05	.00	13.48	.00	.000	.015	.000	.000	598.13	1.45
.001980	300.	300.	300.	0	5	0	.00	79.59	81.05

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 14900.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

14900.000	6.58	706.70	706.70	.00	709.52	2.82	.46	.00	707.62
6000.0	.0	6000.0	.0	.0	445.0	.0	25.6	4.6	707.62
.05	.00	13.48	.00	.000	.015	.000	.000	700.12	1.45
.001980	230.	230.	230.	0	3	0	.00	79.59	81.05

*SECNO 14500.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

14500.000	6.58	706.42	706.42	.00	711.24	2.82	.79	.00	709.34
6000.0	.0	6000.0	.0	.0	445.0	.0	29.7	5.3	709.34
.05	.00	13.48	.00	.000	.015	.000	.000	701.84	1.45
.001980	400.	400.	400.	0	5	0	.00	79.59	81.05

*SECNO 14230.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

14230.000	6.58	709.58	709.58	.00	712.40	2.82	.53	.00	710.50
6000.0	.0	6000.0	.0	.0	445.0	.0	32.5	5.8	710.50
.07	.00	13.48	.00	.000	.015	.000	.000	703.00	1.45
.001980	270.	270.	270.	0	3	0	.00	79.59	81.05

*SECNO 13930.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

13930.000	6.58	710.87	710.87	.00	713.69	2.82	.59	.00	711.79
6000.0	.0	6000.0	.0	.0	445.0	.0	35.6	6.4	711.79
.07	.00	13.48	.00	.000	.015	.000	.000	704.29	1.45
.001980	300.	300.	300.	0	5	0	.00	79.59	81.05

*SECNO 13630.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

13630.000	6.58	712.16	712.16	.00	714.98	2.82	.59	.00	713.08
6000.0	.0	6000.0	.0	.0	445.0	.0	38.6	6.9	713.08
.08	.00	13.48	.00	.000	.015	.000	.000	705.53	1.45
.001980	300.	300.	300.	0	5	0	.00	79.59	81.05

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

```
*SECNO 13330.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED
 13330.000     6.58   713.45   713.45      .00   716.27     2.82      .59      .00   714.37
    6000.0       .0   6000.0       .0       .0    445.0       .0     41.7      7.5   714.37
       .08      .00    13.48      .00     .000     .015     .000     .000   706.87     1.45
   .001980     300.     300.     300.        0        5        0      .00    79.59    81.03


*SECNO 13030.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED
 13330.000     6.58   714.74   714.74      .00   717.58     2.82      .59      .00   715.66
    6000.0       .0   6000.0       .0       .0    445.0       .0     44.7      8.0   715.66
       .08      .00    13.48      .00     .000     .015     .000     .000   708.18     1.45
   .001980     300.     300.     300.        0        5        0      .00    79.59    81.03


*SECNO 12730.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED
 12730.000     6.58   716.03   716.03      .00   718.85     2.82      .59      .00   715.98
    6000.0       .0   6000.0       .0       .0    445.0       .0     47.8      8.6   716.98
       .10      .00    13.48      .00     .000     .015     .000     .000   709.45     1.45
   .001980     300.     300.     300.        0        5        0      .00    79.59    81.03


*SECNO 12430.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED
 12430.000     6.58   717.32   717.32      .00   720.14     2.82      .59      .00   718.24
    6000.0       .0   6000.0       .0       .0    445.0       .0     50.9      9.1   718.24
       .10      .00    13.48      .00     .000     .015     .000     .000   710.74     1.45
   .001980     300.     300.     300.        0        5        0      .00    79.59    81.03


*SECNO 12091.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED
 12091.000     6.58   716.85   716.85      .00   721.67     2.82      .67      .00   719.78
    6000.0       .0   6000.0       .0       .0    445.0       .0     54.3      9.7   719.78
       .11      .00    13.45      .00     .000     .015     .000     .000   713.25     1.45
   .001980     339.     339.     339.        0        5        0      .00    79.59    81.03
```

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	OLOB	OCH	OROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 11751.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

11751.000	6.58	720.21	720.21	.00	723.03	2.82	.59	.00	721.14
6000.0	.0	6000.0	.0	.0	445.0	.0	57.4	10.3	721.14
.12	.00	13.48	.00	.000	.015	.000	.000	713.54	1.45
.001980	300.	300.	300.	0	5	0	.00	79.59	81.05

*SECNO 11491.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

11491.000	6.58	721.57	721.57	.00	724.39	2.82	.59	.00	722.49
6000.0	.0	6000.0	.0	.0	443.0	.0	60.5	10.8	722.49
.12	.00	13.48	.00	.000	.015	.000	.000	714.89	1.45
.001980	300.	300.	300.	0	5	0	.00	79.53	81.05

*SECNO 11191.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

11191.000	6.02	722.37	722.37	.00	725.01	2.63	.50	.02	723.35
6000.0	.0	6000.0	.0	.0	459.4	.0	53.6	11.4	723.85
.13	.00	13.35	.00	.000	.015	.000	.000	716.35	2.33
.002011	300.	300.	300.	0	11	0	.00	87.83	90.17

*SECNO 10500.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

10500.000	5.55	723.48	723.48	.00	725.18	2.57	.53	.01	723.62
6000.0	.0	6000.0	.0	.0	465.2	.0	66.7	12.0	723.62
.13	.00	12.87	.00	.000	.015	.000	.000	717.52	.56
.002008	291.	291.	291.	3	2	0	.00	91.70	92.27

*SECNO 10830.000
3280 CROSS SECTION 10830.00 EXTENDED 1.17 FEET

7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

10830.000	6.32	724.32	724.32	.00	727.23	2.91	.00	.10	723.15
6000.0	.0	6000.3	.3	.0	433.5	.0	66.7	12.0	728.10
.13	.00	13.55	.00	.000	.015	.000	.000	717.80	.00
.002012	0.	0.	0.	0	8	0	.00	76.23	76.23

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 10725.000
3280 CROSS SECTION 10725.00 EXTENDED 1.58 FEET

3301 HV CHANGED MORE THAN HVINS

10725.000	7.33	725.23	724.43	.00	727.47	2.23	.17	.07	723.23
6000.0	.0	6000.0	.0	.0	500.4	.0	67.8	12.2	728.20
.14	.20	11.55	.00	.000	.015	.000	.000	717.90	.00
.001338	105.	105.	105.	5	5	0	.00	77.03	77.03

*SECNO 10724.000

3301 HV CHANGED MORE THAN HVINS

7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3455 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 727.30 ELREA= 727.30

10724.000	8.44	725.48	725.48	.00	728.32	2.84	.00	.15	727.70
6000.0	.0	6000.0	.0	.0	443.7	.0	67.8	12.2	727.70
.14	.00	13.32	.00	.000	.015	.000	.000	719.04	3.43
.001393	1.	1.	1.	0	11	0	.00	78.53	82.33

CCHV= .200 CEHV= .400

SPECIAL BRIDGE

5227 DOWNSTREAM ELEV IS 724.35 , NOT 725.48 HYDRAULIC JUMP OCCURS DOWNSTREAM (IF LOW FLOW CONTROLS)

SB	XK	XKOR	CDFQ	RDLEN	BWC	BWP	BAREA	BS	ELCHU	ELCHD
	.90	1.27	3.00	.00	62.00	4.00	437.00	1.50	719.55	719.04

*SECNO 10624.000
PRESS FLOW BECAUSE EGLWC OF 730.40 EXCEEDS 1.5 DEPTH
PRESSURE AND WEIR FLOW, Weir Submergence Based on TRAPEZOIDAL Shape

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

EGPRS	EGLWC	H3	QWEIR	QPR	AREA	TRAPEZOID AREA	ELLC	ELTRD	WEIRLN
729.20	730.40	.00	317.	5680.	437.	448.	726.15	727.40	72.

3685 20 TRIALS ATTEMPTED WSEL,CWSEL
3710 WSEL ASSUMED BASED ON MIN DIFF
3693 PROBABLE MINIMUM SPECIFIC ENERGY

3495 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 727.40 ELREA= 727.40

10624.000	6.52	726.97	726.93	.00	728.83	2.76	.20	.30	728.31
6000.0	.0	6000.0	.0	.0	430.1	.0	66.8	12.4	728.31
.14	.00	13.33	.00	.000	.015	.000	.000	719.65	3.31
.001905	100.	100.	100.	20	5	2	.00	75.15	82.46

+SECNO 10574.000
7183 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

10574.000	6.65	726.45	726.45	.00	729.37	3.52	.10	.06	726.54
6000.0	.0	6000.0	.0	.0	437.7	.0	68.3	12.4	728.54
.14	.00	13.71	.00	.000	.015	.000	.000	719.80	2.48
.001975	49.	49.	49.	0	5	0	.00	75.05	77.52

CCHV= .100 CEHV= .300
+SECNO 10423.000
7135 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

10423.000	6.60	727.03	727.03	.00	729.54	2.51	.30	.00	728.56
6000.0	.0	6000.0	.0	.0	438.0	.0	70.5	12.7	728.13
.14	.00	13.70	.00	.000	.015	.000	.000	720.43	2.27
.001595	151.	151.	151.	0	5	0	.00	76.24	76.51

+SECNO 10149.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

10149.000	5.61	728.31	728.31	.00	731.21	2.90	.55	.00	730.15
6000.0	.0	6000.0	.0	.0	438.9	.0	73.6	13.2	729.40
.15	.00	13.67	.00	.000	.015	.000	.000	721.70	2.25
.001987	274.	274.	274.	0	5	0	.00	76.27	78.53

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	AV	aL	QLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 9349.300
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

9849.300	6.61	729.47	729.47	.00	732.37	2.90	.60	.00	731.31
6000.0	.0	6000.0	.0	.0	438.8	.0	76.6	13.7	730.56
.15	.00	13.68	.00	.000	.015	.000	.000	732.86	2.26
.001989	300.	300.	300.	0	5	0	.00	76.26	78.52

*SECNO 9549.300
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

9549.300	6.61	730.73	730.73	.00	733.63	2.90	.61	.00	732.57
6000.0	.0	6000.0	.0	.0	438.8	.0	79.7	14.2	731.82
.16	.00	13.68	.00	.000	.015	.000	.000	734.12	2.25
.001989	300.	300.	300.	0	5	0	.00	76.26	78.52

*SECNO 9249.300
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

9249.300	6.61	732.38	732.00	.38	734.38	2.50	.60	.00	733.34
6000.0	.0	6000.0	.0	.0	438.8	.0	82.7	14.8	733.03
.17	.00	13.68	.00	.000	.015	.000	.000	735.39	2.25
.001989	300.	300.	300.	0	5	0	.00	76.26	78.52

*SECNO 8949.300
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

8949.300	6.61	733.25	733.25	.00	735.15	2.50	.60	.00	735.10
6000.0	.0	6000.0	.0	.0	438.8	.0	85.7	15.3	734.35
.17	.00	13.68	.00	.000	.015	.000	.000	736.65	2.25
.001989	300.	300.	300.	0	5	0	.00	76.26	78.52

*SECNO 8649.300
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

8649.300	6.61	734.53	734.53	.00	737.43	2.90	.60	.00	736.37
6000.0	.0	6000.0	.0	.0	438.8	.0	88.7	15.8	735.62
.18	.00	13.68	.00	.000	.015	.000	.000	737.92	2.25
.001989	300.	300.	300.	0	5	0	.00	76.26	78.52

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
J	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 8349.300
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

8349.300	6.61	735.80	735.80	.00	736.70	2.90	.60	.00	737.64
6000.0	.0	6000.0	.0	.0	436.3	.0	91.8	16.3	736.85
.19	.00	13.68	.00	.000	.015	.000	.000	729.19	2.26
.001585	300.	300.	300.	0	5	0	.00	76.26	76.52

*SECNO 8156.700
3280 CROSS SECTION 8156.70 EXTENDED .21 FEET

7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

8156.700	6.51	735.51	735.51	.00	736.35	2.84	.35	.01	735.30
6000.0	.0	6000.0	.0	.0	443.9	.0	93.7	16.7	736.70
.19	.00	13.52	.00	.000	.015	.000	.000	730.00	.00
.002003	193.	193.	193.	0	5	0	.00	79.70	79.79

*SECNO 8049.300
3280 CROSS SECTION 8049.30 EXTENDED .31 FEET

7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

8049.300	6.51	736.56	736.56	.00	739.77	2.82	.21	.00	736.75
6000.0	.0	6000.0	.0	.0	448.5	.0	94.3	16.9	736.75
.19	.00	13.47	.00	.000	.015	.000	.000	730.45	.00
.001550	107.	107.	107.	0	5	0	.00	80.00	80.00

*SECNO 7847.500
3280 CROSS SECTION 7847.50 EXTENDED .21 FEET

7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3495 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 739.07 ELREA= 739.07

7847.500	6.51	737.81	737.81	.00	740.63	2.82	.40	.00	737.80
6000.0	.0	6000.0	.0	.0	445.6	.0	96.3	17.2	737.60
.20	.00	13.47	.00	.000	.015	.000	.300	731.30	.00
.001982	202.	200.	199.	0	5	0	.00	80.00	80.00

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	QLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

CCHV= .300 CEHV= .500

SPECIAL BRIDGE

5227 DOWNSTREAM ELEV IS 735.57 , NOT 737.81 HYDRAULIC JUMP OCCURS DOWNSTREAM (IF LOW FLOW CONTROLS)

SB	XK	XKOR	COFQ	RDLEN	EWC	BWP	EAREA	SS	ELCHU	ELCHD
	.50	1.27	3.00	.00	37.00	6.80	260.00	.00	732.20	731.31

*SECNO 7747.500
3280 CROSS SECTION 7747.50 EXTENDED 2.85 FEET

3301 HV CHANGED MORE THAN HVINS

3302 WARNING: CONVEYANCE CHANGE OUTSIDE OF ACCEPTABLE RANGE, XRATIO = 1.76

PRESSURE AND WEIR FLOW, Weir Submergence Based on TRAPEZOIDAL Shape

ESPRS	EGLWC	HS	QWEIR	QFR	SAREA	TRAPEZOID AREA	ELLE	ELTRD	WEIRLN
746.86	742.14	.00	1700.	4323.	280.	255.	735.50	735.17	90.

7747.500	8.35	741.15	.00	.00	742.51	1.36	1.89	.00	738.50
6000.0	.0	6000.0	.0	.0	641.2	.0	98.1	17.4	738.50
.20	.00	9.36	.00	.000	.015	.000	.000	732.20	.00
.000638	100.	100.	100.	3	0	2	.00	80.00	80.00

*SECNO 7662.600
3280 CROSS SECTION 7662.60 EXTENDED 1.99 FEET

7662.600	8.29	741.09	739.33	.00	742.70	1.62	.06	.13	739.10
6000.0	.0	6000.0	.0	.0	587.9	.0	99.4	17.6	739.10
.20	.00	10.21	.00	.000	.015	.000	.000	732.80	.00
.000834	84.	90.	95.	2	15	0	.00	80.00	80.00

CCHV= .100 CEHV= .300
*SECNO 7584.700
3280 CROSS SECTION 7584.70 EXTENDED .95 FEET

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL .	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST
7584.700	7.79	740.98	735.69	.00	742.85	1.87	.07	.08	740.03
6000.0	.0	6000.0	.0	.0	547.1	.0	100.4	17.7	740.03
.20	.00	10.97	.00	.000	.015	.000	.000	733.19	.00
.001038	78.	78.	78.	2	15	0	.00	80.00	80.00

*SECNO 7460.000
3280 CROSS SECTION 7460.00 EXTENDED .29 FEET

7460.000	7.13	740.81	740.19	.00	743.10	2.29	.13	.13	740.53
6000.0	.0	6000.0	.0	.0	453.8	.0	101.5	17.5	740.53
.21	.00	12.13	.00	.000	.015	.000	.000	733.65	.00
.001431	105.	105.	105.	2	15	0	.00	80.00	80.00

*SECNO 7106.700

3301 HV CHANGED MORE THAN HVINS

7133 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

7106.700	5.50	742.01	742.01	.00	744.85	2.84	.62	.16	742.33
6000.0	.0	6000.0	.0	.0	443.9	.0	105.6	18.6	742.33
.21	.00	13.52	.00	.000	.015	.000	.000	735.51	.51
.001983	371.	371.	371.	0	11	0	.00	78.38	79.49

*SECNO 6606.700
7133 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

6606.700	5.51	743.43	743.43	.00	746.32	2.83	.59	.00	743.82
6000.0	.0	6000.0	.0	.0	444.3	.0	108.7	19.2	743.82
.22	.00	13.51	.00	.000	.015	.000	.000	736.56	.50
.001978	300.	300.	300.	0	5	0	.00	78.95	79.50

*SECNO 6506.700
7133 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

6506.700	5.51	744.96	744.96	.00	747.79	2.83	.59	.00	745.29
6000.0	.0	6000.0	.0	.0	444.3	.0	111.7	19.7	745.29
.23	.00	13.50	.00	.000	.015	.000	.000	738.45	.50
.001978	300.	300.	300.	0	5	0	.00	79.00	79.50

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	CLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 6208.700
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

6208.700	6.51	746.43	746.43	.00	749.26	2.83	.59	.00	746.75
6000.0	.0	6000.0	.0	.0	444.3	.0	114.8	30.2	746.76
.23	.00	13.50	.00	.000	.015	.000	.000	739.92	.50
.001976	300.	300.	300.	0	5	0	.00	75.00	75.50

*SECNO 6190.100
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

6190.100	6.51	746.51	746.51	.00	749.44	2.93	.59	.00	746.84
6000.0	.0	6000.0	.0	.0	444.3	.0	115.0	30.2	746.84
.23	.00	13.50	.00	.000	.015	.000	.000	740.10	.50
.001976	18.	18.	18.	0	5	0	.00	75.00	75.50

*SECNO 5990.100
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

5990.100	6.51	748.86	748.86	.00	751.69	2.83	.59	.00	748.15
6000.0	.0	6000.0	.0	.0	444.3	.0	118.1	30.8	748.15
.24	.00	13.50	.00	.000	.015	.000	.000	742.35	.50
.001976	300.	300.	300.	0	5	0	.00	75.00	75.50

*SECNO 5590.100
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

5590.100	6.51	751.11	751.11	.00	753.94	2.83	.59	.00	751.44
6000.0	.0	6000.0	.0	.0	444.3	.0	121.1	31.4	751.44
.24	.00	13.50	.00	.000	.015	.000	.000	744.60	.50
.001978	300.	300.	300.	0	5	0	.00	75.00	75.50

*SECNO 5484.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

5484.000	5.57	751.57	751.57	.00	754.80	2.83	.21	.00	752.34
6000.0	.0	6000.0	.0	.0	444.6	.0	133.2	31.6	752.34
.25	.00	13.50	.00	.000	.015	.000	.000	745.40	.55
.001970	106.	106.	106.	0	5	0	.00	73.89	73.45

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	OLOB	OCH	OROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

CCHV= .200 CEHV= .400
*SECNO 5290.100
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

5290.100	6.56	753.42	753.42	.00	756.26	2.84	.38	.00	753.79
6000.0	.0	6000.0	.0	.0	443.9	.0	124.2	21.9	753.79
.25	.00	13.52	.00	.000	.015	.000	.000	746.86	.55
.001980	194.	194.	194.	0	3	0	.00	76.89	79.45

*SECNO 5258.300
3280 CROSS SECTION 5258.30 EXTENDED .25 FEET

3301 HV CHANGED MORE THAN HVINS

7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3495 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 755.40 ELREA= 755.40

5258.300	7.49	754.29	754.29	.00	757.99	3.70	.62	.35	754.11
5000.0	.0	5000.0	.0	.0	385.6	.0	124.4	21.3	754.03
.25	.00	15.44	.00	.000	.015	.000	.000	746.80	.90
.002321	22.	22.	22.	0	8	0	.00	52.70	52.70

CCHV= .200 CEHV= .400

SPECIAL BRIDGE

5297 DOWNSTREAM ELEV IS 753.98 , XQT 754.29 HYDRAULIC JUMP OCCURS DOWNSTREAM (IF LOW FLOW CONTROLS)

SB	XK	XKOR	CDFG	RDLEN	BWC	BWP	BAREA	SS	ELCHU	ELCHD
	.90	1.27	3.00	.00	52.70	2.70	250.00	.00	747.30	745.80

*SECNO 5168.300
3280 CROSS SECTION 5168.30 EXTENDED 2.37 FEET

3301 HV CHANGED MORE THAN HVINS

3302 WARNING: CONVEYANCE CHANGE OUTSIDE OF ACCEPTABLE RANGE, KRATIO = 1.45

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

PRESSURE AND WEIR FLOW, Weir Submergence Based on TRAPEZOIDAL Shape

EGPRS	EGLWC	H3	QWEIR	QPR	BAREA	TRAPEZOID AREA	ELLC	ELTRD	WEIRLN
765.65	760.39	.00	2012.	3993.	250.	250.	752.50	755.50	36.

5168.300	5.57	757.07	.00	.00	759.32	2.25	1.33	.00	754.70
6000.0	.0	6000.0	.0	.0	496.2	.0	125.4	22.1	754.70
.25	.00	13.64	.00	.000	.015	.000	.000	747.50	.00
.001105	100.	100.	100.	4	0	3	.00	52.70	52.70

*SECNO 5147.300
3280 CROSS SECTION 5147.30 EXTENDED 2.36 FEET

3301 HV CHANGED MORE THAN HVINS

5147.300	3.32	758.25	755.51	.00	759.53	1.27	.02	.20	755.30
6000.0	.0	6000.0	.0	.0	564.3	.0	125.8	22.1	755.51
.25	.00	3.03	.00	.000	.015	.000	.000	748.94	.00
.000588	20.	20.	20.	4	14	0	.00	80.00	80.00

CCHV= .300 CEHV= .400
*SECNO 5100.000
3280 CROSS SECTION 5100.00 EXTENDED 2.13 FEET

5100.000	3.12	758.25	755.69	.00	759.58	1.33	.03	.03	756.09
6000.0	.0	6000.0	.0	.0	548.3	.0	126.4	22.2	756.10
.25	.00	3.25	.00	.000	.015	.000	.000	749.13	.00
.000512	47.	47.	47.	3	13	0	.00	80.00	80.00

*SECNO 4812.200
3280 CROSS SECTION 4812.20 EXTENDED .47 FEET

3301 HV CHANGED MORE THAN HVINS

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	CLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

3302 WARNING: CONVEYANCE CHANGE OUTSIDE OF ACCEPTABLE RANGE, KRATIO = .69

4812.200	7.42	758.02	757.16	.00	760.15	2.13	.25	.32	757.56
6000.0	.0	6000.0	.0	.0	512.8	.0	130.2	22.7	757.57
.26	.00	11.70	.00	.000	.015	.000	.000	750.60	.00
.001270	288.	288.	288.	2	15	0	.00	80.00	80.00

+SECNO 4512.200

3301 HV CHANGED MORE THAN HVINS

7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

4512.200	5.56	758.69	758.65	.00	761.53	2.84	.47	.29	759.05
6000.0	.0	6000.0	.0	.0	443.8	.0	133.3	23.3	759.10
.27	.01	13.53	.00	.000	.015	.000	.000	753.13	.60
.001962	300.	300.	300.	0	11	0	.00	78.79	79.39

+SECNO 4222.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

4222.000	5.56	758.22	758.22	.00	761.05	2.84	.37	.00	758.62
6000.0	.0	6000.0	.0	.0	443.8	.0	135.4	23.8	758.63
.27	.00	13.52	.00	.000	.015	.000	.000	753.66	.59
.001979	290.	290.	290.	0	5	0	.00	78.80	79.39

+SECNO 4121.000
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

4121.000	5.56	758.73	758.73	.00	761.57	2.84	.20	.00	759.13
6000.0	.0	6000.0	.0	.0	443.8	.0	137.3	24.0	759.14
.26	.00	13.52	.00	.000	.015	.000	.000	754.17	.59
.001979	101.	101.	101.	0	5	0	.00	78.80	79.39

+SECNO 3912.200
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3912.200	6.56	761.80	761.80	.00	764.64	2.84	.41	.00	762.30
6000.0	.0	6000.0	.0	.0	443.8	.0	139.6	24.3	762.21
.26	.00	13.52	.00	.000	.015	.000	.000	755.24	.59
.001979	209.	209.	209.	0	5	0	.00	78.80	79.39

SECNO	DEPTH	CWSEL	CRIWS	WSELR	EG	HV	HL	DLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 3812.200
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3812.200	5.56	763.33	753.33	.00	765.17	2.84	.59	.00	763.73
6000.0	.0	6000.0	.0	.0	443.7	.0	142.7	24.9	763.74
.29	.00	13.52	.00	.000	.015	.000	.000	755.77	.59
.001980	300.	300.	300.	0	5	0	.00	78.80	79.39

*SECNO 3312.200
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3312.200	5.57	764.87	764.87	.00	767.70	2.84	.59	.00	765.28
6000.0	.0	6000.0	.0	.0	443.8	.0	145.7	23.4	765.27
.29	.00	13.52	.00	.000	.015	.000	.000	758.38	.59
.001979	300.	300.	300.	0	5	0	.00	78.80	79.39

*SECNO 3012.200
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3012.200	5.55	765.39	755.39	.00	768.23	2.84	.59	.00	766.79
6000.0	.0	6000.0	.0	.0	443.7	.0	148.8	26.0	765.80
.30	.00	13.52	.00	.000	.015	.000	.000	759.33	.59
.001980	300.	300.	300.	0	5	0	.00	78.80	79.39

*SECNO 2712.200
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

2712.200	5.55	767.92	767.92	.00	770.75	2.84	.59	.00	768.33
6000.0	.0	6000.0	.0	.0	443.7	.0	151.8	26.5	768.33
.31	.00	13.52	.00	.000	.015	.000	.000	761.35	.61
.001979	300.	300.	300.	0	5	0	.00	78.78	79.39

*SECNO 2652.700
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

3455 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 770.40 ELREA= 770.40

2652.700	6.37	768.17	768.17	.00	770.93	2.78	.13	.01	768.70
6000.0	.0	6000.0	.0	.0	448.3	.0	152.4	25.6	768.70
.31	.00	13.35	.00	.000	.015	.000	.000	761.80	.06
.001585	60.	60.	60.	0	8	0	.00	60.86	60.34

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

SPECIAL BRIDGE

5227 DOWNSTREAM ELEV IS 767.13 , NOT 768.17 HYDRAULIC JUMP OCCURS DOWNSTREAM (IF LOW FLOW CONTROLS)

SB	XK	XKOR	COFQ	RDLEN	BWC	BWP	BAREA	SS	ELCHU	ELCHD
	.30	1.27	3.00	.00	62.00	4.00	437.00	1.50	762.10	761.82

*SECNO 2572.700
PRESSURE AND WEIR FLOW, Weir Submergence Based on TRAPEZOIDAL Shape

ESPRS	EELWC	HS	QWEIR	QPR	BAREA	TRAPEZOID AREA	ELLC	ELTRD	WEIRLN
771.89	771.84	.00	364.	5634.	437.	468.	768.66	770.13	71.

3565 30 TRIALS ATTEMPTED WSEL,CWSEL
3710 WSEL ASSUMED BASED ON MIN DIFF
3593 PROBABLE MINIMUM SPECIFIC ENERGY

3495 OVERBANK AREA ASSUMED NON-EFFECTIVE, ELLEA= 770.50 ELREA= 770.50

2572.700	6.63	768.73	768.66	.00	771.50	2.77	.16	.34	769.40
6000.0	.0	6000.0	.0	.0	443.1	.0	153.3	25.8	769.40
.31	.00	13.36	.00	.000	.015	.000	.000	762.10	1.30
.001910	80.	80.	80.	20	8	2	.00	79.00	80.00

*SECNO 2532.200
7135 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

2532.200	6.54	768.79	768.79	.00	771.65	2.86	.09	.03	769.55
6000.0	.0	6000.0	.0	.0	442.2	.0	153.7	26.8	769.55
.31	.00	13.57	.00	.000	.015	.000	.000	762.25	1.13
.002001	41.	41.	41.	0	5	0	.00	78.73	79.67

*SECNO 2237.500
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

2237.500	6.56	769.94	769.94	.00	772.78	2.84	.55	.00	770.55
6000.0	.0	6000.0	.0	.0	443.6	.0	156.7	27.4	770.68
.31	.00	13.52	.00	.000	.015	.000	.000	763.38	1.10
.001579	295.	295.	295.	0	5	0	.00	78.79	79.90

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOBL	XLCH	XLOBR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 1937.500
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

1937.500	6.56	771.10	771.10	.00	773.94	2.84	.59	.00	771.84
6000.0	.0	6000.0	.0	.0	443.5	.0	159.7	27.9	771.84
.32	.00	13.53	.00	.000	.015	.000	.000	764.54	1.11
.001983	300.	300.	300.	0	5	0	.00	78.76	79.89

*SECNO 1637.500
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

1637.500	6.56	772.25	772.25	.00	775.09	2.84	.59	.00	772.99
6000.0	.0	6000.0	.0	.0	443.5	.0	162.8	28.5	772.99
.33	.00	13.53	.00	.000	.015	.000	.000	763.69	1.11
.001581	300.	300.	300.	0	5	0	.00	78.79	79.89

*SECNO 1337.500
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

1337.500	6.56	773.41	773.41	.00	776.25	2.84	.59	.00	774.15
6000.0	.0	6000.0	.0	.0	443.5	.0	165.8	29.1	774.15
.33	.00	13.53	.00	.000	.015	.000	.000	766.83	1.11
.001983	300.	300.	300.	0	5	0	.00	78.76	79.89

*SECNO 1037.500
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

1037.500	6.56	774.56	774.56	.00	777.40	2.84	.59	.00	775.30
6000.0	.0	6000.0	.0	.0	443.5	.0	168.9	29.5	775.30
.34	.00	13.53	.00	.000	.015	.000	.000	765.00	1.11
.001983	300.	300.	300.	0	5	0	.00	78.79	79.89

*SECNO 737.480
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

737.480	6.56	775.72	775.72	.00	778.56	2.84	.59	.00	776.46
6000.0	.0	6000.0	.0	.0	443.5	.0	172.0	30.1	776.46
.35	.00	13.53	.00	.000	.015	.000	.000	769.15	1.11
.001983	300.	300.	300.	0	5	0	.00	78.76	79.89

SECNO	DEPTH	CWSEL	CRIWS	WSELK	EG	HV	HL	OLOSS	L-BANK ELEV
Q	QLOB	QCH	QROB	ALOB	ACH	AROB	VOL	TWA	R-BANK ELEV
TIME	VLOB	VCH	VROB	XNL	XNCH	XNR	WTN	ELMIN	SSTA
SLOPE	XLOSL	XLCH	XLOSR	ITRIAL	IDC	ICONT	CORAR	TOPWID	ENDST

*SECNO 437.480
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

437.480	6.56	776.87	776.87	.00	779.71	2.84	.59	.00	777.61
6000.0	.0	6000.0	.0	.0	443.6	.0	175.0	30.8	777.61
.35	.00	13.53	.00	.000	.015	.000	.000	770.31	1.11
.001982	300.	300.	300.	0	5	0	.00	76.79	75.83

*SECNO 137.480
7185 MINIMUM SPECIFIC ENERGY
3720 CRITICAL DEPTH ASSUMED

137.480	6.56	773.03	776.03	.00	780.87	3.84	.59	.00	773.77
6000.0	.0	6000.0	.0	.0	443.5	.0	173.1	31.2	778.77
.36	.00	13.53	.00	.000	.015	.000	.000	771.47	1.11
.001982	300.	300.	300.	0	5	0	.00	76.79	75.83

THIS RUN EXECUTED 05APR93 10:45:33

****
HEC-2 WATER SURFACE PROFILES

Version 4.6.2; May 1991
****

NOTE- ASTERISK (*) AT LEFT OF CROSS-SECTION NUMBER INDICATES MESSAGE IN SUMMARY OF ERRORS LIST

SUBCRITICAL RUN

SUMMARY PRINTOUT

	SECNO	Q	DEPTH	ELMIN	CWSEL	SSTA	ENDST	VLOB	VCH	VROB
*	17410.000	3300.00	4.56	688.33	693.85	4.63	77.88	.00	11.33	.00
*	17410.000	6000.00	6.57	689.33	695.90	1.46	81.04	.00	13.49	.00
*	17230.000	3300.00	4.55	690.10	694.65	4.64	77.86	.00	11.36	.00
*	17230.000	6000.00	6.58	690.10	696.68	1.45	81.05	.00	13.48	.00
*	16930.000	3300.00	4.55	691.33	695.95	4.63	77.87	.00	11.35	.00
*	16930.000	6000.00	6.58	691.33	697.97	1.45	81.05	.00	13.48	.00
*	16630.000	3300.00	4.55	692.68	697.23	4.64	77.86	.00	11.36	.00
*	16630.000	6000.00	6.58	692.68	699.26	1.45	81.05	.00	13.48	.00
*	16330.000	3300.00	4.55	693.97	698.52	4.63	77.87	.00	11.36	.00
*	16330.000	6000.00	6.58	693.97	700.55	1.45	81.05	.00	13.48	.00
*	16030.000	3300.00	4.55	695.26	699.81	4.64	77.86	.00	11.36	.00
*	16030.000	6000.00	6.58	695.26	701.84	1.45	81.05	.00	13.48	.00
*	15730.000	3300.00	4.55	696.55	701.10	4.63	77.87	.00	11.35	.00
*	15730.000	6000.00	6.58	696.55	703.13	1.45	81.05	.00	13.48	.00
*	15430.000	3300.00	4.55	697.84	702.39	4.64	77.86	.00	11.36	.00
*	15430.000	6000.00	6.58	697.84	704.42	1.45	81.05	.00	13.48	.00
*	15130.000	3300.00	4.55	699.13	703.68	4.63	77.87	.00	11.36	.00
*	15130.000	6000.00	6.58	699.13	705.71	1.45	81.05	.00	13.48	.00
*	14900.000	3300.00	4.55	700.12	704.67	4.64	77.86	.00	11.36	.00
*	14900.000	6000.00	6.58	700.12	706.70	1.45	81.05	.00	13.48	.00
*	14600.000	3300.00	4.55	701.84	706.39	4.63	77.87	.00	11.35	.00
*	14600.000	6000.00	6.58	701.84	708.42	1.45	81.05	.00	13.48	.00

	SECNO	Q	DEPTH	ELMIN	CWSEL	SSTA	ENDST	VLOB	VCH	VROB
*	14230.000	3300.00	4.55	703.00	707.55	4.64	77.86	.00	11.36	.00
*	14230.000	6000.00	6.58	703.00	709.58	1.45	81.05	.00	13.48	.00
*	13930.000	3300.00	4.55	704.29	708.84	4.64	77.86	.00	11.36	.00
*	13930.000	6000.00	6.56	704.29	710.87	1.45	81.05	.00	13.48	.00
*	13630.000	3300.00	4.53	705.58	710.14	4.63	77.87	.00	11.36	.00
*	13630.000	6000.00	6.53	705.58	712.16	1.45	81.05	.00	13.48	.00
*	13330.000	3300.00	4.52	706.87	711.42	4.64	77.86	.00	11.36	.00
*	13330.000	6000.00	6.56	706.87	713.45	1.45	81.05	.00	13.48	.00
*	13030.000	3300.00	4.55	708.16	712.72	4.63	77.87	.00	11.35	.00
*	13030.000	6000.00	6.58	708.16	714.74	1.45	81.05	.00	13.48	.00
*	12730.000	3300.00	4.55	709.45	714.00	4.64	77.86	.00	11.36	.00
*	12730.000	6000.00	6.53	709.45	715.03	1.45	81.05	.00	13.48	.00
*	12430.000	3300.00	4.55	710.74	715.30	4.63	77.87	.00	11.35	.00
*	12430.000	6000.00	6.58	710.74	717.32	1.45	81.05	.00	13.48	.00
*	12081.000	3300.00	4.55	712.28	716.83	4.64	77.86	.00	11.36	.00
*	12081.000	6000.00	6.58	712.28	718.85	1.45	81.05	.00	13.48	.00
*	11781.000	3300.00	4.55	713.54	718.19	4.64	77.86	.00	11.36	.00
*	11781.000	6000.00	6.58	713.54	720.31	1.45	81.05	.00	13.48	.00
*	11481.000	3300.00	4.52	714.99	719.55	4.63	77.87	.00	11.36	.00
*	11481.000	6000.00	6.53	714.99	721.57	1.45	81.05	.00	13.48	.00
*	11181.000	3300.00	4.16	716.33	720.31	5.26	87.24	.00	10.95	.00
*	11181.000	6000.00	6.02	716.35	722.37	2.33	90.17	.00	13.05	.00
*	10900.000	3300.00	4.13	717.52	721.65	3.65	88.26	.00	10.84	.00
*	10900.000	6000.00	5.95	717.52	723.46	.56	92.27	.00	12.87	.00
*	10630.000	3300.00	4.53	717.80	722.33	1.62	74.23	.00	11.39	.00
*	10630.000	6000.00	6.52	717.80	724.32	.00	76.32	.00	13.53	.00
	10725.000	3300.00	5.23	717.90	723.13	.24	74.93	.00	9.68	.00
	10725.000	6000.00	7.33	717.90	725.23	.00	77.03	.00	11.99	.00
*	10724.000	3300.00	4.44	719.04	723.48	6.52	79.98	.00	11.32	.00
*	10724.000	6000.00	6.44	719.04	725.48	3.43	82.35	.00	13.52	.00
*	10524.000	3300.00	5.54	719.55	725.09	4.83	81.38	.00	8.64	.00
*	10524.000	6000.00	6.52	719.55	726.07	3.31	82.46	.00	13.33	.00
	10574.000	3300.00	5.12	719.80	724.92	4.28	75.72	.00	10.12	.00
*	10574.000	6000.00	6.65	719.80	726.45	2.46	77.52	.00	13.71	.00

	SECND	Q	DEPTH	ELMIN	CWSEL	SSTA	ENDST	VLOB	VCH	VROB
*	10423.000	3300.00	4.55	720.43	724.98	4.78	75.74	.00	11.45	.00
*	10423.000	6000.00	5.60	720.43	727.03	2.27	78.51	.00	13.70	.00
*	10149.000	3300.00	4.56	721.70	726.26	4.78	75.75	.00	11.47	.00
*	10149.000	6000.00	5.61	721.70	728.31	2.26	78.53	.00	13.67	.00
*	9849.300	3300.00	4.55	722.66	727.41	4.78	75.75	.00	11.48	.00
*	9849.300	6000.00	6.61	722.86	729.47	2.26	78.52	.00	13.68	.00
*	9549.300	3300.00	4.55	724.12	728.67	4.78	75.75	.00	11.48	.00
*	9549.300	6000.00	5.61	724.12	730.73	2.26	78.52	.00	13.68	.00
*	9249.300	3300.00	4.55	725.39	729.94	4.78	75.75	.00	11.48	.00
*	9249.300	6000.00	5.61	725.39	732.00	2.26	78.52	.00	13.68	.00
*	8949.300	3300.00	4.55	726.65	731.20	4.78	75.75	.00	11.48	.00
*	8949.300	6000.00	5.61	726.65	733.26	2.26	78.52	.00	13.68	.00
*	8649.300	3300.00	4.55	727.92	732.47	4.78	75.75	.00	11.48	.00
*	8649.300	6000.00	5.61	727.92	734.53	2.26	78.52	.00	13.68	.00
*	8349.300	3300.00	4.55	729.19	733.74	4.78	75.75	.00	11.48	.00
*	8349.300	6000.00	5.61	729.19	735.80	2.26	78.52	.00	13.68	.00
*	8156.700	3300.00	4.51	730.00	734.51	2.98	76.33	.00	11.33	.00
*	8156.700	6000.00	5.51	730.00	736.51	.00	79.70	.00	13.58	.00
*	8049.300	3300.00	4.52	730.45	734.97	2.97	77.03	.00	11.31	.00
*	8049.300	6000.00	5.51	730.45	736.56	.00	80.00	.00	13.47	.00
*	7847.500	3300.00	4.52	731.30	735.82	2.97	77.03	.00	11.31	.00
*	7547.500	6000.00	5.51	731.30	737.81	.00	80.00	.00	13.47	.00
*	7747.500	3300.00	4.52	732.20	736.72	2.96	77.04	.00	11.30	.00
*	7747.500	6000.00	5.55	732.20	741.15	.00	80.00	.00	9.38	.00
*	7662.600	3300.00	4.52	732.80	737.32	2.97	77.03	.00	11.32	.00
	7662.600	6000.00	6.25	732.80	741.09	.00	80.00	.00	10.21	.00
*	7584.700	3300.00	4.47	733.19	737.66	3.57	76.43	.00	11.40	.00
	7584.700	6000.00	7.79	733.19	740.98	.00	80.00	.00	10.97	.00
*	7480.000	3300.00	4.48	733.69	738.17	3.56	76.44	.00	11.37	.00
	7480.000	6000.00	7.12	733.69	740.81	.00	80.00	.00	12.15	.00
*	7108.700	3300.00	4.48	735.51	739.99	3.56	76.44	.00	11.37	.00
*	7108.700	6000.00	5.50	735.51	742.01	.51	79.49	.00	13.53	.00
*	6808.700	3300.00	4.48	736.98	741.46	3.56	76.44	.00	11.37	.00
*	6808.700	6000.00	6.51	736.98	743.49	.50	79.50	.00	13.31	.00

	SECNO	Q	DEPTH	ELMIN	CWSEL	SSTA	ENDST	VLOB	VCH	VROB
*	6508.700	3300.00	4.48	738.45	742.93	3.56	76.44	.00	11.38	.00
*	6508.700	6000.00	6.51	738.45	744.96	.50	79.50	.00	13.50	.00
*	6208.700	3300.00	4.48	739.92	744.40	3.56	76.44	.00	11.37	.00
*	6208.700	6000.00	6.51	739.92	746.43	.50	79.50	.00	13.50	.00
*	6190.100	3300.00	4.48	740.10	744.58	3.56	76.44	.00	11.38	.00
*	6190.100	6000.00	6.51	740.10	746.61	.50	79.50	.00	13.50	.00
*	5890.100	3300.00	4.48	742.35	746.83	3.56	76.44	.00	11.37	.00
*	5890.100	6000.00	6.51	742.35	748.86	.50	79.50	.00	13.50	.00
*	5590.100	3300.00	4.48	744.60	749.08	3.56	76.44	.00	11.38	.00
*	5590.100	6000.00	6.51	744.60	751.11	.50	79.50	.00	13.50	.00
*	5484.000	3300.00	4.54	745.40	749.94	3.61	76.39	.00	11.35	.00
*	5484.000	6000.00	6.57	745.40	751.97	.55	79.45	.00	13.50	.00
*	5290.100	3300.00	4.53	746.86	751.39	3.62	76.38	.00	11.39	.00
*	5290.100	6000.00	6.56	746.86	753.42	.55	79.45	.00	13.52	.00
*	5268.300	3300.00	5.06	746.80	751.86	.03	52.67	.00	12.67	.00
*	5268.300	6000.00	7.45	746.80	754.25	.00	52.70	.00	15.44	.00
*	5168.300	3300.00	5.03	747.50	752.53	.12	53.63	.00	10.48	.00
*	5168.300	6000.00	6.57	747.50	757.07	.00	52.70	.00	12.04	.00
*	5147.300	3300.00	4.53	748.34	752.87	3.64	76.35	.00	11.33	.00
	5147.300	6000.00	5.32	748.34	753.66	.00	80.00	.00	9.33	.00
*	5100.000	3300.00	4.53	749.13	753.66	3.64	76.35	.00	11.38	.00
	5100.000	6000.00	5.12	749.13	754.25	.00	80.00	.00	9.25	.00
*	4812.200	3300.00	4.53	750.60	755.13	3.64	76.35	.00	11.38	.00
*	4812.200	6000.00	7.42	750.60	758.02	.00	80.00	.00	11.70	.00
*	4512.200	3300.00	4.53	752.13	756.66	3.64	76.35	.00	11.38	.00
*	4512.200	6000.00	6.56	752.13	758.69	.60	79.39	.00	13.53	.00
*	4222.000	3300.00	4.53	753.66	758.19	3.64	76.35	.00	11.38	.00
*	4222.000	6000.00	6.56	753.66	760.22	.59	79.39	.00	13.52	.00
*	4121.000	3300.00	4.53	754.17	758.70	3.64	76.35	.00	11.38	.00
*	4121.000	6000.00	6.55	754.17	760.73	.59	79.39	.00	13.52	.00
*	3912.200	3300.00	4.53	755.24	759.77	3.64	76.35	.00	11.38	.00
*	3912.200	6000.00	6.56	755.24	761.80	.59	79.39	.00	13.52	.00
*	3812.200	3300.00	4.53	756.77	761.30	3.64	76.35	.00	11.38	.00
*	3812.200	6000.00	6.56	756.77	763.33	.59	79.39	.00	13.53	.00

	SECNO	Q	DEPTH	ELMIN	CWSEL	SSTA	ENDST	VLOB	VCH	VROB
*	3312.200	3300.00	4.53	758.30	762.83	3.64	76.35	.00	11.38	.00
*	3312.200	6000.00	6.57	758.30	764.87	.59	79.39	.00	13.52	.00
*	3012.200	3300.00	4.53	759.83	764.36	3.64	76.35	.00	11.38	.00
*	3012.200	6000.00	6.56	759.83	766.39	.59	79.39	.00	13.52	.00
*	2712.200	3300.00	4.53	761.36	765.89	3.65	76.35	.00	11.38	.00
*	2712.200	6000.00	6.56	761.36	767.92	.61	79.39	.00	13.52	.00
*	2552.700	3300.00	4.43	761.80	766.23	2.32	78.40	.00	11.20	.00
*	2552.700	6000.00	6.37	761.80	768.17	.06	80.94	.00	13.38	.00
*	2572.700	3300.00	5.45	762.10	767.55	2.77	78.23	.00	9.22	.00
*	2572.700	6000.00	6.83	762.10	768.73	1.00	80.00	.00	13.35	.00
*	2532.200	3300.00	5.25	762.25	767.54	3.01	77.95	.00	9.53	.00
*	2532.200	6000.00	6.54	762.25	768.79	1.13	79.87	.00	13.57	.00
*	2137.500	3300.00	4.84	763.33	767.92	4.14	76.86	.00	11.37	.00
*	2137.500	6000.00	6.56	763.38	769.94	1.10	79.90	.00	13.52	.00
*	1937.500	3300.00	4.83	764.34	769.07	4.13	76.85	.00	11.36	.00
*	1937.500	6000.00	6.56	764.34	771.10	1.11	79.89	.00	13.53	.00
*	1837.500	3300.00	4.83	765.35	770.22	4.15	76.85	.00	11.36	.00
*	1837.500	6000.00	6.56	765.35	772.25	1.11	79.89	.00	13.53	.00
*	1837.500	3300.00	4.83	766.85	771.38	4.15	76.85	.00	11.36	.00
*	1837.500	6000.00	6.56	766.85	773.41	1.11	79.89	.00	13.53	.00
*	1837.500	3300.00	4.83	768.00	772.53	4.15	76.85	.00	11.36	.00
*	1837.500	6000.00	6.56	768.00	774.56	1.11	79.89	.00	13.53	.00
*	737.460	3300.00	4.83	768.16	773.69	4.15	76.85	.00	11.36	.00
*	737.460	6000.00	6.56	768.16	775.72	1.11	79.89	.00	13.53	.00
*	437.460	3300.00	4.83	770.31	774.84	4.15	76.85	.00	11.36	.00
*	437.460	6000.00	6.56	770.31	776.87	1.11	79.89	.00	13.53	.00
*	137.460	3300.00	4.83	771.47	776.00	4.15	76.85	.00	11.38	.00
*	137.460	6000.00	6.56	771.47	778.03	1.11	79.89	.00	13.53	.00

SUMMARY OF ERRORS AND SPECIAL NOTES

CAUTION SECNO= 17410.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 17410.000 PROFILE= 2 CRITICAL DEPTH ASSUMED

CAUTION SECNO= 17230.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 17230.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 17230.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 17230.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 16930.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 16930.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 16930.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 16930.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 16630.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 16630.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 16630.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 16630.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 16330.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 16330.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 16330.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 16330.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 16030.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 16030.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 16030.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 16030.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 15730.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 15730.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 15730.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 15730.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 15430.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 15430.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 15430.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 15430.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 15130.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 15130.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 15130.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 15130.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 14900.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 14900.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 14900.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 14900.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 14600.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 14600.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 14500.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 14230.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 14230.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 14230.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 14230.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 13930.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 13930.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 13930.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 13930.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 13630.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 13630.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 13630.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 13630.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 13330.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 13330.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 13330.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 13330.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 13030.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 13030.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 13030.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 13030.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 12730.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 12730.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 12730.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 12730.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 12430.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 12430.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 12430.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 12430.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 12091.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 12091.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 12091.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 12091.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 11791.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 11791.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 11791.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 11791.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 11491.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 11491.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 11491.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 11491.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 11191.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 11191.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY

```
CAUTION SECNO=  11191.000  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=  11191.000  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=  10900.000  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=  10900.000  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=  10900.000  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=  10900.000  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=  10830.000  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=  10830.000  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=  10830.000  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=  10830.000  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=  10724.000  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=  10724.000  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=  10724.000  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=  10724.000  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=  10624.000  PROFILE=  1  HYDRAULIC JUMP D.S.
WARNING SECNO=  10624.000  PROFILE=  1  CONVEYANCE CHANGE OUTSIDE ACCEPTABLE RANGE
CAUTION SECNO=  10624.000  PROFILE=  2  PROBABLE MINIMUM SPECIFIC ENERGY
CAUTION SECNO=  10624.000  PROFILE=  2  WSEL ASSUMED BASED ON MIN DIFF
CAUTION SECNO=  10624.000  PROFILE=  2  20 TRIALS ATTEMPTED TO BALANCE WSEL
CAUTION SECNO=  10624.000  PROFILE=  2  HYDRAULIC JUMP D.S.

CAUTION SECNO=  10574.000  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=  10574.000  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=  10423.000  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=  10423.000  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=  10423.000  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=  10423.000  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=  10149.000  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=  10149.000  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=  10149.000  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=  10149.000  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   9849.300  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   9849.300  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=   9849.300  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   9849.300  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   9549.300  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   9549.300  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=   9549.300  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   9549.300  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   9249.300  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   9249.300  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=   9249.300  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   9249.300  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   8949.300  PROFILE=  1  CRITICAL DEPTH ASSUMED
```

```
 CAUTION SECNO=   8945.300  PROFILE=  1  MINIMUM SPECIFIC ENERGY
 CAUTION SECNO=   8945.300  PROFILE=  2  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   8945.300  PROFILE=  2  MINIMUM SPECIFIC ENERGY

 CAUTION SECNO=   8649.300  PROFILE=  1  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   8649.300  PROFILE=  1  MINIMUM SPECIFIC ENERGY
 CAUTION SECNO=   8649.300  PROFILE=  2  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   8649.300  PROFILE=  2  MINIMUM SPECIFIC ENERGY

 CAUTION SECNO=   8349.300  PROFILE=  1  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   8349.300  PROFILE=  1  MINIMUM SPECIFIC ENERGY
 CAUTION SECNO=   8349.300  PROFILE=  2  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   8349.300  PROFILE=  2  MINIMUM SPECIFIC ENERGY

 CAUTION SECNO=   8156.700  PROFILE=  1  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   8156.700  PROFILE=  1  MINIMUM SPECIFIC ENERGY
 CAUTION SECNO=   8156.700  PROFILE=  2  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   8156.700  PROFILE=  2  MINIMUM SPECIFIC ENERGY

 CAUTION SECNO=   8049.300  PROFILE=  1  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   8049.300  PROFILE=  1  MINIMUM SPECIFIC ENERGY
 CAUTION SECNO=   8049.300  PROFILE=  2  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   8049.300  PROFILE=  2  MINIMUM SPECIFIC ENERGY

 CAUTION SECNO=   7847.500  PROFILE=  1  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   7847.500  PROFILE=  1  MINIMUM SPECIFIC ENERGY
 CAUTION SECNO=   7847.500  PROFILE=  2  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   7847.500  PROFILE=  2  MINIMUM SPECIFIC ENERGY

 CAUTION SECNO=   7747.500  PROFILE=  1  PREVABLE MINIMUM SPECIFIC ENERGY
 CAUTION SECNO=   7747.500  PROFILE=  1  WSEL ASSUMED BASED ON MIN DIFF
 CAUTION SECNO=   7747.500  PROFILE=  1  20 TRIALS ATTEMPTED TO BALANCE WSEL
 CAUTION SECNO=   7747.500  PROFILE=  1  HYDRAULIC JUMP D.S.
 CAUTION SECNO=   7747.500  PROFILE=  2  HYDRAULIC JUMP D.S.
 WARNING SECNO=   7747.500  PROFILE=  2  CONVEYANCE CHANGE OUTSIDE ACCEPTABLE RANGE

 CAUTION SECNO=   7682.600  PROFILE=  1  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   7682.600  PROFILE=  1  MINIMUM SPECIFIC ENERGY

 CAUTION SECNO=   7584.700  PROFILE=  1  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   7584.700  PROFILE=  1  MINIMUM SPECIFIC ENERGY

 CAUTION SECNO=   7460.000  PROFILE=  1  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   7460.000  PROFILE=  1  MINIMUM SPECIFIC ENERGY

 CAUTION SECNO=   7108.700  PROFILE=  1  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   7108.700  PROFILE=  1  MINIMUM SPECIFIC ENERGY
 CAUTION SECNO=   7108.700  PROFILE=  2  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   7108.700  PROFILE=  2  MINIMUM SPECIFIC ENERGY

 CAUTION SECNO=   6808.700  PROFILE=  1  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   6808.700  PROFILE=  1  MINIMUM SPECIFIC ENERGY
 CAUTION SECNO=   6808.700  PROFILE=  2  CRITICAL DEPTH ASSUMED
 CAUTION SECNO=   6808.700  PROFILE=  2  MINIMUM SPECIFIC ENERGY
```

```
CAUTION SECNO=   6508.700  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   6506.700  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=   6506.700  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   6508.700  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   6206.700  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   6206.700  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=   6208.700  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   6208.700  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   6190.100  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   6190.100  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=   6190.100  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   6190.100  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   5890.100  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   5890.100  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=   5890.100  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   5890.100  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   5590.100  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   5590.100  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=   5590.100  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   5590.100  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   5484.000  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   5484.000  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=   5484.000  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   5484.000  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   5290.100  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   5290.100  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=   5290.100  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   5290.100  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   5268.300  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   5268.300  PROFILE=  1  MINIMUM SPECIFIC ENERGY
CAUTION SECNO=   5268.300  PROFILE=  2  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   5268.300  PROFILE=  2  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   5168.300  PROFILE=  1  HYDRAULIC JUMP D.S.
CAUTION SECNO=   5168.300  PROFILE=  2  HYDRAULIC JUMP D.S.
WARNING SECNO=   5168.300  PROFILE=  2  CONVEYANCE CHANGE OUTSIDE ACCEPTABLE RANGE

CAUTION SECNO=   5147.300  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   5147.300  PROFILE=  1  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   5100.000  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   5100.000  PROFILE=  1  MINIMUM SPECIFIC ENERGY

CAUTION SECNO=   4812.200  PROFILE=  1  CRITICAL DEPTH ASSUMED
CAUTION SECNO=   4812.200  PROFILE=  1  MINIMUM SPECIFIC ENERGY
WARNING SECNO=   4812.200  PROFILE=  2  CONVEYANCE CHANGE OUTSIDE ACCEPTABLE RANGE
```

CAUTION SECNO= 4512.200 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 4512.200 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 4512.200 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 4512.200 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 4222.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 4222.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 4222.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 4222.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 4121.000 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 4121.000 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 4121.000 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 4121.000 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 3912.200 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 3912.200 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 3912.200 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 3912.200 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 3812.200 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 3812.200 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 3812.200 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 3812.200 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 3312.200 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 3312.200 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 3312.200 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 3312.200 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 3012.200 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 3012.200 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 3012.200 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 3012.200 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 2712.200 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 2712.200 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 2712.200 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 2712.200 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 2652.700 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 2652.700 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 2652.700 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 2652.700 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 2572.700 PROFILE= 1 HYDRAULIC JUMP D.S.
CAUTION SECNO= 2572.700 PROFILE= 2 PREABLE MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 2572.700 PROFILE= 2 WSEL ASSUMED BASED ON MIN DIFF
CAUTION SECNO= 2572.700 PROFILE= 2 20 TRIALS ATTEMPTED TO BALANCE WSEL
CAUTION SECNO= 2572.700 PROFILE= 2 HYDRAULIC JUMP D.S.

CAUTION SECNO= 2532.200 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 2532.200 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 2237.500 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 2237.500 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 2237.500 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 2237.500 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 1937.500 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 1937.500 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 1937.500 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 1937.500 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 1637.500 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 1637.500 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 1637.500 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 1637.500 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 1337.500 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 1337.500 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 1337.500 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 1337.500 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 1037.500 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 1037.500 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 1037.500 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 1037.500 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 737.480 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 737.480 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 737.480 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 737.480 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 437.480 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 437.480 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 437.480 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 437.480 PROFILE= 2 MINIMUM SPECIFIC ENERGY

CAUTION SECNO= 137.480 PROFILE= 1 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 137.480 PROFILE= 1 MINIMUM SPECIFIC ENERGY
CAUTION SECNO= 137.480 PROFILE= 2 CRITICAL DEPTH ASSUMED
CAUTION SECNO= 137.480 PROFILE= 2 MINIMUM SPECIFIC ENERGY

Data CD



GRAPHIC SCALE

200 0 100 200 400 800

(IN FEET)

1 inch = 200 ft.

FIGURE 1: HEC-RAS CROSS-SECTION MAP

Sloan Channel LOMR

HEC-RAS Cross-Section — STA 116+91 (FIS 106+24)

Note: Aerial Photo as of April 2006

PBSJ
2270 Corporate Circle
Suite 100
Henderson, Nevada 89074
Tele: 702-263-7275
Fax: 702-263-7200
ENGINEERING · PLANNING · SURVEYING · CONSTRUCTION SERVICES

FIGURE 1